
Approval of submitted plans is not an approval of omissions or oversight by this office or noncompliance with any applicable regulations of local government. The contractor is responsible for making sure that the building complies with all applicable building codes and regulations of the local government.

Site shall be graded and have hazards removed, not limited to concrete, construction debris, and utilities.

THE APPROVED CONSTRUCTION PLANS AND ALL ENGINEERING MUST BE POSTED ON THE JOB AT ALL INSPECTIONS IN A VISIBLE AND READILY ACCESSIBLE LOCATION. PRINT in COLOR and to SCALE.

City of Puyallup
Building
REVIEWED
FOR
COMPLIANCE
RayC
02/28/2024
12:52:19 PM



PRDE20240287

City of Puyallup
Development

Engineering APPROVED

The applicant shall request a sediment control and erosion inspection with a City Engineering Inspector through the CityView portal at least 48 hours in advance of job start. See City Standards 02.03.02 & 05.02.01

Sediment control and erosion procedures shall be practiced eliminating and preventing off site damage. Stormwater runoff originating upgrade of exposed areas shall be controlled to reduce erosion and sediment loss during the period of exposure. Refer to the Stormwater Fact Sheet and City standard details 02.03.02 & 05.02.01 for typical erosion and sedimentation control methods. Attached in CityView

If any water or sewer connections are located during the demolition of the two buildings contact the engineering inspector for proper cutting and capping of the utility

Call Before You Dig. It's the law.
Locate all utilities prior to starting work
Dial 811 or call 1-800-424-5555.


APPROVED PLAN
CITY OF PUYALLUP
PLANNING DIVISION


APPROVED BY: ARamirez

DATE: 03/06/2024

CASE NO.: PRDE20240287

CONDITIONS: Please refer to Conditions tab in CityView.





Puyallup

23rd Ave SE

Pierce College Puyallup

39th Ave SE

GESTOSO
DESIGN &
DRAFTING
SERVICES
22420 127TH
AVE SE KENT
WA 98031
(253) 709-7543
E: OSCAR.
GESTOSO
@GMAIL.COM

Pioneer Wy E

Todd's Nursery

& Landscaping

23rd Ave SE

Alderton 96th St E

SHAO RESIDENCE 2317 SHAW ROAD PUYALLUP, WA 98374

		NO.	DESCRIPTION	DATE
$\overline{}$				
7 !				
/1				
\				
1	_			
/	-0			
	10.			
	11			
BSBL = 5.0'	뮏			
∄",	\ 			
	RT			
)PE			
7	PROPERTY LINE = 110.0	S	ITF PI A	N

Project Number 2024.01

Date 02/23/2024

Drawn By OG

Checked By MS

1 SITE PLAN 1" = 20'-0"

BSBL ≠ 5.0'

PROPERTY LINE = 100.0'

HYDRANT

Fact Sheet

Construction Stormwater Pollution Prevention for Projects that disturb less than 2,000 SF



This Worksheet is for projects that create and/or replace less than 2,000 square feet of hard surfaces or disturb less than 7,000 square feet of pervious surfaces. Projects that meet this threshold are not required to submit a Construction Stormwater Pollution Prevention Plan, but are required to follow the 13 Elements outlined below.



Hard Surfaces = Impervious surfaces, green roofs, and permeable pavement.

Pervious Surface = lawn, landscape, native vegetation, etc.

Element 1 Preserve Vegetation and Mark Clearing Limits

 Before you begin construction, mark the limits of the area that is to be disturbed. Make sure to clearly mark trees that are to remain and any sensitive areas (e.g. wetlands, streams) to protect them from being disturbed during construction.

Element 2 Establish Construction Access

Typically, restricting construction traffic to an already paved driveway is acceptable to meet
this element. Less commonly, a stone construction entrance and/or a wheel wash may be
necessary depending on site conditions. It is important to work with your contrator to make
sure you are not tracking sediment and debris offsite during construction.

Element 3 Control Flow Rates

• Ensure that dirty water is not leaving the construction area and that you are not increasing the amount of water that would typically leave the project area. (E.g. do not use a garden hose to wash sediment off of a driveway into the nearest storm inlet)

Element 4 Install Sediment Controls

 City Standard details for common sediment controls (silt fence and inlet proptection) are included in this worksheet. Sometimes, additional controls such as gravel filter berms, vegetated strips, and watlles (straw rolls) are needed. Consult with your contractor to ensure that appropriate controls are being provided.

Element 5 Stabilize Soils

Soils cannot be exposed and unworked for longer than 7 days during the dry season (May 1 September 30) or 2 days in the wet season (October 1 - April 30). Soils can be stabilized in a
number of ways, including temporary or permanent seeding, mulching, net and blankets,
plastic coverings, sodding, and topsoiling/composting.



Element 6 Protect Slopes

• If you have steep slopes on your site (greater than 15%), you should coordinate with a contractor or engineer to ensure that you are adequately protecting those areas and are not potentially creating issues for yourself or adjacent property owners.

Element 7 Protect Drain Inlets

 Ensure that dirty water is not entering any nearby storm inlets. A City standard detail for inlet protection is included in this worksheet.

Element 8 Stabilize Channels and Outlets

 Typically, stablizing channels and outlets is not necessary for small projects. If your property has surface waters such as a stream or wetland, you should consult a professional engineer to ensure that you are properly protecting those areas.

Element 9 Control Pollutants

For small projects, controlling pollutants is primarily related to concrete handling to
ensure that tools are washed in formed areas or ontainers such as Eco-pans. If there will
be harmful chemicals that will be used during construction, consult a professional
contractor or engineer to prepare a pollution prevention plan.

Element 10 Control De-Watering

Small projects typically do not require dewatering. If you plan to excavate a large pit that
may trap stormwater (like excavating a hole for an in-ground pool), consult a professional
engineer to prepare a dewatering plan.

Element 11 Maintain BMPs

- Ensure that BMPs (e.g. silt fence, inlet protection, etc.) are properly functioning throughout the duration of construction. For example, silt fence should be upright and should not have sediment build up greater than one third of the height of the fence. Similarly, inlet protection (typically a piece of fabric inserted into a catch basin) should be cleaned regularly to avoid sediment build up and clogging of the inlet.
- Temporary Erosion and sediment control BMPs can be removed 30 days after the site is stabilized (no exposed soils) or after they are no longer needed.


Element 12 Manage the Project

 Think about what time of year construction is anticipated to occur and if any adjustments are needed to accommodate weather patterns. Claering, grading, and soil disturbing should be avoided or limitied from October 1st through April 30th if possible.

Protect Low Impact Development (LID) Best Management Practices (BMPs)

• If there is already an LID practice installed where construciton activities will occur (e.g. rain garden, permeable pavement, infiltration trench, etc.), it is important to protect them from being damaged or inundated with sediment during construction.

Element 13





PUBLIC WORKS DEPARTMENTS

SILTATION FENCE

DRAWN BY LINDA LANSING LINDA LIAN COLLEEN HARRIS XXXX STANDARD

FILE NAME
F;DWGCOMMON\STDS\CITY\2009\02_SD\02.03.02

DATE APPROVED BY
XXXX

STANDARD

DATE REVISED BY
XXXX

STANDARD


DATE REVISED SCALE
09;01/1992
06;01/2003
NTS
02.03.02

City of Puyallup

PRDE20240287

ISSUED PERMIT					
Building	Planning				
Engineering	Public Works				
Fire	Traffic				

- 1. ALL LIMITS OF CLEARING AND AREAS OF VEGETATION PRESERVATION AS PRESCRIBED ON THE PLANS SHALL BE CLEARLY FLAGGED IN THE FIELD AND OBSERVED DURING CONSTRUCTION.
- 2. ALL REQUIRED SEDIMENTATION AND EROSION CONTROL FACILITIES MUST BE CONSTRUCTED AND IN OPERATION PRIOR TO ANY LAND CLEARING AND/OR OTHER CONSTRUCTION TO ENSURE THAT SEDIMENT LADEN WATER DOES NOT ENTER THE NATURAL DRAINAGE SYSTEM. THE CONTRACTOR SHALL SCHEDULE AN INSPECTION OF THE EROSION CONTROL FACILITIES PRIOR TO ANY LAND CLEARING AND/OR CONSTRUCTION. ALL EROSION AND SEDIMENT FACILITIES SHALL BE MAINTAINED IN A SATISFACTORY CONDITION AS DETERMINED BY THE CITY, UNTIL SUCH TIME THAT CLEARING AND/OR CONSTRUCTION IS COMPLETED AND THE POTENTIAL FOR ON-SITE EROSION HAS PASSED. THE IMPLEMENTATION, MAINTENANCE, REPLACEMENT, AND ADDITIONS TO THE EROSION AND SEDIMENTATION CONTROL SYSTEMS SHALL BE THE RESPONSIBILITY OF THE PERMITEE.
- 3. THE EROSION AND SEDIMENTATION CONTROL SYSTEM FACILITIES DEPICTED ON THESE PLANS ARE INTENDED TO BE MINIMUM REQUIREMENTS TO MEET ANTICIPATED SITE CONDITIONS. AS CONSTRUCTION PROGRESSES AND UNEXPECTED OR SEASONAL CONDITIONS DICTATE, FACILITIES WILL BE NECESSARY TO ENSURE COMPLETE SILTATION CONTROL ON THE SITE. DURING THE COURSE OF CONSTRUCTION, IT SHALL BE THE OBLIGATION AND RESPONSIBILITY OF THE PERMITEE TO ADDRESS ANY NEW CONDITIONS THAT MAY BE CREATED BY HIS ACTIVITIES AND TO PROVIDE ADDITIONAL FACILITIES. OVER AND ABOVE THE MINIMUM REQUIREMENTS. AS MAY BE NEEDED TO PROTECT ADJACENT PROPERTIES, SENSITIVE AREAS, NATURAL WATER COURSES, AND/OR STORM DRAINAGE SYSTEMS.
- 4. APPROVAL OF THESE PLANS IS FOR GRADING, TEMPORARY DRAINAGE, EROSION AND SEDIMENTATION CONTROL ONLY, IT DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT STORM DRAINAGE DESIGN, SIZE OR LOCATION OF PIPES, RESTRICTORS, CHANNELS, OR RETENTION FACILITIES.
- 5. ANY DISTURBED AREA WHICH HAS BEEN STRIPPED OF VEGETATION AND WHERE NO FURTHER WORK IS ANTICIPATED FOR A PERIOD OF 30 DAYS OR MORE, MUST BE IMMEDIATELY STABILIZED WITH MULCHING, GRASS PLANTING, OR OTHER APPROVED EROSION CONTROL TREATMENT APPLICABLE TO THE TIME OF YEAR IN QUESTION. GRASS SEEDING ALONE WILL BE ACCEPTABLE ONLY DURING THE MONTHS OF APRIL THROUGH SEPTEMBER INCLUSVE. SEEDING MAY PROCEED OUTSIDE THE SPECIFIED TIME PERIOD WHENEVER IT IS IN THE INTEREST OF THE PERMITEE BUT MUST BE AUGMENTED WITH MULCHING, NETTING, OR OTHER TREATMENT APPROVED BY THE CITY.
- 6. IN CASE EROSION OR SEDIMENTATION OCCURS TO ADJACENT PROPERTIES, ALL CONSTRUCTION WORK WITHIN THE DEVELOPMENT THAT WILL FURTHER AGGRAVATE THE SITUATION MUST CEASE, AND THE OWNER/CONTRACTOR WILL IMMEDIATELY COMMENCE RESTORATION METHODS. RESTORATION ACTIVITY WILL CONTINUE UNTIL SUCH TIME AS THE AFFECTED PROPERTY OWNER IS SATISFIED.
- 7. NO TEMPORARY OR PERMANENT STOCKPILING OF MATERIALS OR EQUIPMENT SHALL OCCUR WITHIN CRITICAL AREAS OR ASSOCIATED BUFFERS, OR THE CRITICAL ROOT ZONE FOR VEGETATION PROPOSED FOR RETENTION.



GRADING, EROSION, AND SEDIMENTATION CONTROL NOTES

JIM ERWIN-SVOBODA

COLLEEN HARRIS

CITY STANDARD 05.02.01