



GENERAL NOTES

- A. CONTRACTOR TO FIELD VERIFY FRAMING AT ALL DOOR LOCATIONS FOR PROPER OPERATING CLEARANCE WITH VANITY CASEWORK.
- B. DIMENSIONS ARE TO FACE OF STUD OR TO CENTERLINE WHERE NOTED.
- C. CONTRACTOR TO VERIFY SHEAR WALL LOCATIONS PER STRUCTURAL PLANS.
- D. FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS. DIMENSIONS ARE TO FACE OF FINISH, TO FACE OF EXISTING WALL, OR TO FACE OF FOUNDATION WALL UNLESS NOTED OTHERWISE.

NEW FLOOR PLAN KEYED NOTES

- 1 INSTALL NEW FLOORING AND RUBBER BASE THIS GENERAL AREA
- 2 PATCH WALLS WHERE DEMOLITION HAS OCCURRED AND FINISH SEAMLESSLY.
- 3 ALIGN NEW WALL WITH ADJACENT EXISTING WALLS AND FINISH SEAMLESSLY
- 4 SUPPORT COLUMNS. SEE STRUCTURAL DRAWINGS FOR MORE INFORMATION
- 5 SHEAR WALLS. SEE STRUCTURAL DRAWINGS FOR MORE INFORMATION.
- 6 CONCRETE CURBS. SEE CIVIL DRAWINGS FOR MORE INFORMATION.
- 7 NEW STOREFRONT ENTRY. SEE DOOR SCHEDULE FOR MORE INFORMATION.
- 8 (NOT USED)
- 9 PATCH WALLS WHERE DEMOLITION HAS OCCURRED.
- 10 ALIGN NEW WALL WITH ADJACENT EXISTING WALLS AND FINISH SEAMLESSLY.
- 11 (NOT USED)
- 12 INSTALL NEW CARPETING, COLOR, PATTERN, AND MANUFACTURER TO BE DETERMINED BY OWNER.
- 13 NEW WALL PAPER TO MATCH EXISTING WALL PAPER IN CORRIDOR ALL INTERIOR WALLS THIS AREA.
- 14 NEW WALL PAPER TO MATCH EXISTING ROOM WALL PAPER.
- 15 COORDINATE NEW DUCTWORK AND SUPPLY WITH EXISTING PTAC UNIT AT CORRIDOR AND MEETING ROOM WITH MEP DRAWINGS.
- 16 PROVIDE NEW TILE BASE TO MATCH EXISTING BASE THIS GENERAL AREA.
- 17 INFILL EXISTING EXTERIOR WALL WITH LIKE MATERIALS TO MATCH EXISTING AND TO MAINTAIN WATER TIGHTNESS. WALL SURFACES AT INTERIOR AND EXTERIOR SHALL ALIGN AND SHALL BE SEAMLESS. FINISH WITH TEXTURES, PAINT, SHEEN AND COLORS TO MATCH EXISTING.
- 18 NEW RETAINING WALL EXTENSION. REFER TO CIVIL DRAWINGS DATED 3-28-2024, AND SUPPORTING STRUCTURAL CALCULATIONS FROM STRUCTURAL ENGINEER DATED 3-25-2024. VERIFY WALL ELEVATION HEIGHTS WITH CIVIL DRAWINGS.

City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic

City of Puyallup
Planning Division
APPROVED

See permit conditions.
Chris BEALE
04/15/2024
9:06:33 AM

KNIT
909 S. 336TH ST,
SUITE 107
FEDERAL WAY, WA 98003
knitstudios.com

THESE DOCUMENTS HAVE BEEN PRODUCED AS AN INSTRUMENT OF SERVICE AND ARE INTENDED SOLELY FOR THE PURPOSE OF CONSTRUCTION, USING AND IMPROVING THE PROJECT. KNIT AS THE ARCHITECT OF RECORD FOR THE PROJECT RETAINS OWNERSHIP OF THESE DOCUMENTS.
ANY USE OF THESE DOCUMENTS OR USE OF THIS DESIGN IDEAS OR CONCEPTS DESCRIBED HEREIN IN WHOLE OR PART BY ANY PERSON WHATSOEVER IS STRICTLY PROHIBITED EXCEPT BY WRITTEN CONSENT OF KNIT.
REPRODUCTION OF THESE DOCUMENTS IS STRICTLY PROHIBITED EXCEPT BY WRITTEN CONSENT OF KNIT.
COPYRIGHT 2021 KNIT

ISSUE DATE 09/25/23
PROGRESS SET

REV	DATE	COMMENT
1	03.03.2023	AC RESPONSE
2	08.14.2023	CORRECTIONS
3	09.25.2023	CORRECTIONS
4	10.17.2023	CORRECTIONS
5	12.21.2023	CORRECTIONS
6	02.26.2023	CITY REVIEW COMMENTS
7	03.21.2024	CORRECTIONS
8	03.25.2024	STUCCO WALL CHANGE
9	03.26.2023	RETAINING WALL

8677 REGISTERED ARCHITECT
Chris Beale
RHONDA A. GILLOGLY
STATE OF WASHINGTON
03/28/2024

PRRWF20240597 - RETAINING WALL PERMIT FOR HAMPTON INN
SITE PLAN TO REFLECT LOCATION OF RETAINING WALL ALONG ROW REFERENCE CIVIL PLAN

A sufficient number of 1 1/2" diameter weep holes are required to satisfy all requirements of PCS Structural Solutions retaining wall design
See Section Detail 4/535 on the structural plans showing 1 1/2" diameter weep hole

City of Puyallup
Development & Permitting Services
Engineering APPROVED

See permit for additional requirements.
Linda Lian
04/18/2024
3:32:58 PM

1ST FLOOR PLAN
ADDITION TO HAMPTON INN & SUITES
1515 S MERIDIAN
PUYALLUP, WA 98371
HAMPTON INN & SUITES

TITLE PROJECT CLIENT
JOB NO: 210158