

Bradley Heights Apartments

A 236-Unit Apartment Development Puyallup, Washington

Bradley Heights SS LLC

PROJECT TEAM

Owner/Developer	Bradley Heights SS LLC 614 Boylston Ave E Seattle, WA 98102 (206) 557-7236
Architect	Milbrandt Architects, Inc., P.S. 25 Central Way, Suite 210 Kirkland, WA 98033 (425) 454-7130
Structural Engineer	Solutions 4 Structure, Inc. 11605 135th St Ct E Puyallup, WA 98374 (253) 268-2923
Civil Engineer	Azure Green Consultants 409 East Pioneer Puyallup, WA 98372 (253) 770-3144
Landscape Architect	Nature By Design 1320 Alameda Avenue, Suite B Fircrest, WA 98466 (253) 460-6067
MEP Engineer	Robison Engineering Inc. 19401 40th Avenue W, Suite 302 Lynnwood, WA 98036 (206) 364-3343

PROJECT INFORMATION

Site Address:	202 27th Ave SE, Puyallup, WA 98374
Project Description:	Construction of 236 wood framed apartment units in eight stacked flat buildings along with a leasing amenity building.
Site Area:	7.785 acres (+/- 339,107 SQ. FT.)
Tax Parcel Number:	419036006
Occupancy Type:	All Apartment Buildings are R2 occupancy.
Type of Construction:	All Apartment Buildings are Type V-B construction with NFPA 13R automatic sprinklers.
Applicable Codes:	2018 International Building Code 2018 Uniform Plumbing Code 2018 Washington State Energy Code 2018 International Mechanical code 2018 International Fire Code 2022 National Electrical Code ICC/ANSI A117.1-2009 Standard Washington State Amendments as modified and adopted by the local jurisdiction.

RATED ASSEMBLIES

Rated assemblies shall be provided in accordance with IBC section 420

Assembly	Fire Rating	Detail
Common walls separating dwelling units:	1-hour	4/D1
Exterior walls:	non-rated	1/D1
Interior bearing walls:	non-rated	2/D1
Interior non-bearing walls:	non-rated	2/D1
Corridor-to-unit walls:	1-hour	3/D1
Floor/ceiling:	1-hour	13/D1
Roof/ceiling:	1-hour	17/D1
Penetrations (firestopping)	Per situation	17/D7
Membrane penetrations by ducts in ceiling	26 ga. steel ducting	6/D7
Stair fire barrier wall:	1-hour @ 3-story 2-hour @ 4-story	3/D1 7/D1

Fire Alarm systems and smoke alarms shall be provided in accordance with IBC section 420.5 Refer to unit plan sheets for smoke detector locations and requirements.

GENERAL NOTES

- Comply with 2018 IBC and all applicable codes and ordinances of the local jurisdiction and the State of Washington.
- Do not scale drawings.
- Verify all rough-in dimensions for equipment provided in this contract or by others.
All rough-ins shall be approved and fireblocking shall be installed prior to framing inspection.
- Verify size and location of and provide all openings through floors and walls, furring, anchors, inserts, rough bucks and backing for surface mounted items.
- Provide furring as required to conceal mechanical and electrical work in all finished areas.
- All swinging doors not located by dimensions on plans, interior elevations, or details shall be 3" from face of stud to edge of rough openings or centered between room partitions as shown.
- Plans are drawn assuming the following rough openings:
Swinging doors: Nominal size +2".
Bi-Fold doors: Nominal size +1/2".
Bi-Pass doors: Nominal size +0".
Windows: Nominal size +0".
Sliding glass doors: Nominal size +0".
- Fill where required with earth free from organic material. Compact fill in 12" layers maximum.
- "Finish Floor" refers to the top of concrete slab or top of wood floor sheathing.
- Exterior walls shall be 2x6 studs at 16" o.c. and interior walls shall be 2x4 studs at 16" o.c., unless noted otherwise.
- Unless otherwise noted, plan dimensions are to face of studs and face of concrete walls.
- Refer to interior elevations for cabinet and counter lengths, dimensions, countertop materials and detail reference. Verify all existing dimensions before installation.
- Provide caulking between sole plates and subfloor and between rim joists at both top plate and subfloor.
- Hydrants shall be in service prior to start of framing.
- Through penetrations and membrane penetrations of rated wall or floor/ceiling assembly will require firestopping per 2018 IBC Section 714. See detail 7/D7 for diagram of specifics.
- Shall be no asbestos used on this project.
- All Tub-Shower valves installed shall conform to UPC 408.3 & ASSE 1016 or ASME A112.18.1.
- Milbrandt Architects is not responsible for construction means, methods, techniques or procedures, or for the safety precautions and programs in connection with the work, and is not responsible for the failure of any contractor or subcontractor to carry out the work in accordance with the various contract documents and or governing jurisdiction, regardless of what is shown on these drawings.

FEDERALLY DECLARED SAFE HARBOR

Declared Safe Harbor: HUD Fair Housing Accessibility Guidelines published on March 6, 1991 and the Supplemental Notice to Fair Housing Accessibility Guidelines: Questions and Answers about the Guidelines, published on June 28, 1994.

ACCESSIBILITY

Design is based on the 2018 IBC Chapter 11 which has been amended by the State of Washington, & 2009 ICC A117.1 Accessible & Useable Buildings & Facilities.

None of the buildings are an elevator type building.
There are a total of 84 one-story dwelling units at ground level. All ground floor units are 1 or 2-bed unit designs. Provided total 84 accessible units: 12 Type A and 72 Type B units.
Type A units meet the requirements for Type B units.

- The 12 Type A units are proportioned as follows (see Site Plan):
 - (7) 1-Bed units (1 BR) in each of Buildings A, C, D, E, F & G - for a total of 7.
 - (5) 2-Bed units (2 BR) in Buildings A, D, E, F & G - for a total of 5.

Parking:
Section 1106.2 IBC requires 2% of each proposed parking stall type to be accessible.
Of the 354 total open stalls, 12 are accessible, including 5 van stalls. Each accessible open stall is indicated by the wheelchair symbol on the site plan and further designated by the detail symbols 10/A3.

VENTILATION NOTES

- Design Criteria: 2018 International Mechanical Code with Washington State Amendments.
- System Type: Balanced whole house fan system with energy recovery ventilator
- Use: Group R occupancy.
- Specifics: See mechanical plans by others.

ENERGY NOTES

Reference: 2018 WSEC
Chapter 4 using climate zone category 5 & marine 4 for all calculations.

All residential units shall comply with the Requirements By Component Table 402.1.1. Including but not limited to the following:

Code Requirements	Associated Notes/Details Showing Compliance
Window U-Factor	.24 or better See Insul. Notes on sheets U1, U2, U3, U4, U5
Ceiling R-Value	R-49 13 / D1
Wood Frame Wall R-Value	R-21 int. 1, 3, 4, 7 & 8 / D1
Floor R-Value	R-30 N/A
Slab R-Value & Depth	R-10, 2ft 1, 3, 5 & 6 / D2
"int." (intermediate framing) denotes standard framing 16" o.c. with headers insulated with a min. of R-10 (see 6/D6).	

All units need to have a certificate posted within 3 feet of the electrical distribution panel listing the following information: R-values, U-values, duct air leakage test results, building envelope air leakage test results, types and efficiencies of heating, cooling and service water heating equipment per R401.3

All insulation shall comply with table R402.4.1.1 WSEC
Hot water piping shall be insulated to a minimum of R-3 per R403.5.2
Water heaters in unheated spaces, or on concrete floors shall be placed on minimum of R-10 incompressible insulated surface per R403.5.5
Mechanical ventilation shall be provided per R403.6
A minimum of 90% of all permanently installed lamps in lighting fixtures shall be high-efficacy lamps per R404.1

See Insulation Notes on the Unit Plans, and Insulation and Energy Notes on sheet D7.

Energy Credits used (see 2018 WSEC table 406.3 for all requirements):

Fuel Normalization Credit System Type 3	-1.0 CREDITS
Option 1.1 Efficient Building Envelope	0.5 CREDITS
Option 2.1 Air Leakage Control	1.0 CREDITS
Option 5.5 Efficient Water Heating	2.5 CREDITS
Option 7.1 Appliance Package	1.5 CREDITS
TOTAL PROVIDED	4.5 CREDITS

Revise to match 2018 Prescriptive Energy Code Compliance report. Page A

Report selected 1.7 credit; plans show 1.1 credit

FIRE SYSTEMS

Buildings shall have an NFPA 13R sprinkler system installed throughout per 2018 IBC Section 903.3.1.2 which shall include a notification appliance which is activated upon sprinkler flow. Any alarms, bells or lights required due to the design of the sprinkler system or integral with the sprinkler system shall be considered part of the sprinkler system. The sprinkler system design, therefore, needs to include any and all integrated alarms.

Plans and specifications for sprinklers shall be submitted to the city of Puyallup as a separate permit for review and approval before installation.

DESIGN LOADS

See structural notes. Sheet S1.0

DEFERRED SUBMITTALS

Shop drawings and calculations are required for:

- Firestopping details. Firestopping methods and materials shall be determined by the Contractor except where details or notes are indicated in these drawings. Firestopping locations are indicated in part by detail 17/07. Contractor shall submit UL assembly details and product cuts of all relevant situations to the Architect for conformance to the building design. Upon the Architect's approval, they shall be submitted to the Building Official for approval. Firestopping shall not be installed without City approval.


SEPARATE PERMITS

The following required permits will be submitted separately:



- Automatic Fire Sprinkler System (See fire systems note, this sheet).
- Fire Alarm System.



VICINITY MAP



Sunset Garden Senior Living Apartments



SITE PLAN 236 UNITS
1" = 40'


Provide egress plan with all dimensions with travel distance for all floors.
Page A2

SITE INFORMATION

SITE ADDRESS: 202 27th Ave SE, Puyallup, WA
 PARCEL #: 419036006
 SITE AREA: 339,107 SF (7.785 Acres)
 ZONE: RM-CORE
 SETBACKS: NORTH/FRONT: 10 FT setback to buildings
 WEST/SIDE: 0 FT Building setback - 6 FT landscape buffer
 SOUTH/REAR: 0 FT Building setback - 6 FT landscape buffer
 EAST/SIDE: 25 FT Building setback - 15 ft landscape buffer
 BUILDING HEIGHT: 50' Max
 DENSITY: Min 16 units per acre (125 units)
 no Max density
 LOT COVERAGE: Max 90%
 LANDSCAPE AREA: Min 10% of net lot area (33,910 SF)
 OPEN SPACE: 10% of net lot area (33,910 SF)
 38,500 SF provided
 PRIVATE OPEN SPACE: 60 SF per ground floor unit
 10' x 6' per upper story unit
 PARKING: 1.5 PARKING SPACES PER UNIT
 Required Parking: 354 Stalls
 Provided Parking: 354 Stalls
 EASEMENTS: no existing easements on site

PARKING SUMMARY		
Parking Stalls Required		354
Standard Stalls		118
Compact Stalls	41.5%	100
Parallel Stalls		0
Carport Stalls		124
Attached Garage Stalls		0
Detached Garage Stalls		0
Accessible Standard Stalls		6
Accessible Van Stalls		5
Accessible Parallel Stalls		0
Accessible Carport Stalls		1
Accessible Garage Stalls		0
Tandem Stalls		0
Tandem Garage Stalls		0
Subtotal	354	1.50 Stalls / D.U.
Aprons		0
Total Parking Stalls Provided	354	1.50 Stalls / D.U.

UNIT COUNT	
1 BED	137 (58%)
2 BED	99 (42%)
TOTAL	236



- SITE NOTES**
- 1) TYPICAL SIDEWALK WIDTH IS 6'
 - 2) A MINIMUM CLEAR WIDTH OF 44" IS REQUIRED FOR ALL EXTERIOR ACCESSIBLE ROUTES PER WASHINGTON STATE AMENDMENT SECTION 1101.2.1


NOTE: ALL DIMENSIONS ARE FROM FINISHED SURFACE

CHANGES IN LEVEL

CHANGES IN LEVEL OF 1/4" MAX. SHALL BE PERMITTED TO BE VERTICAL AND WITHOUT EDGE TREATMENT.
CHANGES IN LEVEL BETWEEN 1/4" AND 1/2" MAX. SHALL BE BEVELED WITH A SLOPE NOT STEEPER THAN 1:2

TURNING SPACE & CLEAR FLOOR SPACE

TURNING SPACES SHALL BE EITHER A 60" CIRCLE OR A T-SHAPED SPACE WITHIN A 60" SQUARE. CLEAR FLOOR SPACE IS DEFINED AS A SPACE 30"x48" A SLOPE OF NOT MORE THAN 1:48 SHALL BE PERMITTED WITHIN TURNING AND CLEAR FLOOR SPACES. NO CHANGES IN LEVEL ARE PERMITTED.




1 FLOOR CLEARANCES

3/8"=1'-0"

KNEE AND TOE CLEARANCE

TOE OR KNEE CLEARANCE SHALL BE 30" WIDE MIN. THE DIP OF THE OVERFLOW ON A SINK SHALL NOT BE CONSIDERED IN DETERMINING KNEE AND TOE CLEARANCE.
* WATER SUPPLY & DRAINPIPES UNDER LAVATORIES AND SINKS SHALL BE INSULATED OR OTHERWISE CONFIGURED TO PROTECT AGAINST CONTACT. THERE SHALL BE NO SHARP OR ABRASIVE SURFACES UNDER LAVATORIES AND SINKS.




2 KNEE AND TOE SPACE

3/8"=1'-0"

PROTRUDING OBJECTS


OBJECTS WITH LEADING EDGES MORE THAN 27" AND NOT MORE THAN 80" ABOVE THE FINISH FLOOR MAY PROTRUDE 4" MAX INTO THE CIRCULATION PATH. EXCEPT HANDRAILS, WHICH ARE PERMITTED TO PROTRUDE 4 1/2".
WHERE VERTICAL CLEARANCE IS LESS THAN 80", GUARDRAILS OR OTHER BARRIERS SHALL BE PROVIDED WITH THE LEADING EDGE OF THE GUARDRAIL NO MORE THAN 27" MAX. ABOVE THE FLOOR.



3 PROTRUDING OBJECTS

3/8"=1'-0"

CLEAR FLOOR SPACE SHALL EXTEND BENEATH THE ELEMENT FOR A DISTANCE NOT LESS THAN THE REQUIRED REACH DEPTH OVER THE OBSTRUCTION.



OPERABLE PARTS

A 30"x48" CLEAR FLOOR SPACE SHALL BE PROVIDED AT ALL OPERABLE PARTS. ALL OPERABLE PARTS SHALL BE WITHIN ONE OR MORE OF THE REACH RANGES.
OPERABLE PARTS SHALL BE OPERABLE WITH ONE HAND AND SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE OPERABLE PARTS SHALL BE 5.0 LBS MAX.

4 REACH RANGES

3/8"=1'-0"


ACCESSIBLE ROUTE (PER IBC SECTION 1104.2)

AT LEAST ONE ACCESSIBLE ROUTE WITHIN THE SITE SHALL BE PROVIDED FROM PUBLIC TRANSPORTATION STOPS, ACCESSIBLE PARKING, ACCESSIBLE PASSENGER LOADING ZONES, AND PUBLIC STREETS OR SIDEWALKS TO THE ACCESSIBLE BUILDING ENTRANCES SERVED.
WHEN A BUILDING OR PORTION OF A BUILDING IS REQUIRED TO BE ACCESSIBLE, AT LEAST ONE ACCESSIBLE ROUTE SHALL BE PROVIDED TO EACH PORTION OF THE BUILDING, TO ACCESSIBLE BUILDING ENTRANCES CONNECTING ACCESSIBLE WALKWAYS AND TO THE PUBLIC WAY.
ACCESSIBLE ROUTES SHALL COINCIDE WITH OR BE LOCATED IN THE SAME AREAS AS A GENERAL CIRCULATION PATH.
ACCESSIBLE ROUTES SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING COMPONENTS: WALKING SURFACES WITH A SLOPE NOT STEEPER THAN 1:20, DOORS & DOORWAYS, RAMPS, CURB RAMPS EXCLUDING THE FLARED SIDES, ELEVATORS, AND PLATFORM LIFTS.

WALKING SURFACES

SLOPE: THE RUNNING SLOPE OF WALKING SURFACES SHALL NOT BE STEEPER THAN 1:20. THE CROSS SLOPE OF A WALKING SURFACE SHALL NOT BE STEEPER THAN 1:48.
CHANGES IN LEVEL: CHANGES IN LEVEL SHALL COMPLY WITH SECTION 303 (see detail 1 ACC sheets)
CLEAR WIDTH: THE WIDTH OF AN ACCESSIBLE ROUTE SHALL BE 36" MIN. THE CLEAR WIDTH SHALL BE PERMITTED TO BE REDUCED TO 32" MIN. FOR A LENGTH OF 24" MAX. PROVIDED THE REDUCED WIDTH SEGMENTS ARE SEPARATED BY SEGMENTS THAT ARE 48" MIN. IN LENGTH AND 36" MIN. IN WIDTH. FOR EXTERIOR ROUTES OF TRAVEL, THE CLEAR WIDTH SHALL BE 44" MIN.
PASSING SPACE: AN ACCESSIBLE ROUTE WITH A CLEAR WIDTH LESS THAN 60" SHALL PROVIDE PASSING SPACES AT MAXIMUM INTERVALS OF 200 FEET. PASSING SPACES SHALL BE EITHER A 60"x60" MIN. SPACE, OR AN INTERSECTION OF WALKING SURFACES WITH A T-SHAPED TURNING SPACE (See detail 1 ACC sheets). PROVIDED THE BASE AND ARMS OF THE T-SHAPED SPACE EXTEND 48" MIN. BEYOND THE INTERSECTION.

5 ACCESSIBLE ROUTE



MANEUVERING CLEARANCES

MIN. MANEUVERING CLEARANCES SHALL COMPLY WITH THESE DIAGRAMS AND SHALL NOT INCLUDE KNEE & TOE CLEARANCE. THE FLOOR SURFACE WITHIN THE MANEUVERING CLEARANCE SHALL HAVE A SLOPE NOT GREATER THAN 1:48

DOORS

DOORWAY CLEAR WIDTH: DOOR OPENINGS SHALL PROVIDE A CLEAR WIDTH OF 32" MIN. CLEAR OPENING OF DOORWAYS WITH SWINGING DOORS SHALL BE MEASURED FROM THE FACE OF THE DOOR TO THE STOP WITH THE DOOR OPEN 90°.
THRESHOLDS: IF PROVIDED, THRESHOLDS SHALL BE 1/2" MAX. IN HEIGHT & SHALL COMPLY WITH SECTIONS 302 & 303. (See detail 1 ACC sheets)
DOOR HARDWARE: HANDLES, PULLS, LATCHES, LOCKS AND OTHER OPERABLE PARTS ON ACCESSIBLE DOORS SHALL HAVE A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST TO OPERATE. OPERABLE PARTS OF SUCH HARDWARE SHALL BE 34" MIN. AND 48" MAX. ABOVE THE FLOOR.


CLOSING SPEED: DOORS WITH CLOSERS SHALL BE ADJUSTED SO THAT FROM A 90° OPEN POSITION, THE TIME REQUIRED TO MOVE THE DOOR TO A POSITION OF 12° FROM THE LATCH IS 5 SECONDS MIN.
DOORS WITH A SPRING HINGE: SHALL BE ADJUSTED SO THAT FROM A 70° OPEN POSITION, THE TIME REQUIRED TO MOVE THE DOOR TO A CLOSED POSITION IS 1.5 SECONDS MIN.
DOOR OPENING FORCE: HINGED, SLIDING OR FOLDING DOORS OTHER THAN FIRE DOORS SHALL HAVE AN OPENING FORCE AS FOLLOWS:
INTERIOR DOORS: 5 LBS. MAX.
EXTERIOR DOORS: 10 LBS. MAX.

6 DOORS

1/4"=1'-0"


RAMPS

GENERAL: RAMP RUNS SHALL HAVE A RUNNING SLOPE GREATER THAN 1:20 AND NOT STEEPER THAN 1:12. THE MAX. CROSS SLOPE OF A RAMP SHALL BE 1:48. THE MAX. RISE FOR ANY RAMP RUN SHALL BE 30". LANDINGS SUBJECT TO WET CONDITIONS SHALL BE DESIGNED TO PREVENT THE ACCUMULATION OF WATER.
CHANGES IN LEVEL: CHANGES IN LEVEL SHALL COMPLY WITH SECTION 303 (See detail 1 ACC sheets)



CLEAR WIDTH: THE CLEAR WIDTH SHALL BE 36" MIN. FOR EXTERIOR ROUTES OF TRAVEL THE CLEAR WIDTH SHALL BE 44" MIN. THE HANDRAILS SHALL NOT PROJECT INTO THE REQUIRED CLEAR WIDTH OF THE RAMP RUN.
LANDINGS: RAMP SHALL HAVE LANDINGS AT THE BOTTOM & TOP OF EACH RAMP RUN WITH A MAX. SLOPE OF 1:48. CLEAR WIDTH OF LANDINGS SHALL BE AS WIDE AS THE WIDEST RAMP RUN LEADING TO THE LANDING AND A MIN. CLEAR LENGTH OF 60". RAMP THAT CHANGE DIRECTION AT THE LANDING SHALL BE SIZED TO PROVIDE A TURNING SPACE (See detail 1 ACC sheets)

HANDRAILS: RAMP RUNS WITH A RISE GREATER THAN 6" SHALL HAVE HANDRAILS
EDGE PROTECTION: THE FLOOR SURFACE OF THE RAMP RUN OR LANDING SHALL EXTEND 12" BEYOND THE INSIDE FACE OF A RAILING OR THERE SHALL BE A 4" MIN. HEIGHT CURB OR A BARRIER AT THE EDGE OF THE RAMP OR LANDING CONSTRUCTED SO THAT IT PREVENTS THE PASSAGE OF A 4" DIAMETER SPHERE




7 RAMPS

1/4"=1'-0"


CURB RAMPS

THE MIN. WIDTH OF CURB RAMPS SHALL BE 36". ALL ADJOINING GUTTERS AND ROAD SURFACES IMMEDIATELY ADJACENT TO THE CURB RAMP SHALL NOT BE STEEPER THAN 1:20. THE CURB RAMP SHALL HAVE A MAX. SLOPE OF 1:12 WITH A MAX. CROSS SLOPE OF 1:48. LANDINGS SUBJECT TO WET CONDITIONS SHALL BE DESIGNED TO PREVENT THE ACCUMULATION OF WATER.



DETECTABLE WARNINGS

DETECTABLE WARNINGS SHALL CONTRAST VISUALLY WITH ADJACENT SURFACES, EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT.
DETECTABLE WARNING SURFACES IN INTERIOR LOCATIONS SHALL DIFFER FROM ADJOINING WALKING SURFACES IN RESILIENCY OR SOUND-ON-CANE CONTACT. TRUNCATED DOMES SHALL BE ALIGNED IN A SQUARE PATTERN.




8 CURB RAMPS AND DETECTABLE WARNINGS

1/4"=1'-0"

ACCESSIBLE PARKING SPACES

LOCATION: PER IBC SECTION 1106.6, ACCESSIBLE PARKING SPACES SHALL BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTE OF TRAVEL FROM ADJACENT PARKING TO AN ACCESSIBLE BUILDING ENTRANCE. WHERE PRACTICAL, THE ACCESSIBLE ROUTE SHALL NOT CROSS LANES OF TRAFFIC. WHERE CROSSING TRAFFIC LANES IS NECESSARY, THE ROUTE SHALL BE DESIGNATED AND MARKED AS A CROSSWALK.
PARKING STALL SIZE: CAR AND VAN PARKING SPACES SHALL BE 96" MIN. WIDTH. ACCESS AISLES SERVING CAR PARKING SPACES SHALL BE 60" MIN. IN WIDTH. ACCESS AISLES SERVING VAN PARKING SPACES SHALL BE 96" MIN. IN WIDTH.
ACCESS AISLE: CAR AND VAN PARKING SPACES SHALL HAVE AN ADJACENT ACCESS AISLE ON EITHER SIDE OF THE PARKING SPACE. THE ACCESS AISLES SHALL BE 60" MIN. IN WIDTH FOR CAR STALLS AND 96" MIN. IN WIDTH FOR VAN STALLS AND EXTEND THE FULL LENGTH OF AND AT THE SAME LEVEL AS THE PARKING SPACE THEY SERVE. ACCESS AISLES SHALL BE MARKED SO AS TO DISCOURAGE PARKING IN THEM.
FLOOR SURFACES: PARKING STALLS & ADJACENT ACCESS AISLES SHALL HAVE A SURFACE SLOPE NOT GREATER THAN 1:48. WHERE MOUNTING IS NECESSARY WITHIN A PATH OF CIRCULATION, SIGNS SHALL MEET THE REQUIREMENTS OF IBC SECTION 1003.3 FOR PROTRUDING OBJECTS AND POST-MOUNTED OBJECTS.
IDENTIFICATION: ACCESSIBLE PARKING SPACES SHALL BE INDICATED BY A VERTICAL SIGN. SIGNS SHALL INCLUDE THE INTERNATIONAL SYMBOL OF ACCESSIBILITY THAT IS WHITE WITH A BLUE BACKGROUND. SIGNS IDENTIFYING VAN PARKING SPACES SHALL CONTAIN THE DESIGNATION "VAN ACCESSIBLE". A VERTICAL "NO PARKING" SIGN SHALL BE ERRECTED AT THE HEAD OF EACH ACCESS AISLE LOCATED ADJACENT TO AN ACCESSIBLE PARKING SPACE. THESE SIGNS MAY INCLUDE ADDITIONAL LANGUAGE SUCH AS, BUT NOT LIMITED TO, AN INDICATION OF THE AMOUNT OF THE MONETARY PENALTY FOR PARKING IN THE SPACE WITHOUT A VALID PERMIT OR THE ACCESS AISLE. THESE SIGNS SHALL BE 60" MIN. ABOVE THE FLOOR OF THE PARKING SPACE MEASURED TO THE BOTTOM OF THE SIGN.
SIGN MOUNTING: SIGNS ARE TO BE MOUNTED COMPLETELY OUTSIDE OF CIRCULATION PATHS WHEREVER POSSIBLE. WHERE MOUNTING IS NECESSARY WITHIN A PATH OF CIRCULATION, SIGNS SHALL MEET THE REQUIREMENTS OF IBC SECTION 1003.3 FOR PROTRUDING OBJECTS AND POST-MOUNTED OBJECTS.
* SIGNS MOUNTED ON POSTS WITHIN A CIRCULATION PATH SHALL BE INSTALLED WITH A VERTICAL CLEARANCE OF 80" MIN. FROM THE LOWEST POINT OF THE SIGN(S) TO THE WALKING SURFACE. IF A POST MOUNTED SIGN IS SIZED SUCH THAT IT PROTRUDES 4" MAX. FROM THE MOUNTING POST, THEN THE MOUNTING HEIGHT SHALL BE MOUNTED AT 60" MIN. ABOVE THE PARKING SURFACE SO AS TO NOT BE OBSTRUCTED BY ANY PARKED VEHICLES.



10 ACCESSIBLE PARKING SPACES

NTS

ACCESSIBLE STAIR REQUIREMENTS

ALL STEPS ON A FLIGHT OF STAIRS SHALL HAVE UNIFORM RISER HEIGHTS AND UNIFORM TREAD DEPTHS. RISERS SHALL BE 4" HIGH MIN. AND 7" HIGH MAX. TREADS SHALL BE 11" DEEP MIN.
OPEN RISERS ARE NOT PERMITTED & TREADS SHALL HAVE A SLOPE NOT MORE THAN 1:48.
STAIR NOSINGS SHALL CONFORM TO THE DIAGRAMS SHOWN HERE AND THE LEADING 2" OF THE TREAD SHALL HAVE VISUAL CONTRAST OF DARK-ON-LIGHT OR LIGHT-ON-DARK FROM THE REMAINDER OF THE TREAD.
STAIR TREADS & LANDINGS SUBJECT TO WET CONDITIONS SHALL BE DESIGNED TO PREVENT ACCUMULATION OF WATER.
FLOOR IDENTIFICATION SIGNS SHALL BE LOCATED AT EACH FLOOR LANDING ADJACENT TO THE STAIRWELL DOOR LEADING INTO THE CORRIDOR. SIGNS SHALL BE IN RAISED CHARACTERS & BRAILLE. "EXIT" SIGNS SHALL BE LOCATED AT STAIRS LEADING TO THE EXTERIOR OF THE BUILDING. (See detail 21 ACC sheets)




11 ACCESSIBLE STAIRS

3/8"=1'-0"

HANDRAILS

HANDRAILS SHALL BE PROVIDED ON BOTH SIDES OF STAIRS & RAMPS. THEY SHALL BE CONTINUOUS FOR THE FULL LENGTH OF EACH STAIR FLIGHT OR RAMP RUN. INSIDE HANDRAILS ON SWITCHBACK STAIRS SHALL BE CONTINUOUS BETWEEN FLIGHTS OR RUNS.
HANDRAIL GRIPPING SURFACES & ANY SURFACES ADJACENT TO THEM SHALL BE FREE OF SHARP OR ABRASIVE ELEMENTS & SHALL HAVE ROUNDED EDGES. THEY SHALL BE CONTINUOUS ALONG THEIR LENGTH AND SHALL NOT BE OBSTRUCTED ALONG THEIR TOPS OR SIDES. THE BOTTOM SHALL NOT BE OBSTRUCTED FOR MORE THAN 20% OF ITS LENGTH




HANDRAIL EXTENSIONS

EXTENSIONS SHALL EXTEND BEYOND AND IN THE SAME DIRECTION OF A STAIR FLIGHT OR RAMP RUN EXCEPT FOR THE INSIDE CONTINUOUS HANDRAIL AT SWITCHBACK STAIRS OR RAMPS. HANDRAILS SHALL RETURN TO A WALL, GUARD OR THE LANDING SURFACE, OR BE CONTINUOUS TO THE HANDRAIL OF AN ADJACENT STAIR FLIGHT OR RAMP RUN.
AT THE BOTTOM OF A STAIR FLIGHT THE HANDRAIL SHALL EXTEND AT THE SLOPE OF THE STAIR FLIGHT FOR A HORIZONTAL DISTANCE EQUAL TO ONE TREAD DEPTH BEYOND THE BOTTOM TREAD NOSING.

12 HANDRAILS

1 1/2" = 1'-0" AND 3/8"=1'-0"

LEGEND



FRONTAGE INCREASE TO BUILDING AREA

Per IBC Section 506.3 buildings that adjoin or have access to a public way or qualifying green space for more than 25% of their total perimeter are eligible for an area factor increase based on frontage.

To qualify for an area factor increase based on frontage, the public way or open space adjacent to the building perimeter shall have a minimum distance (W) of 20 feet, and only the first 30 feet shall be considered in the calculation. The measurement shall be to the nearest lot line, the entire width of a street, alley or public way, or the exterior face of an adjacent building on the same property.

For purposes of simplifying this calculation only those portions of perimeter fronting right of way or green space with a dimension of 30 feet or more are considered. Those portions of perimeter that front areas that may qualify (are more than 20 feet, but are less than 30 feet) are not included in the frontage calculation.

Frontage Area increase calculation:

$$I_f = [F/P - 0.25]W/30$$

- I_f = area of increase due to frontage
- F = Building perimeter that fronts on a public way or open space
- P = Full building perimeter
- W = Width of public way or open space (max of 30')

For Building D

- F = 528.18'
- P = 528.18'
- W = 30'

$$I_f = [528.18/528.18 - 0.25]30/30 = 0.75 \text{ factor of increase due to frontage}$$


ALLOWABLE BUILDING AREA

Per IBC Table 506.2: Buildings of R-2 occupancy with VB construction type are allowed to have an area of 7,000 square feet per floor. With the area factor increase from above this allowable area per floor is increased as follows:

$$7,000 \text{ s.f.} \times (7,000 \text{ s.f.} \times 0.75) = 12,250 \text{ square feet per floor allowed}$$

Proposed floor area for Building D

- Bsmt: 5,958 s.f.
- Floor 1: 11,633 s.f.
- Floor 2: 11,570 s.f.
- Floor 3: 11,762 s.f.



BUILDING D AREA INCREASE DIAGRAM
1" = 20'



Grade Plane Calculations
Building D

Bradley Heights Apartments
Puyallup, Wa

Timberlane Partners

Revisions		
No.	Date	Description

Initial Publish Date:	
Date Plotted:	2-20-24
Job No.:	23-06
Drawn By:	TMK
Sheet No.:	

A5

IBC SECTION 202 DEFINITIONS

BASEMENT. A STORY THAT IS NOT A STORY ABOVE GRADE PLANE (SEE "STORY ABOVE GRADE PLANE"). THIS DEFINITION OF "BASEMENT" DOES NOT APPLY TO THE PROVISIONS OF SECTION 1612 FOR FLOOD LOADS.

STORY ABOVE GRADE PLANE. ANY STORY HAVING ITS FINISHED FLOOR SURFACE ENTIRELY ABOVE GRADE PLANE, OR IN WHICH THE FINISHED SURFACE OF THE FLOOR NEXT ABOVE IS:

- MORE THAN 6 FEET (1829 MM) ABOVE GRADE PLANE; OR
- MORE THAN 12 FEET (3658 MM) ABOVE THE FINISHED GROUND LEVEL AT ANY POINT

GRADE PLANE. A REFERENCE PLANE REPRESENTING THE AVERAGE OF FINISHED GROUND LEVEL ADJOINING THE BUILDING AT EXTERIOR WALLS, WHERE THE FINISHED GROUND LEVEL SLOPES AWAY FROM THE EXTERIOR WALLS, THE REFERENCE PLANE SHALL BE ESTABLISHED BY THE LOWEST POINTS WITHIN THE AREA BETWEEN THE BUILDING AND THE LOT LINE OR, WHERE THE LOT LINE IS MORE THAN 6 FEET (1829 MM) FROM THE BUILDING, BETWEEN THE BUILDING AND A POINT 6 FEET (1829 MM) FROM THE BUILDING.

BUILDING D

AVERAGE GRADE ELEVATION AT EACH EXTERIOR WALL:

SEGMENT 1:	
POINT A	= 399.20
POINT B	= 393.15
POINT C	= 403.29
POINT D	= 400.43
1596.07/4 = 399.02 AEG	

FIRST FLOOR (FLOOR NEXT ABOVE GRADE PLANE) IS LESS THAN 6 FEET (ACTUAL 4.85 FEET) BELOW FIRST FLOOR FINISHED FLOOR ELEVATION OF 403.87.


SEGMENT 2:	
POINT D	= 400.43
POINT E	= 395.65
POINT F	= 405.79
POINT G	= 403.13
1605/4 = 401.25 AEG	

FIRST FLOOR (FLOOR NEXT ABOVE GRADE PLANE) IS LESS THAN 6 FEET (ACTUAL 5.12 FEET) BELOW FIRST FLOOR FINISHED FLOOR ELEVATION OF 406.37.


SEGMENT 3:	
POINT G	= 403.13
POINT H	= 398.15
POINT I	= 408.29
POINT J	= 402.44
1612.01/4 = 403.00 AEG	

FIRST FLOOR (FLOOR NEXT ABOVE GRADE PLANE) IS LESS THAN 6 FEET (ACTUAL 4.43 FEET) BELOW FIRST FLOOR FINISHED FLOOR ELEVATION OF 408.87.

BUILDING A QUALIFIES AS 3-STORY OVER BASEMENT




BUILDING D AVERAGE GRADE CALCULATIONS
1" = 20'



Provide fire stop detail for plumbing in 1-HR rated wall for all penetration in wall separating units. Wall section #6 unit separation wall does not reflect penetration in rated wall.
Page B5

BUILDING D
1st LEVEL PLAN
1/8" = 1'-0"
3/4 SPLIT LEVEL, 42-UNIT BUILDING




LEGEND


- EXTENT OF 1-HR FIRE PARTITION
- 1-HR FIRE PARTITION SEPARATES THE INTERIOR SPACES BETWEEN UNITS IN THE SAME BUILDINGS. IT'S EXTENT ENDS WHERE ONE SIDE WOULD BE AN EXTERIOR FACE. SEE 4/D1
- EXTENT OF 1-HR FIRE BARRIER AROUND EXIT STAIRS. SEE 3/D1
- EXTENT OF 2-HR FIRE BARRIER AROUND EXIT STAIRS. SEE 7/D1
- EXTENT OF 1-HR EXTERIOR WALL. SEE LOCATION SPECIFIC DETAIL
- FE* - SEMI RECESSED FIRE EXTINGUISHER CABINET/SEE DETAIL 2/D7

BUILDING D
BASEMENT LEVEL PLAN
1/8" = 1'-0"
3/4 SPLIT LEVEL, 42-UNIT BUILDING






BUILDING D 3rd LEVEL PLAN
 1/8" = 1'-0" 3/4 SPLIT LEVEL, 42-UNIT BUILDING




BUILDING D 2nd LEVEL PLAN
 1/8" = 1'-0" 3/4 SPLIT LEVEL, 42-UNIT BUILDING

LEGEND

- EXTENT OF 1-HR FIRE PARTITION
- 1-HR FIRE PARTITION SEPARATES THE INTERIOR SPACES BETWEEN UNITS IN THE SAME BUILDINGS. IT'S EXTENT ENDS WHERE ONE SIDE WOULD BE AN EXTERIOR FACE. SEE 4/D1
- EXTENT OF 1-HR FIRE BARRIER AROUND EXIT STAIRS. SEE 3/D1
- EXTENT OF 2-HR FIRE BARRIER AROUND EXIT STAIRS. SEE 7/D1
- EXTENT OF 1-HR EXTERIOR WALL. SEE LOCATION SPECIFIC DETAIL
- FE* - SEMI RECESSED FIRE EXTINGUISHER CABINET/SEE DETAIL 2/D7






1-BED-INT-1 UNIT TYPE 'A' ACCESSIBLE
BASEMENT & 1st LEVEL FLOOR PLAN

1/4" = 1'-0"

AREA SUMMARY		
Total SF	Heated SF	Patio/Deck SF
61	684	61



1-BED-INT-1 UNIT TYPE 'B' ACCESSIBLE
BASEMENT & 1st LEVEL FLOOR PLAN

1/4" = 1'-0"

AREA SUMMARY		
Total SF	Heated SF	Patio/Deck SF
61	684	61

UNIT PLAN NOTES

- FRAMING:** 2x6'S AT EXTERIOR WALLS
2x4'S AT INTERIOR WALLS
UNLESS NOTED OTHERWISE.
- R-21 BATT INSULATION U.N.O.
- R-13 BATT INSULATION
3/8" ACOUSTICAL INSULATION ONE
SIDE OF PARTYWALL, U.N.O.
- [Pattern] LOCATION OF SOFFIT FOR VENT
RUNS, SOFFIT HEIGHT +8'-0" A.F.F.
U.N.O. ON PLANS; SEE DETAIL 1/D7
- [SD] SMOKE DETECTOR
- [SM] CARBON MONOXIDE/SMOKE DETECTOR
- PROVIDE WATER RESISTANT GYPSUM WALLBOARD
BEHIND TUB AND SHOWER ENCLOSURE MATERIALS TO A
HEIGHT OF 7'-0" MINIMUM ABOVE THE DRAIN INLET.
- NO PLUMBING SHALL BE LOCATED IN THE 1" AIR SPACE OF FIRE
PARTITIONS OR FIRE WALLS.
- ALL BEDROOM AND BATHROOM DOORS SHALL BE UNDERCUT
A MINIMUM OF 1/2" ABOVE THE ADJACENT FLOOR COVERING.
- THE FRONT DOOR SHALL BE OPENABLE FROM THE INSIDE
WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR
EFFORT. IT MAY BE PROVIDED WITH A NIGHT LATCH, DEAD
BOLT OR SECURITY CHAIN, PROVIDED SUCH DEVICES ARE
OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR
TOOL, AND MOUNTED NOT TO EXCEED 48" ABOVE THE
FINISHED FLOOR.

DOOR KEY:

- TYPE: SW = SWING
BF = BIFOLD
BP = BYPASS
- CONSTRUCTION: HCW = HOLLOW CORE WD.
SCW = SOLID CORE WD.
MTL = METAL
HM = HOLLOW METAL

WINDOW KEY:

- TYPE: FIX = FIXED/PICTURE
SL = SLIDER
SH = SINGLE HUNG
SGD = SLIDING GLASS DOOR

ACCESSIBILITY NOTES:

ALL GROUND FLOOR UNITS IN THIS PROJECT MUST
MEET THE ACCESSIBILITY REQUIREMENTS OF
TYPE 'B' ACCESSIBLE UNITS AS REQUIRED
BY CHAPTER 11 OF THE 2018 IBC.

INCLUDED IN THE ABOVE GROUND FLOOR UNITS
5% OF ALL UNITS NEED TO MEET THE ACCESSIBILITY
REQUIREMENTS OF TYPE 'A' ACCESSIBLE UNITS
AS REQUIRED BY CHAPTER 11 OF THE 2018 IBC.
SEE BUILDING PLANS FOR LOCATION OF TYPE 'A' UNITS

SEE SHEET U9 FOR SPECIFIC ADAPTABILITY STANDARD
FOR BOTH TYPE 'A' AND TYPE 'B' ACCESSIBLE UNITS.
SEE INTERIOR ELEVATION SHEETS FOR ADDITIONAL
ACCESSIBILITY REQUIREMENTS.

LIGHTING CONTROLS, ELECTRICAL SWITCHES,
ENVIRONMENTAL CONTROLS, OPERATING HARDWARE
FOR DOORS AND WINDOWS, AND PLUMBING
FIXTURE CONTROLS SHALL BE OPERABLE WITH
ONE HAND AND SHALL NOT REQUIRE TIGHT
GRASPING, PINCHING OR TWISTING OF THE WRIST
TO OPERATE. EXCEPT FOR OPERABLE DOOR
HARDWARE, SUCH ITEMS SHALL BE 15" MINIMUM
AND 44" MAXIMUM ABOVE THE FLOOR (48" FOR
WINDOWS).

INSULATION

FOUNDATION PERIMETER - R-10 RIGID INSULATION
TO A DEPTH OF 24" OR TO TOP OF FOOTING AT
HEATED PERIMETER

EXTERIOR WALLS - FIBERGLASS BATTS OR BLANKETS
2x6 WALLS - R21

FLOORS OVER UNHEATED SPACES - R30

ATTICS AND ROOF ASSEMBLIES - R-49

FULL HEIGHT OF UNCOMPRESSED INSULATION
EXTENDS OVER THE WALL TOP PLATE AT
THE EAVES

EXTERIOR DOORS: MAIN ENTRY U=0.20
ALL OTHERS U=0.40

WINDOWS: MILGARD VINYL U-VALUE
TYPE (VINYL) MODEL 0.24 or BETTER

SLIDING 6110 ARGON/LoE 0.24 or BETTER

FIXED 6310 ARGON/LoE 0.24 or BETTER

SINGLE HUNG 6210 ARGON/LoE 0.24 or BETTER

DBL SLIDER 8125 ARGON/LoE 0.24 or BETTER

SGD 6610 ARGON/LoE 0.24 or BETTER

NOTE: ALL CONCEALED OR EXPOSED INSULATION
SHALL HAVE A FLAME SPREAD INDEX OF NOT
MORE THAN 25 AND A SMOKE-DEVELOPED
INDEX OF NOT MORE THAN 450

CONCEALED SPACES SHALL BE FIRESTOPPED IN BOTH
DIRECTIONS AT 10'-0" ON CENTER AND AT FLOORS. TYPICAL.

ALL ESCAPE OR RESCUE WINDOWS FROM SLEEPING ROOMS
SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE
FEET. THE MINIMUM CLEAR OPENING HEIGHT DIMENSION
SHALL BE 24". MINIMUM CLEAR OPENING WIDTH DIMENSION
SHALL BE 20". EMERGENCY ESCAPE AND RESCUE OPENINGS
SHALL HAVE THE BOTTOM OF CLEAR OPENING NOT GREATER
THAN 44 INCHES MEASURED FROM THE FLOOR.


WHERE THE OPENING OF THE SILL PORTION OF AN OPERABLE
WINDOW IS LOCATED MORE THAN 72 INCHES ABOVE THE
FINISHED GRADE OR OTHER SURFACE BELOW, THE LOWEST
PART OF THE CLEAR OPENING OF THE WINDOW SHALL BE AT
A HEIGHT NOT LESS THAN 36 INCHES ABOVE THE FINISHED
FLOOR SURFACE OF THE ROOM IN WHICH THE WINDOW IS
LOCATED. OPERABLE SECTIONS OF WINDOWS SHALL NOT
PERMIT OPENINGS THAT ALLOW PASSAGE OF A 4 INCH
DIAMETER SPHERE WHERE SUCH OPENINGS ARE LOCATED
WITHIN 36 INCHES OF THE FINISHED FLOOR.

ALL GLAZING SHALL CONFORM TO THE 2018 IBC,
CHAPTER 24, SEC. 2406, SAFETY GLAZING. GLAZING IN ALL
DOORS SHALL BE SAFETY TYPE AND ALL GLAZING WITHIN A
24" ARC OF EITHER VERTICAL EDGE SHALL BE SAFETY TYPE.

PROVIDE 3/8" TYPE 'X' (MIN.) GYPSUM SHEATHING ON WALLS
BEHIND TUB/SHOWERS TO SATISFY FIRE REQUIREMENTS AT
PARTYWALL CONDITION. PROVIDE 3/8" PLYWOOD UNDER TUB
IN PLACE OF THE GYPCRETE, SEE DETAIL 14/D1

1-BED-INT-2 UNIT TYPE 'A' & 'B' ACCESSIBLE
BASEMENT & 1st LEVEL FLOOR PLAN

1/4" = 1'-0"



AREA SUMMARY		
Total SF	Heated SF	Patio/Deck SF
71	684	71

* SEE 1-BED-INT-1 UNIT TYPE 'A' OR
TYPE 'B' FOR REMAINDER OF UNIT

30x48

UNIT PLAN NOTES

- FRAMING:**
- 2x6'S AT EXTERIOR WALLS
 - 2x4'S AT INTERIOR WALLS UNLESS NOTED OTHERWISE.
 - R-21 BATT INSULATION U.N.O.
 - R-13 BATT INSULATION
 - 3/8" ACOUSTICAL INSULATION ONE SIDE OF PARTYWALL, U.N.O.
 - LOCATION OF SOFFIT FOR VENT RUNS. SOFFIT HEIGHT +8'-0" A.F.F. U.N.O. ON PLANS; SEE DETAIL 1/07
 - SMOKE DETECTOR
 - CARBON MONOXIDE/SMOKE DETECTOR

PROVIDE WATER RESISTANT GYPSUM WALLBOARD BEHIND TUB AND SHOWER ENCLOSURE MATERIALS TO A HEIGHT OF 70" MINIMUM ABOVE THE DRAIN INLET.

NO PLUMBING SHALL BE LOCATED IN THE 1" AIR SPACE OF FIRE PARTITIONS OR FIRE WALLS.

ALL BEDROOM AND BATHROOM DOORS SHALL BE UNDERCUT A MINIMUM OF 1/2" ABOVE THE ADJACENT FLOOR COVERING.

THE FRONT DOOR SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT. IT MAY BE PROVIDED WITH A NIGHT LATCH, DEAD BOLT OR SECURITY CHAIN, PROVIDED SUCH DEVICES ARE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR TOOL, AND MOUNTED NOT TO EXCEED 48" ABOVE THE FINISHED FLOOR.

GYPSUM WALLBOARD SCHEDULE
EXCEPT WHERE NOTED OTHERWISE, 5/8" TYPE 'X' GYPSUM WALLBOARD SHALL BE USED THROUGHOUT; ON INTERIOR NON-RATED WALLS, EXTERIOR WALLS, CORRIDOR WALLS, AND 1-HOUR AND 2-HOUR FIRE-RATED WALLS.

DOOR KEY:

TYPE: SW = SWING, BF = BIFOLD, BP = BYPASS

CONSTRUCTION: HCW = HOLLOW CORE WD., SCW = SOLID CORE WD., MTL = METAL, HM = HOLLOW METAL

WINDOW KEY:

TYPE: FIX = FIXED/PICTURE, SL = SLIDER, SH = SINGLE HUNG, SGD = SLIDING GLASS DOOR

ACCESSIBILITY NOTES:

ALL GROUND FLOOR UNITS IN THIS PROJECT MUST MEET THE ACCESSIBILITY REQUIREMENTS OF 'TYPE B' ACCESSIBLE UNITS AS REQUIRED BY CHAPTER 11 OF THE 2018 IBC.

CONCEALED SPACES SHALL BE FIRESTOPPED IN BOTH DIRECTIONS AT 10'-0" ON CENTER AND AT FLOORS. TYPICAL.

ALL ESCAPE OR RESCUE WINDOWS FROM SLEEPING ROOMS SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE FEET. THE MINIMUM CLEAR OPENING HEIGHT DIMENSION SHALL BE 24". MINIMUM CLEAR OPENING WIDTH DIMENSION SHALL BE 20". EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL HAVE THE BOTTOM OF CLEAR OPENING NOT GREATER THAN 44 INCHES MEASURED FROM THE FLOOR.

WHERE THE OPENING OF THE SILL PORTION OF AN OPERABLE WINDOW IS LOCATED MORE THAN 72 INCHES ABOVE THE FINISHED GRADE OR OTHER SURFACE BELOW, THE LOWEST PART OF THE CLEAR OPENING OF THE WINDOW SHALL BE AT A HEIGHT NOT LESS THAN 36 INCHES ABOVE THE FINISHED FLOOR SURFACE OF THE ROOM IN WHICH THE WINDOW IS LOCATED. OPERABLE SECTIONS OF WINDOWS SHALL NOT PERMIT OPENINGS THAT ALLOW PASSAGE OF A 4 INCH DIAMETER SPHERE WHERE SUCH OPENINGS ARE LOCATED WITHIN 36 INCHES OF THE FINISHED FLOOR.

ALL GLAZING SHALL CONFORM TO THE 2018 IBC, CHAPTER 24, SEC. 2406, SAFETY GLAZING. GLAZING IN ALL DOORS SHALL BE SAFETY TYPE AND ALL GLAZING WITHIN A 24" ARC OF EITHER VERTICAL EDGE SHALL BE SAFETY TYPE.

PROVIDE 3/4" TYPE 'X' (MIN.) GYPSUM SHEATHING ON WALLS BEHIND TUB/SHOWERS TO SATISFY FIRE REQUIREMENTS AT PARTYWALL CONDITION. PROVIDE 3/4" PLYWOOD UNDER TUB IN PLACE OF THE GYPCRETE. SEE DETAIL 14/D1

INSULATION

FOUNDATION PERIMETER - R-10 RIGID INSULATION TO A DEPTH OF 24" OR TO TOP OF FOOTING AT HEATED PERIMETER

EXTERIOR WALLS: FIBERGLASS BATTS OR BLANKETS 2x6 WALLS - R21

FLOORS OVER UNHEATED SPACES - R30

ATTICS AND ROOF ASSEMBLIES - R-49

FULL HEIGHT OF UNCOMPRESSED INSULATION EXTENDS OVER THE WALL TOP PLATE AT THE EAVES

EXTERIOR DOORS: MAIN ENTRY U=0.20
ALL OTHERS U=0.40

WINDOWS: MILGARD VINYL

TYPE (VINYL)	MODEL	U-VALUE
SLIDING	6110 ARGON/LoE	0.24 or BETTER
FIXED	6310 ARGON/LoE	0.24 or BETTER
SINGLE HUNG	6210 ARGON/LoE	0.24 or BETTER
DBL. SLIDER	8125 ARGON/LoE	0.24 or BETTER
SGD	6610 ARGON/LoE	0.24 or BETTER


NOTE: ALL CONCEALED OR EXPOSED INSULATION SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE DEVELOPED INDEX OF NOT MORE THAN 450

STANDARD PLATE HEIGHT: 9'-1"

SEE ELEVATION SHEETS FOR FLOOR TO FLOOR HEIGHTS


WINDOW HDR IS 8'-0" UNLESS NOTED OTHERWISE

SEE SHEET U6 FOR INTERIOR ELEVATIONS AND ACCESSIBILITY REQUIREMENTS.




1-BED-INT-ALT-1 ALTERNATE 3rd LEVEL FLOOR PLAN
1/4" = 1'-0"

AREA SUMMARY		
	Heated SF	Deck/Patio SF
Total SF	634	74



1-BED-INT-ALT-2 ALTERNATE 3rd LEVEL FLOOR PLAN
1/4" = 1'-0"


AREA SUMMARY		
	Heated SF	Deck/Patio SF
Total SF	634	86



1-BED-INT-1 UNIT NON-ACCESSIBLE 2nd & 3rd LEVEL FLOOR PLAN
1/4" = 1'-0"

AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	684	61

* Side of exterior walls to which area was measured




1-BED-INT-2 UNIT NON-ACCESSIBLE 2nd & 3rd LEVEL FLOOR PLAN
1/4" = 1'-0"

AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	684	71

* Side of exterior walls to which area was measured




No.	Date	Description
-----	------	-------------



2-BED-ALT UNIT ALTERNATE TYPE 'A' OR 'B' ACCESSIBLE
1st LEVEL FLOOR PLAN

1/4" = 1'-0"


SEE TYPICAL 2-BED UNIT TYPE 'A' ACCESSIBLE FLOOR PLAN OR TYPE 'B' ACCESSIBLE FLOOR PLAN FOR REMAINDER OF UNIT



2 BED UNIT TYPE 'A' ACCESSIBLE
1st LEVEL FLOOR PLAN

1/4" = 1'-0"


AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	1019	66



2-BED UNIT TYPE 'B' ACCESSIBLE
1st LEVEL FLOOR PLAN

1/4" = 1'-0"

AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	1019	66



2-BED-ALT UNIT ALT. 'A' OR 'B' ACCESSIBLE
BASEMENT PLAN

1/4" = 1'-0"

SEE TYPICAL 2-BED UNIT TYPE 'A' ACCESSIBLE FLOOR PLAN OR TYPE 'B' ACCESSIBLE FLOOR PLAN FOR REMAINDER OF UNIT

UNIT PLAN NOTES

- FRAMING:**
- 2x6'S AT EXTERIOR WALLS
 - 2x4'S AT INTERIOR WALLS UNLESS NOTED OTHERWISE.
 - R-21 BATT INSULATION U.N.O.
 - R-13 BATT INSULATION
 - 3/8" ACOUSTICAL INSULATION ONE SIDE OF PARTYWALL, U.N.O.
 - LOCATION OF SOFFIT FOR VENT RUNS, SOFFIT HEIGHT +8'-0" A.F.F. U.N.O. ON PLANS; SEE DETAIL 1/D7
 - SMOKE DETECTOR
 - CARBON MONOXIDE/SMOKE DETECTOR
- CONCEALED SPACES SHALL BE FIRESTOPPED IN BOTH DIRECTIONS AT 10'-0" ON CENTER AND AT FLOORS. TYPICAL.
- ALL ESCAPE OR RESCUE WINDOWS FROM SLEEPING ROOMS SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE FEET. THE MINIMUM CLEAR OPENING HEIGHT DIMENSION SHALL BE 24". MINIMUM CLEAR OPENING WIDTH DIMENSION SHALL BE 20". EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL HAVE THE BOTTOM OF CLEAR OPENING NOT GREATER THAN 44 INCHES MEASURED FROM THE FLOOR.
- WHERE THE OPENING OF THE SILL PORTION OF AN OPERABLE WINDOW IS LOCATED MORE THAN 72 INCHES ABOVE THE FINISHED GRADE OR OTHER SURFACE BELOW, THE LOWEST PART OF THE CLEAR OPENING OF THE WINDOW SHALL BE AT A HEIGHT NOT LESS THAN 36 INCHES ABOVE THE FINISHED FLOOR SURFACE OF THE ROOM IN WHICH THE WINDOW IS LOCATED. OPERABLE SECTIONS OF WINDOWS SHALL NOT PERMIT OPENINGS THAT ALLOW PASSAGE OF A 4 INCH DIAMETER SPHERE WHERE SUCH OPENINGS ARE LOCATED WITHIN 36 INCHES OF THE FINISHED FLOOR.
- ALL GLAZING SHALL CONFORM TO THE 2018 IBC, CHAPTER 24, SEC. 2406, SAFETY GLAZING. GLAZING IN ALL DOORS SHALL BE SAFETY TYPE AND ALL GLAZING WITHIN A 24" ARC OF EITHER VERTICAL EDGE SHALL BE SAFETY TYPE.
- PROVIDE 3/8" TYPE 'X' (MIN.) GYPSUM SHEATHING ON WALLS BEHIND TUB/SHOWERS TO SATISFY FIRE REQUIREMENTS AT PARTYWALL CONDITION. PROVIDE 3/4" PLYWOOD UNDER TUB IN PLACE OF THE GYPCRETE, SEE DETAIL 14/D1

- PROVIDE WATER RESISTANT GYPSUM WALLBOARD BEHIND TUB AND SHOWER ENCLOSURE MATERIALS TO A HEIGHT OF 70" MINIMUM ABOVE THE DRAIN INLET.
- NO PLUMBING SHALL BE LOCATED IN THE 1" AIR SPACE OF FIRE PARTITIONS OR FIRE WALLS.
- ALL BEDROOM AND BATHROOM DOORS SHALL BE UNDERCUT A MINIMUM OF 1/2" ABOVE THE ADJACENT FLOOR COVERING.
- THE FRONT DOOR SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT. IT MAY BE PROVIDED WITH A NIGHT LATCH, DEAD BOLT OR SECURITY CHAIN. PROVIDED SUCH DEVICES ARE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR TOOL, AND MOUNTED NOT TO EXCEED 48" ABOVE THE FINISHED FLOOR.

GYPSUM WALLBOARD SCHEDULE
EXCEPT WHERE NOTED OTHERWISE, 5/8" TYPE 'X' GYPSUM WALLBOARD SHALL BE USED THROUGHOUT.
ON INTERIOR NON-RATED WALLS, EXTERIOR WALLS, CORRIDOR WALLS, AND 1-HOUR AND 2-HOUR FIRE-RATED WALLS.

STANDARD PLATE
HEIGHT: 9'-1"
SEE ELEVATION SHEETS FOR FLOOR TO FLOOR HEIGHTS

WINDOW HDR IS 8'-0"
UNLESS NOTED OTHERWISE

SEE SHEET U8 FOR INTERIOR ELEVATIONS AND ACCESSIBILITY REQUIREMENTS.

DOOR KEY:

- TYPE:**
- SW = SWING
 - BF = BIFOLD
 - BP = BYPASS
- CONSTRUCTION:**
- HCW = HOLLOW CORE WD.
 - SCW = SOLID CORE WD.
 - MTL = METAL
 - HM = HOLLOW METAL

WINDOW KEY:

- TYPE:**
- FIX = FIXED/PICTURE
 - SL = SLIDER
 - SH = SINGLE HUNG
 - SGD = SLIDING GLASS DOOR


INSULATION

- FOUNDATION PERIMETER - R-10 RIGID INSULATION TO A DEPTH OF 24" OR TO TOP OF FOOTING AT HEATED PERIMETER
- EXTERIOR WALLS: FIBERGLASS BATTS OR BLANKETS 2x6 WALLS - R21
- FLOORS OVER UNHEATED SPACES - R30
- ATTICS AND ROOF ASSEMBLIES - R-49
- FULL HEIGHT OF UNCOMPRESSED INSULATION EXTENDS OVER THE WALL TOP PLATE AT THE EAVES
- EXTERIOR DOORS: MAIN ENTRY U=0.20
ALL OTHERS U=0.40
- WINDOWS: MILGARD VINYL
- | TYPE (VINYL) | MODEL | U-VALUE |
|--------------|----------------|----------------|
| SLIDING | 6110 ARGON/LoE | 0.24 or BETTER |
| FIXED | 6310 ARGON/LoE | 0.24 or BETTER |
| SINGLE HUNG | 6210 ARGON/LoE | 0.24 or BETTER |
| DBL. SLIDER | 8125 ARGON/LoE | 0.24 or BETTER |
| SGD | 6610 ARGON/LoE | 0.24 or BETTER |
- NOTE: ALL CONCEALED OR EXPOSED INSULATION SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 450

ACCESSIBILITY NOTES:

- ALL GROUND FLOOR UNITS IN THIS PROJECT MUST MEET THE ACCESSIBILITY REQUIREMENTS OF TYPE 'B' ACCESSIBLE UNITS AS REQUIRED BY CHAPTER 11 OF THE 2018 IBC.
- INCLUDED IN THE ABOVE GROUND FLOOR UNITS 5% OF ALL UNITS NEED TO MEET THE ACCESSIBILITY REQUIREMENTS OF TYPE 'A' ACCESSIBLE UNITS AS REQUIRED BY CHAPTER 11 OF THE 2018 IBC. SEE BUILDING PLANS FOR LOCATION OF 'TYPE A' UNITS
- SEE SHEET U9 FOR SPECIFIC ADAPTABILITY STANDARD FOR BOTH 'TYPE A' AND 'TYPE B' ACCESSIBLE UNITS. SEE INTERIOR ELEVATION SHEETS FOR ADDITIONAL ACCESSIBILITY REQUIREMENTS.
- LIGHTING CONTROLS, ELECTRICAL SWITCHES, ENVIRONMENTAL CONTROLS, OPERATING HARDWARE FOR DOORS AND WINDOWS, AND PLUMBING FIXTURE CONTROLS SHALL BE OPERABLE WITH ONE HAND AND SHALL NOT REQUIRE TIGHT GRASPING, PINCHING OR TWISTING OF THE WRIST TO OPERATE. EXCEPT FOR OPERABLE DOOR HARDWARE, SUCH ITEMS SHALL BE 15" MINIMUM AND 44" MAXIMUM ABOVE THE FLOOR (48" FOR WINDOWS).
- OPERABLE ENTRY DOOR HARDWARE SHALL BE 34" MINIMUM AND 48" MAXIMUM ABOVE THE FLOOR.
- OPENING FORCES FOR ENTRY DOOR SHALL BE: 15 POUNDS TO RELEASE THE LATCH
30 POUNDS TO SET DOOR IN MOTION
15 POUNDS TO OPEN DOOR TO FULL 90° FORCE MEASURED AT LATCH SIDE OF DOOR.
- THE DOOR CLOSER ON THE ENTRY DOOR SHALL BE ADJUSTED TO CLOSE FROM AN OPEN POSITION OF 90° TO AN OPEN POSITION OF 12° IN NOT LESS THAN 5 SECONDS.
- OPENING FORCE OF ALL SWINGING INTERIOR DOORS AND THE SLIDING GLASS DOOR SHALL NOT EXCEED 5 POUNDS APPLIED TO THE LATCH SIDE OF THE DOOR.
- THE FORCE REQUIRED TO ACTIVATE ALL OTHER OPERABLE ITEMS LISTED ABOVE SHALL BE 5 POUNDS.
- *BIFOLD DOOR HARDWARE AT LAUNDRY TO BE 'FULL ACCESS HARDWARE'.
- THE 30"x48" CLEAR FLOOR SPACE IS REQUIRED AT EACH FIXTURE OR LOCATION SHOWN ON THE FLOOR PLAN.






2-BED-ALT UNIT

1/4" = 1'-0"

ALTERNATE 3rd LEVEL FLOOR PLAN

AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	980	60

* Side of exterior walls to which area was measured



2-BED UNIT

1/4" = 1'-0"

NON-ACCESSIBLE 2nd & 3rd LEVEL FLOOR PLAN

AREA SUMMARY		
	Heated SF	Patio/Deck SF
Total SF	1019	66

UNIT PLAN NOTES

- FRAMING: 2x6'S AT EXTERIOR WALLS
2x4'S AT INTERIOR WALLS
UNLESS NOTED OTHERWISE.
- R-21 BATT INSULATION U.N.O.
- R-13 BATT INSULATION
3/8" ACOUSTICAL INSULATION ONE
SIDE OF PARTYWALL, U.N.O.
- [Pattern] LOCATION OF SOFFIT FOR VENT
RUNS. SOFFIT HEIGHT +8'-0" A.F.F.
U.N.O. ON PLANS; SEE DETAIL 1/D7
- [SD] SMOKE DETECTOR
- [SM] CARBON MONOXIDE/SMOKE DETECTOR

PROVIDE WATER RESISTANT GYPSUM WALLBOARD
BEHIND TUB AND SHOWER ENCLOSURE MATERIALS TO A
HEIGHT OF 70" MINIMUM ABOVE THE DRAIN INLET.

NO PLUMBING SHALL BE LOCATED IN THE 1" AIR SPACE OF FIRE
PARTITIONS OR FIRE WALLS.

ALL BEDROOM AND BATHROOM DOORS SHALL BE UNDERCUT
A MINIMUM OF 1/2" ABOVE THE ADJACENT FLOOR COVERING.

THE FRONT DOOR SHALL BE OPENABLE FROM THE INSIDE
WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR
EFFORT. IT MAY BE PROVIDED WITH A NIGHT LATCH, DEAD
BOLT OR SECURITY CHAIN, PROVIDED SUCH DEVICES ARE
OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR
TOOL, AND MOUNTED NOT TO EXCEED 48" ABOVE THE
FINISHED FLOOR.

GYPSUM WALLBOARD SCHEDULE
EXCEPT WHERE NOTED OTHERWISE, 5/8" TYPE 'X' GYPSUM
WALLBOARD SHALL BE USED THROUGHOUT;
ON INTERIOR NON-RATED WALLS, EXTERIOR WALLS,
CORRIDOR WALLS, AND 1-HOUR AND 2-HOUR FIRE-RATED
WALLS.

STANDARD PLATE
HEIGHT: 9'-1"

SEE ELEVATION SHEETS FOR
FLOOR TO FLOOR HEIGHTS

WINDOW HDR IS 8'-0"

UNLESS NOTED OTHERWISE

SEE SHEET U8 FOR INTERIOR ELEVATIONS
AND ACCESSIBILITY REQUIREMENTS.

CONCEALED SPACES SHALL BE FIRESTOPPED IN BOTH
DIRECTIONS AT 10'-0" ON CENTER AND AT FLOORS. TYPICAL.

ALL ESCAPE OR RESCUE WINDOWS FROM SLEEPING ROOMS
SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE
FEET. THE MINIMUM CLEAR OPENING HEIGHT DIMENSION
SHALL BE 24". MINIMUM CLEAR OPENING WIDTH DIMENSION
SHALL BE 20". EMERGENCY ESCAPE AND RESCUE OPENINGS
SHALL HAVE THE BOTTOM OF CLEAR OPENING NOT GREATER
THAN 44 INCHES MEASURED FROM THE FLOOR.

WHERE THE OPENING OF THE SILL PORTION OF AN OPERABLE
WINDOW IS LOCATED MORE THAN 72 INCHES ABOVE THE
FINISHED GRADE OR OTHER SURFACE BELOW, THE LOWEST
PART OF THE CLEAR OPENING OF THE WINDOW SHALL BE AT
A HEIGHT NOT LESS THAN 36 INCHES ABOVE THE FINISHED
FLOOR SURFACE OF THE ROOM IN WHICH THE WINDOW IS
LOCATED. OPERABLE SECTIONS OF WINDOWS SHALL NOT
PERMIT OPENINGS THAT ALLOW PASSAGE OF A 4-INCH
DIAMETER SPHERE WHERE SUCH OPENINGS ARE LOCATED
WITHIN 36 INCHES OF THE FINISHED FLOOR.

ALL GLAZING SHALL CONFORM TO THE 2018 IRC,
CHAPTER 24, SEC. 2406, SAFETY GLAZING. GLAZING IN ALL
DOORS SHALL BE SAFETY TYPE AND ALL GLAZING WITHIN A
24" ARC OF EITHER VERTICAL EDGE SHALL BE SAFETY TYPE.

PROVIDE 3/8" TYPE 'X' (MIN.) GYPSUM SHEATHING ON WALLS
BEHIND TUB/SHOWERS TO SATISFY FIRE REQUIREMENTS AT
PARTYWALL CONDITION. PROVIDE 1/2" PLYWOOD UNDER TUB
IN PLACE OF THE GYPCRETE, SEE DETAIL 14/D1

DOOR KEY:

- TYPE:
SW = SWING
BF = BIFOLD
BP = BYPASS
- CONSTRUCTION:
HCW = HOLLOW CORE WD.
SCW = SOLID CORE WD.
MTL = METAL
HM = HOLLOW METAL

WINDOW KEY:

- TYPE:
FIX = FIXED/PICTURE
SL = SLIDER
SH = SINGLE HUNG
SGD = SLIDING GLASS DOOR

INSULATION

FOUNDATION PERIMETER - R-10 RIGID INSULATION
TO A DEPTH OF 24" OR TO TOP OF FOOTING AT
HEATED PERIMETER

EXTERIOR WALLS: FIBERGLASS BATTS OR BLANKETS
2x6 WALLS - R21

FLOORS OVER UNHEATED SPACES - R30


ATTICS AND ROOF ASSEMBLIES - R-49
FULL HEIGHT OF UNCOMPRESSED INSULATION
EXTENDS OVER THE WALL TOP PLATE AT
THE EAVES.

EXTERIOR DOORS: MAIN ENTRY U=0.20
ALL OTHERS U=0.40

WINDOWS: MILGARD VINYL
TYPE (VINYL) MODEL U-VALUE
SLIDING 6110 ARGON/LoE 0.24 or BETTER
FIXED 6310 ARGON/LoE 0.24 or BETTER
SINGLE HUNG 6210 ARGON/LoE 0.24 or BETTER
DBL SLIDER 8125 ARGON/LoE 0.24 or BETTER
SGD 6610 ARGON/LoE 0.24 or BETTER

NOTE: ALL CONCEALED OR EXPOSED INSULATION
SHALL HAVE A FLAME SPREAD INDEX OF NOT
MORE THAN 25 AND A SMOKE-DEVELOPED
INDEX OF NOT MORE THAN 450







1-BED-UNIT

3/8" = 1'-0"


TYPE 'A'
KITCHEN PLAN



1 KITCHEN



2 KITCHEN





1-BED-UNIT BATHROOM PLAN

3/8" = 1'-0"

TYPE 'A'


3 BATH




1-BED-UNIT

3/8" = 1'-0"


TYPE 'B'
KITCHEN PLAN



1 KITCHEN



2 KITCHEN





1-BED-UNIT BATHROOM PLAN

3/8" = 1'-0"

TYPE 'B'


3 BATH




1-BED-UNIT

3/8" = 1'-0"


NON-ACCESSIBLE
KITCHEN PLAN



1 KITCHEN



2 KITCHEN




1-BED-UNIT NON-ACCESSIBLE BATHROOM PLAN

3/8" = 1'-0"

NON-ACCESSIBLE

3 BATH




*SEE SHEET U9 FOR ACCESSIBILITY STANDARDS

CLEAR FLOOR SPACE LEGEND
TYPE A UNIT

- (A) 60x66 CLEAR FLOOR SPACE AT TOILET.
- (B) 30x60 CLEAR FLOOR SPACE AT TUB.
- (C) 30"x48" CLEAR FLOOR SPACE CENTERED ON SINK
- (D) 60" DIAMETER TURNING CIRCLE OR T-SHAPE TURNING SPACE
- (AA) 30x48 CLEAR FLOOR SPACE AT STOVE.
- (BB) 30x48 CLEAR FLOOR SPACE AT OVEN.
- (CC) 30x48 CLEAR FLOOR SPACE AT SINK.
- (DD) 30x48 CLEAR FLOOR SPACE AT DISHWASHER.
- (EE) 30x48 CLEAR FLOOR SPACE AT REFRIGERATOR.
- (FF) 30x48 CLEAR FLOOR SPACE AT WORK SURFACE.
- (GG) 30x48 CLEAR FLOOR SPACE AT WASHER/DRYER

CLEAR FLOOR SPACE LEGEND
TYPE B UNIT


- (A) 48x56 CLEAR FLOOR SPACE AT TOILET.
- (B) 30x48 CLEAR FLOOR SPACE AT TUB.
- (C) 30"x48" CLEAR FLOOR SPACE CENTERED ON SINK
- (D) 30"x48" CLEAR FLOOR SPACE BEYOND ARC OF DOOR.
- (AA) 30x48 CLEAR FLOOR SPACE AT STOVE.
- (BB) 30x48 CLEAR FLOOR SPACE AT OVEN.
- (CC) 30x48 CLEAR FLOOR SPACE AT SINK.
- (DD) 30x48 CLEAR FLOOR SPACE AT DISHWASHER.
- (EE) 30x48 CLEAR FLOOR SPACE AT REFRIGERATOR.
- (GG) 30x48 CLEAR FLOOR SPACE AT WASHER/DRYER




2-BED UNIT

3/8" = 1'-0"


TYPE 'A'
KITCHEN PLAN



① KITCHEN




② KITCHEN




2-BED UNIT

3/8" = 1'-0"

TYPE 'A'
MAIN BATHROOM PLAN




③ MAIN BATH




2-BED UNIT

3/8" = 1'-0"


TYPE 'B'
KITCHEN PLAN



① KITCHEN




② KITCHEN




2-BED UNIT BATHROOM PLAN

3/8" = 1'-0"

TYPE 'B' ACCESSIBLE UNIT




③ BATH




2-BED UNIT

3/8" = 1'-0"


NON-ACCESSIBLE
KITCHEN PLAN



① KITCHEN




② KITCHEN




2-BED UNIT NON-ACCESSIBLE
BATHROOM PLAN

3/8" = 1'-0"




③ BATH



2-BED UNIT

3/8" = 1'-0"

TYPE 'A' & 'B' & NON-ACCESSIBLE
SECONDARY BATHROOM PLAN



④ SECONDARY

*SEE SHEET U9
FOR
ACCESSIBILITY
STANDARDS

CLEAR FLOOR SPACE LEGEND TYPE A UNIT	
(A)	60x66 CLEAR FLOOR SPACE AT TOILET.
(B)	30x60 CLEAR FLOOR SPACE AT TUB.
(C)	30"x48" CLEAR FLOOR SPACE CENTERED ON SINK
(D)	60" DIAMETER TURNING CIRCLE OR T-SHAPE TURNING SPACE
(AA)	30x48 CLEAR FLOOR SPACE AT STOVE.
(BB)	30x48 CLEAR FLOOR SPACE AT OVEN.
(CC)	30x48 CLEAR FLOOR SPACE AT SINK.
(DD)	30x48 CLEAR FLOOR SPACE AT DISHWASHER.
(EE)	30x48 CLEAR FLOOR SPACE AT REFRIGERATOR.
(FF)	30x48 CLEAR FLOOR SPACE AT WORK SURFACE.
(GG)	30x48 CLEAR FLOOR SPACE AT WASHER/DRYER

CLEAR FLOOR SPACE LEGEND TYPE B UNIT	
(A)	48x56 CLEAR FLOOR SPACE AT TOILET.
(B)	30x48 CLEAR FLOOR SPACE AT TUB.
(C)	30"x48" CLEAR FLOOR SPACE CENTERED ON SINK
(D)	30"x48" CLEAR FLOOR SPACE BEYOND ARC OF DOOR.
(AA)	30x48 CLEAR FLOOR SPACE AT STOVE.
(BB)	30x48 CLEAR FLOOR SPACE AT OVEN.
(CC)	30x48 CLEAR FLOOR SPACE AT SINK.
(DD)	30x48 CLEAR FLOOR SPACE AT DISHWASHER.
(EE)	30x48 CLEAR FLOOR SPACE AT REFRIGERATOR.
(GG)	30x48 CLEAR FLOOR SPACE AT WASHER/DRYER

F:\2306\INTERIOR ELEVATIONS.DWG

NUMBER OF TYPE A UNITS

IN GROUP R-2 OCCUPANCIES CONTAINING MORE THAN 10 DWELLING UNITS OR SLEEPING UNITS AT LEAST 5% BUT NOT LESS THAN ONE OF THE UNITS SHALL BE A TYPE A UNIT. ALL UNITS ON THE SITE SHALL BE CONSIDERED TO DETERMINE THE TOTAL NUMBER OF UNITS AND THE REQUIRED NUMBER OF TYPE A UNITS. EXISTING STRUCTURES ON A SITE SHALL NOT CONTRIBUTE TO THE TOTAL NUMBER OF UNITS ON A SITE. TYPE A UNITS SHALL BE DISPERSED AMONG THE VARIOUS CLASSES OF UNITS. THE NUMBER OF TYPE A UNITS IS PERMITTED TO BE REDUCED IN ACCORDANCE WITH CONDITIONS DEFINED IN SECTION 1107.7 OF THE IBC.

ACCESSIBLE ROUTE

AT LEAST ONE ACCESSIBLE ROUTE SHALL CONNECT ALL SPACES AND ELEMENTS THAT ARE PART OF THE UNIT. ACCESSIBLE ROUTES SHALL CONCLUDE WITH OR BE LOCATED IN THE SAME AREA AS THE GENERAL CIRCULATION PATH. (See detail 5 ACC sheets)

TURNING SPACE & CLEAR FLOOR SPACE

ALL ROOMS SERVED BY AN ACCESSIBLE ROUTE SHALL PROVIDE A TURNING SPACE EXCEPT FOR BATHROOMS THAT ARE NOT REQUIRED TO MEET ACCESSIBILITY STANDARDS, OR CLOSETS OR PANTRIES THAT ARE 48" MAX IN DEPTH. (See detail 1 ACC sheets)

NOTE: BALCONIES AND CORRIDORS ARE NOT ROOMS AND AS SUCH DO NOT NEED TO HAVE A TURNING SPACE

DOORS AND DOORWAYS

THE PRIMARY ENTRANCE DOOR AND ALL DOORS INTENDED FOR USER PASSAGE, SHALL COMPLY WITH SECTION 404. (See detail 6 ACC sheets)

BALCONY DOORS: THRESHOLDS AT EXTERIOR SLIDING DOORS SHALL BE PERMITTED TO BE 3/4" MAX. IN HEIGHT PROVIDED THEY ARE BEVELED WITH A MAX. SLOPE OF 1:2

WHERE EXTERIOR SPACE DIMENSIONS OF BALCONIES ARE LESS THAN THE REQUIRED MANEUVERING CLEARANCE, DOOR MANEUVERING CLEARANCES ARE NOT REQUIRED ON THE EXTERIOR SIDE OF THE DOOR.

BATHROOM DOORS: BATHROOMS NOT REQUIRED TO BE ACCESSIBLE ONLY NEED TO PROVIDE DOOR MANEUVERING CLEARANCE ON THE OUTSIDE OF THE DOOR. BATHROOM DOORS MAY SWING INTO THE BATHROOM AND INTO THE REQUIRED CLEAR FLOOR SPACE AT ANY FIXTURE WHEN A CLEAR FLOOR SPACE OF AT LEAST 30"x48" IS PROVIDED WITHIN THE ROOM BEYOND THE ARC OF THE DOOR SWING.

OPERABLE PARTS
LIGHTING CONTROLS, ELECTRICAL PANELBOARDS, ELECTRICAL SWITCHES & RECEPTACLE OUTLETS, ENVIRONMENTAL CONTROLS, APPLIANCE CONTROLS, OPERATING HARDWARE FOR OPERABLE WINDOWS, PLUMBING FIXTURES CONTROLS, AND USER CONTROLS FOR SECURITY OR INTERCOM SYSTEMS SHALL COMPLY WITH SECTION 309. (See detail 4 ACC sheets)

1. Receptacle outlets serving a dedicated use.
2. Where two or more receptacle outlets are provided in a kitchen above a counter top that is unintercepted by a sink or appliance, one receptacle outlet shall not be required to comply with Section 309.
3. Floor receptacle outlets.
4. HVAC diffusers.
5. Controls mounted on ceiling fans.
6. Where redundant controls other than light switches are provided for a single element, one control shall not be required to be accessible.
7. Reset buttons & shut-offs serving appliances, piping & plumbing fixtures.
8. Electrical panelboards shall not be required to comply with Section 309.4.

WINDOWS
ONLY WINDOWS REQUIRED TO BE OPERABLE FOR NATURAL VENTILATION OR TO PROVIDE AN EMERGENCY ESCAPE AND RESCUE OPENING NEED TO HAVE OPERABLE PARTS COMPLYING WITH SECTION 309. (See detail 4 ACC sheets)


LAUNDRY EQUIPMENT
WASHING MACHINES AND CLOTHES DRYERS SHALL COMPLY WITH SECTION 611. **TOILET AND BATHING FACILITIES** (See detail 20 ACC sheets)
AT LEAST ONE TOILET AND BATHING FACILITY SHALL CONTAIN: ONE LAVATORY, ONE WATER CLOSET AND EITHER A BATHTUB OR SHOWER WITHIN THE UNIT THAT MEETS THE REQUIREMENTS DETAILED FOR TYPE A FIXTURES (See details 23 thru 28 ACC sheets). THE ACCESSIBLE TOILET AND BATHING FIXTURES SHALL BE IN A SINGLE TOILET/BATHING AREA SUCH THAT TRAVEL BETWEEN FIXTURES DOES NOT REQUIRE TRAVEL THROUGH OTHER PARTS OF THE UNIT.
ALL TOILET & BATHING FACILITIES WITHIN A TYPE A UNIT SHALL PROVIDE REINFORCEMENT FOR THE FUTURE INSTALLATION OF GRAB BARS AT WATER CLOSETS, BATHTUBS AND SHOWER SEATS. REINFORCEMENT IS NOT REQUIRED IN ANY OTHER PURPOSES ONLY A LAVATORY AND A WATER CLOSET, PROVIDED THE ROOM DOES NOT CONTAIN THE ONLY LAVATORY OR WATER CLOSET ON THE ACCESSIBLE LEVEL OF THE DWELLING UNIT.

VISIBLE NOTIFICATION APPLIANCES
ACCESSIBLE AUDIBLE AND VISIBLE ALARMS AND NOTIFICATION APPLIANCES SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 72 LISTED IN SECTION 105.2.2. BE POWERED BY A COMMERCIAL LIGHT AND POWER SOURCE, BE PERMANENTLY CONNECTED TO THE WIRING OF THE PREMISES ELECTRIC SYSTEM, AND BE PERMANENTLY INSTALLED.
1. The interconnection of the building fire alarm system with the unit smoke alarms.
2. Replacement of audible appliances with combination audible/visual appliances.
3. The future extension of the existing wiring from the unit smoke alarm location to required locations for visible appliances.


VISIBLE NOTIFICATION APPLIANCES, WHERE PROVIDED AS PART OF THE UNIT SMOKE DETECTION SYSTEM OR BUILDING FIRE ALARM SYSTEM, SHALL BE ACTIVATED UPON SMOKE DETECTION OR WITH ACTIVATION OF THE BUILDING FIRE ALARM. THE SAME VISIBLE NOTIFICATION APPLIANCE CAN BE USED FOR BOTH SMOKE DETECTION AND FIRE ALARM ACTIVATION, BUT SHALL NOT BE USED FOR ANY OTHER PURPOSES WITHIN THE UNIT.

UNIT PRIMARY ENTRANCE
THE ACCESSIBLE PRIMARY ENTRANCE SHALL BE ON AN ACCESSIBLE ROUTE FROM PUBLIC AND COMMON AREAS.
COMMUNICATION FEATURES SHALL BE PROVIDED AT THE UNIT PRIMARY ENTRANCE. A HARD-WIRED ELECTRIC DOORBELL SHALL BE PROVIDED. A BUTTON OR SWITCH SHALL BE PROVIDED ON THE PUBLIC SIDE OF THE UNIT PRIMARY ENTRANCE.
WHERE A SYSTEM PERMITTING VOICE COMMUNICATION BETWEEN A VISITOR AND THE OCCUPANT OF THE UNIT IS PROVIDED AT A LOCATION OTHER THAN THE UNIT ENTRY DOOR, THE SYSTEM SHALL INCLUDE THE CAPABILITY OF SUPPORTING VOICE AND TTY COMMUNICATION WITHIN THE UNIT INTERFACE.


A MEANS FOR VISUALLY IDENTIFYING A VISITOR WITHOUT OPENING THE UNIT ENTRY DOOR SHALL BE PROVIDED. PEEPHOLES, WHERE USED SHALL PROVIDE A MINIMUM 180-DEGREE RANGE OF VIEW. PEEPHOLES SHALL BE PLACED AT A STANDARD HEIGHT FOR BOTH STANDING PERSONS AND WHEELCHAIR USERS. (See detail 32 ACC sheets)



23 GENERAL TYPE A UNIT NOTES




24 LAVATORY




25 WATER CLOSET




26 BATHTUB & TUB / SHOWER COMBO




32 TYPICAL ACCESSORY & FIXTURE MOUNTING HEIGHTS




33 SHOWER COMPARTMENTS



27 SHOWER COMPARTMENTS



28 KITCHENS & KITCHENETTES



31 KITCHENS AND KITCHENETTES

NUMBER OF TYPE B UNITS

IN GROUP R-2 OCCUPANCIES WHERE THERE ARE 4 OR MORE DWELLING UNITS OR SLEEPING UNITS INTENDED TO BE OCCUPIED AS A RESIDENCE IN A SINGLE STRUCTURE, EVERY DWELLING UNIT AND SLEEPING UNIT SHALL BE A TYPE B UNIT. THE NUMBER OF TYPE B UNITS IS PERMITTED TO BE REDUCED IN ACCORDANCE WITH CONDITIONS DEFINED IN SECTION 1107.7 OF THE IBC. THIS REDUCTION OF TYPE B UNITS IS TYPICALLY FOR UNITS THAT ARE ON UPPER STORIES OF A MULTISTORY BUILDING WITHOUT ELEVATOR SERVICE OR MULTI-STORY DWELLING UNITS (SEE IBC FOR SPECIFIC CONDITIONS ALLOWING REDUCTION OF TYPE B UNITS).

UNIT PRIMARY ENTRANCE

SAME REQUIREMENTS AS FOR TYPE A UNITS EXCEPT THAT ONLY A SINGLE PEEP-HOLE NEED BE PROVIDED AT A STANDARD HEIGHT FOR STANDING PERSONS.

ACCESSIBLE ROUTE

SAME REQUIREMENTS AS FOR TYPE A UNITS EXCEPT YOU ARE PERMITTED TO HAVE ONE OF THE FOLLOWING: A RAISED / SUNKEN FLOOR AREA IN A LIVING, DINING OR SLEEPING ROOM OR IN A MEZZANINE THAT IS NOT ENCLOSED AND DOES NOT HAVE PLUMBING FIXTURES.

CHANGES IN LEVEL

SAME REQUIREMENTS AS FOR TYPE A UNITS EXCEPT WHERE EXTERIOR DECK, PATIO OR BALCONY SURFACE MATERIALS ARE IMPERVIOUS, THE THRESHOLD SHALL BE 4" MAX. BELOW THE INTERIOR FLOOR LEVEL.

DOORS


SAME REQUIREMENTS AS FOR TYPE A UNITS EXCEPT DOORS INTENDED FOR USER PASSAGE SHALL HAVE A CLEAR OPENING WIDTH OF 31 3/4" MIN. MEASURED BETWEEN THE FACE OF THE DOOR & THE STOP WITH THE DOOR OPENED 90°.

BATHROOM DOORS: BATHROOM DOORS MAY SWING INTO THE REQUIRED CLEAR FLOOR SPACE AT ANY FIXTURE WHEN A CLEAR FLOOR SPACE OF AT LEAST 30"x48" IS PROVIDED WITHIN THE ROOM BEYOND THE ARC OF THE DOOR SWING.


29 GENERAL TYPE B UNIT NOTES

WITH TOILET AND BATHING AREAS WITHIN TYPE B UNITS EITHER ALL TOILET AND BATHING AREAS PROVIDED SHALL COMPLY WITH OPTION A OR ONE TOILET AND BATHING AREA SHALL COMPLY WITH OPTION B.

EVERY FIXTURE PROVIDED IN ALL TOILET AND BATHING AREAS SHALL COMPLY WITH THE REQUIREMENTS LISTED. ONE OF EACH TYPE OF FIXTURE PROVIDED SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS AND BE LOCATED IN A SINGLE TOILET/BATHING AREA.



29 GENERAL TYPE B UNIT NOTES



30 TYPE B - TOILET & BATHING FIXTURES

MINIMUM CLEARANCES
CLEARANCE BETWEEN ALL OPPOSING BASE CABINETS, COUNTER TOPS, APPLIANCES, OR WALLS WITHIN KITCHEN WORK AREAS SHALL BE 40" MIN. OR 60" MIN. AT U-SHAPED KITCHENS. SEE MINIMUM CLEARANCE DIAGRAMS FOR TYPE A UNITS (Detail 28 ACC sheets).

APPLIANCES

SINK: A CLEAR FLOOR SPACE OF 30"x48" POSITIONED FOR A PARALLEL APPROACH SHALL BE PROVIDED CENTERED ON THE SINK BOWL. NOTE: ON A MULTI-BOWL SINK THE CLEAR FLOOR SPACE SHALL BE CENTERED ON THE WHOLE SINK PLUMBING FIXTURE.

DISHWASHER: A CLEAR FLOOR SPACE SHALL BE POSITIONED ADJACENT TO THE DISHWASHER DOOR SUCH THAT THE DOOR IN THE OPEN POSITION DOES NOT OBSTRUCT THE CLEAR FLOOR SPACE.


COOKTOP: A CLEAR FLOOR SPACE SHALL BE PROVIDED FOR A PARALLEL APPROACH CENTERED ON THE APPLIANCE.

31 KITCHENS AND KITCHENETTES


31 KITCHENS AND KITCHENETTES

TYPE B DWELLING UNITS


CHAPTER 10 SECTION 1004




STAIR 2 3RD LEVEL FLOOR PLAN
1/4" = 1'-0"



STAIR 2 2ND LEVEL FLOOR PLAN
1/4" = 1'-0"



STAIR 2 1ST LEVEL FLOOR PLAN
1/4" = 1'-0"



STAIR 2 BASEMENT LEVEL PLAN
1/4" = 1'-0"



Building D
Partial Architectural Foundation Plan


Bradley Heights Apartments
Puyallup, Wa

Timberlane Partners

Revisions

No.	Date	Description

Initial Publish Date:
Date Plotted: **2-20-24**
Job No.: **23-06** Drawn By: **APT/HDM/TMK**
Sheet No.:




FOUNDATION NOTES

- LOCATION OF DOWNSPOUT: PROVIDE TIGHT LINE AND RISER BOOT
- ELEVATION AT TOP OF CONCRETE (TOP OF FOOTING MAY VARY BECAUSE OF EXCAVATION)
- FINISH SLAB ELEVATION
- R-10 RIGID PERIMETER INSULATION

BUILDING D PARTIAL FOUNDATION PLAN
1/4" = 1'-0"
3/4 SPLIT LEVEL, 42-UNIT BUILDING

SEE S2.6 FOR STRUCTURAL FOUNDATION PLAN

PT 2306 BUILDING D.DWG




BUILDING D PARTIAL FOUNDATION PLAN
 1/4" = 1'-0"
 3/4 SPLIT LEVEL, 42-UNIT BUILDING

SEE S2.6 FOR STRUCTURAL FOUNDATION PLAN

25 Central Way, Suite 210
 Kirkland, Washington 98033
 P: 425.454.7130 F: 425.658.1208
 Web: www.milbrandtarch.com

© Copyright 2023
 Milbrandt Architects, Inc., P.S.
 All rights reserved



Building D
 Partial Architectural Foundation Plan

Bradley Heights Apartments


Puyallup, Wa

Timberlane Partners

Revisions

No. Date Description

Initial Publish Date:
 Date Plotted: 2-20-24
 Job No.: 23-06
 Drawn By: APT/HDM/TMK
 Sheet No.:




BUILDING D
ROOF PLAN
1/8" = 1'-0"

Area Description	Attic Area (SF)	Venting Ratio	Required Venting (SI)	ROOF VENTING CALCULATIONS					Venting Provided (SI)				Total	% of req'd
				Low Eave Vent (LF)	Low Jacks (Qty)	High Jacks (Qty)	Vented Soffit (SF)	Ridge Vent (LF)	Lower	%	Upper	%		
AREA 1	2,160	1/300	1,037	20	8	0	58	64	790	51%	768	49%	1,558	150%
AREA 2	1,448	1/300	695	40	3	4	63	24	618	56%	488	44%	1,106	159%
AREA 3	1,435	1/300	689	32	3	5	53	20	540	52%	490	48%	1,030	150%
STAIR	462	1/150	444	0	0	0	124	5	732	92%	60	8%	792	179%


ROOF LEGEND	
[Symbol]	ROOF JACK 50 SQ.IN. NET FREE AREA
[Symbol]	4:12 SLOPE INDICATOR U.N.O.
[Symbol]	6:12 SLOPE INDICATOR U.N.O.
[Symbol]	BUILDING OUTLINE
[Symbol]	EAVE VENTING 2.4 SQ.IN./LF. NET FREE AREA
[Symbol]	RIDGE VENTING 12 SQ.IN./LF. NET FREE AREA
[Symbol]	UNIT SEPARATION AND DRAFT STOPPING LOCATIONS AT ATTIC
[Symbol]	GUTTER (DOUBLE LINE)
[Symbol]	DOWNSPOUT LOCATION
[Symbol]	VENTED FIBER CEMENT SOFFIT 5.9 SQ.IN./LF. NET FREE AREA

P:\2306\BUILDING D.DWG




BUILDING D FRONT ELEVATION
1/8" = 1'-0"

WINDOW HEADER
HEIGHT 8' A.F.F. U.N.O.



BUILDING D REAR ELEVATION
1/8" = 1'-0"



Building D
Exterior Elevations

Bradley Heights Apartments

Puyallup, Wa


Timberlane Partners

Revisions
No. Date Description


Initial Publish Date:
Date Plotted: 2-20-24

Job No.: 23-06
Drawn By: APT/HDM/TMK


Sheet No.:




BUILDING D SECTION D
1/8" = 1'-0"




BUILDING D SIDE ELEVATION
1/8" = 1'-0"




BUILDING D SIDE ELEVATION
1/8" = 1'-0"



BUILDING D SECTION A
1/8" = 1'-0"



BUILDING D SECTION B
1/8" = 1'-0"



BUILDING D SECTION C
1/8" = 1'-0"

STRUCTURAL NOTES-TABLES

Special Inspection required per Chapter 17 of the 2018 IBC - SUBMIT REPORTS TO INSPECTORS WITH THE CITY OF PUYALLUP

WIND PRESSURE TABLE FOR COMPONENTS & CLADDING (ASD)						
ROOF SURFACES ¹						
EFFECTIVE WIND AREA	POSITIVE PRESSURE (PSF)			NEGATIVE PRESSURE (PSF)		
	ZONE ²					
	1	2	3	1	2	3
10 SF	7.80	7.80	7.80	-12.39	-21.56	-31.89
20 SF	7.04	7.04	7.04	-12.01	-19.65	-29.59
50 SF	6.27	6.27	6.27	-11.62	-17.74	-27.30
100 SF	5.51	5.51	5.51	-11.24	-15.83	-25.01
500 SF	5.51	5.51	5.51	-11.24	-15.83	-25.01

WALL SURFACES						
EFFECTIVE WIND AREA	POSITIVE PRESSURE (PSF)			NEGATIVE PRESSURE (PSF)		
	ZONE ²					
	4	5	4	5	4	5
10 SF	12.18	12.18	-13.21	-16.31	-13.21	-16.31
20 SF	11.56	11.56	-12.59	-15.07	-12.59	-15.07
50 SF	10.94	10.94	-11.98	-13.83	-11.98	-13.83
100 SF	10.32	10.32	-11.36	-12.57	-11.36	-12.57
500 SF	9.08	9.08	-10.12	-11.36	-10.12	-11.36

1. NET WIND PRESSURES AT ROOF SURFACES = VALUE FROM TABLE ABOVE +2/3 DEAD LOAD (DEAD LOAD REDUCES NEGATIVE PRESSURE + ADDS TO POSITIVE PRESSURES)
 2. ZONES ARE DEFINED BY FIGURE 30.6-1 ASCE/SEI 07-10 FOR ROOF AND WALL ELEMENTS

2018 International Building Code – Statement of Special Inspection

MATERIAL/ TYPE INSPECTION	IBC CODE REFERENCE	REFERENCE STANDARD	FREQUENCY APPLICABLE TO THIS PROJECT			SCOPE OF SERVICE
			CONT.	PERIODIC	REQUIRED	
Site Preparation	Table 1705.6 Item 5	-	-	X	N/A	Inspection to determine that the site has been prepared in accordance with the approved soils or geotechnical report.
Prepared Fill – During Fill Preparation	Table 1705.6 Item 4	-	X	-	YES	Inspection to determine that the materials being used and maximum lift thicknesses comply with the approved report as specified in Section 1804.2.
Evaluation of in-place Density	Table 1705.6 Item 3	-	-	X	YES	Tests to determine, at the approved frequency, that the in-place dry density of the compacted fill complies with the approved report.
Footings and Foundations	1805.1 – 1805.9 Table 1705.6 Item 1	-	-	X	YES	Confirm soils suitable for the design allowable soil bearing pressure are present at bearing grade. Confirm the footing dimensions are as specified on the project plans.
Foundation Depth	Table 1705.6 Item 2	-	-	X	YES	Confirm excavation are extended to proper depth and have reached proper materials.

2018 International Building Code – Statement of Special Inspection

MATERIAL/ TYPE INSPECTION	IBC CODE REFERENCE	REFERENCE STANDARD	FREQUENCY APPLICABLE TO THIS PROJECT			SCOPE OF SERVICE
			CONT.	PERIODIC	REQUIRED	
Materials	1705.3.1, Table 1705.3 Item 1	Applicable ASTM material spec.; AISC 360, Section A3.3	-	X	YES	Manufacturer's Certificates of Compliance or Tests per Chapter 3 of ACI 318, per ASTM A 706, and per 1705.3.1
Installation of Reinforcing Steel	1910.4 Table 1705.3 Item 1	ACI 318.3.5; 7.1 – 7.7	-	X	YES	Inspection to confirm compliance with details shown on approved Construction Documents, Shop Drawings, ACI 318 and Code Section 1910.4
Welding of Reinforcing Steel	Table 1705.3 Item 2	AWS D1.4, ACI 318.3.5.2	-	-	N/A	Observation of reinforcing steel welding in accordance with Table 1705.2.2, Item 2, (see attached steel construction table).
Bolt Installation	1908.5, 1901.1 Table 1705.3 Item 3	ACI 318: 8.1.3, 21.2.8	X	-	YES	Observation of anchor bolts to be installed in concrete prior to and during placement of concrete where allowable loads have been increased.
Formwork	Table 1705.3 Item 12	ACI 318.6.1.1	-	X	YES	Inspection for compliance with ACI 318, Section 6.1, 6.2, for shape, location and dimensions of concrete member being formed.
Concrete Strength	1910.10, Table 1705.3 Item 6	ASTM C 172, ASTM C 31, ACI 318.5.6, 5.8	-	X	NO	Evaluation of Concrete strength in accordance with ACI 318, Section 5.6 and in accordance with the requirements of IBC 1905.6.
Concrete Mixes	1904.2, 1910.2, 1910.3 Table 1705.3 Item 5	ACI 318: 4, 5.2-5.4	-	X	YES	Inspection for use of proper mix proportions and techniques, ACI 318, Chapter 4, Sections 5.2 – 5.4.
Concrete Sampling	1910.10 Table 1705.3 Item 6	ASTM C 172, ASTM C 31, ACI 318.5.6, 5.8	X	-	NO	
Concrete Placement	1910.6, 1910.7, 1910.8, Table 1705.3 Item 7	ACI 318.5.9, 5.10	X	-	YES	Inspection for proper application techniques; ACI 318, Sections 5.9 and 5.10
Curing Temperatures and Techniques	1910.9 Table 1705.3 Item 8	ACI 318: 5.11-5.13	-	X	NO	Inspection for maintenance of curing temperatures and techniques; ACI 318, Sections 5.11, 5.12 and 5.13.
Prestressed Concrete: Application Prestressing Forces	Table 1705.3 Item 9a	ACI 318: 18.20, ACI 18.18.4	X	-	NO	Field inspections of precast concrete members in accordance with ACI 318, Section 18.20.
Prestressed Concrete: Grouting of unbonded prestressing tendons in seismic-force-resisting system	Table 1705.3 Item 9b	ACI 318: 18.20, ACI 18.18.4	X	-	NO	Field inspections of precast concrete members in accordance with ACI 318, Chapter 18.18.4.
Manufacture of Precast Concrete	1704.2.1	-	-	X	NO	Certificate from Independent Agency and current agreement for periodic (minimum 6 month intervals) in-plant quality assurance inspections.
Erection of Precast Concrete	Table 1705.3 Item 10	ACI 318: 16	-	X	NO	Field inspections of precast concrete members in accordance with ACI 318, Chapter 16.
Post Tensioning	Table 1705.3 Item 11	ACI 318: 6.2	-	X	NO	Verification of in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms for beams and structural slabs in accordance with ACI 318, Section, 6.2.
Post Installed Anchors	1909.1, Table 1705.3 Item 11	ACI 318: 3.8.6, 8.1.3, 21.1.8	-	X	YES	Verification of anchors post installed in hardened concrete members.

2018 International Building Code – Statement of Special Inspection

MATERIAL/ TYPE INSPECTION	IBC CODE REFERENCE	REFERENCE STANDARD	FREQUENCY APPLICABLE TO THIS PROJECT			SCOPE OF SERVICE
			CONT.	PERIODIC	REQUIRED	
Fabrication – Inspection of Fabricator's Quality Control Procedures	1704.2.5	-	-	X	YES	Certificate from Independent Agency and current agreement for periodic (minimum 6 month intervals) in-plant quality assurance inspections.

2018 International Building Code – Statement of Special Inspection

MATERIAL/ TYPE INSPECTION	IBC CODE REFERENCE	REFERENCE STANDARD	FREQUENCY APPLICABLE TO THIS PROJECT			SCOPE OF SERVICE
			CONT.	PERIODIC	REQUIRED	
Structural Steel	1705.11.1	AISC 341	X	-	N/A	Observation of structural welding in accordance with AISC Seismic. Not required for 5/16" single pass fillet welds or welding of metal deck.
Structural Wood: Inspection of field gluing operations of elements of the seismic force resisting system.	1705.11.2	-	X	-	N/A	Inspection of field gluing operations of elements of the seismic force resisting system.
Structural Wood: Inspection of nailing, bolting, anchoring and other fastening components within the seismic force resisting system, including drag struts, braces and hold-downs.	1705.11.2	-	-	X	YES	Inspection of nailing, bolting, anchoring and other fastening components within the seismic force resisting system, including drag struts, braces and hold-downs. Not required for nailing o.c., spacing greater than 4" o.c.
Cold-formed Steel Framing	1705.11.3	-	-	X	NO	Inspection of welding operations of elements of the seismic force resisting system.
Cold-formed Steel Framing	1705.11.3	-	-	X	NO	Inspection of screw attachments, bolting, anchoring and other fastening components within the seismic force resisting system, including struts, braces and hold-downs.

2018 International Building Code – Statement of Special Inspection

MATERIAL/ TYPE INSPECTION	IBC CODE REFERENCE	REFERENCE STANDARD	FREQUENCY APPLICABLE TO THIS PROJECT			SCOPE OF SERVICE
			CONT.	PERIODIC	REQUIRED	
Structural Observations	1704.5	-	-	X	If required by jurisdiction	Structural observations to be performed to observe general conformance to the construction documents.


Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

PROJECT NO. : 23-007
 DESIGNED BY : TLC, OGG, MRO
 DRAWN BY : RSO
 ISSUE DATE : 2-20-24
 LATEST REV. OF DWG. SET :


SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
 THESE DRAWINGS ARE SUBJECT TO REVISIONS PENDING LOCAL JURISDICTIONAL REVIEW.

S1.1




Puyallup, Washington 98374
Ph. 253-314-9822
www.solutions4structures.com

Solutions 4 Structures
A Structural Engineering Corporation




10 TYPICAL SHEAR WALL ELEVATION

- DIAPHRAGM BOUNDARY NAILING PLYWOOD OR OSB, ONE OR TWO SIDES - SEE SCHEDULE.
- WALL CHORD MEMBER - SEE SHEAR WALL SCHEDULE.
- AT SECOND STORY CONDITION PROVIDE TIES PER PLAN.
- FLOOR JOISTS - SEE PLAN.
- 2x STUDS AT 16" O.C. AT ALL SHEAR WALLS U.N.O.
- SILL PLATE AND ANCHOR BOLTS PER SCHEDULE.
- HOLDOWNS AT SHEAR WALL ENDS AS SHOWN ON PLAN.
- FOOTING SIZE AND REINFORCING PER PLAN & DETAILS.
- DOUBLE STUD OR COLUMN - SEE PLAN.
- OPENING.
- HEADER - SEE PLAN.
- RIM JOIST OR S.O.G. - SEE PLAN, EDGE NAIL DIRECTLY TO P.T. SILL AT S.O.G. LOCATIONS.




7 TYPICAL TOP CHORD SPLICE

NOTE: WHERE PLATE DISCONTINUITIES ARE CREATED BY BEAMS & PIPES, ETC. STRAP W/ (1)-SIMPSON CS16 x 28" W/ (13)-8d NAILS EA END AT EACH PLATE NOT ACHIEVING 4'-0" LAP UNLESS NOTED OTHERWISE.




6 STRAP @ BEAM TO TOP PLATE

NOTE: CS16 MAY BE PLACED ALONG SIDE OF COLLECTOR JOIST AND CONT RIM AT FLOOR CONDITION AT CONTRACTORS OPTION.




3 TYPICAL HORIZONTAL SHEATHING DIAPHRAGM LAYOUT


- NOTES:**
- PROVIDE APA APPROVED GLUE, NAIL ALL SHEATHING TO JOISTS PER GENERAL NOTES ON S1.0.
 - STAGGER PANELS TO OFFSET JOINTS AS SHOWN.
 - WHERE BLOCKED DIAPHRAGM IS REQUIRED, PROVIDE TIMBER BLKG 2x4 FLAT (MIN) BELOW SHEATHING @ UNSUPPORTED EDGES W/ EDGE NAILING OR PROVIDE 3" x 27mil (22GA) x CONT STEEL STRAP W/ #8 SCREWS @ 6" O.C. TO EA UNSUPPORTED PANEL EDGE PER DETAIL 7/S1.3.



9 TYPICAL WALL SHEATHING




8 SPECIAL SHEAR WALL WITH OPENINGS



5 UPPER TO LOWER WALL STRAP/HOLDOWN KEY

MSTC40
MSTC52
MSTC40 FROM 3rd FLOOR WALL TO 2nd FLOOR WALL & MSTC52 2nd FLOOR WALL TO 1st FLOOR WALL
EXAMPLE @ 3RD FLOOR FRAMING PLAN




4 TYPICAL STUD AND SHEAR WALL

- NOTES:**
- MAINTAIN 3/8" MIN EDGE DISTANCE FROM PLYWOOD SHEATHING TO NAILS.
 - EDGE NAILING TO BE APPLIED TO ALL PANEL EDGES.
 - PLACE FACE GRAIN OF PLYWOOD HORIZONTAL.
 - FOR NON-SHEAR CHORD WALLS, USE SINGLE KING STUDS.

MARK	BOUNDARY ELEMENT		TOTAL FASTENERS	ANCHOR DIAMETER	ANCHOR EMBEDMENT	MIN EDGE DISTANCE WITHOUT ADD'L REINF
	2x4 WALL	2x6 WALL				
MST37	4x4 #2 HF	4x6 #2 HF	(20) 16d	N/A	N/A	N/A
MST48	4x4 #2 HF	4x6 #2 HF	(32) 16d	N/A	N/A	N/A
(2)MST48	4x6 #2 HF	6x6 #2 DF	(46) 16d	N/A	N/A	N/A
MST60	4x6 #2 HF	4x6 #2 HF	(64) 16d	N/A	N/A	N/A
(2)MST60	4x6 #2 HF	6x6 #2 DF	PER MFR	N/A	N/A	N/A
HDU2	4x4 #2 HF	4x6 #2 HF	PER MFR	5/8"	8"	4"
HDU4	4x4 #2 HF	4x6 #2 HF	PER MFR	5/8"	8"	4"
HDU5	4x6 #2 HF	4x6 #2 HF	PER MFR	5/8"	8"	8"
HDU8	4x6 #2 DF	6x6 #2 DF	PER MFR	7/8"	12"	8"
HDU11	4x6 #2 DF	6x6 #2 DF	PER MFR	1"	12"	12"
HDU14	4x8 #2 DF	6x6 #2 DF	PER MFR	1"	12"	16"

MARK	MARK ¹⁴	COMPONENTS	1/2" A.B. PL TO CONCRETE SPACING (IN)	5/8" A.B. PL TO CONCRETE SPACING (IN)	10d COMMON PL TO PL SPACING (IN)	SIMPSON A35 CLIP ANGLE SPACING (IN)	SIMPSON LTP4 CLIP ANGLE SPACING (IN)
W2	W2P	7/16" PWD OR OSB, BLOCKED, W/ 8d NAILS @ 4" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD.	32" O.C.	47" O.C.	5.5" O.C.	20" O.C.	20" O.C.
W3	W3P	7/16" PWD OR OSB, BLOCKED, W/ 8d NAILS @ 3" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD. SEE NOTE 2	25" O.C.	36" O.C.	4.3" O.C.	16" O.C.	15" O.C.
W4	W4P	7/16" PWD OR OSB, BLOCKED, W/ 8d NAILS @ 2" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD. SEE NOTE 2	19" O.C.	28" O.C.	6.6" O.C. EA ROW	12" O.C.	12" O.C.
W5	W5P	7/16" PWD OR OSB, BLOCKED, W/ 10d NAILS @ 2" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD. SEE NOTE 2.	16" O.C.	23" O.C.	5.6" O.C. EA ROW	10" O.C.	10" O.C.
W6	W6P	15/32" PWD OR OSB, (2) LAYERS (ONE EACH SIDE), BLOCKED, W/ 10d NAILS @ 3" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD. SEE NOTE 2, 3 & 15	12" O.C.	18" O.C.	4.3" O.C. EA ROW	8" O.C.	8" O.C.
W7	W7P	15/32" PWD OR OSB, (2) LAYERS (ONE EACH SIDE), BLOCKED, W/ 10d NAILS @ 2" O.C. @ PANEL EDGES AND @ 12" O.C. @ FIELD. SEE NOTE 2, 3, & 15	9" O.C.	14" O.C.	3" O.C. EA ROW STAGGERED	5" O.C.	5" O.C.

- NOTES:**
- ALL NAILING PER ANS/AF & PA SDPWS - 2018 TABLE 4.3A
 - USE 3x STUDS AT ALL ABUTTING PANEL EDGES. NAILS SHALL BE STAGGERED WHERE NAILS ARE SPACED AT 2" O.C.
 - IF CALLOUT REQUIRES BLOCKING, SHEATHING MAY BE PLACED WITH THE LONGITUDINAL DIRECTION VERTICAL. STUDS AND PLATES WILL BE CONSIDERED TO ACT AS BLOCKING.
 - WALL SHEATHING CALLED OUT SHALL EXTEND FOR ENTIRE WALL LENGTH AT THAT ELEVATION AND SHALL BE CONTINUOUS AROUND OPENINGS TYPICALLY.
 - 8d NAILS ARE TO BE .131" AND 2-1/2" IN LENGTH. 10d NAILS ARE TO BE .148" AND A MINIMUM OF 3" IN LENGTH. 16d NAILS ARE TO BE .162" AND 3-1/4" IN LENGTH. NAILS SHALL BE INSTALLED SO AS TO NOT SPLIT THE TIMBER FRAMING.
 - SIMPSON A35 OR LTP4 CLIP ANGLES SHALL BE INSTALLED WITH THE APPROPRIATE FASTENERS PER THE MANUFACTURER'S SPECIFICATIONS.
 - USE 3"x3"x0.229" PLATE WASHERS AT ALL ANCHOR BOLTS PER SECTION 4.3.6.4.3
 - SPACING SHOWN ABOVE FOR ANCHOR BOLTS, NAILING AND CLIPS IS MAXIMUM AMOUNT ALLOWED.
 - FRAMING AT SHEARWALLS SHALL BE SPACED NO FARTHER THAN 16" O.C.
 - MINIMUM NAIL SPACING IN A SINGLE ROW SHALL BE 4 INCHES ON CENTER. USE (2) ROWS IF SPACING LESS THAN THIS. USE 2ND RIM BOARD, RIM JOIST OR BLOCKING WHERE THREE ROWS OF NAILING CALLED OUT.
 - EXTEND SHEATHING UP TO DOUBLE TOP PLATES AND INSTALL NAILS THROUGH SHEATHING INTO UPPER TOP PLATE PER TYPICAL DETAILS. NO PLATE TO PLATE NAILING REQUIRED IN DOUBLE TOP PLATES WITH THIS CONFIGURATION.
 - OPTIONAL TO USE (2) 2x's IN PLACE OF SINGLE 3x IN SHEARWALLS W3, W4 AND W5 W/ STITCH NAILING.
 - (2) ROWS OF 0.148" x 3" STITCH NAILING (2)2x STUDS TOGETHER @ 10" O.C. FOR W3 SHW, 8" O.C. FOR W4 SHW & 6" O.C. FOR W5 SHW PER SECTION 4.3.7 NOTE 4.
 - THE "W_P" INDICATES SHEAR WALL TYPE WITH OPENINGS. PROVIDE SHEATHING AROUND ALL OPENINGS AND ABOVE AND BELOW ALL OPENINGS. PROVIDE HORIZONTAL STRAPS & NAILING AT OPENINGS PER 8/S1.2



Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington






















Solutions 4 Structures
A Structural Engineering Corporation

PROJECT NO. : 23-007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS PENDING LOCAL JURISDICTIONAL REVIEW.

S1.2

CAD FILE: F:\Projects\2023\Projects\23.007 Bradley Heights\Drawings\51_3.dwg
 PLOT DATE/TIME: 2/15/2024 - 9:24am THANK YOU FOR USING SOLUTIONS 4 STRUCTURES




Revisions to this sheet:

Bradley Heights Apartments
 202 27th Ave SE
 Puyallup, Washington

SOLUTIONS 4 STRUCTURES
 A Structural Engineering Corporation

PROJECT NO.: 23.007
 DESIGNED BY: TLC, OGG, MRO
 DRAWN BY: RSO
 ISSUE DATE: 2-20-24
 LATEST REV. OF DWG. SET:



SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
 THESE DRAWINGS ARE SUBJECT TO REVISIONS
 PENDING LOCAL JURISDICTIONAL REVIEW.




Foundation / Basement Floor Framing Plan - Bldg D
SCALE 1/8"=1'-0"

SEE SHEET S1.2 FOR
SHEARWALL AND HOLDOWN
TABLES

SEE SHEET S2.10 FOR
FOUNDATION, ROOF & FLOOR
FRAMING NOTES & TABLES



Foundation Plan Basement - Bldg D
SCALE 1/8"=1'-0"



Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

Solutions 4 Structures
A Structural Engineering Corporation


Puyallup, Washington 98374
Ph 253-314-9822
www.solutions4structures.com

PROJECT NO. : 23.007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS PENDING LOCAL JURISDICTIONAL REVIEW.

S2.8



CAD FILE: F:\Projects\2023\007 Bradley Heights\Drawings\S2.9.dwg
PLOT DATE/TIME: 2/15/2024 - 9:35am THANK YOU FOR USING SOLUTIONS 4 STRUCTURES




3rd Floor Framing Plan - Bldg D
SCALE 1/8"=1'-0"

SEE SHEET S1.2 FOR
SHEARWALL AND HOLDOWN
TABLES

SEE SHEET S2.10 FOR
FOUNDATION, ROOF & FLOOR
FRAMING NOTES & TABLES



2nd Floor Framing Plan - Bldg D
SCALE 1/8"=1'-0"



Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

Solutions 4 Structures
A Structural Engineering Corporation

Puyallup, Washington 98374
Ph 253-314-9822
www.solutions4structures.com

PROJECT NO. : 23-007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :


SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS
PENDING LOCAL JURISDICTIONAL REVIEW.

S2.9


CAD FILE: F:\Projects\2023\Projects\23.007 Bradley Heights\Drawings\S2.10.dwg PLOT DATE/TIME: 2/15/2024 - 9:37am THANK YOU FOR USING SOLUTIONS 4 STRUCTURES

Floor & Roof Framing Notes

- ROOF AND FLOOR JOIST LOCATIONS ARE SCHEMATICALLY SHOWN ON THE PLANS. IT IS NOT THE INTENT OF THE STRUCTURAL PLANS TO GRAPHICALLY LOCATE ALL FRAMING MEMBERS. THE ARCHITECT SHALL VERIFY THE COMPATIBILITY OF JOIST LAYOUT AND FRAMING W/ MECHANICAL, ELECTRICAL & PLUMBING AND ARCHITECTURAL PLANS. THE CONTRACTOR IS RESPONSIBLE FOR SPACING FRAMING MEMBERS AS NOTED ON THE PLANS AND GENERATING MEMBER LAYOUT FOR SHOP DRAWINGS AND QUANTITY TAKEOFFS.
- FOR ALL UNIT TYPES SEE WALL STUD SCHEDULE FOR BEARING WALL STUD REQUIREMENTS. ALL OTHER NON-BEARING 2x4 & 2x6 WALLS ARE AT 16" O.C.
- THE TRUSS AND JOIST MANUFACTURER SHALL VERIFY BEARING COMPATIBILITY (CRUSHING) WITH THE PLATE MATERIAL. TYPICALLY, COMPOSITE BEAMS SHALL BE FULLY BEARING ON 2x... WALLS. I.E. BREAK RIM OR BLOCKING TO ALLOW FULL BEARING OVER PLATES.
- PLACE LONG DIRECTION OF ALL OSB SHEETS PERPENDICULAR TO TRUSS/RAFTER OR JOIST DIRECTION. SEE DETAIL 3/S1.2. FLOOR SHEATHING IS TO BE CONTINUOUS FROM UNIT TO UNIT. TYPICAL NAILING AT FLOOR AND ROOF DIAPHRAGMS IS PROVIDED IN THE GENERAL STRUCTURAL NOTES ON SHEETS S1.0.
- Δ DENOTES THE SHEARWALL TYPE. SEE THE SHEARWALL TABLE ON SHEET S1.2. \square INDICATES SHEARWALL LOCATION, THE CALLOUTS ON THE SHEARWALL TABLE APPLY ONLY ALONG THE LENGTH OF WALL SHOWN SHADED. PROVIDE SOLID BLOCKING IN FLOOR SPACE BELOW PERPENDICULAR SHEARWALLS.
- ∇ INDICATES SHEAR WALL TYPE WITH OPENINGS. PROVIDE SHEATHING AROUND ALL OPENINGS AND ABOVE AND BELOW ALL OPENINGS. PROVIDE HORIZONTAL STRAPS & NAILING AT OPENINGS PER 8/S1.2
- THE DOUBLE TOP PLATE IS TO BE CONTINUOUS ALONG ALL EXTERIOR WALLS AND AT ALL WALL LINES CONTAINING SHEARWALLS. TYPICAL WALL TOP PLATE SPLICES SHALL BE PER DETAIL 7/S1.2 TYP.
- WHERE COMPOSITE JOISTS AND BEAMS ARE USED AS DRAG STRUTS THE MANUFACTURER SHALL PROVIDE THE FRAMING MEMBERS WITH THE CAPACITY CALLED OUT ON THE PLANS.
- TYPICAL FLOOR JOISTS SHALL BE 11-7/8" T&I/10 @ 16" O.C. TYP. U.N.O. THE MANUFACTURER SHALL BE RESPONSIBLE FOR ALL JOIST AND BEAM HANGERS, WEB STIFFENERS, SOLID BLOCKING, AND ADDITIONAL RM OR JOIST MATERIAL TO ACCOMMODATE FLUSH-FRAMED CONDITIONS (F.F.), CANTILEVERED CONDITIONS, CONCENTRATED BEARING LOADS AND NAILING FROM SHEARWALLS ABOVE AND BELOW.
- F.F. = FLUSH-FRAMED BEAM. VERIFY FLUSH OR DROPPED BEAM CONDITION PER ARCHITECT.
- ALL BEAMS PER SCHEDULE U.N.O. ALL NON BEARING BEAMS SHALL BE A MIN OF (2)2x8 U.N.O. ALL OTHER BEAMS ARE AS MARKED ON PLANS.



- INDICATES ROOF OVERFRAMING - SEE DETAILS 5/S5.0
- PROVIDE WALL FIREBLOCKING @ DROPPED SOFFITS SHOWN ON ARCH.
- PROVIDE WALL BLOCKING FOR ALL WALL MOUNTED EQUIPMENT (SUCH AS TOWEL BARS, GRAB BARS, TOILET PAPER HOLDERS, DOOR STOPS, ETC.).
- LFA INDICATES - LOAD FROM ABOVE
- FF INDICATES FLUSH FRAMED BEAM
- ∇ INDICATES STRAP HOLDOWN, SEE SHEET 2/S1.2 FOR HOLDOWN TABLE & UPPER TO LOWER WALL STRAP/HOLDOWN KEY.
- REFER TO ARCHITECTURAL DRAWINGS FOR ALL FLOOR ELEVATIONS.
- SIMPSON STRONG THE PRODUCTS ARE CALLED OUT ON THE DRAWINGS. HOWEVER, EITHER SIMPSON OR KC METALS PRODUCTS MAY BE USED PROVIDED IT HAS SAME OR GREATER CAPACITY.



SEE SHEET S1.2 FOR SHEARWALL AND HOLDOWN TABLES

Beam Schedule

MARK	BEAM SIZE
B1	4x8
B2	4x10
B3	6x10 DF #2
B4	3-1/8 x 10-1/2 GLB
B5	P.T. 4x8
B6	P.T. 4x10
B7	P.T. 6x10 HF#1
B8	P.T. 3-1/8 x 10-1/2 GLB
B9	P.T. 5-1/8 x 10-1/2 GLB
B10	5-1/4x11-7/8 PSL
B11	3-1/2x11-7/8 LSL

Jamb Stud Schedule

TYPE	C1	C2	C3	C4	C5	C6	-	-
BEARING/FULL HT STUDS	1/2	1/3	2/1	2/2	2/3	2/4	-	-

NOTE: STUD SIZE SHOULD MATCH WALL SIZE PER PLAN.

Wall Stud Schedule

FRAMING LEVEL	2x6 EXTERIOR	2x6 BRG INT	2x6 BRG INT	2x4 BRG	2x4 BRG
ROOF	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x4 HF#2 @ 16" O.C.	2x4 HF#2 @ 16" O.C.
1ST	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x4 HF#2 @ 16" O.C.	2x4 HF#2 @ 16" O.C.
2ND	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x6 @ 16" O.C.	2x4 HF#2 @ 16" O.C.	2x4 HF#2 @ 16" O.C.
BASEMENT	2x6 @ 16" O.C.	2x6 @ 12" O.C.	2x6 @ 16" O.C.	2x4 HF#2 @ 12" O.C.	2x4 HF#2 @ 16" O.C.


NOTES:

- ALL STUD MATERIAL SHALL BE HEM FIR STUD GRADE OR BETTER UNLESS NOTED OTHERWISE AND PLATE MATERIAL SHALL BE HEM FIR STANDARD OR BETTER UNLESS NOTED OTHERWISE.
- STUDS CALLED OUT IN THIS SCHEDULE ARE FOR WALL SUPPORTING THE FRAMING LEVEL INDICATED, THAT IS WALLS BELOW THE FRAMING LEVEL SHOWN.
- THIS SCHEDULE COVERS BUILDING UNITS 3 STORES IN HEIGHT. FIRST, DETERMINE THE NUMBER OF STORIES FOR THE UNIT. SECOND, DETERMINE THE FRAMING LEVEL. THIRD, READ SCHEDULE HORIZONTALLY FOR THE WALL LOCATION.

Foundation Notes

- TYPICAL DIMENSIONS ARE TO FACE OF WALL OR TO CENTERLINE OF COLUMN OR FOOTING. VERIFY ALL DIMENSIONS & ELEVATIONS WITH THE ARCHITECT.
- PROVIDE FOOTING SUBSTRATE PREPARATION PER THE SOILS REPORT.
- F-- INDICATES ISOLATED FOOTING TYPICAL ISOLATED FTG SHALL BE CONSTRUCTED PER FOOTING SCHEDULE 5/S3.0.
- EXTEND ALL CONTINUOUS FOOTINGS AT END WALLS 1'-0" MIN. BEYOND END OF ALL BEARING WALLS & SHEARWALLS. (TYPICAL) UNO
- ALL EXTERIOR WALLS SHALL HAVE AN 8" STEMWALL AND A 18" WIDE x 8" DEEP FOOTING W/ STEEL REINFORCING 3" CLR. OF SOIL UNLESS NOTED OTHERWISE
- ADD STRIP DRAINS AT FACE OF BUILDINGS WHEN WALKS SLOPE TOWARD BUILDING, CONNECT TO TIGHTLINE.
- PROVIDE #4-24" x 24" CORNER BARS TO MATCH ALL HORIZONTAL REINFORCEMENT IN STEMWALLS AND FOOTINGS. (TYPICAL)
- FLOOR SLABS - 4" CONC. SLAB ON GRADE 6x6 - W/ 2xW1.2 WWF @ CENTER-LINE OR FIBER MESH PER MANUFACTURER OVER SUBSTRATE PER SOILS ENGINEER, USE WWF WHERE INDICATED. PROVIDE CONTROL JOINTS PER DETAIL 15/S3.0 AT THE DIRECTION OF THE ARCHITECT.
- ENTRY SLABS - 4" CONC. SLAB (BROOM FINISH)
- PATIO SLABS - 4" CONC. W/ THICKENED EDGES. SLOPE AWAY FROM BUILDING AT 1/4"/FT. SEE 3/S3.0
- ALL THICKENED SLABS FOR BEARING WALLS AND PARTY WALLS SHALL BE 18" WIDE x 12" DEEP W/ (2) #4 BARS CONTINUOUS UNLESS NOTED OTHERWISE. DEEPEN LOCALLY AT HOLDOWNS TO OBTAIN EMBEDMENT DEPTH +3" MIN.
- ALL THICKENED EDGE SLABS SHALL BE 8" WIDE x 8" DEEP W/ (1) #4 BAR CONTINUOUS (3" FROM BOTTOM) UNLESS NOTED OTHERWISE. SEE 3/S3.0.
- Δ DENOTES THE SHEARWALL TYPE. SEE THE SHEARWALL TABLE ON SHEET S1.2. \square INDICATES SHEARWALL LOCATION, THE CALLOUTS ON THE SHEARWALL TABLE APPLY ONLY ALONG THE LENGTH OF WALL SHOWN SHADED. PROVIDE SOLID BLOCKING IN FLOOR SPACE BELOW PERPENDICULAR SHEARWALLS.
- ∇ INDICATES SHEAR WALL TYPE WITH OPENINGS. PROVIDE SHEATHING AROUND ALL OPENINGS AND ABOVE AND BELOW ALL OPENINGS. PROVIDE HORIZONTAL STRAPS & NAILING AT OPENINGS PER 8/S1.2
- ∇ INDICATES HOLDOWN, SEE 2/S1.2 FOR HOLDOWN TABLE & UPPER TO LOWER WALL STRAPS HOLDOWN/KEY.
- VERIFY ALL TOP OF SLAB ELEVATIONS AND BUILDING STEPS WITH ARCH/CIVIL PLANS TYPICAL.

Revisions to this sheet:




Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

Solutions 4 Structures
A Structural Engineering Corporation

Puyallup, Washington 98374
Ph 253-314-9822
www.solutions4structures.com





















PROJECT NO. : 23-007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS PENDING LOCAL JURISDICTIONAL REVIEW.



Roof Framing Plan - Bldg D
SCALE 1/8"=1'-0"

CAD FILE: F:\Projects\2023 Projects\3.007 Bradley Heights\Drawings\S3.0.dwg
 PLOT DATE/TIME: 2/15/2024 - 9:46am THANK YOU FOR USING SOLUTIONS 4 STRUCTURES



Bradley Heights Apartments
 202 27th Ave SE
 Puyallup, Washington


Solutions 4 Structures
 A Structural Engineering Corporation

PROJECT NO. : 23-007
 DESIGNED BY : TLC, OGG, MRO
 DRAWN BY : RSO
 ISSUE DATE : 2-20-24
 LATEST REV. OF DWG. SET :


SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
 THESE DRAWINGS ARE SUBJECT TO REVISIONS
 PENDING LOCAL JURISDICTIONAL REVIEW.

Puyallup, Washington 98374
 Ph. 253-314-9822
 www.solutions4structures.com


S3.0




10 JOISTS TO RETAINING WALL




7 TOP OF RETAINING WALL




9 TYP HOLDOWN AT FDN INTERSECTION




6 INTERIOR FOOTING AT GRADE BEAM AT BREEZEWAY'S




8 GRADE BEAM TO RET WALL




5 TYPICAL GRADE BEAM




4 GRADE BEAM AT BASEMENT WALL



11 STEP PERPENDICULAR FOOTING/WALL BEHIND RETAINING WALL



3 PARTIAL HT BASEMENT RETAINING WALL




2 FULL HT BASEMENT WALL

DESIGN PARAMETERS

1. SOIL BEARING = 2,000 PSF
2. ACTIVE & AT REST FLUID PRESSURES PER DIAGRAM
3. PASSIVE FLUID PRESSURE = 450 PCF
4. 20 PSF (MAX) LIVE LOAD SURCHARGE, HORIZ.
5. 12"H PSF (MAX) SEISMIC SURCHARGE, HORIZ.
6. SOIL FRICTION COEF. = 0.53
7. SOIL UNIT WEIGHT = 120 PCF (MIN)

NOTES


1. PROVIDE CORNER STEEL @ FTG CORNERS & INTERSECTIONS. USE 36"x36" ELBOW STEEL TO LAP HORIZ REINF, MATCH SIZE.
2. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND HEIGHTS PRIOR TO CONSTRUCTION. NOTIFY ENGR/OWNER OF ANY DISCREPANCIES.
3. REINFORCEMENT GRADES SHALL TYPICALLY BE : GRADE 60
4. CONCRETE STRENGTH SHALL BE A MINIMUM OF 2500 PSI PRIOR TO BACKFILL.



WALL HEIGHT MAX	FOOTING DIMENSIONS				"T" THKNS	BAR "A"		BAR "B"	
	TOE	STEM	HEEL	TOTAL		SIZE & SPACING	VERT LEG	HORIZ LEG	SIZE & SPACING
10'-0"	2'-8"	8"	1'-8"	5'-0"	14"	#5 @ 10" O.C.	5'-6"	2'-10"	#4 @ 10" O.C.
8'-0"	2'-0"	8"	1'-4"	4'-0"	12"	#5 @ 12" O.C.	4'-6"	2'-2"	#4 @ 12" O.C.
6'-0"	1'-4"	8"	1'-0"	3'-0"	12"	#4 @ 12" O.C.	FULL HT	1'-6"	#4 @ 12" O.C.
4'-0"	0'-8"	8"	0'-8"	2'-0"	10"	#4 @ 16" O.C.	FULL HT	0'-10"	#4 @ 16" O.C.

1 STEPPED BASEMENT WALL SCHEDULE

Revisions to this sheet:



Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

Solutions 4 Structures
A Structural Engineering Corporation





















PROJECT NO. : 23.007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS
PENDING LOCAL JURISDICTIONAL REVIEW.

S3.1

CAD FILE: F:\Projects\2023\Projects\23.007 Bradley Heights\Drawings\S4.0.dwg

PLOT DATE/TIME: 2/15/2024 - 9:49am THANK YOU FOR USING SOLUTIONS 4 STRUCTURES



Revisions to this sheet:


Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington

Solutions 4 Structures
A Structural Engineering Corporation

PROJECT NO. : 23.007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS PENDING LOCAL JURISDICTIONAL REVIEW.

S4.0



THOMAS L. CHASE, PE
MARTIN R. OMAN, PE, SE
OLEG G. KONDRATYUK, PE

Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington


Puyallup, Washington 98374
Ph. 253-314-9822
www.solutions4structures.com

Solutions 4 Structures
A Structural Engineering Corporation


PROJECT NO. : 23.007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS
PENDING LOCAL JURISDICTIONAL REVIEW.


S4.1




7 PARTY WALL NON-BEARING EA SIDE (W1, W2 SHEAR TRANSFER)




4 PARTY WALL NON-BEARING EA SIDE (W1, W2 SHEAR TRANSFER)




5 EXT. DECK/STAIR LANDING CONNECTION




6 EXT. DECK/STAIR LANDING CONNECTION




1 EXT. DECK/STAIR LANDING CONNECTION




2 EXT. DECK/STAIR LANDING CONNECTION




3 DECK OUTSIDE EDGE




18 SHEAR TRANSFER @ GIRDER TRUSS




17 SHEAR TRANSFER @ GIRDER TRUSS




16 OPEN GABLE END CONNECTION




14 ROOF SHEAR TRANSFER @ STEPPED PARTYWALL




13 SHEAR TRANSFER @ ROOF PARTY WALL




12 SHEAR TRANSFER AT STEP IN ROOF




10 ROOF SHEAR TRANSFER TO PARTY WALL @ RIDGE




9 SHEAR TRANSFER AT PARTY WALL




8 DRAG TRUSS TO STRAP @ SHEARWALL TOP PLATE




7 ROOF SHEAR TRANSFER W/ TRUSSES PERPENDICULAR




6 GIRDER TRUSS TO WALL CONNECTION




5 TYP CONNECTION @ OVERFRAMING




15 P.E. TRUSS TO WALL




11 SHEAR TRANSFER AT SINGLE SHEAR WALL WITH STEP IN ROOF




4 2x BRACE TO ROOF CONNECTION




3 TYPICAL GABLE END CONNECTION



2 SHEAR TRANSFER @ INTERIOR W/ ALIGNED TRUSS



1 TYPICAL EXT. WALL PERP. TO TRUSS



THOMAS L. CHASE, PE
MARTIN R. OMAN, PE, SE
OLEG G. KONDRATYUK, PE

Revisions to this sheet:

Bradley Heights Apartments
202 27th Ave SE
Puyallup, Washington


Solutions 4 Structures
A Structural Engineering Corporation

Puyallup, Washington 98374
Ph: 253-314-9822
www.solutions4structures.com

PROJECT NO. : 23.007
DESIGNED BY : TLC, OGG, MRO
DRAWN BY : RSO
ISSUE DATE : 2-20-24
LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
THESE DRAWINGS ARE SUBJECT TO REVISIONS
PENDING LOCAL JURISDICTIONAL REVIEW.

S5.0



2-20-24
 THOMAS L. CHASE, PE
 MARTIN R. OMAN, PE, SE
 OLEG G. KONDRATYUK, PE

Revisions to this sheet:

Bradley Heights Apartments
 202 27th Ave SE
 Puyallup, Washington







Puyallup, Washington 98374
 Ph 253-314-9822
 www.solutions4structures.com


Solutions 4 Structures
 A Structural Engineering Corporation

PROJECT NO. : 23.007
 DESIGNED BY : TLC, OGG, MRO
 DRAWN BY : RSO
 ISSUE DATE : 2-20-24
 LATEST REV. OF DWG. SET :

SUBMITTAL SET ONLY NOT FOR CONSTRUCTION
 THESE DRAWINGS ARE SUBJECT TO REVISIONS
 PENDING LOCAL JURISDICTIONAL REVIEW.

S5.1






1-HR GA File No. RC 2602
 Base layer 5/8\" type X gypsum wallboard applied at right angles to wood roof trusses 24\" o.c. with 1/2\" Type W or S drywall screws 24\" o.c. Face layer 5/8\" type X gypsum wallboard or gypsum veneer base applied at right angles to trusses with 1/2\" Type W or S drywall screws 12\" o.c. at joints and intermediate trusses and 1/2\" Type G drywall screws 12\" o.c. placed 2\" back on either side of end joints. Joints offset 24\" from base layer joints. Wood trusses supporting 5/8\" wood structural panels applied at right angles to trusses with 8d nails. Appropriate roof covering. Ceiling provides one hour fire resistance protection for trusses.

17 TYPICAL 1-HR ROOF/CEILING SECTION
 1-1/2\" = 1'-0\"


1-HR ESR-1153 Assembly B, Sound Rating Option 2

- The flooring must consist of a single layer of 3/4\" span-rated, T&G, sheathing (Exposure 1). Construction adhesive conforming to ASTM D3498 must be applied to the top or the joists prior to placing sheathing. All butt joints of the sheathing must be located over framing members.
- TJI joists must be installed with a maximum spacing of 24\" o.c. for floor-ceiling assemblies.
- Optional minimum 3/2\" glass fiber insulation or glass fiber insulation rated R-30 or less may be installed in the joist plenum when resilient channels are used. The insulation must be placed above the resilient channels between the joist bottom flanges.
- Ceiling membrane shall be two layers of same-type gypsum board, either: 1/2\" USG Firecode \"C\", 1/2\" NGC Gold Bond Fire-Shield \"C\", or 5/8\" type \"X\" complying with ASTM C36.
- The first layer of gypsum board must be installed perpendicular to the TJI joist and attached using 1\" long, Type S screws spaced 12\" o.c. The second layer must be installed with the joints staggered from the first layer. The second layer must be fastened to the TJI joists with 2\" long, Type S screws spaced 12\" o.c. in the field and 8\" o.c. at the butt joints. Type G screws, 1 1/2\" long, must be spaced 8\" o.c. and 6\" from each side of the transverse joints of the second layer. The second layer must be finished with joint tape and compound.
- Resilient channels are required to be used as part of the ceiling attachment system, provided they are spaced 16\" o.c. and fastened perpendicular to the TJI joists using 1\" long, Type S screws spaced 12\" o.c. When resilient channels are used, the first layer of the ceiling membrane must be installed perpendicular to the channels and attached to the resilient channels using 1\" long, Type S screws spaced 12\" o.c. The second layer must be installed with the joints staggered from the first layer and attached using 3/4\" long, Type S screws. The screw spacing for the second layer of gypsum board must be a maximum of 12\" o.c. in the field and 8\" o.c. at the butt joints. Type G screws, 1 1/2\" long, must be spaced 8\" o.c. and 6\" from each side of the transverse joints of the second layer, the second layer must be finished with joint tape and compound.




STC = 58 per ICC-ES Evaluation Report IIC = 54 With Carpet & Pad

13 TYP. 1-HR FLOOR/CEILING AT DWELLING UNITS SECTION
 1-1/2\" = 1'-0\"




14 FLOOR BENEATH TUB SECTION
 1 1/2\" = 1'-0\"




ASSEMBLY ALLOWED TO BE NON-RATED PER OSSC SECTIONS 705.2.2 AND 705.2.3 WITH FIRE SPRINKLERS PROTECTING DECK


19 FLOOR AT DECK SECTION
 1 1/2\" = 1'-0\"




15 FLOOR AT CORRIDOR/LANDING SECTION
 1-1/2\" = 1'-0\"




20 TYP. SLAB-ON-GRADE SECTION
 1-1/2\" = 1'-0\"



12 CONCRETE WALL @ EXTERIOR WALL PLAN
 1-1/2\" = 1'-0\"




6 FURRED PLUMBING WALL PLAN
 3\" = 1'-0\"




2-HR GA File No. WP4136 STC 50 (TL-93-103)
 Base layer 5/8\" type X gypsum wallboard or gypsum veneer base applied parallel or at right angles to each side of 2 x 4 wood studs 16\" o.c. with 1 1/2\" Type W drywall screws 12\" o.c. Face layer 5/8\" type X gypsum wallboard or gypsum veneer base applied parallel or at right angles to each side with 1 1/4\" Type W drywall screws 12\" o.c. and offset 6\" from screws in base layer. Joints staggered 16\" each layer and side. At shear walls, increase fastener length by the thickness of the shear panel. Add resilient channel and 3\" insulation to achieve sound rating (see plans for actual stud size)


7 TYP. 2-HR FIRE BARRIER WALL AT EXIT CORRIDOR PLAN
 3\" = 1'-0\"



1 TYPICAL EXTERIOR WALL PLAN
 3\" = 1'-0\"




2 TYP. INTERIOR WALL PLAN
 3\" = 1'-0\"




1-HR GA File No. WP3243 50-54 STC Sound
 Resilient channels 24\" o.c. attached at right angles to ONE SIDE of 2x4\" wood studs 24\" o.c. with 1 1/2\" Type S drywall screws. One layer 5/8\" type X gypsum wallboard or gypsum veneer base applied at right angles to channels with 1\" Type S drywall screws 8\" o.c. with vertical joints located midway between studs. 3\" mineral or glass fiber insulation in stud space.
 OPPOSITE SIDE - One layer 5/8\" type X gypsum wallboard or gypsum veneer base applied parallel or at right angles to studs with 6d cement coated nails 1 1/4\" long, 0.0915\" shank, 3/8\" heads, 7\" o.c. Vertical joints staggered 24\" on opposite sides. (LOAD-BEARING)
 * Per general note 16 greater stud sizes are permitted than those specified.
 † At shear walls, increase fastener length by the thickness of the shear panel

3 TYP. 1-HR CORRIDOR WALL PLAN
 3\" = 1'-0\"




1-HR Using Calculated Fire Resistance Method
 Using IBC Section 722, Tables 722.6.2(1) and 722.6.2(2), 5/8\" Type X\" GWB (40 min.) and studs at 16\" o.c. (20 min.) provide 60 minutes of protection
 DETAIL SIMILAR WHERE UNIT SEPARATION WALL CONTINUES DOWN TO GARAGES

4 TYP. 1-HR COMMON WALL SEPARATING DWELLING UNITS PLAN
 3\" = 1'-0\"




18 BASEMENT RETAINING WALL
SECTION
1" = 1'-0"




13 CORRIDOR / SLAB FLASHING
SECTION
3" = 1'-0"


SEE STRUCTURAL ENGINEERS DESIGN, PAGE S3.1




20 CONCRETE WALL
SECTION
1" = 1'-0"




14 CORRIDOR / SLAB TRANSITION
SECTION
1-1/2" = 1'-0"




16 COMMON WALL FOUNDATION UNIT -T0- UNIT AT STEP
SECTION
1" = 1'-0"




5 SWING DOOR THRESHOLD AT PATIO OR GARAGE
SECTION
1" = 1'-0"




6 SWING DOOR THRESHOLD AT ACCESSIBLE ENTRANCE
SECTION
1" = 1'-0"




7 POST FOOTING AT PATIO
SECTION
1" = 1'-0"




8 THICKENED CONC. SLAB EDGE AT PORCH / PATIO
SECTION
1-1/2" = 1'-0"




1 TYP. EXTERIOR WALL FOOTING
SECTION
1-1/2" = 1'-0"





2 INTERIOR WALL FOOTING
SECTION
1" = 1'-0"




3 TYP. STAIR WALL FOOTING
SECTION
1 1/2" = 1'-0"




4 COMMON WALL FOUNDATION
SECTION
1" = 1'-0"





17 FURRED COLUMN
1-1/2" = 1'-0"




18 SCUPPER AT DECK
1-1/2" = 1'-0"




20 LOW WALL @ DECK EDGE
1-1/2" = 1'-0"




13 STEPPED COMMON WALL @ DECK
1-1/2" = 1'-0"




15 UNIT SEP. WALL AT DECK
1-1/2" = 1'-0"




9 ATTIC ACCESS
1-1/2" = 1'-0"




10 TUB/SHOWER AT 1-HR SEP. WALL
1" = 1'-0"




11 INTERIOR WALL AT UNIT SEP. WALL
1-1/2" = 1'-0"




5 1-HR STAIR WALL AT ROOF
1-1/2" = 1'-0"




6 UNIT SEP. WALL AT EXT. WALL
1-1/2" = 1'-0"




7 UNIT SEP. WALL AT STEPPED ROOF
1-1/2" = 1'-0"




8 2-HR STAIR WALL AT ROOF
1-1/2" = 1'-0"




1 UNIT SEP. WALL AT ROOF TRUSSES
1-1/2" = 1'-0"




2 UNIT SEPAR. AT FLOOR
1-1/2" = 1'-0"




3 COMMON WALL AT STEPPED FLOOR
1-1/2" = 1'-0"



4 EXTERIOR WALL AT FLOOR
1-1/2" = 1'-0"




A BOX BEAM AT RAKE
1-1/2" = 1'-0"




B BOX BEAM AT EAVE
1-1/2" = 1'-0"




17 ENTRY BOX-BEAM DETAILS
1-1/2" = 1'-0"




20 ENTRY COLUMN AND LOW ROOF
1-1/2" = 1'-0"




13 EXIT STAIR ROOF OVERHANG
1-1/2" = 1'-0"




15 GUARD AT LANDING
1-1/2" = 1'-0"




16 LOW ROOF
1-1/2" = 1'-0"




9 EXIT STAIR ROOF
1-1/2" = 1'-0"




5 RIDGE VENT
1-1/2" = 1'-0"




6 EAVE AT DECK HEADER
1-1/2" = 1'-0"




7 RAKE AT DECK
1-1/2" = 1'-0"




1 EAVE OVERHANG
1-1/2" = 1'-0"




2 OVERHANG W/ RAISED HEEL
1-1/2" = 1'-0"




3 EXTERIOR WALL AT ROOF
1-1/2" = 1'-0"




A Rake @ Deck @ 2-Bed Unit
1-1/2" = 1'-0"




B Deck @ 1-Bed Unit @ Lap siding
1-1/2" = 1'-0"




C Deck @ 1-Bed Unit @ Panel Siding
1-1/2" = 1'-0"




4 SPRK./ELEC. ROOM RAKE
1-1/2" = 1'-0"




17 STRINGER/RAILING AT WALL
SECTION
1 1/2" = 1'-0"



13 ENTRY DOOR THRESHOLD
SECTION
1-1/2" = 1'-0"




9 WATERPROOF DECK
SECTION
1-1/2" = 1'-0"




NOTE: SEE STRUCTURAL DETAIL SHEETS FOR ALL POST AND BEAM CONNECTIONS.


A PATIO SWING DOOR STANDARD THRESHOLD




18 UPPER FLOOR STAIR DETAIL
SECTION
1 1/2" = 1'-0"




14 STAIR WALL AT FLOOR
SECTION
1-1/2" = 1'-0"




10 DECK OVER UNIT BELOW
SECTION
1-1/2" = 1'-0"




B PATIO SWING DOOR STANDARD THRESHOLD




19 UPPER FLOOR STAIR DETAIL
SECTION
1 1/2" = 1'-0"




15 2-HR STAIR WALL AT FLOOR
SECTION
1-1/2" = 1'-0"




11 GUARD RAIL DETAILS
SECTION
1-1/2" = 1'-0"




C SLIDING GLASS DOOR STANDARD CONDITION




20 STAIR AT BASE
SECTION
1-1/2" = 1'-0"



16 STAIR FLOOR
SECTION
3\"/>




12 POST AT DECK
SECTION
1-1/2" = 1'-0"




2 DECK THRESHOLD DETAILS
SECTION

CHANGES IN LEVEL
CHANGES IN LEVEL OF 1/4" MAX. SHALL BE PERMITTED TO BE VERTICAL AND WITHOUT EDGE TREATMENT.
CHANGES IN LEVEL BETWEEN 1/4" AND 1/2" MAX. SHALL BE BEVELED WITH A SLOPE NOT STEEPER THAN 1:2


4 DOOR CHANGES IN LEVEL
SECTION
1" = 1'-0"




17 PATIO SWING DOOR - HEAD
UNIT DECK OR PATIO
SECTION
3" = 1'-0"




13 EXTERIOR DOOR JAMB
SECTION
3" = 1'-0"




18 PATIO SWING DOOR - JAMB
UNIT DECK OR PATIO
PLAN
3" = 1'-0"




14 EXTERIOR DOOR HEAD
SECTION
3" = 1'-0"




19 VERTICAL SIDING TRANSITION
PLAN
6" = 1'-0"




15 TYP. PANEL REVEAL DETAIL:
VERTICAL REVEAL TRIM
PLAN
6" = 1'-0"




11 TYPICAL OUTSIDE CORNER
@ PANEL SIDING
PLAN
6" = 1'-0"




7 SILL @ STONE VENEER
SECTION
3" = 1'-0"




3 EXT. VENEER @ TRIM CAP
SECTION
3" = 1'-0"




20 TYPICAL BELLY BAND
SECTION
3" = 1'-0"




16 TYP. PANEL REVEAL DETAIL:
HORIZONTAL REVEAL TRIM
SECTION
6" = 1'-0"




12 TYPICAL INSIDE CORNER
@ PANEL SIDING
PLAN
6" = 1'-0"




8 TYPICAL EXTERIOR CORNER
PLAN
3" = 1'-0"



4 EXT. VENEER BASE
SECTION
3" = 1'-0"




6 NAIL-FLANGE WINDOW DETAILS
SECTION
3" = 1'-0"



6 NAIL-FLANGE WINDOW DETAILS (continued)
SECTION
3" = 1'-0"

FR: 2306-VEDETAILS (01-100) DWG



THE PURPOSE OF THIS DETAIL IS TO INDICATE TYPES OF LOCATIONS OF WALL, CEILING AND FLOOR PENETRATIONS THAT NEED TO BE FIRESTOPPED IN ACCORDANCE WITH 706, 708, 711, 713, 714 AND 717 OF THE 2018 INTERNATIONAL BUILDING CODE. THE THICK LINES IN THE DETAIL INDICATE A PENETRATION BY A PIPE, CONDUIT, VENT, ETC., WHETHER PLASTIC (COMBUSTIBLE) OR NON-COMBUSTIBLE. IN GENERAL THESE PENETRATIONS (OR THE ANNULAR SPACE AROUND THEM) WOULD COMPROMISE THE INTEGRITY OF THE FIRE-RATED ASSEMBLY UNLESS IT WERE CLOSED OFF AND PROTECTED DURING A FIRE. COMMON WALLS BETWEEN UNITS ARE FIRE-RATED WALLS. UNRATED WALLS WITHIN UNITS (EVEN THOUGH THEY MAY HAVE RATED WALLBOARD) NEED NOT BE PROTECTED. HOWEVER, PENETRATION OF THE TOP AND BOTTOM PLATES OF UNRATED WALLS INTO THE RATED FLOOR ASSEMBLY NEEDS TO BE FIRESTOPPED. THE CONTRACTOR SHALL DETERMINE FIRESTOPPING FOR EACH SITUATION, AND TESTED ASSEMBLIES SHALL BE SUBMITTED TO THE ARCHITECT AND THE CITY IN ACCORDANCE WITH THE "DEFERRED SUBMITTALS" SECTION ON THE COVER SHEET.

17 PENETRATION LOCATIONS FOR FIRESTOPPING SECTION
NO SCALE


NOTE: THESE FIRESTOPPING DETAILS ARE REPRESENTATIVE OF TYPICAL SITUATIONS ONLY. FOR OTHER CONDITIONS REFER TO 3M MATRIX OF UL TESTED SYSTEMS BELOW. IF CONDITION IS NOT COVERED IN THIS MATRIX, CONTACT MANUFACTURER FOR TESTED ASSEMBLY RECOMMENDATION. ALL FIRESTOP DETAILS TO BE EXECUTED BY LICENSED AND/OR CERTIFIED INSTALLER.

FIRESTOPPING PENETRATIONS AND VOIDS IN RATED CONSTRUCTION: MATRIX OF UL TESTED SYSTEMS:


PENETRATING ITEM	ASSEMBLY	FIRE RATING	SYSTEM	PRODUCT	PENETRATING ITEM	ASSEMBLY	FIRE RATING	SYSTEM	PRODUCT
METAL PIPE/CONDUIT	CONC. WALLS/FLRS	2,3,8,4 HR	CAJ1044	CP25WB+	PLASTIC PIPE	CONC. WALLS/FLRS	18,2 HR	CAJ2001	*PPD
MULTIPLE METAL	CONC. WALLS/FLRS	2 HR	CAJ1092	CP25WB+	PLASTIC PIPE	GYP. WALLS	18,2 HR	WL2002	*PPD
METAL PIPE/CONDUIT	GYP. WALLS	1,2&3 HR	WL1001	CP25WB+	PLAS. JACKETED CABLE	CONC. WALLS/FLRS	2 HR	CAJ3021	MOLDABLE PUTTY
MULTIPLE METAL	GYP. WALLS	1&2 HR	WL1016	CP25WB+	PLAS. JACKETED CABLE	GYP. WALLS	18,2 HR	WL3031	MOLDABLE PUTTY
INSULATED PIPE	CONC. WALLS/FLRS	1,2,8,3 HR	CAJ5001	CP25WB+	CABLE TRAYS	CONC. WALLS/FLRS	2&3 HR	CAJ4003	CP25WB+ CS195+
INSULATED PIPE	GYP. WALLS	1&2 HR	WL5039	CP25WB+	CABLE TRAYS	GYP. WALLS	18,2 HR	WL4004	CP25WB+ CS195+
HVAC DUCTS (RECT.)	CONC. WALLS/FLRS	2 HR	CAJ7016	CP25WB+	BUS DUCT	CONC. WALLS/FLRS	2&3 HR	CAJ6001	CP25WB+ CS195+
HVAC DUCTS (ROUND)	CONC. WALLS/FLRS	2 HR	CAJ7003	CP25WB+	ELEC. OUTLET BOXES	GYP. WALLS	18,2 HR	ANSJ UL263	MOLDABLE PUTTY
HVAC DUCTS	GYP. WALLS	1&2 HR	WL7008	CP25WB+	CONSTRUCTION JOINTS:				
PVDF PLASTIC	CONC. WALLS/FLRS	2 HR	CAJ2121	F5195+ CP25WB+	GYP. WALL TO CONC. DECK	CONC. DECK	18,2 HR	HW0012	SILICONE 2300
PVDF PLASTIC	GYP. WALLS	1&2 HR	WL2092	F5195+ CP25WB+	CONC. FLOOR TO CONC. FLOOR	CONC. FLOOR	3 HR	FFD1002	SILICONE 2003

*PPD = 3M PLASTIC PIPE DEVICE


18 MATRIX OF UL TESTED SYSTEMS FOR FIRESTOPPING NTS




19 TYP. FIRESTOP AT PENETRATION SECTION
1-1/2" = 1'-0"




7 VENT TERMIN./HOOD AT EXTR. SECTION
1" = 1'-0"



1 FURRED CEILING SECTION
1-1/2" = 1'-0"



6 PENETRATIONS AT FLR./CLG. SECTION
1-1/2" = 1'-0"



2 SEMI-RECESSED FIRE EXT. CAB. PLAN
1-1/2" = 1'-0"

INSULATION AND ENERGY NOTES

Insulation - General
All insulation materials shall be installed according to the manufacturer's instructions to achieve proper densities, and maintain uniform R-values. Substantial contact of the insulation with the surface being insulated is required.
Where required, insulation shall be installed with clearances according to manufacturer's specifications. Insulation shall be installed so that required ventilation is unobstructed. For blown or poured loose fill insulation clearances shall be maintained through installation of a permanent retainer.

Slab on Grade
R-10 slab on grade insulation shall be installed inside the foundation wall.

Insulated Floors
Floor insulation shall be installed in a permanent manner in substantial contact with the surface being insulated. Insulation supports shall be installed so spacing is no more than twenty-four inches on center.
Floors separating conditioned space from unconditioned space shall have a vapor barrier installed. Vapor barrier shall be installed on the warm side of the insulation. The vapor barrier shall have a one perm dry cup rating or less (i.e. four mil polyethylene or kraft faced material). The floor sheathing may be used as the vapor barrier if rated (and so stamped) at one perm (max). Otherwise place vapor barrier on top of joists before placing sheathing.

Exterior Walls
All wall insulation shall fill the entire cavity. Exterior wall cavities isolated during framing shall be fully insulated to the levels of the surrounding walls. All faced insulation shall be face stapled to avoid compression.
Walls separating conditioned space from unconditioned space shall have a vapor barrier installed. Faced batt insulation shall be face stapled. Vapor barrier shall be installed on the warm side of the insulation.

Air Leakage
These air leakage notes apply to those locations separating outdoor ambient conditions from interior spaces that are heated or mechanically cooled.
Exterior joints around windows and door frames, between wall cavities and window or door frames, openings between walls and foundation, between walls and roof and wall panels, openings of utility services through walls, floors and roof, and all other openings in the building envelope shall be sealed, caulked, gasketed, or weatherstripped to limit air leakage in a manner approved by the building official.

Doors
All exterior doors or doors serving as access to an enclosed unheated area shall be weatherstripped to limit leakage around their perimeter when in a closed position.
The thermal transfer characteristics of insulated doors shall be determined per NFRC 100-91.

Windows
Glazing U-values shall be determined in accordance with NFRC 100-91.
Windows and SGD shall be double glazed vinyl type with the U-values indicated on the unit plans.
Windows shall be furnished with outdoor air inlets as indicated on the Unit Electrical plans. Inlets shall have a controllable and secure opening and be capable of a total opening area of not less than four (4) square inches and tested by a nationally recognized standard or approved agency and located to avoid drafts. Inlets shall be screened or otherwise protected from entry by insects, leaves, or other material.

Roof/Ceilings
Roof/Ceiling insulation: Open-Blown or poured loose fill insulation may be used in attic spaces where the slope of the ceiling is more than 4 in 12 and there is at least 44 inches of clear distance from the top of the bottom chord of the truss or ceiling joist to the underside of the sheathing. When eave vents are installed, baffling of the vent openings shall be provided so as to deflect the incoming air above the surface of the insulation. Baffles shall be rigid material, resistant to wind driven moisture. When feasible, the baffles shall be installed from the top of the outside of the exterior wall, extending inward, to a point six inches vertically above the height of noncompressed insulation, and twelve inches vertically above loose fill insulation. Baffles shall be in place at the time of framing inspection.
Where the ventilation space above the insulation is less than an average of twelve inches roof ceiling assemblies shall be provided with a vapor barrier having a 0.5 perm cup rating or less. Faced batt insulation where used as a vapor barrier shall be face stapled.
Vapor barriers shall not be required in roof/ceiling assemblies where the ventilation space above the insulation averages twelve inches or greater.
Vapor barriers shall be installed on the warm side of the insulation.

MILBRANDT ARCHITECTS
25 Central Way, Suite 210
Kirkland, Washington 98033
P: 425.454.7130 F: 425.658.1208
Web: www.milbrandtarch.com
© Copyright 2023
Milbrandt Architects, INC., P.S.
All rights reserved.

11063 REGISTERED ARCHITECT
ANNA P. THOMPSON
STATE OF WASHINGTON

Details

Bradley Heights Apartments

Puyallup, Wa

Timberlane Partners

Revisions
No. Date Description

Initial Publish Date:
Date Plotted: 2-20-24
Job No.: 23-06
Drawn By: APT/HDM
Sheet No.: D7

WHOLE HOUSE VENTILATION NOTES

EACH DWELLING UNIT OR SLEEPING UNIT SHALL BE EQUIPPED WITH A WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM THAT COMPLIES WITH SECTIONS 403.4.1 THROUGH 403.4.6. EACH DWELLING UNIT OR SLEEPING UNIT SHALL BE EQUIPPED WITH LOCAL EXHAUST COMPLYING WITH SECTION 403.4.7. ALL OCCUPIED SPACES, INCLUDING PUBLIC CORRIDORS, OTHER THAN GROUP R DWELLING UNITS AND/OR SLEEPING UNITS, THAT SUPPORT THESE GROUP R OCCUPANCIES, SHALL MEET THE VENTILATION REQUIREMENTS OF SECTION 402 OR THE MECHANICAL VENTILATION REQUIREMENTS OF SECTIONS 403.1 THROUGH 403.3.

THE WHOLE HOUSE VENTILATION SYSTEM SHALL CONSIST OF ONE OR MORE SUPPLY FANS, ONE OR MORE EXHAUST FANS, OR AN ERV/HRV WITH INTEGRAL FANS; AND THE ASSOCIATED DUCTS AND CONTROLS. LOCAL EXHAUST FANS SHALL BE PERMITTED TO SERVE AS PART OF THE WHOLE-HOUSE VENTILATION SYSTEM WHEN PROVIDED WITH THE PROPER CONTROLS IN ACCORDANCE WITH SECTION 403.4.5. THE SYSTEMS SHALL BE DESIGNED AND INSTALLED TO SUPPLY AND EXHAUST THE MINIMUM OUTDOOR AIRFLOW RATES PER SECTION 403.4.2 AS CORRECTED BY THE BALANCED AND/OR DISTRIBUTED WHOLE-HOUSE VENTILATION SYSTEM COEFFICIENTS IN ACCORDANCE WITH SECTION 403.4.3 WHERE APPLICABLE.

THE DWELLING UNIT WHOLE-HOUSE MECHANICAL VENTILATION MINIMUM OUTDOOR AIRFLOW RATE SHALL BE DETERMINED IN ACCORDANCE WITH EQUATION 4-10 OR TABLE 403.4.2.

RESIDENTIAL DWELLING AND SLEEPING UNITS IN GROUP R-2 OCCUPANCIES SYSTEM SHALL INCLUDE SUPPLY AND EXHAUST FANS AND BE A BALANCED WHOLE-HOUSE VENTILATION SYSTEM IN ACCORDANCE WITH SECTION 403.4.6.3. THE SYSTEM SHALL INCLUDE A HEAT OR ENERGY RECOVERY VENTILATOR WITH A SENSIBLE HEAT RECOVERY EFFECTIVENESS AS PRESCRIBED IN SECTION C403.3.6 OF THE WASHINGTON STATE ENERGY CODE. THE WHOLE-HOUSE VENTILATION SYSTEM SHALL OPERATE CONTINUOUSLY AT THE MINIMUM VENTILATION RATE DETERMINED IN ACCORDANCE WITH SECTION 403.4. THE WHOLE-HOUSE SUPPLY FAN SHALL PROVIDE DUCTED OUTDOOR VENTILATION AIR TO EACH HABITABLE SPACE WITHIN THE RESIDENTIAL UNIT.

CONTROLS FOR THE WHOLE-HOUSE VENTILATION SYSTEM SHALL COMPLY WITH THE FOLLOWING:

1. THE WHOLE-HOUSE VENTILATION SYSTEM SHALL BE CONTROLLED WITH MANUAL SWITCHES, TIMERS OR OTHER MEANS THAT PROVIDE FOR AUTOMATIC OPERATION OF THE VENTILATION SYSTEM THAT HAVE READY ACCESS FOR THE OCCUPANT.
2. THE WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM SHALL BE PROVIDED WITH CONTROLS THAT ENABLE MANUAL OVERRIDE OFF OF THE SYSTEM BY THE OCCUPANT DURING PERIODS OF POOR OUTDOOR AIR QUALITY. CONTROLS SHALL INCLUDE PERMANENT TEXT OR A SYMBOL INDICATING THEIR FUNCTION. RECOMMENDED CONTROL PERMANENT LABELING TO INCLUDE TEXT SIMILAR TO THE FOLLOWING; "LEAVE ON UNLESS OUTDOOR AIR QUALITY IS VERY POOR."
3. WHOLE-HOUSE VENTILATION SYSTEMS SHALL BE CONFIGURED TO OPERATE CONTINUOUSLY EXCEPT WHERE INTERMITTENT OFF CONTROLS ARE PROVIDED IN ACCORDANCE WITH SECTION 403.4.6.5 AND ALLOWED BY SECTION 403.4.4.2.

WHOLE HOUSE VENTILATION SUPPLY AND EXHAUST FANS SPECIFIED IN THIS SECTION SHALL HAVE A MINIMUM EFFICACY AS PRESCRIBED IN THE WASHINGTON STATE ENERGY CODE. THE FANS SHALL BE RATED FOR SOUND AT A MAXIMUM OF 1.0 SONE AT DESIGN AIRFLOW AND STATIC PRESSURE CONDITIONS. DESIGN AND INSTALLATION OF THE SYSTEM OR EQUIPMENT SHALL BE CARRIED OUT IN ACCORDANCE WITH MANUFACTURERS' INSTALLATION INSTRUCTIONS

A BALANCED WHOLE HOUSE VENTILATION SYSTEM SHALL INCLUDE BOTH SUPPLY AND EXHAUST FANS. THE SUPPLY AND EXHAUST FANS SHALL HAVE AIRFLOW THAT IS WITHIN 10 PERCENT OF EACH OTHER. THE TESTED AND BALANCED TOTAL MECHANICAL EXHAUST AIRFLOW RATE IS WITHIN 10 PERCENT OR 5 CFM, WHICHEVER IS GREATER, OF THE TOTAL MECHANICAL SUPPLY AIRFLOW RATE. THE FLOW RATE TEST RESULTS SHALL BE SUBMITTED AND POSTED IN ACCORDANCE WITH SECTION 403.4.6.6. THE EXHAUST FAN SHALL MEET THE REQUIREMENTS OF SECTION 403.4.6.2. THE SUPPLY FAN SHALL MEET THE REQUIREMENTS OF SECTION 403.4.6.3. FOR R-2 DWELLING AND SLEEPING UNITS, THE SYSTEM IS REQUIRED TO HAVE BALANCED WHOLE-HOUSE VENTILATION BUT IS NOT REQUIRED TO HAVE DISTRIBUTED WHOLE-HOUSE VENTILATION WHERE THE NOT DISTRIBUTED SYSTEM COEFFICIENT FROM TABLE 403.4.3 IS UTILIZED TO CORRECT THE WHOLE-HOUSE MECHANICAL VENTILATION RATE. THE SYSTEM SHALL BE DESIGNED AND BALANCED TO MEET THE PRESSURE EQUALIZATION REQUIREMENTS OF SECTION 501.4. INTERMITTENT DRYER EXHAUST, INTERMITTENT RANGE HOOD EXHAUST, AND INTERMITTENT TOILET ROOM EXHAUST AIRFLOW RATES ABOVE THE RESIDENTIAL DWELLING OR SLEEPING UNIT MINIMUM VENTILATION RATE ARE EXEMPT FROM THE BALANCED AIRFLOW CALCULATION.

FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATIONS


PER 2018 IMC 401.4.3, ITEM 3, EXCEPTION, SEPARATION IS NOT REQUIRED BETWEEN INTAKE AIR OPENINGS AND LIVING SPACE RELIEF AIR EXHAUST AIR OPENINGS OF AN INDIVIDUAL DWELLING UNIT OR SLEEPING UNIT, NOT TO INCLUDE COMMON AREAS OUTSIDE OF THE DWELLING OR SLEEPING UNIT, WHERE A FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATION FITTING, LISTED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, IS USED TO SEPARATE THE AIR STREAMS. A MINIMUM OF 5 FEET HORIZONTAL SEPARATION BETWEEN OTHER ENVIRONMENTAL AIR EXHAUST OUTLETS AND OTHER DWELLING OR SLEEPING UNIT FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATION FITTINGS SHALL BE MAINTAINED.

CALCULATIONS

RESIDENTIAL VENTILATION CALCULATIONS

UNIT TYPE	UNIT SQUARE FOOTAGE	NUMBER OF BEDROOMS	2018 IMC CRITERIA (1)			VENTILATION QUALITY ADJUSTMENT COEFFICIENT (3)	MINIMUM WHOLE HOUSE VENTILATION RATE, CFM	TOTAL CFM PROVIDED BY WHOLE HOUSE FAN SYSTEM
			FLOOR AREA, SQFT	NUMBER OF BEDROOMS	REQUIRED CFM (2)			
1 BEDROOM	660	1	500 - 1,000	1	30	1.5	45	55
2 BEDROOM	1000	2	500 - 1,000	2	35	1.5	53	55

- NOTE:
- (1) VENTILATION CRITERIA IS PER THE 2018 WA RESIDENTIAL CODE SECTION M1505.4.3
 - (2) MINIMUM OSA FOR CONTINUOUSLY OPERATING FAN(S).
 - (3) ADJUSTMENT COEFFICIENT IS PER 2018 WRC, TABLE M1505.4.3(2) FOR A NOT BALANCED, AND NOT DISTRIBUTED WHOLE HOUSE VENTILATION SYSTEM.



DRAWN: OP	DESIGNED: ABE	CHECKED: ABE	APPROVED: JOB
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
 202 27TH AVE SE
 PUYALLUP, WA 98374
 19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343
ROBISON ENGINEERING, INC

DATE: 02/15/2024

SHEET TITLE:
TABLES & CALCULATIONS

SHEET NO.
M0.2

NO.	DATE	DESCRIPTION

WSEC FORMS

6/16/23, 11:08 AM waenergycodes.com/print_project_summary_form.php?k=aWQ9MTkxMjZpPTE3JmN0aT00Ng==&print=1

2018 WSEC Compliance Forms for Commercial Buildings including Group R2, R3 & R4 over 3 stories and all R1 Administered by: ©2023 NECA, All rights reserved

MECHANICAL COMPLIANCE SUMMARY

Project Title: Bradley Heights Apartments Building D - 2018 WSEC
 Project Address: 202 27th Ave SE, Puyallup, WA 98374
 Applicant Name: Ark Equine
 Applicant Phone: 206-364-3343
 Applicant Email: aespindel@robisonengineering.com
 Date: Jun 16, 2023

For questions about this report, contact WSEC Commercial Technical Support at 360-539-5300 or via email at comtechsupport@waenergycodes.com

General Occupancy	General Building Use Type	Building Cond. Floor Area
All Group R - R2, R3 & R4 over 3 stories and all R1	Multifamily/Residential	35,046

General Project Types	New Building	New Building or Addition Mechanical Scope	Single Zone Systems & Equipment	Alteration Mechanical Scope	Project Cond. Floor Area	Floors Above Grade
	New Building	Single Zone Systems & Equipment			35,046	3

Mechanical Project Description: Full mechanical design for new 3 story residential building with basement.

Mechanical Compliance Scope and Method	Project Type	Mechanical Scope	Economizer Exception(s) Applied?	DOAS Ventilation Provided?	Higher Equipment Efficiency Option Applied?	Equipment Efficiency Compliance Verification
	New Building	Single Zone Systems & Equipment	No	Yes	NA	COMPLIES

Additional Efficiency Credits Included (AEC):
 Does building include occupancy classifications requiring DOAS? No
 Does project include DOAS equipment? No
 Based on project scope do TSPR requirements apply? No
 Do all systems comply with Appendix D standard reference design or qualify for an exception to TSPR? No

Scope & Space Conditioning: NEW BUILDING - SINGLE ZONE SYSTEMS & EQUIPMENT Compliance Verification: COMPLIES

Single Zone Air Systems Category - Unit heaters & duct heaters

System/Equip ID	Quantity of Items	Ventilation Standard	Ventilation CFM (Total if Multiple Items)	Ventilation Air Source	Paired with DOAS
EW1-1	84	IMC Ventilation		Other System	
EW1-2	14	IMC Ventilation		Other System	

System/Equip ID	Heating System/Equip Type	Specific Type	Heating Capacity	HC Units	Proposed Heating Efficiency	HE Units	Efficiency Compliance Verification
EW1-1	Unit heater	Electric resistance	1	Btu/h			COMPLIES
EW1-2	Unit heater	Electric resistance	2	Btu/h			COMPLIES

System/Equip ID	Area(s) Served	Location In Project Documents - Plan/Detail #
EW1-1	APARTMENT UNITS	M0.3
EW1-2	APARTMENT UNITS	M0.3

System/Equip ID for a single or multiple items? Multiple items w/ identical heating & cooling capacity

System/Equip ID for a single or multiple items? Multiple items w/ identical heating & cooling capacity

https://waenergycodes.com/print_project_summary_form.php?k=aWQ9MTkxMjZpPTE3JmN0aT00Ng==&print=1 1/1

MECHANICAL SCHEDULES

ELECTRIC HEATERS

EQUIP NO.	SERVICE	MOUNTING/ DISCHARGE	HEATING	ELECTRICAL	BASIS OF DESIGN (3)
			KW	VOLTAGE	
EW1-1	APARTMENT UNIT	WALL	1.0	208V/1P	(1)(2)
EW1-2	APARTMENT UNIT	WALL	1.5	208V/1P	(1)(2)


NOTES: (1) BROAN, KING, CADET OR EQUIVALENT.
 (2) PROVIDE REMOTE THERMOSTAT. COORDINATE FINAL LOCATION WITH ELECTRICAL DRAWINGS.
 (3) ALL ELECTRIC HEATERS TO BE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR.

FAN SCHEDULE

EQUIP NO.	SERVICE	TYPE	AIRFLOW, CFM	ESP. IN WG	ELECTRICAL		OPERATION	WEIGHT, LBS	BASIS OF DESIGN (1)(2)(3)
					VOLTAGE	HP			
BEF-1	RESTROOM	CEILING MOUNTED	55/80	0.5	115V/1P	FHP	CONTINUOUS	10	GREENHECK SP-AP0511W (4)
BEF-2	RESTROOM	CEILING MOUNTED	50	0.5	115V/1P	FHP	(2)	10	GREENHECK SP-AP0511W

NOTES: (1) PROVIDE BACKDRAFT DAMPERS ON EXHAUST FANS.
 (2) 1.0 SONES MAXIMUM.
 (3) VIBRATION ISOLATION: FANS < 125 LBS RUBBER ISOLATORS, FANS > 125 LBS SPRING ISOLATORS
 (4) FAN SHALL BE 2-SPEED: 35 CFM CONTINUOUS LOW SETTING AND 80 CFM HIGH SPEED ACTIVATED BY INTEGRAL OCCUPANCY SENSOR ON GRILLE.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: OP	DESIGNED: ABE	CHECKED: ABE	APPROVED: JOB
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/2024


SHEET TITLE:
MECHANICAL SCHEDULES & WSEC FORMS

SHEET NO.
M0.3



BUILDING D
1st LEVEL PLAN
1/8" = 1'-0"
3/4 SPLIT LEVEL, 42-UNIT BUILDING

Provide lengths to all duct work for all floors to identify maximum duct length for all areas.
Page M2.0



BUILDING D
BASEMENT LEVEL PLAN
1/8" = 1'-0"
3/4 SPLIT LEVEL, 42-UNIT BUILDING


RESIDENTIAL UNIT NOTES:

1 M300 = REFER TO DWG M300, DETAIL 1.

Did not locate sheets M300-M303 duct sizes and length.
Page M2.0

FOR DUCT SIZES WITHIN THE RESIDENTIAL UNITS, REFER TO THE ENLARGED UNIT PLANS ON DWGS M300-M303.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	ABE
APPROVED:	JOB

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
202 27TH AVE SE
PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 864-3343

ROBISON
ENGINEERING, INC.


DATE: 02/15/2024

SHEET TITLE:
HVAC PLAN -
BASEMENT &
1ST LEVEL

SHEET NO.
M2.0



BUILDING D 3rd LEVEL PLAN
 1/8" = 1'-0" 3/4 SPLIT LEVEL, 42-UNIT BUILDING





BUILDING D 2nd LEVEL PLAN
 1/8" = 1'-0" 3/4 SPLIT LEVEL, 42-UNIT BUILDING

RESIDENTIAL UNIT NOTES:

1 M300 = REFER TO DWG M300, DETAIL 1.

FOR DUCT SIZES WITHIN THE RESIDENTIAL UNITS, REFER TO THE ENLARGED UNIT PLANS ON DWGS M300-M303.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	ABE
APPROVED:	JOB

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 864-3343

ROBISON
 ENGINEERING, INC.

DATE: 02/15/2024

SHEET TITLE:
 HVAC PLAN -
 2ND & 3RD
 LEVEL

SHEET NO.
M2.1




HVAC ENLARGED PLANS

2-BED-ALT-1

SCALE: 1/4" = 1'-0"

1
M300



HVAC ENLARGED PLANS

2-BED-ALT-2

SCALE: 1/4" = 1'-0"

2
M300

Provide lengths to all duct work for all floors to identify and verify does not exceed Table 504.8.4.1 for allowable exhaust duct length.

Page M3.0

GENERAL NOTES:


- ENVIRONMENTAL EXHAUST TERMINATIONS: MAINTAIN 3 FOOT SEPARATION FROM PROPERTY LINES AND OPERABLE OPENINGS INTO BUILDING, 10 FEET FROM MECHANICAL AIR INTAKES.
- MOUNT REMOTE THERMOSTATS 48" AFF. PER WSEC C403.4.9, AT LEAST ONE THERMOSTAT SHALL BE PROGRAMMABLE ON A 5-2 SCHEDULE.
- UNDERCUT ALL BATHROOM DOORS BY MINIMUM 1/2" TO ALLOW TRANSFER OF MAKEUP AIR FOR BATHROOM EXHAUST.
- ELECTRIC WALL HEATERS SHALL BE RECESSED IN WALL UNLESS FIRE RATED OR EXTERIOR WALL. FOR HEATERS MOUNTED ON SUCH WALL, PROVIDE SURFACE-MOUNT WALL CAN.
- PROVIDE ACCESSIBLE MANUAL VOLUME DAMPERS AT BRANCHES OR OPPOSED-BLADE DAMPERS AT GRILLES FOR AIR BALANCING PER VOLUME DAMPERS NOTE ON SHEET M0.00.

FLAG NOTES:

- CLOSETS CONTAINING DRYERS SHALL BE PROVIDED WITH LOUVERED DOOR OR 100 SQ. IN FREE-AREA OPENING ABOVE DOOR. OPENING PROVIDES PATH FOR EXHAUST AIR DURING WASHER OPERATION PER WSMC TABLE 403.3.1.1 NOTE (I) AND MAKEUP AIR DURING DRYER OPERATION PER 504.6.
- 4ø POC TO DRYER. PROVIDE METAL DRYER BOX WHERE DUCT IS ROUTED IN 2x6 FRAMED WALL. REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WSMC 504.8.4.1 FOR THE MAXIMUM ALLOWED LENGTH OF THE DRYER VENT. PROVIDE PERMANENT PLACARD OF TYPE PLAC34 SHOWING NET EQUIVALENT LENGTH. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- 4" DRYER EXHAUST TERMINATION WALL CAP. PROVIDE BACKDRAFT DAMPER AT TERMINATION. DO NOT INSTALL SCREENS ON DRYER EXHAUST TERMINATIONS. CLEARANCES PER GENERAL NOTE 1.

- POC TO DOMESTIC KITCHEN RANGE HOOD. SEE PLANS FOR SIZE. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- DOMESTIC KITCHEN RANGE HOOD EXHAUST TERMINATION WALL CAP WITH SCREEN. PROVIDE BACKDRAFT DAMPER AT TERMINATION. CLEARANCES PER GENERAL NOTE 1.
- LOWERED SOFFIT FOR MECHANICAL EQUIPMENT.
- 8ø POC FOR HEAT PUMP WATER HEATER EXHAUST.
- CLOSETS CONTAINING WATER HEATERS SHALL BE PROVIDED WITH MINIMUM 3/4" UNDERCUT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	ABE
APPROVED:	JOB

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
202 27TH AVE SE
PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON
ENGINEERING, INC

DATE: 02/15/2024

SHEET TITLE:
HVAC
ENLARGED
PLANS

SHEET NO.
M3.0




HVAC ENLARGED PLANS

1-BED-INT-1

SCALE: 1/4" = 1'-0"

1
M301




HVAC ENLARGED PLANS

1-BED-INT-2

SCALE: 1/4" = 1'-0"

2
M301



HVAC ENLARGED PLANS

1-BED-END

SCALE: 1/4" = 1'-0"

3
M301

Provide lengths to all duct work for all floors to identify and verify does not exceed Table 504.8.4.1 for allowable exhaust duct length.
Page M3.1

GENERAL NOTES:



- ENVIRONMENTAL EXHAUST TERMINATIONS: MAINTAIN 3 FOOT SEPARATION FROM PROPERTY LINES AND OPERABLE OPENINGS INTO BUILDING, 10 FEET FROM MECHANICAL AIR INTAKES.
- MOUNT REMOTE THERMOSTATS 48" AFF. PER WSEC C403.4.9, AT LEAST ONE THERMOSTAT SHALL BE PROGRAMMABLE ON A 5-2 SCHEDULE.
- UNDERCUT ALL BATHROOM DOORS BY MINIMUM 1/2" TO ALLOW TRANSFER OF MAKEUP AIR FOR BATHROOM EXHAUST.
- ELECTRIC WALL HEATERS SHALL BE RECESSED IN WALL UNLESS FIRE RATED OR EXTERIOR WALL. FOR HEATERS MOUNTED ON SUCH WALL, PROVIDE SURFACE-MOUNT WALL CAN.
- PROVIDE ACCESSIBLE MANUAL VOLUME DAMPERS AT BRANCHES OR OPPOSED-BLADE DAMPERS AT GRILLES FOR AIR BALANCING PER VOLUME DAMPERS NOTE ON SHEET M0.00.

FLAG NOTES: #

- CLOSETS CONTAINING DRYERS SHALL BE PROVIDED WITH LOUVERED DOOR OR 100 SQ. IN FREE-AREA OPENING ABOVE DOOR. OPENING PROVIDES PATH FOR EXHAUST AIR DURING WASHER OPERATION PER WSMC TABLE 403.3.1.1 NOTE (I) AND MAKEUP AIR DURING DRYER OPERATION PER 504.6.
- 4ø POC TO DRYER. PROVIDE METAL DRYER BOX WHERE DUCT IS ROUTED IN 2x6 FRAMED WALL. REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WSMC 504.8.4.1 FOR THE MAXIMUM ALLOWED LENGTH OF THE DRYER VENT. PROVIDE PERMANENT PLACARD OF TYPE PLAC34 SHOWING NET EQUIVALENT LENGTH. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- 4" DRYER EXHAUST TERMINATION WALL CAP. PROVIDE BACKDRAFT DAMPER AT TERMINATION. DO NOT INSTALL SCREENS ON DRYER EXHAUST TERMINATIONS. CLEARANCES PER GENERAL NOTE 1.

- POC TO DOMESTIC KITCHEN RANGE HOOD. SEE PLANS FOR SIZE. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- DOMESTIC KITCHEN RANGE HOOD EXHAUST TERMINATION WALL CAP WITH SCREEN. PROVIDE BACKDRAFT DAMPER AT TERMINATION. CLEARANCES PER GENERAL NOTE 1.
- LOWERED SOFFIT FOR MECHANICAL EQUIPMENT.
- 8ø POC FOR HEAT PUMP WATER HEATER EXHAUST.
- CLOSETS CONTAINING WATER HEATERS SHALL BE PROVIDED WITH MINIMUM 3/4" UNDERCUT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	ABE
APPROVED:	JOB

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
202 27TH AVE SE
PUYALLUP, WA 98374

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/2024

SHEET TITLE:
HVAC ENLARGED PLANS

SHEET NO.
M3.1

SYMBOLS

GENERAL	
	LIGHT LINE INDICATES NON-ELECTRICAL OR BACKGROUND (THIS IS NOT CONTRACTUAL DEFINITION OF WORK)
	HEAVY LINE INDICATES NEW WORK (THIS IS NOT CONTRACTUAL DEFINITION OF WORK)
DETAIL IDENTIFICATION	
	FLAG NOTE
	REVISION NOTE
	REVISION DEFINITION, AREA ENCIRCLED CONTAINS DRAWING CHANGES MADE SUBSEQUENT TO PREVIOUS ISSUE
SWITCHES	
	SWITCH, SINGLE POLE; WITH SWITCHING SUBSCRIPT
	OCCUPANCY SENSOR SWITCH
	SWITCH, SINGLE POLE; WITH SWITCHING SUBSCRIPT "D" INDICATES WALLBOX DIMMER
	CEILING MOUNTED OCCUPANCY SENSOR
	SWITCH, TIMER.
	SWITCH, THREE WAY.
RECEPTACLES	
	SINGLE RECEPTACLE
	DUPLEX RECEPTACLE: WALL MOUNTED, +18" AFF
	CONTROLLED AND NON CONTROLLED DUPLEX RECEPTACLE (SPLIT WIRED RECEPTACLE)
	DUPLEX RECEPTACLE - ABOVE COUNTER
	DUPLEX GFCI ABOVE COUNTER
	DUPLEX GFCI
	DUPLEX RECEPTACLE, WITH HEIGHT ABOVE FINISHED FLOOR INDICATED
	CEILING MOUNTED DUPLEX RECEPTACLE
	DOUBLE DUPLEX RECEPTACLE: WALL MOUNTED, +18" AFF
	FLOOR BOX ONE DUPLEX RECEPTACLE
	FLOOR BOX ONE DUPLEX RECEPTACLE + ONE DATA
	FLOOR BOX ONE DUPLEX RECEPTACLE + ONE DATA + ONE VOICE
	SPECIAL PURPOSE RECEPTACLE, AS NOTED
MISCELLANEOUS	
	JUNCTION BOX: 4SQ MOUNTED
	JUNCTION BOX: 4SQ WALL MOUNTED
	JUNCTION BOX: 4SQ TRACK
	CONNECTION FOR LIGHTED MIRROR COORDINATE LOCATION AND ELEVATION WITH ARCHITECT PRIOR TO ROUGH-IN
	THERMOSTAT
SIGNAL/COMMUNICATION	
	DATA OUTLET: WALL MOUNTED @ +18" AFF U.O.N.
	TELEPHONE/DATA OUTLET: WALL MOUNTED @ +18" AFF U.O.N.
	TELEVISION OUTLET: WALL MOUNTED @ +18" AFF U.O.N.
POWER	
	PANELBOARD
	NON-FUSED DISCONNECT SWITCH (WP = NEMA 3R WHERE APPROPRIATE)
	FUSED DISCONNECT SWITCH
	MOTOR CONNECTION (EQUIPMENT NAME, HORSEPOWER, VOLTAGE, AND PHASE INDICATED)
	EQUIPMENT CONNECTION (EQUIPMENT NAME, LOAD, VOLTAGE, AND PHASE INDICATED)
	TRANSFORMER, DRY TYPE, SHOWN TO SCALE
	KW METER AND BASE
FIRE ALARM SYSTEM	
	FIRE ALARM SYSTEM CONTROL PANEL
	FIRE ALARM SYSTEM PULL STATION
	FIRE ALARM SYSTEM STROBE/SPEAKER
	FIRE ALARM PHOTOELECTRIC SMOKE DETECTOR AND SPEAKER.
	FIRE ALARM COMBINATION PHOTOELECTRIC SMOKE DETECTOR, CARBON MONOXIDE DETECTOR, AND SPEAKER, GUESTROOM.
	CARBON MONOXIDE DETECTOR.
	ELECTRO-MAGNETIC DOOR HOLDER
	DUCT SMOKE DETECTOR

ABBREVIATIONS

A	AMPERE
AC	ALTERNATING CURRENT, ABOVE COUNTER
AFF	ABOVE FINISHED FLOOR
AIC	AMPS INTERRUPTING CAPACITY
AL	ALUMINUM
AMP	AMPERE
AWG	AMERICAN WIRE GAUGE
BKR	BREAKER
BLDG	BUILDING
C	COIL or CONDUIT
CKT	CIRCUIT
CO	CONDUIT/RACEWAY ONLY
CT	CURRENT TRANSFORMER
Cu	COPPER
CW	COOL WHITE
D	DIMMER
DED	DEDICATED
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
ELEC	ELECTRICAL
EMT	ELECTRICAL METALLIC TUBING
EQUIP	EQUIPMENT
EXIST	EXISTING
FAA	FIRE ALARM ANNUNCIATOR
FACP	FIRE ALARM CONTROL PANEL
FLUOR	FLUORESCENT
GC	GENERAL CONTRACTOR
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GND	GROUND
GRS	GALVANIZED RIGID STEEL
HID	HIGH INTENSITY DISCHARGE
HP	HORSEPOWER
IG	ISOLATED GROUND
KCMIL	THOUSAND CIRCULAR MILLS
KVA	KILOVOLT AMPERES
KW	KILOWATT
LTG	LIGHTING
LV	LOW VOLTAGE
MFR	MANUFACTURER
MIN	MINIMUM
MLO	MAIN LUGS ONLY
N	NEUTRAL
NEC	NATIONAL ELECTRICAL CODE (NFPA-70)
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NTS	NOT TO SCALE
PNL	PANEL
POC	POINT OF CONNECTION
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
PWR	POWER
QTY	QUANTITY
RECEPT	RECEPTACLE
REF	REFERENCE
RI	ROUGH-IN
RM	ROOM
RO	RACEWAY ONLY
SHT	SHEET
SPEC	SPECIFICATIONS
SW	SWITCH
SWBD	SWITCHBOARD
SWGR	SWITCHGEAR
TYP	TYPICAL
UG	UNDERGROUND
UL	UNDERWRITERS LABORATORIES
UON	UNLESS OTHERWISE NOTED
V	VOLTS
W	WATTS
WW	WARM WHITE
WP	WEATHERPROOF
W/	WITH
W/O	WITHOUT
XFMR	TRANSFORMER
XFR	TRANSFER
Z	IMPEDANCE OR ZONE

GENERAL NOTES

GENERAL

- PROVIDE ELECTRICAL INSTALLATION IN ACCORDANCE WITH THE GOVERNING ELECTRICAL CODE, LOCAL CODES, ORDINANCES AND REQUIREMENTS OF UTILITY COMPANIES FURNISHING SERVICES TO INSTALLATION.
- PROVIDE ALL WORK AND ITEMS NECESSARY FOR COMPLETE AND FUNCTIONAL ELECTRICAL SYSTEMS. THE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND DO NOT NECESSARILY SHOW EVERY CONDUIT, BOX, CONDUCTOR OR SIMILAR ITEMS FOR A COMPLETE INSTALLATION.
- THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID AND DETERMINE CONDITIONS WHICH MAY AFFECT BID. ANY ITEMS NOT FULLY UNDERSTOOD SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO BIDDING.
- "REF" INDICATIONS DENOTE WORK COVERED ELSEWHERE (ARCHITECTURAL, STRUCTURAL, OR MECHANICAL).
- REFERENCE ARCHITECTURAL DRAWING FOR EXACT LOCATION OF DEVICES. QUESTIONS CONCERNING THE LOCATION OF DEVICES AND EQUIPMENT SHALL BE DIRECTED TO THE ARCHITECT. FAILURE TO COORDINATE REQUIREMENTS SHALL IN NO WAY RESULT IN ADDITIONAL COMPENSATION BEING PROVIDED TO THE CONTRACTOR.
- WHEREVER THE WORD "PROVIDE" IS USED, IT MEANS, "FURNISH AND INSTALL COMPLETE AND READY FOR USE."
- COORDINATE LOCATION OF ELECTRICAL WITH OTHER TRADES.
- REFER TO EQUIPMENT DRAWINGS FOR MECHANICAL CHARACTERISTICS (SIZE, LOCATION, ETC.) OF MECHANICAL EQUIPMENT, UNLESS OTHERWISE INDICATED. COORDINATE INSTALLATION AND LOCATION OF ALL EQUIPMENT WITH MECHANICAL CONTRACTOR. VERIFY ALL FUSE RATINGS, WIRE SIZES AND DISCONNECT SIZES PRIOR TO INSTALLATION.

MATERIALS AND METHODS

- PROVIDE RACEWAY AND WIRING ROUTED CONCEALED WITHIN BUILDING STRUCTURE WHERE POSSIBLE. WHERE RACEWAY CANNOT BE CONCEALED, IT SHALL BE INSTALLED PER PROJECT MANAGER'S DIRECTION. ALL CONDUIT SHALL BE INSTALLED IN NEAT SYMMETRICAL LINES HORIZONTAL OR PERPENDICULAR TO BUILDING COLUMNS AND ROOF LINES. CONDUITS SHALL BE GROUPED ON COMMON SUPPORTS WHEREVER POSSIBLE.
- EXPOSED CONDUIT ROUTING: CONDUITS MAY BE ROUTED EXPOSED IN MECHANICAL AND ELECTRICAL ROOMS ONLY. EXPOSED CONDUITS SHALL BE SECURED A MINIMUM OF 6" ABOVE FLOOR.
- OUTDOOR EXPOSED CONDUIT ROUTING: CONDUITS ROUTED ON ROOF OR EXPOSED TO WEATHER SHALL BE GRC, PVC OR LIQUID-TIGHT FLEX. PROVIDE WATER-TIGHT CONNECTIONS AND FITTINGS.
- CLEARANCES: VERIFY PHYSICAL DIMENSIONS OF EQUIPMENT TO ENSURE THAT ACCESS CLEARANCES CAN BE MET.
- CONNECTIONS: PROVIDE GRS, METALLIC FLEX, OR LIQUIDTITE FLEX CONDUITS FOR CONNECTIONS TO MOTORS OR MOTORIZED EQUIPMENT.
- WIRING: PROVIDE MINIMUM #12 AWG WIRE SIZE. IF CONDUIT IS TO BE USED MINIMUM IS TO BE 1/2". FLEXIBLE CONDUIT AND FLEXIBLE CABLE IS PERMISSIBLE THROUGHOUT THE BUILDING.

SITE ELECTRICAL

- TRENCHING: COORDINATE ALL TRENCHING WORK WITH OTHER UTILITY LOCATIONS AND DRAINAGE TRENCHES.
- UNDERGROUND CONDUITS: PROVIDE PVC, SCHEDULE 40, 3/4" MINIMUM. PROVIDE GRC CONDUIT TRANSITION ELBOW WHEN TURNING UP TO ABOVE GRADE.
- DIRECT-BURIED CONDUITS: CONDUIT FOR BRANCH CIRCUITS OUTSIDE BUILDINGS NOT BENEATH DRIVEWAYS OR PARKING AREAS SHALL BE DIRECTLY BURIED WITHOUT CONCRETE ENCASEMENT. THE DEPTH TO THE TOP OF BURIED CONDUITS SHALL BE 36". PROVIDE MARKER TAPE 12" BELOW GRADE.
- BELOW SLAB: CONDUIT ROUTED BELOW ON-GRADE FLOOR SLABS SHALL BE INSTALLED PRIOR TO FLOOR SLAB POUR. ROUTE CONDUITS BELOW SLAB AS STRAIGHT AS POSSIBLE TO MINIMIZE BENDS.
- ALL CONDUITS PENETRATING THE BUILDING ENVELOPE BELOW GRADE SHALL FOLLOW WATERPROOFING REQUIREMENTS IN THE ARCHITECTURAL DRAWINGS.

NEUTRALS

- AT CONTRACTORS OPTION, NEUTRALS MAY BE SHARED ON COMBINED HOMERUNS UNLESS THE CIRCUIT HAS A GFCI BREAKER, AN ISOLATED GROUND, OR IS FROM A PANEL WITH TVSS PROTECTION. ANY NEUTRAL DOWNSTREAM FROM A DIMMER SHALL BE DEDICATED TO THE DIMMED LOAD.
- NEUTRAL WIRES SHOWN FOR TWO AND THREE POLE MECHANICAL AND KITCHEN EQUIPMENT MAY BE OMITTED UPON VERIFICATION THAT THEY ARE NOT REQUIRED EITHER FOR OPERATION OR CONTROL CIRCUITS PER MANUFACTURER'S SPECIFICATIONS.

LIGHTING

- PROVIDE LIGHT FIXTURES WITH PROPER FITTING FLANGES, MOUNTING SUPPORTS, AND ACCESSORY ITEMS, UL LISTED FOR CONDITIONS OF USE.

LOW VOLTAGE LIGHTING

- PROVIDE LOW VOLTAGE TRANSFORMERS IN NEARBY ACCESSIBLE CEILING SPACE.
- PROVIDE LOW VOLTAGE CONDUCTORS SIZED PER MANUFACTURER'S GUIDELINES TO MINIMIZE VOLTAGE DROP.

LIGHTING CONTROL

- THE MAXIMUM LIGHTING POWER THAT MAY BE CONTROLLED FROM A SINGLE SWITCH OR AUTOMATIC CONTROL SHALL NOT EXCEED THAT WHICH IS PROVIDED BY A TWENTY AMPERE CIRCUIT LOADED TO NOT MORE THAN EIGHTY PERCENT. A MASTER CONTROL MAY BE INSTALLED PROVIDED THE INDIVIDUAL SWITCHES RETAIN THEIR CAPABILITY TO FUNCTION INDEPENDENTLY.
- EMERGENCY FIXTURES: EMERGENCY BATTERY/CHARGER SHALL BE CONNECTED TO AN UNSWITCHED LEG OF THE DESIGNATED CIRCUIT.

GENERAL REQUIREMENTS

- DRAWINGS ARE DIAGRAMMATIC, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT, AND EQUIPMENT REQUIRED.
- THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS.
- REFER TO MANUFACTURER'S STANDARD INSTALLATION DRAWINGS FOR EQUIPMENT CONNECTIONS AND INSTALLATION REQUIREMENTS.
- PROVIDE CONNECTIONS, ACCESSORIES, OFFSETS, AND MATERIALS NECESSARY FOR A COMPLETE SYSTEM.

CONTRACTOR SUBSTITUTIONS & REVISIONS

- PLEASE SUBMIT PROPOSALS FOR SUBSTITUTIONS OR REVISIONS FOR REVIEW AND APPROVAL PRIOR TO ORDERING MATERIAL OR DOING WORK.
- FOR EQUIPMENT THAT IS SCHEDULED BY MANUFACTURER'S NAME AND CATALOG DESIGNATIONS, THE MANUFACTURER'S PUBLISHED DATA AND/OR SPECIFICATION FOR THAT ITEM ARE CONSIDERED PART OF SPECIFICATION.
- ENGINEERING COSTS FOR REVISING MEP PLANS SHALL BE ADDRESSED IN THE COST ANALYSIS OF THE SUBSTITUTION PROPOSAL.
- CONTRACTOR TO COORDINATE WITH ENGINEER AND DETERMINE ASSOCIATED DESIGN AND PERMITTING COSTS. CONTRACTOR SHALL BE RESPONSIBLE FOR OTHER COSTS ASSOCIATED WITH UNFORESEEN ISSUES RESULTING FROM SUBSTITUTIONS OR REVISIONS.

PRE-CON MEETING NOTES

CONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH THE ENGINEER FOR THE PURPOSE OF REVIEWING THE WORK PRIOR TO ORDERING ANY EQUIPMENT OR PERFORMING ANY WORK. THE MEETING SHALL BE LOCATED AT THE PROJECT SITE ON A DATE AND TIME TO BE MUTUALLY AGREED. THE MEETING WILL BE A WORKING SESSION. THE MEETING WILL BE FACILITATED BY THE ENGINEER AND THE AGENDA WILL INCLUDE A DETAILED REVIEW OF THE PLANS AND SPECIFICATIONS, CROSS CHECK WITH OTHER TRADES FOR COORDINATION ISSUES, REVIEW OF PROPOSED PRODUCTS, REVIEW OF PLANNED MEANS AND METHODS, AND ON-SITE INVESTIGATION OF FIELD CONDITIONS RELATIVE TO EXISTING CONDITIONS THAT COULD AFFECT THE WORK. PERSONS ATTENDING THE MEETING SHALL BE KNOWLEDGEABLE OF THE PROJECT AND SHALL BE THE SPECIFIC PERSONS INTENDED TO CONTINUE WITH THE PROJECT THROUGH TO COMPLETION. IF REQUIRED, REVISED PLANS WILL BE ISSUED THROUGH OFFICIAL CHANNELS. CHANGES IN THE BID PRICE WILL BE DISCUSSED, BUT NO CHANGE ORDERS WILL BE ISSUED UNLESS PROCESSED THROUGH OFFICIAL CHANNELS. IT SHALL BE UNDERSTOOD THAT THE ENGINEER HAS NO AUTHORITY TO ISSUE CHANGE ORDERS.

THE FOLLOWING TRADES SHALL BE REPRESENTED FOR THE MINIMUM TIME INDICATED:

MECHANICAL SHEET METAL	4 HOURS
PLUMBING/PIPING	4 HOURS
ELECTRICAL	4 HOURS
SPRINKLER	2 HOURS
GENERAL CONTRACTOR	ALL SESSIONS


DRAWING INDEX

DWG	DESCRIPTION	INCLUDED IN SET			
		PERMIT REVIEW SET 10/06/23	PERMIT SET 02/15/24		
E0.00	LEGEND, GENERAL NOTES, DRAWING INDEX	X	X		
E0.01	PROJECT NOTES	X	X		
E0.10	SITE POWER PLAN - EAST	X	X		
E0.11	SITE LIGHTING PLAN - EAST	X	X		
E1.01	LIGHTING & PHOTOMETRIC PLAN-1ST FLOOR	X	X		
E1.02	LIGHTING PLAN - 2ND & 3RD FLOOR	X	X		
E1.50	LIGHTING NOTES & LUMINAIRE SCHEDULES	X	X		
E3.00	POWER PLAN - BASEMENT & 1ST FLOOR	X	X		
E3.01	POWER PLAN - 2ND & 3RD FLOOR	X	X		
E3.02	POWER PLAN - ROOF	X	X		
E5.00	UNIT PLANS NOTES	X	X		
E5.01	UNIT PLANS & SCHEDULES	X	X		
E5.02	UNIT PLANS & SCHEDULES	X	X		
E6.00	ONE-LINE DIAGRAM & NOTES	X	X		
E6.00	PANELS SCHEDULES	X	X		

Separate electrical permit is required with Washington State Department of Labor & Industries.

<https://lni.wa.gov/licensing-permits/electrical/electrical-perm-its-fees-and-inspections> or Licensing information: Call 1-800-647-0982

NO.	DATE	DESCRIPTION



DRAWN: KL
DESIGNED: MHS
CHECKED: PSR
APPROVED: JAY

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206)364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24

SHEET TITLE:
LEGEND, GENERAL NOTES, DRAWING INDEX

SHEET NO.
E0.00

APPLICABLE CODES

THE FOLLOWING PROJECT DESIGN IS BASED ON THE FOLLOWING CODES:
 -2020 NATIONAL ELECTRICAL CODE (NEC)
 -2018 WASHINGTON STATE ENERGY CODE (WSEC)
 -2018 INTERNATIONAL BUILDING CODE (IBC) & WASHINGTON STATE AMENDMENTS
 -2018 INTERNATIONAL FIRE CODE (IFC) & WASHINGTON STATE AMENDMENTS
 -2018 INTERNATIONAL MECHANICAL CODE (IMC) & WASHINGTON STATE AMENDMENTS
 -2018 UNIFORM PLUMBING CODE (UPC) & WASHINGTON STATE AMENDMENTS

VIBRATION AND ACOUSTICAL ISOLATION

THE FOLLOWING MEASURES SHALL BE TAKEN TO MINIMIZE VIBRATION AND NOISE TRANSMISSION FROM MECHANICAL AND ELECTRICAL EQUIPMENT TO THE INTERIOR SPACES:

TRANSFORMERS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.
- B) MOUNT TRANSFORMERS ON NEOPRENE GROMMET ISOLATORS.

SUBDUCT EXHAUST FANS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.

ENCLOSED GARAGE EXHAUST FANS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.

ROOFTOP AIR HANDLERS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.

FAN COIL UNITS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.

ROOF MOUNTED CONDENSERS:

- A) PROVIDE FLEXIBLE CONDUIT OR MC CABLE AT EQUIPMENT CONNECTION.

FLEXIBLE CONDUIT OR MC CABLE CONNECTIONS FOR VIBRATION ISOLATION SHALL BE A MINIMUM OF TWO FEET LONG.



TEMPERATURE LIMITATION OF CONDUCTORS

ADDITIONAL ADJUSTMENTS FOR CONDUITS EXPOSED TO SUNLIGHT ON OR ABOVE ROOFTOPS SHALL BE FACTORED PER NEC TABLE 310.15(B)(2)(C)

CONDUIT & CONDUCTOR FIRE RATING

1. CONDUIT FOR ELECTRICAL CONDUCTORS BY THE FACP OR FIRE ALARM SYSTEM SHALL BE IN 2 HOUR RATED ENCLOSURES OR ENCASED IN 2-INCH OF CONCRETE AND RATED CABLE ASSEMBLIES, OR BE CONDUCTORS IN 2 HOUR-RATED RACEWAYS PER NFPA 72.
2. THE EQUIPMENT AND CONTROL WIRING SHALL BE ENCLOSED BY FIRE BARRIERS CONSTRUCTED IN ACCORDANCE WITH IBC SECTION 707 OR HORIZONTAL ASSEMBLIES CONSTRUCTED IN ACCORDANCE WITH IBC SECTION 711, OR USING A 2 HR RATED CABLE SYSTEM OR ENCLOSED WITHIN 2" OF CONCRETE.
3. FIRE ALARM WIRING SHALL COMPLY WITH IBC 907.6.1. WIRING SHALL COMPLY WITH THE REQUIREMENTS OF NFPA 70.
4. RACEWAYS FOR THE DEDICATED BRANCH CIRCUIT(S) REQUIRED FOR PRIMARY POWER TO THE FIRE ALARM CONTROL PANEL (FACP) SHALL BE IN 2 HOUR RATED ENCLOSURES OR ENCASED IN 2-INCH OF CONCRETE AND RATED CABLE ASSEMBLIES, OR BE CONDUCTORS IN 2 HOUR-RATED RACEWAYS PER IBC 907 AND NFPA 72 SECTION 10.6.11.3.1.3

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24

SHEET TITLE:
 LEGEND, GENERAL NOTES, DRAWING INDEX

SHEET NO.
E0.01





SHEET NOTES:

1. EV CHARGER LOCATIONS:
 - 1.1. PROVIDE PRE-FABRICATED EV CHARGING STATION.
 - 1.2. FOUNDATION TO INCLUDE ACCESSIBLE UNDERGROUND PULLBOX, CONDUIT ENTRY PORTS AND COVERPLATE DESIGNED FOR DIRECT-MOUNTING EV CHARGER PEDESTAL.
 - 1.3. PROVIDE FOUNDATION PRODUCTS BY BREEZE-EV, EV-BLOCKS OR EQUIVALENT.
 - 1.4. IF FOUNDATION IS INSTALLED LESS THAN 2'-0" FROM THE EDGE OF THE CURB, THEN PROVIDE A BOLLARD AT EACH CORNER OF THE FOUNDATION THAT COMPLIES WITH 2018 IBC 1607.9
2. (F) DUAL EV CHARGING STATIONS: PROVIDE 1-1/4" CONDUIT WITH PULL WIRE FROM EV PANEL(S) IN ELECTRICAL ROOM AS INDICATED.
3. DUAL EV CHARGING STATIONS: PROVIDE AND INSTALL 1-1/4" CONDUIT, CONDUCTORS, AND REQUIRED BREAKERS FOR DUAL EV CHARGING STATIONS.

SITE POWER PLAN - EAST

SCALE: 1/32" = 1'-0"

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24


SHEET TITLE:
SITE POWER - EAST SITE PLAN

SHEET NO.
E0.10



SITE LIGHTING PLAN – EAST
SCALE: 1/32" = 1'-0"

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24


SHEET TITLE:
SITE LIGHTING - EAST SITE PLAN

SHEET NO.
E0.11




LIGHTING PLAN – BASEMENT

SCALE: 1/8" = 1'-0"



GENERAL NOTES	
1.	EMERGENCY EGRESS LIGHTING: EMERGENCY LUMINAIRE(S) WITH 90 MINUTE BATTERY BACKUP.
2.	REFER TO SERIES E500 DRAWINGS FOR TYPICAL UNIT PLANS SHOWING ELECTRICAL AND LIGHTING LAYOUT.
3.	SEE SHEET E1.50 FOR LUMINAIRE SCHEDULE AND LIGHTING NOTES.

FLAG NOTES	
1.	CIRCUIT STAIRS VERTICALLY. LUMINAIRE(S) IN STAIRWELL
2.	EXIT SIGNS: PROVIDE UNSWITCHED HOT.



PHOTOMETRIC PLAN – BASEMENT


SCALE: 1/8" = 1'-0"



*Egress Stair
Photometric Schedule*

AVERAGE FOOT-CANDLES	5.60
MAXIMUM FOOT-CANDLES	9.0
MINIMUM FOOT-CANDLES	1.6
MINIMUM TO MAXIMUM FC RATIO	0.18
MAXIMUM TO MINIMUM FC RATIO	5.69
AVERAGE TO MINIMUM FC RATIO	3.53

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	KL
DESIGNED:	MHS
CHECKED:	PSR
APPROVED:	JAY

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24


SHEET TITLE:
LIGHTING & PHOTOMETRIC PLAN - 1ST FLOOR

SHEET NO.
E1.01



LIGHTING PLAN – 1ST FLOOR

SCALE: 1/8" = 1'-0"



PHOTOMETRIC PLAN – 1ST FLOOR

SCALE: 1/8" = 1'-0"



GENERAL NOTES	
1.	EMERGENCY EGRESS LIGHTING: EMERGENCY LUMINAIRES WITH 90 MINUTE BATTERY BACKUP.
2.	REFER TO SERIES E500 DRAWINGS FOR TYPICAL UNIT PLANS SHOWING ELECTRICAL AND LIGHTING LAYOUT.
3.	SEE SHEET E1.50 FOR LUMINAIRE SCHEDULE AND LIGHTING NOTES.

FLAG NOTES	
1.	CIRCUIT STAIRS VERTICALLY. LUMINAIRE(S) IN STAIRWELL
2.	EXIT SIGNS: PROVIDE UNSWITCHED HOT.

Egress Stairs
Photometric Schedule

AVERAGE FOOT-CANDLES	11.08
MAXIMUM FOOT-CANDLES	13.9
MINIMUM FOOT-CANDLES	6.1
MINIMUM TO MAXIMUM FC RATIO	0.44
MAXIMUM TO MINIMUM FC RATIO	2.28
AVERAGE TO MINIMUM FC RATIO	1.82


Egress Corridor
Photometric Schedule

AVERAGE FOOT-CANDLES	4.18
MAXIMUM FOOT-CANDLES	6.6
MINIMUM FOOT-CANDLES	2.9
MINIMUM TO MAXIMUM FC RATIO	0.44
MAXIMUM TO MINIMUM FC RATIO	2.28
AVERAGE TO MINIMUM FC RATIO	1.44

Egress Long Stairs
Photometric Schedule

AVERAGE FOOT-CANDLES	6.46
MAXIMUM FOOT-CANDLES	12.0
MINIMUM FOOT-CANDLES	1.9
MINIMUM TO MAXIMUM FC RATIO	0.16
MAXIMUM TO MINIMUM FC RATIO	6.36
AVERAGE TO MINIMUM FC RATIO	3.43

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	KL
DESIGNED:	MHS
CHECKED:	PSR
APPROVED:	JAY

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.


DATE: 02/15/24

SHEET TITLE:
LIGHTING PLAN - 2ND & 3RD FLOOR

SHEET NO.
E1.02





LIGHTING PLAN - 3RD FLOOR
SCALE: 1/8" = 1'-0"



LIGHTING PLAN - 2ND FLOOR
SCALE: 1/8" = 1'-0"

- GENERAL NOTES
- EMERGENCY EGRESS LIGHTING: EMERGENCY LUMINAIRES WITH 90 MINUTE BATTERY BACKUP.
 - REFER TO SERIES E500 DRAWINGS FOR TYPICAL UNIT PLANS SHOWING ELECTRICAL AND LIGHTING LAYOUT.
 - SEE SHEET E1.50 FOR LUMINAIRE SCHEDULE AND LIGHTING NOTES.
- FLAG NOTES
- CIRCUIT STAIRS VERTICALLY. LUMINAIRE(S) IN STAIRWELL
 - EXIT SIGNS: PROVIDE UNSWITCHED HOT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206/364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24

SHEET TITLE:
LIGHTING PLAN - 2ND & 3RD FLOOR

SHEET NO.
E1.03

EXTERIOR LUMINAIRE SCHEDULE									
CALLOUT	SYMBOL	MOUNTING	DESCRIPTION	MODEL	VOLTAGE	TYPE	CRI / CCT	LAMPING	WATTAGE
SP1		16' POLE	POLE LIGHT - PARKING & DRIVE AISLE - COMFORT OPTICS - B2 U0 G2	GARDCO: P20 C A02 830 T1S AR1 120 BL30-MW PCB	MULTIPLE	INTEGRAL CONTROLS	80 / 3000K	(1) 36W LED	36
SW1		SURFACE - 12' AFF	WALL SCONCE - AREA LIGHT - B1 U0 G1	GARDCO: GWM A06 830 T3M 120 MW30 PCB	120	INTEGRAL CONTROLS	80 / 3000K	(1) 16W LED	16

- NOTES:
- CONTRACTOR TO FURNISH AND INSTALL ALL FIXTURES.
 - LUMINAIRE SCHEDULE IS BOD ONLY. CONTRACTOR TO SUBMIT FIXTURE MODEL OR EQUIVALENT. CONTRACTOR TO COORDINATE FIXTURE FINISHES WITH ARCHITECT/OWNER.
 - FIXTURE CATALOG NUMBERS DO NOT NECESSARILY DENOTE SPECIFIC MOUNTING ACCESSORIES. CONTRACTOR TO PROVIDE ALL NECESSARY ACCESSORIES TO SUCCESSFULLY COMPLETE THE INSTALLATION.
 - 'BUG' RATING ON EXTERIOR FIXTURES INDICATES 'BACKLIGHT', 'UPLIGHT', AND 'GLARE' AS STANDARDS IN CLASSIFYING OUTDOOR LIGHT FIXTURES.

GENERAL LUMINAIRE SCHEDULE									
CALLOUT	SYMBOL	MOUNTING	DESCRIPTION	MODEL	VOLTAGE	TYPE	CRI / CCT	LAMPING	WATTAGE
B1		SURFACE	4" NARROW WRAP - BOH	DAY-BRITE CFI: FSW440L835 UNV DIM	120	0-10V DIMMING	80 / 3000K	(1) 31.4W LED	31.4
C1E		SURFACE	4" SURFACE DOWNLIGHT	DMF: DRDH N JO 70S EM / DRD5S 4 R 07 9 30 EM	120	0-10V DIMMING	90 / 3000K	(1) 9W LED	9
D1		RECESSED	RECESSED DOWNLIGHT - SLOPED CEILING	DMF: DRD4M 10 9 30 FL X 0 / DRDH N JS 1004	120	0-10V DIMMING	90 / 3000K	(1) 12W LED	12
P1		PENDANT	STEM MOUNT DOWNLIGHT - SLOPED CEILING - 4' STEM	DMF: DCR T4 S X A 30 FL 0 00 30 XX 0 00 [FINISH]	120	0-10V DIMMING	90 / 3000K	(1) 40W LED	40
WS1		SURFACE	WALL SCONCE - EM BATTERY BACKUP	TBD	120	TBD DIMMING	TBD / TBD	(1) 5W LED	5
X1		SURFACE	EXIT SIGN - EMERGENCY BATTERY BACKUP - HATCH INDICATES LIT FACE	LSI: EMS WB SERIES (OR EQUAL)	MULTIPLE	EM	EM / EM	(1) 5W EM	5
X2		SURFACE	COMBO EXIT SIGN	LSI: CEC (OR EQUAL)	MULTIPLE	EM	EM / EM	(1) 5W EM	5
X3		SURFACE	EMERGENCY LIGHT - EMERGENCY BATTERY BACKUP - DAMP LOCATION RATED - MAX 35' SPACING	LITHONIA: ELM2LF (OR EQUAL)	120	EM	EM / EM	(1) 5W EM	5
X4		WALL	EXTERIOR EMERGENCY LIGHT - EMERGENCY ON ONLY - MAX SPACING 35'	NORA LIGHTING: NE-902LED	120	EM	35' MAX SPACING	(1) 5W LED	5
Z1E		WALL	WALL PACK	LITHONIA: WPX1 LED P1 30K MVOLT	120	EM	70 / 3000K	(1) 11W LED	11

- NOTES:
- CONTRACTOR TO FURNISH AND INSTALL ALL FIXTURES.
 - LUMINAIRE SCHEDULE IS BOD ONLY. CONTRACTOR TO SUBMIT FIXTURE MODEL OR EQUIVALENT. CONTRACTOR TO COORDINATE FIXTURE FINISHES WITH ARCHITECT/OWNER.
 - FIXTURE CATALOG NUMBERS DO NOT NECESSARILY DENOTE SPECIFIC MOUNTING ACCESSORIES. CONTRACTOR TO PROVIDE ALL NECESSARY ACCESSORIES TO SUCCESSFULLY COMPLETE THE INSTALLATION.


LIGHTING CONTROLS LEGEND		
SYMBOL	CONTROL TYPE	CONTROL FUNCTION
	TOGGLE SWITCH	MANUAL ON/OFF LIGHTING CONTROL. SUBSCRIPT INDICATES WHICH FIXTURES ARE TO BE CONTROLLED BY WHICH SWITCH (WSEC C405.2.3). SUBSCRIPT 'k' INDICATES TAMPER RESISTANT KEYED SWITCH FOR USE BY AUTHORIZED PERSONNEL ONLY.
	DIMMER SWITCH	MANUAL MULTI-LEVEL LIGHTING CONTROL. SWITCH SHALL ALSO HAVE MANUAL ON/OFF FUNCTIONALITY. SUBSCRIPT INDICATES WHICH FIXTURES ARE TO BE CONTROLLED BY WHICH DIMMER. (C405.2.3)
	TOGGLE/DIMMER SWITCH WITH OCCUPANCY SENSOR	SWITCHES LABELED 'os' OR 'vs' SHALL TURN OFF ALL CONNECTED LUMINAIRES WITHIN 20 MINUTES OF SPACE BEING VACANT. (C405.2.1.1)
	CONTROL STATION; SEE LIGHTING CONTROL ZONE TABLE ON PLANS.	MANUAL LOCAL LIGHTING CONTROL (C405.2.1.1). CONTROL STATION SHALL HAVE CAPACITY TO CONTROL MULTIPLE ZONES AND MULTIPLE SCENES AS NEEDED. SUBSCRIPT CORRESPONDS TO 'LIGHTING CONTROLS' TABLE ON PLANS.
	SURFACE MOUNTED OCCUPANCY SENSOR	AUTOMATIC LIGHTING CONTROL SHALL TURN OFF ALL CONNECTED LUMINAIRES WITHIN 20 MINUTES OF SPACE BEING VACANT. (C404.2.1.1)
	MULTIZONE PHOTOSENSOR	AUTOMATIC LIGHTING CONTROL SHALL AUTOMATICALLY ADJUST THE LIGHT OUTPUT OF ALL CONNECTED LUMINAIRES BASED ON THE DAYLIGHT LEVEL IN THE PRIMARY AND SECONDARY ZONES (C405.2.4). SUBSCRIPT INDICATES WHICH FIXTURES ARE TO BE CONTROLLED BY ZONE; 'x' INDICATES MULTIPLE ZONE CONTROL.

- ### GENERAL LIGHTING NOTES
- LIGHTING CONTROLS SHALL BE INSTALLED WHICH MEET ALL REQUIREMENTS OF LOCAL ENERGY CODES.
 - EMERGENCY LIGHT FIXTURES: IN ADDITION TO SWITCH-LEG, PROVIDE UNSWITCHED HOT TO SERVE INTERNAL BATTERY AND CHARGER.
 - LOCATIONS OF OCCUPANCY SENSORS, PHOTO SENSORS, DIMMERS, AND SWITCHES ARE DIAGRAMMATIC. CONTRACTOR TO COORDINATE QUANTITIES AND OPTIMAL LOCATIONS WITH LIGHTING CONTROL MANUFACTURER AND ARCH/OWNER.
 - AUTOMATIC LIGHTING SHUT-OFF CONTROLS SHALL BE PROVIDED BY LOCAL OCCUPANCY SENSORS UNLESS OTHERWISE NOTED. PUBLIC SPACES ARE ACTIVE 24/7 AND THEREFORE EXEMPT FROM AUTOMATIC LIGHTING SHUT-OFF REQUIREMENTS FOR SECURITY. (WSEC C405.2)
 - DAYLIGHT ZONES ARE SHOWN ON PLANS AS DEFINED BY WASHINGTON STATE ENERGY CODE (WSEC) C405.2.4.2. SIDELIGHT DAYLIGHT ZONES ARE REFERRED TO AS 'PRIMARY' AND 'SECONDARY' ON PLANS AND DENOTED BY DASHED LINES.
 - FOR CUSTOM FF&E FIXTURES, IT IS THE MANUFACTURER'S RESPONSIBILITY TO FURNISH PRODUCTS WHICH ARE COMPLIANT WITH ALL REQUIREMENTS OF LOCAL ENERGY CODES, AS WELL AS MATCH THE ELECTRICAL SPECIFICATIONS PROVIDED IN THE LUMINAIRE SCHEDULES. PROVIDE SUBMITTAL SHOP DRAWINGS WITHIN 30 DAYS OF RECEIVING FIXTURE ORDER. SUBMITTALS SHALL CLEARLY INDICATE LAMPING AND MAXIMUM WATTAGE RATING OF LAMP SOCKETS. NON-COMPLIANT FIXTURES REJECTED BY ELECTRICAL INSPECTOR SHALL BE RETURNED TO THE MANUFACTURER FOR REWORKING AND/OR RE-LABELING.
 - ALL FIXTURES SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS.
 - CONTRACTOR SHALL BE RESPONSIBLE TO ORDER ALL NECESSARY HARDWARE, ELECTRICAL CABLE, TIMERS, TRANSFORMERS, ETC., AS REQUIRED FOR COMPLETION OF INSTALLATION OF A FULLY FUNCTIONING SYSTEM.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR EQUIPPING ALL FIXTURES WITH THE EXACT LAMPS SPECIFIED IN THE FIXTURE SCHEDULE.
 - WHERE FIXTURES REQUIRE REMOTE TRANSFORMERS OR BALLASTS, THE CONTRACTOR SHALL DETERMINE LOCATIONS AS REQUIRED FOR EVEN LOAD DISTRIBUTION, SERVICE ACCESS, AND VENTILATION.
 - THE CONTRACTOR SHALL COORDINATE WITH THE ELECTRICAL ENGINEER FOR EXACT LOCATIONS OF TIMERS AND/OR PHOTO CELLS, IF ANY.
 - WHERE APPLICABLE, THE CONTRACTOR SHALL AIM AND ADJUST LIGHTING FIXTURES AS DIRECTED BY THE LIGHTING DESIGNER UPON COMPLETION OF THE INSTALLATION.
- SPECIAL NOTE TO THE CONTRACTOR:**
- FIXTURE SUBMITTALS THAT DO NOT INCLUDE LAMP SPECIFICATIONS WILL BE CONSIDERED INCOMPLETE AND WILL NOT BE REVIEWED.

- ### LIGHTING CONTROL SYSTEM REQUIREMENTS
- CONTRACTOR TO PROVIDE A FULLY OPERATIONAL LIGHTING CONTROL SYSTEM.
 - CONTRACTOR SHALL VERIFY THE COMPATIBILITY OF DIMMING AND CONTROL MODULES WITH FIXTURE TYPES PRIOR TO INSTALLATION.
 - ELECTRICAL CONTRACTOR SHALL COORDINATE WITH A LIGHTING CONTROLS VENDOR TO OBTAIN LIGHTING CONTROL SYSTEM PACKAGE COMPLETE WITH DEVICES, WIRING DIAGRAMS, ANNOTATED PLANS INDICATING WHICH DEVICE TO BE USED IN EACH LOCATION, CONNECTION REQUIREMENTS, SET UP INSTRUCTIONS, COMMISSIONING AND CHECK-OUT FOLLOWING COMPLETION. PROVIDE ALL LOW VOLTAGE WIRING AS REQUIRED FOR CONTROL DEVICE INTERCONNECTIONS.
 - INSTALLER QUALIFICATIONS: TECHNICIAN INSTALLING AND WIRING THE LIGHTING CONTROL SYSTEM SHALL HAVE INSTALLED THIS SAME SYSTEM AT LEAST ONCE PREVIOUSLY. TECHNICIAN SHALL HAVE RECEIVED TRAINING BY FACTORY REPRESENTATIVE ON THE SYSTEM BEING INSTALLED.
 - PROVIDE LIGHTING CONTROL SYSTEM TO PERFORM THE FUNCTIONS DESCRIBED BELOW:
 - LIGHTING CONTROL SCHEDULE: PROVIDE SEPARATE SWITCHING AND DIMMING CONTROL FOR LIGHTING ZONES AS INDICATED.
 - AUTOMATIC LIGHTING CONTROLS:
 - UNLESS OTHERWISE NOTED ON PLANS, OCCUPANCY SENSORS SHALL AUTOMATICALLY TURN OFF ALL CONNECTED LIGHTING WITHIN 20 MINUTES OF SPACE BEING UNOCCUPIED. OCCUPANCY SENSORS SHALL EITHER BE MANUAL ON OR SHALL BE CONTROLLED TO AUTOMATICALLY TURN THE LIGHTING ON TO NOT MORE THAN 50 PERCENT POWER EXCEPT WHERE MANUAL ON WOULD ENDANGER THE SAFETY OR SECURITY OF THE ROOM OR BUILDING OCCUPANTS. (C405.2.1.1)
 - MULTI-ZONE PHOTO-SENSORS SHALL PROVIDE SEPARATE CONTROL FOR LUMINAIRES IN EACH TYPE OF DAYLIGHT ZONE. (C405.2.4.1)
 - EXTERIOR LIGHTING CONTROLS SHALL AUTOMATICALLY TURN OFF ALL EXTERIOR LIGHTING AS A FUNCTION OF AVAILABLE DAYLIGHT. BUILDING FACADE AND LANDSCAPE LIGHTING SHALL HAVE CONTROLS THAT AUTOMATICALLY SHUT OFF THE LIGHTING FOR A MINIMUM OF 6 HOURS PER NIGHT OR NOT LATER THAN ONE HOUR AFTER BUSINESS CLOSING TO NOT EARLIER THAN ONE HOUR BEFORE BUSINESS OPENING, WHICHEVER IS LESS. OTHER LIGHTING SHALL HAVE CONTROLS CONFIGURED TO AUTOMATICALLY REDUCE THE CONNECTED LIGHTING POWER BY AT LEAST 30 PERCENT FROM NO LATER THAN 12 MIDNIGHT TO 6 AM OR FROM ONE HOUR AFTER BUSINESS CLOSING TO ONE HOUR BEFORE BUSINESS OPENING OR DURING ANY PERIOD WHEN NO ACTIVITY HAS BEEN DETECTED FOR A TIME OF NO LONGER THAN 15 MINUTES. (C405.2.6)
 - MEANS OF EGRESS ILLUMINATION: AT ANY TIME THE BUILDING IS OCCUPIED, THE MEANS OF EGRESS SHALL BE ILLUMINATED AT AN INTENSITY OF NOT LESS THAN 1 FOOTCANDLE AT FLOOR LEVEL. (IBC 1008.2.1)
 - DURING EMERGENCY CONDITIONS EMERGENCY LIGHTING CIRCUITS SHALL BYPASS ALL LIGHTING CONTROLS IN ORDER TO ENERGIZE ALL CONNECTED LUMINAIRES AT FULL CAPACITY. PROVIDE UL924 RELAYS AS REQUIRED TO BYPASS AREA CONTROLS.
 - EMERGENCY PATHWAY EGRESS LIGHTING: ILLUMINATION PROVIDED ALONG THE EGRESS PATH AT FLOOR LEVEL SHALL AVERAGE AT LEAST 1 FOOT CANDLE. (IBC 1008.3.5)
 - EMERGENCY LIGHTING SHALL BE SUPPLIED BY: ELECTRICAL CONTRACTOR

- ### EXIT SIGN NOTES
- DURING CONSTRUCTION UPON COMPLETION OF A TYPICAL FLOOR FRAMING AND BEFORE WALL COVER, ELECTRICAL CONTRACTOR SHALL WALK THE EGRESS PATHS WITH THE LOCAL INSPECTOR (AHJ) TO CONFIRM THAT ALL THE EXIT SIGNS ARE LOCATED PER THE AHJ'S SATISFACTION AND IDENTIFY ANY ADDITIONAL EXIT SIGNS THAT THE AHJ WISHES TO BE INSTALLED (IBC 1013.1); CONTRACTOR SHALL PROVIDE UP TO 10% ADDITIONAL EXIT SIGNS AT NO ADDITIONAL COST.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206)364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24


SHEET TITLE:
LIGHTING PLAN - 3RD FLOOR

SHEET NO.
E1.50



POWER PLAN - 1ST FLOOR

SCALE: 1/8" = 1'-0"



POWER PLAN - BASEMENT

SCALE: 1/8" = 1'-0"



SHEET NOTES:


1. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10

FLAG NOTES:

(NOT EVERY FLAG IS USED ON EVERY SHEET)

1. FUTURE EV CHARGING STATIONS: PROVIDE 1-1/4" CONDUIT WITH PULL WIRE FROM EV PANEL(S) IN MAIN ELECTRICAL ROOM. TERMINATE CONDUIT IN A J-BOX ON WALL FOR FUTURE USE.
2. PROVIDE 2 1/2" C WITH PULL STRING WEATHER CAP TO ROOF FOR FUTURE SOLAR PATHWAY. COORDINATE RISER LOCATION WITH ARCHITECT.
3. LOCATION OF FIRE ALARM PANEL TO BE COORDINATED BY FIRE ALARM CONTRACTOR WITH FIRE AUTHORITIES.
4. SPACE FOR FUTURE SOLAR EQUIPMENT.
5. PROVIDE LEVEL ACCESS SURFACE IN FRONT OF ELECTRICAL EQUIPMENT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA


ROBISON ENGINEERING, INC.

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

DATE: 02/15/24


SHEET TITLE:
**POWER PLAN
 - 1ST & 2ND
 FLOOR**

SHEET NO.
E3.00



POWER PLAN – 3RD FLOOR

SCALE: 1/8" = 1'-0"



POWER PLAN – 2ND FLOOR

SCALE: 1/8" = 1'-0"



SHEET NOTES:


1. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10

FLAG NOTES:

(NOT EVERY FLAG IS USED ON EVERY SHEET)

1. FUTURE EV CHARGING STATIONS: PROVIDE 1-1/4" CONDUIT WITH PULL WIRE FROM EV PANEL(S) IN MAIN ELECTRICAL ROOM. TERMINATE CONDUIT IN A J-BOX ON WALL FOR FUTURE USE.
2. PROVIDE 2 1/2" C WITH PULL STRING WEATHER CAP TO ROOF FOR FUTURE SOLAR PATHWAY. COORDINATE RISER LOCATION WITH ARCHITECT.
3. LOCATION OF FIRE ALARM PANEL TO BE COORDINATED BY FIRE ALARM CONTRACTOR WITH FIRE AUTHORITIES.
4. SPACE FOR FUTURE SOLAR EQUIPMENT.
5. PROVIDE LEVEL ACCESS SURFACE IN FRONT OF ELECTRICAL EQUIPMENT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24

SHEET TITLE:
POWER PLAN - 2ND & 3RD FLOOR

SHEET NO.
E3.01



POWER PLAN – ROOF

SCALE: 1/8" = 1'-0"




SHEET NOTES:

1. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10

FLAG NOTES: (NOT EVERY FLAG IS USED ON EVERY SHEET)

1. FUTURE EV CHARGING STATIONS: PROVIDE 1-1/4" CONDUIT WITH PULL WIRE FROM EV PANEL(S) IN MAIN ELECTRICAL ROOM. TERMINATE CONDUIT IN A J-BOX ON WALL FOR FUTURE USE.
2. PROVIDE 2 1/2" C WITH PULL STRING WEATHER CAP TO ROOF FOR FUTURE SOLAR PATHWAY. COORDINATE RISER LOCATION WITH ARCHITECT.
3. LOCATION OF FIRE ALARM PANEL TO BE COORDINATED BY FIRE ALARM CONTRACTOR WITH FIRE AUTHORITIES.
4. SPACE FOR FUTURE SOLAR EQUIPMENT.
5. PROVIDE LEVEL ACCESS SURFACE IN FRONT OF ELECTRICAL EQUIPMENT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24

SHEET TITLE:
**POWER PLAN
- ROOF**

SHEET NO.
E3.02

UNIT LUMINAIRE SCHEDULE


CALLOUT	SYMBOL	MOUNTING	DESCRIPTION	MODEL	VOLTAGE	TYPE	LAMPING	WATTAGE	NOTES
U1	○	CEILING	4" DOWNLIGHT	DMF: DRD5S-4-R-10-9-30-0	120	0-10V DIMMING	(1) 12W LED 3000K	12	
U2	○	CEILING	4" DOWNLIGHT WET RATED	DMF: DRD5S-4-S-10-9-30-0	120	0-10V DIMMING	(1) 12W LED 3000K	12	
U3	⏏	WALL	24" VANITY LIGHT	MAXIM - 52102	120	ELV DIMMING	(1) 16W LED 3000K	16	
U4	⏏	WALL	SLIM BALCONY LIGHT	MAXIM - 26106BK	120	NON DIMMING	(1) 10W LED 3000K	10	
U5	○	SURFACE	6" FLUSH MOUNT DOWNLIGHT	MAXIM - 57413WTWT	120	0-10V DIMMING	(1) 11W LED 3000K	11	

ACCESSIBILITY NOTES:

- ALL SWITCHES AND CONTROLS - 15" MIN; 48" MAX TO CONTROL.
- GENERAL OUTLETS MIN 18" AFF.
- ALL SWITCHES/CONTROLS ABOVE COUNTERTOPS 48" MAX.
- ELECTRICAL SUB-PANELS IN UNITS MUST COMPLY WITH ABOVE REACH RANGES.
- SWITCHES FOR EXHAUST HOODS AND GARBAGE DISPOSALS MUST COMPLY WITH ABOVE REACH RANGES. INSTALL SWITCHES ON FACE OF CABINETS IF REQUIRED TO COMPLY.

APARTMENT NOTES:

- ALL ELECTRICAL WORK SHALL COMPLY WITH ALL LOCAL AND NATIONAL CODES.
- DEVICE BOXES ON OPPOSITE SIDES OF DEMISING WALLS SHALL BE IN SEPARATE STUD BAYS. PROVIDE BACKING EQUIVALENT TO LOWRY'S OUTLET BOX PADS. CONDUIT FROM ONE UNIT SHALL NOT PASS THROUGH STUDS OF A SHARED WALL(DOUBLE STUDS) FROM AN ADJACENT UNIT(BRIDGING).
- PROVIDE ARC-FAULT PROTECTION, TAMPER PROOF AND GFCI RECEPTACLES AS REQUIRED BY CODE AND LOCAL AHJ. ARC-FAULT PROTECTION MUST BE PROVIDED FOR CIRCUITS IN THE AREAS LISTED IN NEC 210.12(A).
- PROVIDE SUFFICIENT DUPLEX RECEPTACLES TO MEET NEC 210.52.
- THERMOSTATS SHALL NOT INTERFERE WITH DOOR SWINGS.
- ELECTRICAL CONTRACTOR SHALL MAKE ALL FINAL CONNECTIONS FOR KITCHEN APPLIANCES. COORDINATE ALL J-BOX LOCATIONS WITH APPLIANCE INSTALLATION INSTRUCTIONS PRIOR TO ROUGH-IN.
- ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL CORD AND PLUG ASSEMBLY FOR EACH DISPOSER.
- PROVIDE A DEDICATED 20 AMP CIRCUIT TO EACH UNIT BATHROOM RECEPTACLE. BATHROOM LIGHTS, FAN TO BE ON SAME CIRCUIT PER 210.11(C)(3) EXCEPTION.
- HOME RUNS AND LOOPS CONNECTING LIGHT FIXTURES, WIRING DEVICES, AND HVAC EQUIPMENT ON PLANS INDICATE CIRCUITING SCHEME. SEE TYPICAL PANEL SCHEDULES FOR ACTUAL CIRCUIT NUMBERS FOR TYPICAL APARTMENT.
- LIGHTS WITHIN 3' HORIZONTAL OF SHOWER OR TUB TO BE WET LOCATION RATED AND HAVE FULLY ENCLOSED TRIMS. PROVIDE GFCI PROTECTION IF THE LUMINAIRE INSTALLATION MANUAL STATES IT IS REQUIRED.
- PROVIDE SMOKE DETECTORS AND CO ALARMS AS REQUIRED. DETECTORS AND ALARMS TO BE HARDWIRED AND PROVIDED WITH BATTERY BACKUP.
- ELECTRICAL CONTRACTOR SHALL INSTALL RECEPTACLES AND TV, DATA/PHONE OUTLETS UNDER COMMON COVER PLATE WHERE POSSIBLE. PROVIDE AND INSTALL DIVIDERS AS REQUIRED FOR CABLE/POWER SEPARATION.
- SEE ARCHITECTURAL DRAWINGS FOR DIMENSIONS AND LAYOUTS OF ALL DEVICES.
- ALL WALL PENETRATIONS SHALL BE CAULKED WITH APPROVED MATERIAL TO MAINTAIN THE FIRE RATING OF ALL WALLS AND FLOORS.
- ALL CONDUIT SHALL BE INSTALLED IN NEAT SYMMETRICAL LINES HORIZONTAL OR PERPENDICULAR TO BUILDING COLUMNS AND ROOF LINES. CONDUITS SHALL BE GROUPED ON COMMON SUPPORTS WHEREVER POSSIBLE.
- REFERENCE MECHANICAL DRAWINGS FOR EXACT LOCATION OF ALL MECHANICAL EQUIPMENT.
- ELECTRICAL CONTRACTOR SHALL VERIFY ALL FUSE RATING WIRE SIZES AND DISCONNECT SIZES WITH EQUIPMENT SERVED ON THE JOB PRIOR TO INSTALLATION.
- SEE ARCHITECTURAL DRAWINGS AND ELEVATIONS FOR ADDITIONAL DETAILS AND CASEWORK DIMENSIONS.
- DEVICE LOCATIONS IN 1ST DWELLING/RESIDENT UNIT SHALL BE REVIEWED AND APPROVED BY OWNER PRIOR TO ROUGH-IN OF REMAINING UNITS
- CONFIRM FINAL LOCATION OF HEATERS AND THERMOSTATS IN FIELD PRIOR TO ROUGH-IN




DWELLING UNIT VENTILATION WIRING DIAGRAM DETAIL

ELECTRIC HEATERS					
EQUIP NO.	SERVICE	MOUNTING/DISCHARGE	HEATING	ELECTRICAL	BASIS OF DESIGN
			KW	VOLTAGE	
EWH-1	BEDROOM	WALL	1	208V/1P	(1)
EWH-2	LIVING ROOM	WALL	1.5	208V/1P	(1)

- NOTES:
- (1) BROAN, CADET OR EQUIVALENT.
 - (2) PROVIDE REMOTE THERMOSTAT.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA



19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24

SHEET TITLE:
UNIT PLANS NOTES

SHEET NO.
E5.00



UNIT TYPICALS
1-BED-INT-2 TYPE 'A'
 SCALE: 1/4" = 1'-0"

UNIT TYPICALS
1-BED-INT-1 TYPE 'B'
 SCALE: 1/4" = 1'-0"

Panel 1-BED TYPE 'A'				Panel 1-BED TYPE 'B'			
ROOM MOUNTING FLUSH 'A'				ROOM MOUNTING FLUSH 'B'			
FED FROM				FED FROM			
NOTE				NOTE			
Panel	ROOM	VOLTS	208/120V 2P 3W	AIC	22,000		
	MOUNTING	BUS AMPS	125	MAIN BKR	MLO		
	FED FROM	NEUTRAL	100%	LUGS	STANDARD		
CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION	CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION
1	50/2	8	RANGE	a 2	20/1	0.23	ERV, LIGHTING, RECEPTACLE
3				b 4	20/1	0.19	LIGHTING, RECEPTACLE
5	30/2	4.99	DRYER	a 6	20/1	1.28	LIGHTING, MEDIA BOX, RECEPTACLE
7				b 8	20/1	1.5	SMALL APPLIANCE
9	20/1	1.5	WASHER	a 10	20/1	1.5	SMALL APPLIANCE
11	30/2	4.4	WATER HEATER	b 12	20/1	1.58	MICRO/HOOD
13				a 14	20/1	0.192	LIGHTING, RECEPTACLE
15	20/1	1.2	DISHWASHER	b 16	20/1	0.15	SDCO
17	20/2	0.75	WALL HEATER	a 18	20/1	0	SPARE
19				b 20	20/1	0	SPARE
21	20/1	1.34	LIGHTING, RECEPTACLE	a 22	20/1	0	SPARE
23	20/1	0.7	DISPOSAL	b 24	20/1	0	SPARE

OPTIONAL DWELLING UNIT CALCULATION (NEC 220.82)			
	CONN KVA	871 SF (3 VA/SF)	GENERAL LOAD
LIGHTING AND RECEPTACLES	2.61		UP TO 10 KVA
SMALL-APPLIANCE	3		10
LAUNDRY	1.5		OVER 10 KVA
APPLIANCES	8.47		13.6
ELECTRIC COOKING	8		5.43 (40%)
TOTAL GENERAL LOAD	23.6		3.35 (220.82(C)(4))
			TOTAL LOAD
			BALANCED LOAD
			PHASE A
			PHASE B
			18.8
			90.3 A
			102%
			97.8%

Panel 1-BED TYPE 'A'				Panel 1-BED TYPE 'B'			
ROOM MOUNTING FLUSH 'A'				ROOM MOUNTING FLUSH 'B'			
FED FROM				FED FROM			
NOTE				NOTE			
Panel	ROOM	VOLTS	208/120V 2P 3W	AIC	22,000		
	MOUNTING	BUS AMPS	125	MAIN BKR	MLO		
	FED FROM	NEUTRAL	100%	LUGS	STANDARD		
CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION	CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION
1	50/2	8	RANGE	a 2	20/1	0.23	ERV, LIGHTING, RECEPTACLE
3				b 4	20/1	0.372	LIGHTING, MEDIA BOX, RECEPTACLE
5	30/2	4.99	DRYER	a 6	20/1	0.912	LIGHTING, RECEPTACLE
7				b 8	20/1	1.5	SMALL APPLIANCE
9	20/1	1.5	WASHER	a 10	20/1	1.5	SMALL APPLIANCE
11	30/2	4.4	WATER HEATER	b 12	20/1	1.58	MICRO/HOOD
13				a 14	20/1	0.19	LIGHTING, RECEPTACLE
15	20/1	1.2	DISHWASHER	b 16	20/1	0.53	RECEPTACLE, SDCO
17	20/2	0.75	WALL HEATER	a 18	20/1	0	SPARE
19				b 20	20/1	0	SPARE
21	20/1	1.35	LIGHTING, RECEPTACLE	a 22	20/1	0	SPARE
23	20/1	0.7	DISPOSAL	b 24	20/1	0	SPARE

OPTIONAL DWELLING UNIT CALCULATION (NEC 220.82)			
	CONN KVA	871 SF (3 VA/SF)	GENERAL LOAD
LIGHTING AND RECEPTACLES	2.61		UP TO 10 KVA
SMALL-APPLIANCE	3		10
LAUNDRY	1.5		OVER 10 KVA
APPLIANCES	8.47		13.6
ELECTRIC COOKING	8		5.43 (40%)
TOTAL GENERAL LOAD	23.6		3.35 (220.82(C)(4))
			TOTAL LOAD
			BALANCED LOAD
			PHASE A
			PHASE B
			18.8
			90.3 A
			99.4%
			101%

GENERAL NOTES:

- COORDINATE FINAL LOCATION OF THERMOSTATS, SWITCHES, RECEPTACLES, DATA, PHONE, LIGHT FIXTURES AND J-BOXES WITH ARCHITECTURAL ELEVATIONS AND INTERIOR DESIGN PLANS PRIOR TO ROUGH-IN.
- ADA UNITS SHALL HAVE HOOD CONTROLS INSTALLED IN THE FACE OF THE LOWER CABINET WORK.
- PROVIDE TAMPER RESISTANT RECEPTACLES PER NEC 406.12.
- ALL UNITS: PROVIDE SWITCH CONTROLLING GARBAGE DISPOSAL TO BE LOCATED ABOVE BACKSPASH NEXT TO SINK OR ON COUNTER. SEE ARCHITECTURE.
- BATHROOM GFCI RECEPTACLES TO HAVE INTEGRAL NIGHTLIGHT.
- RECESSED CEILING LIGHT IN BATHROOM SHALL BE LED RATED FOR WET LOCATIONS W/ SHATTER PROOF LENS.
- ALL RECEPTACLES SHALL MEET REQUIREMENTS OF NEC ARTICLE 210.
- PROVIDE TELEPHONE & CABLE T.V. MEDIA TERMINATION ENCLOSURE (MEDIA BOX): PROVIDE LEVITON COMPACT MEDIA ENCLOSURE OR EQUIVALENT IN WALL WITH TOP NO HIGHTER THAN 60" AFF WITH 120V RECEPTACLE ADJACENT.
- PROVIDE COMBINATION HARDWIRED 120VAC PHOTOELECTRIC SMOKE DETECTOR AND CARBON MONOXIDE DETECTOR WITH BATTERY-BACKUP
 - DETECTOR SHALL BE MINIMUM 6' HORIZONTAL DISTANCE FROM PERMANENT COOKING APPLIANCE PER CFC 90.2.11.8.
 - DETECTOR SHALL BE MINIMUM 3' HORIZONTAL DISTANCE FROM THE DOOR OF A BATHROOM THAT CONTAINS A BATHTUB OR SHOWER PER CFC 90.2.11.8.
 - PROVIDE INTERCONNECTION WIRING SUCH THAT ACTUATION OF ONE ALARM WILL ACTIVATE ALL ALARMS IN THE DWELLING UNIT.
 - COORDINATE WITH AHJ ON INTERCONNECTING EACH DWELLING UNIT INTO THE FIRE ALARM SYSTEM FOR THE BUILDING.
 - COORDINATE WITH AHJ AS TO THE NUMBER AND LOCATION OF DEVICES PRIOR TO ROUGH-IN. DEVICES SHOWN ARE DIAGRAMMATIC.
- DISHWASHER OUTLET SHALL BE ACCESSIBLE. RECEPTACLE SHALL BE LOCATED IN SPACE ADJACENT TO THE DISHWASHER.
- PROVIDE 7-DAY PROGRAMMABLE THERMOSTAT FOR THE LIVING ROOM.



FLAG NOTES

- INTERLOCK ERV/BEF TO ON/OFF SWITCH. PROVIDE PERMANENT LABEL SAYING, "WHOLE HOUSE VENTILATION. LEAVE ON UNLESS OUTDOOR AIR QUALITY IS VERY POOR." ADHERE PERMANENT LABEL TO WALL ABOVE WALL SWITCH.

AFCI/GFCI REQUIREMENTS FOR DWELLING UNITS:

- ALL 15 AND 20A, 120V SINGLE PHASE CIRCUITS NOT INCLUDING THE BATHROOM SHALL BE AFCI PROTECTED (210.12).
- ALL DWELLING UNIT CIRCUITS IN BATHROOMS, GARAGES, OUTDOORS, KITCHENS, LAUNDRY AREAS, AND AREAS WITHIN 6' OF A SINK SHALL BE GFCI PROTECTED (210.8).
 - BATHROOM CIRCUIT TO BE GFCI PROTECTED VIA A GFCI RECEPTACLE, WHILE OTHER CIRCUITS SHALL BE PROTECTED AT THE BREAKER.
- UTILIZE "DUAL FUNCTION" BREAKER WHEN BOTH AFCI AND GFCI PROTECTION IS REQUIRED.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24

SHEET TITLE:
UNIT PLANS & SCHEDULES

SHEET NO.
E5.01



UNIT TYPICALS

2-BED TYP

SCALE: 1/4" = 1'-0"

Panel		ROOM MOUNTING FLUSH		VOLTS 208/120V 2P 3W		AIC 22,000	
2-BED TYP		FED FROM		BUS AMPS 125		MAIN BKR MLO	
		NOTE		NEUTRAL 100%		LUGS STANDARD	
CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION	CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION
1	50/2	8	RANGE	a 2	20/1	0.23	ERV, LIGHTING, RECEPTACLE
3				b 4	20/1	0.128	BATH EX FAN, LIGHTING
5	30/2	4.99	DRYER	a 6	20/1	1.5	SMALL APPLIANCE
7				b 8	20/1	1.5	SMALL APPLIANCE
9	20/1	1.5	WASHER	a 10	20/1	0.19	LIGHTING, RECEPTACLE
11	30/2	4.4	WATER HEATER	b 12	20/1	1.58	MICRO/HOOD
13				a 14	20/1	1.28	LIGHTING, RECEPTACLE
15	20/1	1.2	DISHWASHER	b 16	20/1	1.19	LIGHTING, RECEPTACLE
17	20/2	0.75	WALL HEATER	a 18	20/1	1.28	LIGHTING, MEDIA BOX, RECEPTACLE
19				b 20	20/1	0.7	DISPOSAL
21	20/2	1	WALL HEATER	a 22	20/1	0.2	SDCO
23				b 24	20/1	0	SPARE

OPTIONAL DWELLING UNIT CALCULATION (NEC 220.82)				
	CONN KVA		CONN KVA	CALC KVA
LIGHTING AND RECEPTACLES	3.52	1,173 SF (3 VA/SF)	GENERAL LOAD UP TO 10 KVA	10 (100%)
SMALL-APPLIANCE	3		OVER 10 KVA	14.5 (40%)
LAUNDRY APPLIANCES	1.5		MAX HEATING OR COOLING	4 (220.82(C)(4))
ELECTRIC COOKING	8		TOTAL LOAD	19.8
TOTAL GENERAL LOAD	24.5		BALANCED LOAD	95.2 A
			PHASE A	99.7%
			PHASE B	100%

GENERAL NOTES:

- COORDINATE FINAL LOCATION OF THERMOSTATS, SWITCHES, RECEPTACLES, DATA, PHONE, LIGHT FIXTURES AND J-BOXES WITH ARCHITECTURAL ELEVATIONS AND INTERIOR DESIGN PLANS PRIOR TO ROUGH-IN.
- ADA UNITS SHALL HAVE HOOD CONTROLS INSTALLED IN THE FACE OF THE LOWER CABINET WORK.
- PROVIDE TAMPER RESISTANT RECEPTACLES PER NEC 406.12.
- ALL UNITS: PROVIDE SWITCH CONTROLLING GARBAGE DISPOSAL TO BE LOCATED ABOVE BACKSPLASH NEXT TO SINK OR ON COUNTER. SEE ARCHITECTURE.
- BATHROOM GFCI RECEPTACLES TO HAVE INTEGRAL NIGHTLIGHT.
- RECESSED CEILING LIGHT IN BATHROOM SHALL BE LED RATED FOR WET LOCATIONS W/ SHATTER PROOF LENS.
- ALL RECEPTACLES SHALL MEET REQUIREMENTS OF NEC ARTICLE 210.
- PROVIDE TELEPHONE & CABLE T.V. MEDIA TERMINATION ENCLOSURE (MEDIA BOX): PROVIDE LEVITON COMPACT MEDIA ENCLOSURE OR EQUIVALENT IN WALL WITH TOP NO HIGHTER THAN 60" AFF WITH 120V RECEPTACLE ADJACENT.
- PROVIDE COMBINATION HARDWIRED 120VAC PHOTOELECTRIC SMOKE DETECTOR AND CARBON MONOXIDE DETECTOR WITH BATTERY-BACKUP
 - DETECTOR SHALL BE MINIMUM 6' HORIZONTAL DISTANCE FROM PERMANENT COOKING APPLIANCE PER CFC 90.2.11.8.
 - DETECTOR SHALL BE MINIMUM 3' HORIZONTAL DISTANCE FROM THE DOOR OF A BATHROOM THAT CONTAINS A BATHTUB OR SHOWER PER CFC 90.2.11.8.
 - PROVIDE INTERCONNECTION WIRING SUCH THAT ACTUATION OF ONE ALARM WILL ACTIVATE ALL ALARMS IN THE DWELLING UNIT.
 - COORDINATE WITH AHJ ON INTERCONNECTING EACH DWELLING UNIT INTO THE FIRE ALARM SYSTEM FOR THE BUILDING.
 - COORDINATE WITH AHJ AS TO THE NUMBER AND LOCATION OF DEVICES PRIOR TO ROUGH-IN. DEVICES SHOWN ARE DIAGRAMMATIC.
- DISHWASHER OUTLET SHALL BE ACCESSIBLE. RECEPTACLE SHALL BE LOCATED IN SPACE ADJACENT TO THE DISHWASHER.
- PROVIDE 7-DAY PROGRAMMABLE THERMOSTAT FOR THE LIVING ROOM.


FLAG NOTES

- INTERLOCK ERV/BEF TO ON/OFF SWITCH. PROVIDE PERMANENT LABEL SAYING, "WHOLE HOUSE VENTILATION. LEAVE ON UNLESS OUTDOOR AIR QUALITY IS VERY POOR." ADHERE PERMANENT LABEL TO WALL ABOVE WALL SWITCH.

AFCI/GFCI REQUIREMENTS FOR DWELLING UNITS:

- ALL 15 AND 20A, 120V SINGLE PHASE CIRCUITS NOT INCLUDING THE BATHROOM SHALL BE AFCI PROTECTED (210.12).
- ALL DWELLING UNIT CIRCUITS IN BATHROOMS, GARAGES, OUTDOORS, KITCHENS, LAUNDRY AREAS, AND AREAS WITHIN 6' OF A SINK SHALL BE GFCI PROTECTED (210.8).
 - BATHROOM CIRCUIT TO BE GFCI PROTECTED VIA A GFCI RECEPTACLE, WHILE OTHER CIRCUITS SHALL BE PROTECTED AT THE BREAKER.
- UTILIZE "DUAL FUNCTION" BREAKER WHEN BOTH AFCI AND GFCI PROTECTION IS REQUIRED.

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC

DATE: 02/15/24

SHEET TITLE:
UNIT PLANS & SCHEDULES

SHEET NO.
E5.02

REQUIRED ELECTRIC VEHICLE CHARGING INFRASTRUCTURE WAC 427:

- WHERE PARKING IS PROVIDED, TEN PERCENT OF PARKING SPACES SHALL BE PROVIDED WITH ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.
- ELECTRICAL ROOM(S) SERVING PARKING AREAS SHALL BE DESIGNED TO ACCOMMODATE THE ELECTRICAL EQUIPMENT AND DISTRIBUTION REQUIRED TO SERVE A MINIMUM OF 20 PERCENT OF THE TOTAL PARKING SPACES WITH 208/240 V 40-AMP ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.
- MINIMUM ONE ACCESSIBLE PARKING SPACE SHALL BE SERVED BY ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.

TOTAL NUMBER OF PARKING SPACES = 354
 AVERAGE NUMBER OF PARKING SPACES PER BUILDING = $354/8 = 44.25$
 $44.25 \times 0.2 = 8.85$
 5 OUTDOOR EV CHARGERS WITH INFRASTRUCTURE
 4 CONDUITS TO FUTURE EV CHARGING LOCATIONS

CAPACITY FOR 9 CHARGERS \times 208V/1PH \times 40A = 74.9 KVA = (208)A 3 PHASE POWER @ 120/208V
 UTILIZING LOAD MANAGEMENT INFRASTRUCTURE, EV LOAD CAN BE REDUCED BY 50%. $208A/2 = 104A$ @ 208V 3 PHASE

PER WAC 427, ELECTRICAL INFRASTRUCTURE FOR EACH BUILDING SHALL BE DESIGNED TO ACCOMMODATE 104 AMPS OF EV ELECTRICAL LOAD.

ID	FEEDER AMPS	CONDUIT AND FEEDER	FEEDING THESE DEVICES
①	125	1-1/2" C, 2#2/0 AL, #2/0 AL N, #4 AL G	A-001, A-002, A-003, A-004, A-101, A-102, A-103, A-104, A-105, A-106, A-107, A-108, A-201, A-202, A-203, A-204, A-205, A-206, A-207, A-208, A-301, A-302, A-303, A-304, A-305, A-306, A-307, A-308, B-001, B-002, B-101, B-102, B-103, B-104, B-201, B-202, B-203, B-204, B-301, B-302, B-303, B-304, C-101, C-102, C-103, C-104, C-105, C-106, C-107, C-108, C-109, C-110, C-111, C-112, C-201, C-202, C-203, C-204, C-205, C-206, C-207, C-208, C-209, C-210, C-211, C-212, C-301, C-302, C-303, C-304, C-305, C-306, C-307, C-308, C-309, C-310, C-311, C-312
②	100	1-1/2" C, 3#1/0 AL, #1/0 AL N, #6 AL G	AM-B, POOL
⑤	1200	(4)3-1/2" C, 3#500kcmil AL, #500kcmil AL N, #250kcmil AL G	A-MC, C-MC, E-MC, F-MC, G-MC
⑥	800	(3)3" C, 3#400kcmil AL, #400kcmil AL N, #4/0 AL G	B-MC
⑦	1600	(5)4" C, 3#600kcmil AL, #600kcmil AL N, #500kcmil AL G	D-MC
⑬	400	(2)2-1/2" C, 3#250kcmil AL, #250kcmil AL N, #1/0 AL G	AM-CT
⑮	1000	(4)3" C, 3#350kcmil AL, #350kcmil AL N, #4/0 AL G	H-MC
⑰	400	3-1/2" C, 3#500kcmil, #500kcmil N, #2G	AM-A
⑱	200	2" C, 3#3/0, #3/0N, #6G	A-HOUSE, B-HOUSE, C-HOUSE, D-HOUSE, E-HOUSE, F-HOUSE, G-HOUSE, H-HOUSE

SIZING METHOD: COPPER, 60°C #12 THROUGH #1, 75°C 1/0 AND ABOVE

FEEDER SCHEDULE NOTES:

CONDUIT FILL:

- FOR CONDUIT SIZES 1-1/2" AND BELOW, FILL IS BASED ON EMT.
- FOR CONDUIT SIZES 2" AND ABOVE, FILL IS BASED ON SCHEDULE 40 PVC.

IN LOCATIONS APPROVED FOR THE PURPOSE, CONTRACTOR MAY USE MC CABLE.
 IN LOCATIONS APPROVED FOR THE PURPOSE, CONTRACTOR MAY USE OTHER CONDUIT TYPES, INCLUDING RMC, FMC AND LFMC. CONTRACTOR REQUIRED TO ENSURE CONDUIT FILL DOES NOT EXCEED 40%.

CONTRACTOR RESPONSIBLE TO ENSURE TERMINATION/LUG CAPACITY FOR ALL SCHEDULED FEEDERS.


XHHW/THHN/THWN SHALL BE USED FOR INSULATION OF THE CONDUCTOR.

GROUNDING NOTES AND REQUIREMENTS:

THE ELECTRICAL CONTRACTOR SHALL COORDINATE WITH THE GENERAL CONTRACTOR, POWER COMPANY, PHONE COMPANY, INTERNET COMPANY, CABLE TV COMPANY, AND THE SATELLITE TV COMPANY TO ENSURE REQUIRED GROUNDING IS INSTALLED FOR EACH SYSTEM.

THIS SHALL BE DONE PRIOR TO AND DURING INSTALLATION OF FOUNDATION RE-BAR AND CONTINUE DURING THE CONSTRUCTION PHASES, TO ENSURE EACH SYSTEM HAS IT'S REQUIRED GROUNDING INSTALLED FOR PROPER OPERATION OF THE SYSTEM.

- THE ELECTRICAL CONTRACTOR SHALL COORDINATE AND PROVIDE WHAT IS REQUIRED TO DO THE FOLLOWING:
- FOOTING GROUND RE-BAR COMES UP IN THE ELECTRICAL ROOM AND THE RE-BAR IS SNUGLY SECURED TO THE FOOTING RE-BAR.
- THE MSB GROUNDING TIES TO THE FOOTING RE-BAR, COUNTERPOISE, BUILDING STEEL, AND WATER PIPING.
- THE GROUND WIRE FOR THE COUNTERPOISE SHALL BE STRANDED, INSULATED WIRE IN CONDUIT UNTIL IT REACHES THE FIRST BAR OF THE COUNTERPOISE. BETWEEN THE COUNTERPOISE BARS IT SHALL BE A STRANDED BARE COPPER WIRE.



COORDINATION AND ARC FLASH STUDIES:

IMMEDIATELY UPON SELECTION OF ACTUAL EQUIPMENT BEING PROVIDED FOR THE PROJECT, THE ELECTRICAL CONTRACTOR SHALL PERFORM AN ARC FLASH ANALYSIS AND COORDINATION STUDY ON THE STANDBY DISTRIBUTION BASED ON ACTUAL EQUIPMENT TO BE PROVIDED. CONDUCTOR TYPES/SIZES/LENGTHS, ETC. COORDINATION SHALL BE CONFIRMED BASED ON FAULT NUMBERS SHOWN ON THIS DRAWING.

STUDIES SUBMITTED SHALL BE STAMPED BY A PROFESSIONAL ELECTRICAL ENGINEER HOLDING A CURRENT LICENSE FROM THE STATE OF WA.

PRELIMINARY ARC FLASH AND COORDINATION STUDIES ARE TO BE SUBMITTED WITH THE SUBMITTALS FOR THE PROTECTIVE DEVICES, PANELBOARDS, SWITCHBOARDS, AND OTHER ELECTRICAL EQPT.

THE ELECTRICAL CONTRACTOR SHALL SUBMIT THE STAMPED AND SIGNED ARC FLASH AND COORDINATION STUDY TO THE AHJ AS REQUIRED.


THE ELECTRICAL CONTRACTOR SHALL PROVIDE AND INSTALL PERMANENT LABELS INDICATING ARC FLASH HAZARD RISK CATEGORIES ON ALL DISTRIBUTION POINTS (SWITCHBOARDS, PANELBOARDS, VFDS, DISCONNECT SWITCHES, ETC). LABELS SHALL COMPLY WITH NFPA 70E.

SHEET NOTES:


- CONTRACTOR TO OBTAIN UTILITY APPROVAL OF ALL SERVICE AND METERING EQUIPMENT PRIOR TO ORDERING.
- DISTRIBUTION SYSTEM AS DESIGNED IS FULLY RATED. CONTRACTOR WILL BE RESPONSIBLE FOR ENGINEERING IF SERIES RATED SYSTEMS ARE SUBMITTED, THE SUBMITTED SYSTEM SHALL MEET NEC 240.86(B) REQUIREMENTS FOR TESTED COMBINATIONS, AND SHALL NOT BE USED IF MOTOR CONTRIBUTION EXCEEDS LIMITS PER 240.86(C). NEC 110.22 MARKING REQUIREMENTS MUST BE MET.
- PROVIDE PERMANENT WARNING LABELS FOR ARC FLASH AND PPE REQUIREMENTS FOR THE SERVICE EQUIPMENT AND PANELS.

FLAG NOTES:

- GROUNDING ELECTRODE CONDUCTOR AND SYSTEM GROUNDING SIZED PER N.E.C. 250
- PROVIDE ARC ENERGY REDUCTION: ENERGY REDUCING MAINTENANCE SWITCH PER NEC 240.87(B)(3)
- PROVIDE A LISTED SURGE PROTECTIVE DEVICE FOR DWELLING UNITS AS REQUIRED BY NEC 230.67. CONTRACTOR TO CONFIRM LOCATION IS ACCEPTABLE TO AUTHORITY HAVING JURISDICTION. OBTAIN PRICING FOR OPTION TO HAVE SPDs LOCATED IN UNIT PANELS VS UPSTREAM.
- METER ELEVATIONS AND METERS PER STACK SHALL BE INSTALLED PER UTILITY ELECTRICAL PROVIDER REQUIREMENTS. METER SOCKET IN ELECTRICAL ROOM. VERIFY EXACT LOCATION AND REQUIREMENTS WITH ELECTRIC UTILITY (TYPICAL)
- PROVIDE (1) 2 1/2" CONDUITS FOR SOLAR READY PATHWAY AND RESERVE SPACE IN THE MAIN ELECTRIC ROOM FOR FUTURE SOLAR EQUIPMENT. RESERVE SPACE FOR INSTALLATION OF FUTURE SOLAR CIRCUIT BREAKER AND PERMANENTLY MARK THIS LOCATION AS "FOR FUTURE SOLAR ELECTRIC".



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
 27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206)364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24

SHEET TITLE:
ONE-LINE DIAGRAM & NOTES

SHEET NO.
E6.00

Panel			ROOM	VOLTS	208Y/120V 3P 4W	AIC	42,000
D-HOUSE			MOUNTING SURFACE	BUS AMPS	200	MAIN BKR	MLO
			FED FROM D-MC	NEUTRAL	100%	LUGS	STANDARD
CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION	CKT #	CKT BKR	LOAD KVA	CIRCUIT DESCRIPTION
1	20/1	0.72	RECEPTACLE	a 2	40/2	6.6	EV CHARGER
3	20/1	0.72	RECEPTACLE	b 4			
5	20/1	0.72	RECEPTACLE	c 6	40/2	6.6	EV CHARGER
7	20/1	0.18	RECEPTACLE	a 8			
9	20/1	0.296	LIGHTING	b 10	40/2	6.6	EV CHARGER
11	20/1	0.296	LIGHTING	c 12			
13	20/1	0.296	LIGHTING	a 14	40/2	6.6	EV CHARGER
15	20/1	0.5	HEAT TRACE	b 16			
17	20/1	0.18	RECEPTACLE	c 18	40/2	6.6	EV CHARGER
19	20/1	0.128	LIGHTING	a 20			
21	20/1	0.5	FACP	b 22	40/2	6.6	(F) EV CHARGER
23	20/1	0.18	SITE LIGHTING	c 24			
25	-/1	0	SPACE	a 26	40/2	6.6	(F) EV CHARGER
27	-/1	0	SPACE	b 28			
29	-/1	0	SPACE	c 30	40/2	6.6	(F) EV CHARGER
31	-/1	0	SPACE	a 32			
33	-/1	0	SPACE	b 34	40/2	6.6	(F) EV CHARGER
35	-/1	0	SPACE	c 36			
37	-/1	0	SPACE	a 38	-/3	0	SOLAR BREAKER
39	-/1	0	SPACE	b 40			
41	-/1	0	SPACE	c 42			

	CONN KVA	CALC KVA		CONN KVA	CALC KVA	
LIGHTING	1.2	1.5	(125%)	EV LOAD	59.4	37.1 (63%)
RECEPTACLES	2.52	2.52	(50%>10)	CONTINUOUS	0.5	0.625 (125%)
				HEATING	0.5	0.5 (100%)
				TOTAL LOAD		42.3
				BALANCED 3-PHASE LOAD		117 A
				PHASE A		98.8%
				PHASE B		102%
				PHASE C		99.1%

D-MC			ROOM	VOLTS	208Y/120V 3P 4W	AIC	65,000
			MOUNTING SURFACE	BUS AMPS	1600	MAIN BKR	1600
			FED FROM XFMR C/D/CLUB	NEUTRAL	100%	LUGS	STANDARD
CKT #	BREAKER TRIP/POLES	CIRCUIT DESCRIPTION	LOAD KVA			FEEDER RACEWAY AND CONDUCTORS	
			A	B	C		
1	125/2	PANEL D001	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
2	125/2	PANEL D002	16.5	15.8	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
3	125/2	PANEL D003	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
4	125/2	PANEL D004	15.8	15.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
5	125/2	PANEL D005		15.7	15	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
6	125/2	PANEL D006	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
7	125/2	PANEL D101	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
8	125/2	PANEL D102	15.8	15.7	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
9	125/2	PANEL D103	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
10	125/2	PANEL D104	15.8	15.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
11	125/2	PANEL D105		15.8	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
12	125/2	PANEL D106	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
13	125/2	PANEL D107	15.7	15		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
14	125/2	PANEL D108	15.7	15	15	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
15	125/2	PANEL D109	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
16	125/2	PANEL D110	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
17	125/2	PANEL D111	15.7		15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
18	125/2	PANEL D112	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
19	125/2	PANEL D201	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
20	125/2	PANEL D202		15.8	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
21	125/2	PANEL D203	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
22	125/2	PANEL D204	15.8	15.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
23	125/2	PANEL D205	15.8	15.7	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
24	125/2	PANEL D206	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
25	125/2	PANEL D207	15.7	15		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
26	125/2	PANEL D208		15.7	15	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
27	125/2	PANEL D209	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
28	125/2	PANEL D210	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
29	125/2	PANEL D211	15.8	15.7	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
30	125/2	PANEL D212	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
31	125/2	PANEL D301	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
32	125/2	PANEL D302	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
33	125/2	PANEL D303	16.7	16.5		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
34	125/2	PANEL D304	15.8	15.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
35	125/2	PANEL D305		15.8	15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
36	125/2	PANEL D306	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
37	125/2	PANEL D307	15.7	15		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
38	125/2	PANEL D308	15.7		15	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
39	125/2	PANEL D309	15.7		15.8	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
40	125/2	PANEL D310	16.5	16.7		1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
41	125/2	PANEL D311	15.7		15.7	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
42	125/2	PANEL D312	16.7		16.5	1-1/2"C,2#2/0 AL,#2/0 AL N,#4 AL G	
43	200/3	PANEL D-HOUSE	21.1	21.8	21	2"C,3#3/0,#3/0N,#6G	


TOTAL CONNECTED KVA BY PHASE			
A	474	B	467
C	463		

OPTIONAL MULTIFAMILY DWELLING CALCULATION (NEC 220.84)			
DWELLING UNIT LOADS			
	KVA		KVA
LIGHTING AND RECEPTACLES	122	40,791 SF (3 VA/SF)	1,300
SMALL-APPLIANCE	126		42
LAUNDRY	63		(28%)
APPLIANCES	356		365
ELECTRIC COOKING	336		
HEATING	300	(100%)	

HOUSE LOADS			
	CONN KVA	CALC KVA	
LIGHTING	0.891	1.11	(125%)
RECEPTACLES	2.52	2.52	(50%>10)
EV LOAD	59.4	37.1	(63%)
CONTINUOUS	0.5	0.625	(125%)
HEATING	0.5	0.5	(100%)
TOTAL HOUSE LOAD		41.9	

TOTAL LOAD			
	KVA		KVA
TOTAL DWELLING UNIT LOAD	365		407
TOTAL HOUSE LOAD	41.9		1,130 A

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: KL	DESIGNED: MHS	CHECKED: PSR	APPROVED: JAY
-----------	---------------	--------------	---------------

PROJECT: BRADLEY HEIGHTS APARTMENTS BLDG D
27TH AVE SE AND 5TH ST SE PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206)364-3343

ROBISON ENGINEERING, INC.

DATE: 02/15/24

SHEET TITLE:
PANEL SCHEDULES

SHEET NO.
E6.01

GENERAL NOTES

- REFERENCE TO RELATED WORK: "REF" INDICATIONS DENOTE WORK COVERED ELSEWHERE (ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL, LANDSCAPE, OR KITCHEN), OR ITEM BASED ON A SPECIFIC MANUFACTURER'S DIMENSIONS (VERIFY).
- ELECTRICAL CHARACTERISTICS: REFER TO ELECTRICAL DRAWINGS FOR ELECTRICAL CHARACTERISTICS (VOLTAGES, ETC. OF MECHANICAL EQUIPMENT, UNLESS OTHERWISE INDICATED).
- CODES: COMPLETE INSTALLATION OF THE PLUMBING SYSTEM SHALL BE PER THE APPLICABLE BUILDING, MECHANICAL, ENERGY, PLUMBING, FIRE, AND HEALTH CODES AND REGULATIONS AS ADOPTED BY THE LOCAL AHJ.
- PREPARE AND SUBMIT FOR REVIEW A SHOP DRAWING BASED ON FINAL STRUCTURAL SHOP DRAWINGS FOR LOCATING AND ROUTING ALL EQUIPMENT, PIPING, ETC.
 - COORDINATE FLOOR AND BEAM PENETRATIONS WITH STRUCTURAL.
 - COORDINATE FINAL LOCATION AND ROUTING WITH CEILING, LIGHTS, WALLS, FIRE SPRINKLER PIPING, AND OTHER TRADES WORK.
 - INCLUDE ADDITIONAL OFFSETS, ELBOWS, ROUTING, EQUIVALENT DUCT SIZING EXCHANGE, RELOCATING, ETC. AS REQUIRED FOR A COMPLETE OPERATING MECHANICAL SYSTEM.
 - PROVIDE SHOP DRAWINGS AT NO ADDITIONAL COST TO THE OWNER.
- PLUMBING CONTRACTOR SHALL LOCATE AND COORDINATE EXACT LOCATION OF ALL PLUMBING EQUIPMENT WITHIN THE STRUCTURE.
- ACCESS DOORS: COORDINATE WITH ARCHITECT AND LOCATE ALL ACCESS DOORS ON SHOP DRAWINGS PRIOR TO BEGINNING OF CONSTRUCTION. ACCESS DOORS IN FIRE RATED STRUCTURE SHALL BE FIRE RATED. VERIFY ACCESS DOOR LOCATIONS WITH GENERAL CONTRACTOR PRIOR TO BIDDING.
- ROOF PENETRATIONS: SEE ARCHITECTURAL DRAWINGS FOR ROOF CAP, ROOF CURB, ROOF DRAIN, OVERFLOW DRAINS AND VTR DETAILS.
- EXPOSED PIPING: PROVIDE CHROME PLATING FOR EXPOSED PIPING IN FINISHED ROOMS.
- PENETRATIONS: PROVIDE ESCUTCHEON PLATES FOR EXPOSED PIPING PENETRATIONS AND SHEET METAL FLASHING FOR EXPOSED DUCTWORK PENETRATIONS.
- SHAFT AND PLENUM CONNECTIONS: SEAL CONNECTIONS TO AIR SHAFTS AIRTIGHT. PROVIDE AIRTIGHT SEAL AROUND PENETRATIONS IN AIR PLENUMS.
- LIGHT FIXTURE CLEARANCE: COORDINATE LOCATIONS OF MECHANICAL WORK TO PROVIDE CLEARANCES OVER LIGHTING FIXTURES FOR REMOVAL AND REPLACEMENT.
- CABLE TRAYS: PIPING INSTALLED ADJACENT TO ELECTRICAL CABLE TRAYS SHALL ALLOW MINIMUM ACCESS OF 6" ABOVE AND TO THE SIDE OF CABLE TRAYS.
- MOTORS: COMPLY WITH ENERGY CODE ENFORCED BY AHJ FOR MINIMUM EFFICIENCIES UNDER FULL LOAD.
- ACCESS CLEARANCES FOR MAINTENANCE AND REPLACEMENT: VERIFY PHYSICAL DIMENSIONS OF EQUIPMENT TO ENSURE THAT ACCESS CLEARANCES CAN BE MET. COORDINATE LOCATIONS OF MECHANICAL WORK AND WORK OF OTHER TRADES TO PROVIDE ACCESS CLEARANCES FOR SERVICE AND MAINTENANCE.

COORDINATION REQUIREMENTS


- IRRIGATION SYSTEM: COORDINATE IRRIGATION WATER DEMAND, MINIMUM WATER PRESSURE REQUIREMENTS & CONTROL CABINET LOCATIONS WITH IRRIGATION CONTRACTOR.
- GAS: CONTRACTOR/GAS COMPANY SHALL FINALIZE GAS METER AND GAS SERVICE LOCATIONS. INSTALL SEISMIC GAS SHUT OFF VALVE PER GAS COMPANY REGULATIONS.
- UTILITIES: COORDINATE WITH SITE UTILITY CONTRACTOR AND CIVIL DRAWINGS FOR UTILITY CONNECTIONS AND EXTENSIONS.
- ROOF DRAINAGE: COORDINATE WITH GENERAL CONTRACTOR FOR ROOF DRAIN AND OVERFLOWS, SCUPPER DRAINS, AND CONDENSATE DRAINS.
- PLUMBING FIXTURES & EQUIPMENT: COORDINATE EXACT LOCATION OF ALL PLUMBING FIXTURES & EQUIPMENT WITH ARCHITECTURAL AND OTHER TRADES DOCUMENTS.
- PIPING: COORDINATE EXACT LOCATION OF ALL STRUCTURAL FRAMING & FOOTINGS AND FINALIZE THE EXACT ROUTING OF ALL PIPES WITH STRUCTURAL ENGINEER AT THE SITE PRIOR TO AND DURING THE CONSTRUCTION. COORDINATE UNDER GRADE PIPING & FOUNDATION DRAINAGE PIPING WITH CIVIL ENGINEER.
- ADJUSTMENTS: ALL EQUIPMENT, MOTORS, FANS GAS BURNERS, IGNITION DEVICES, DRIVES, ETC. SHALL BE ADJUSTED AND BALANCED TO OPERATE AT SPECIFIED RATINGS AS REQUIRED FOR THIS PROJECT SITE AND ACCOUNTING FOR ELEVATION ABOVE SEA LEVEL.
- APPROVALS: MECHANICAL AND PLUMBING EQUIPMENT SHALL BE APPROVED FOR INSTALLATION IN THE PROJECT LOCATION AND SHALL HAVE ALL CERTIFICATIONS AND RATINGS TO MEET ALL ENERGY, POLLUTION, ENVIRONMENTAL, SEISMIC, APPLICABLE CODES & REGULATIONS. THE CONTRACTOR SHALL COORDINATE WITH MANUFACTURE SUPPLIERS AND SHALL INCLUDE ALL COSTS REQUIRED TO MEET THE BID DOCUMENTS.
- FIRE PROTECTION: CONTRACTOR SHALL PROVIDE A FULLY DESIGNED FIRE PROTECTION SPRINKLER SYSTEM IN COMPLIANCE WITH NFPA AND LOCAL CODES. PROVIDE DESIGN, PERMITS, MATERIALS, INSTALLATION, TESTING AND ALL OTHER FOR A FULLY OPERATIONAL SYSTEM. LOCATION OF ALL PIPING TO BE COORDINATED WITH OTHER TRADES.
- PRIOR TO PIPING INSTALLATION: PLUMBING CONTRACTOR TO COORDINATE PIPING LAYOUT WITH ALL OTHER TRADES.
- ACCESS: COORDINATE ALL ACCESS LOCATIONS WITH GENERAL CONTRACTOR AND ARCHITECT TO ENSURE ALL REQUIRED ACCESS HATCHES, ACCESS PANELS & ACCESS COVERS ARE PROVIDED.
- PROVIDE WATER TIGHT SEALS FOR ANY PIPING PENETRATING THE EXTERIOR FOUNDATION WALLS OR SLABS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT IMMEDIATELY.
- PROVIDE FIRE PROOFING FOR ALL PIPING PENETRATING FIRE BARRIER WALLS OR FLOOR SLABS.

DISINFECTION OF POTABLE WATER SYSTEM REQUIREMENTS


- NEW OR REPAIRED POTABLE WATER SUPPLY SYSTEMS SHALL BE DISINFECTED PRIOR TO USE.
- INITIAL COLIFORM SAMPLE IS REQUIRED PRIOR TO ADMINISTERING WATER-CHLORINE SOLUTION.
- SECTION 609.9 ITEMS #2 OR #3 CAN BE USED PRECEDED BY AND FOLLOWED BY ITEM #1.
- NOTE FILL PORT TO ADD CHLORINE MUST BE WHERE WATER SUPPLY ENTERS BUILDING AND A FLOW METER TO MEASURE SOLUTION.
- AFTER WATERCHLORINE SOLUTION IS INCORPORATED INTO THE NEW OR REPAIRED WATER SUPPLY SYSTEM A 48 HOUR WAITING PERIOD MUST BE OBSERVED PRIOR TO BACTERIOLOGICAL TEST.
- BACTERIOLOGICAL TEST SHALL BE CONDUCTED BY A LABORATORY CERTIFIED FOR DRINKING WATER IN WASHINGTON STATE AFFIRMING WATER QUALITY CONTAINS NO COLIFORM BY SAMPLE TESTING THE FURTHEST FIXTURE FROM PUBLIC WATER SOURCE AND NOT LESS THAN TWO OTHER LOCATIONS PART OF THE WATER SUPPLY SYSTEM.
- CHLORINE LEVEL IN THE NEW OR REPAIRED WATER SUPPLY SYSTEM SHALL NOT BE LESS THAN THE MEAN AVERAGE OF THE AREA IN RELATIONSHIP FROM THE WATER PURVEYOR SOURCE.
- WARNING: IN CASE A WATER SOFTENER IS PART OF THE COLD WATER SYSTEM, CONTRACTOR TO ENSURE THE WATER SOFTENER IS CONNECTED AND OPERATIONAL BEFORE STARTING THE DISINFECTION PROCESS. FAILURE TO FOLLOW THE INSTRUCTIONS WILL VOID THE WATER HEATER OR HEAT PUMP WARRANTY.

SYMBOLS


GENERAL



SECTION IDENTIFICATION




DETAIL IDENTIFICATION







EQUIPMENT



PIPING



PIPE SYMBOLS




ABBREVIATIONS

ABV	ABOVE	FLR	FLOOR	OPD	OVERFLOW DRAIN/DECK DRAIN
AD	AREA DRAIN	FPM	FEET PER MINUTE	OPNG	OVER PRESSURE DEVICE OPENING
AFF	ABOVE FINISHED FLOOR	FPS	FEET PER SECOND	P	PUMP
AHJ	AUTHORITY HAVING JURISDICTION	FS	FLOOR SINK	PD	PRESSURE DROP, PLANTER DRAIN
BFF	BELOW FINISHED FLOOR	FT	FEET	POC	POINT OF CONNECTION
BFP	BACKFLOW PREVENTER	FU	FIXTURE UNITS	PRV	PRESSURE REDUCING VALVE
BOH	BACK OF HOUSE	G	GAS (LOW PRESSURE)	PS	PRESSURE RELIEF VALVE
BP	BOOSTER PUMP	GAL	GALLONS	PSD	PUMPED STORM DRAINAGE
BT	BATHTUB	GD	GARAGE DRAIN	PSG	POUNDS PER SQUARE INCH GAUGE
BTUH	BRITISH THERMAL UNIT PER HOUR	GM	GAS METER	PSO	PUMPED STORM DRAINAGE
CB	CATCH BASIN	GPM	GALLONS PER GALLON	PSS	PUMPED SANITARY SEWER
C	COMMON	GV	GATE VALVE	PSW	PUMPED SANITARY WASTE
CAP	CAPACITY	HP	HORSEPOWER	RD	ROOF DRAIN
CD	CONDENSATE DRAIN	HW	HOT WATER	REF	REFERENCE
CFM	CUBIC FEET PER MINUTE	HD	HEAD	RFP	REDUCED PRESSURE BACKFLOW PREVENTER
CI	CAST IRON	HDR	HUB DRAIN	RPM	REVOLUTIONS PER MINUTE
CLG	CEILING, COOLING	HDV	HOSE END DRAIN VALVE	S	SINK
CM	CLOTHES WASHER	HORIZ	HORIZONTAL	SC	SCHEDULE
CO	CLEANOUTS	HP	HORSEPOWER	SCW	SOFTENED COLD WATER
COMB	COMBUSTION	HPCW	HIGH PRESSURE COLD WATER	SD	STORM DRAIN
CONT	CONTINUE, CONTROL	HW	HOT WATER	SEP	SEWAGE EJECTOR PUMP
CONTR	CONTRACTOR	HWC	HOT WATER RE-CIRCULATION	SF	SQUARE FOOT
COTG	CLEANOUTS TO GRADE	HWCP	HOT WATER CIRCULATION PUMP	SGSV	SEISMIC GAS SHUT-OFF VALVE
CP	CIRCULATING PUMP	HWR	HOT WATER RETURN	SH	SHOWER
CPV	CHECK VALVE	HWT	HOT WATER STORAGE TANK	SO	STORM OVERFLOW
CW	COLD WATER	HX	HEAT EXCHANGER	SP	STATIC PRESSURE/SUMP PUMP
D	DIAMETER	ICW	INDUSTRIAL COLD WATER	SR	SUDS RELIEF
DB	DRY BULB, DECIBEL	ID	INDIRECT DRAIN, INSIDE DIAMETER	SS	STAINLESS STEEL/SANITARY SEWER
DF	DRINKING FOUNTAIN	IE	INVERT ELEVATION	SSS	SIDE SANITARY SEWER
DFU	DRAIN FIXTURE UNITS	IHW	INDUSTRIAL HOT WATER	STD	STANDARD
DI	DUCTILE IRON	IN	INCH	SQ	SQUARE
DIM	DIMENSION	KS	KITCHEN SINK	TD	TRENCH DRAIN
DN	DOWN	KW	KILOWATT	TMV	THERMOSTATIC MIXING VALVE
DS	DOWN SPOUT	L	LONG, LENGTH	TYP	TYPICAL
DWG	DRAWING	LAV	LAVATORY	U	UNIT HEATER
(E)	EXISTING	LB	POUND	UON	UNLESS OTHERWISE NOTED
EFF	EFFICIENCY	M	METER	UR	URNAL
ELEC	ELECTRIC	MEB	MECHANICAL	V	VENT
EQUIV	EQUIVALENT	MECH	MECHANICAL	VTR	VENT THRU ROOF
EWC	ELECTRIC WATER COOLER	MCA	MIN. CIRCUIT AMPACITY	W	WASTE, WATT, WDE
EW	ELECTRIC WATER HEATER	MCCP	MAX. OVER CURRENT PROTECTION	WC	WATER CLOSET
EXT	EXTERIOR, EXTERNAL	MFG	MEDIUM PRESSURE GAS	W	WALL
F	FAHRENHEIT	MTD	MOUNTED	WCD	WALL CLEANOUTS
FCO	FLOOR CLEANOUTS	(N)	NEW	WHD	WALL HYDRANT
FD	FLOOR DRAIN	NC	NORMALLY CLOSED	WM	WASHING MACHINE
FDC	FIRE DEPARTMENT CONNECTION	NO	NORMALLY OPEN	WSFU	WATER SUPPLY FIXTURE UNITS
FF	FINISHED FLOOR	OD	OUTSIDE DIMENSION/DIAMETER		

DRAWING INDEX

DWG	DESCRIPTION	INCLUDED IN SET
POD.00	LEGEND, GENERAL NOTES, AND DRAWING INDEX	x
POD.01	PLUMBING NOTES AND TABLES	x
POD.02	PLUMBING CALCULATIONS	x
POD.03	PLUMBING SCHEDULES	x
P2D.00	UNDERSLAB WASTE & VENT PLAN	x
P2D.01	BASEMENT WASTE & VENT PLAN	x
P2D.02	LEVEL 1 WASTE & VENT PLAN	
P2D.03	LEVEL 2 WASTE & VENT PLAN	x
P2D.04	LEVEL 3 WASTE & VENT PLAN	x
P2D.05	ROOF WASTE & VENT PLAN	x
P3D.01	BASEMENT PLUMBING SUPPLY PLAN	
P3D.02	LEVEL 1 PLUMBING SUPPLY PLAN	x
P3D.03	LEVEL 2 PLUMBING SUPPLY PLAN	x
P3D.04	LEVEL 3 PLUMBING SUPPLY PLAN	x
P4D.00	WASTE & VENT RISER DIAGRAM	x
P4D.01	WASTE & VENT RISER DIAGRAM	x
P7D.00	DETAILS	x
P7D.01	DETAILS	x



DRAWN: JM	DESIGNED: JM	CHECKED: RJ	APPROVED: JR
-----------	--------------	-------------	--------------

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
202 27TH AVE SE
PUYALLUP, WA 98374

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
LEGEND GENERAL NOTES AND DRAWING INDEX

SHEET NO.
POD.00

PLUMBING TABLES

PIPE INSULATION SCHEDULE

SERVICE	OPTION 1		OPTION 2		VAPOR RETARDER REQUIRED	NOTES
	MATERIAL	THICKNESS	MATERIAL	THICKNESS		
DOMESTIC COLD WATER, IRRIGATION WATER, CONDENSATE DRAINS, STORM DRAIN (IN CONDITIONED SPACE)	MINERAL-FIBER WITH JACKET	ALL SIZES: 1/2"	PVC/NBR	ALL SIZES: 3/8"	YES	12,13
DOMESTIC COLD WATER, IRRIGATION WATER, CONDENSATE DRAINS, WASTE (OUTSIDE THE CONDITIONED SPACE)	MINERAL-FIBER WITH JACKET	(R-3) 1/2" PIPE: 1/2" ALL OTHER SIZES: 1"	PVC/NBR	(R-3) 1/2" PIPE: 1/2" ALL OTHER SIZES: 3/4"	YES	7,8,10
ROOF DRAIN BODIES	MINERAL-FIBER OR CELLULAR GLASS WITH JACKET	1"	PVC/NBR	1"	YES	12
DOMESTIC HOT WATER AND RECIRCULATED HOT WATER (RESIDENTIAL)	MINERAL-FIBER WITH JACKET	(R-3) 1/2" PIPE: 1/2" ALL OTHER SIZES: 1"	PVC/NBR	(R-3) 1/2" PIPE: 1/2" ALL OTHER SIZES: 3/4"	NO	2,10
DOMESTIC HOT WATER AND RECIRCULATED HOT WATER (NONRESIDENTIAL)	MINERAL-FIBER WITH JACKET	1/2"-1 1/4" PIPE: 1" 1 1/2"-4" PIPE: 1.5"	PVC/NBR	1/2"-1 1/4" PIPE: 1" 1 1/2"-4" PIPE: 1.5"	NO	3,9
EXPOSED SANITARY DRAINS AND DOMESTIC WATER SUPPLIES AND STOPS FOR ADA FIXTURES.	TRUEBRO LAV-GUARD	N/A	N/A	N/A	NO	11

NOTES:

- PIPING INSULATION EXPOSED TO THE WEATHER SHALL BE PROTECTED FROM DAMAGE. CONTRACTOR SHALL PROVIDE SHIELDING FROM SOLAR RADIATION THAT CAN CAUSE DEGRADATION OF THE MATERIAL. ADHESIVE TAPE SHALL NOT BE PERMITTED.
- PER 2019 CEC SECTION R403.5.3 (RESIDENTIAL) INSULATION FOR HOT WATER PIPE SHALL HAVE A MINIMUM R-VALUE OF R-3.
- PIPING FROM WATER HEATER TO THE TERMINATION OF HEATED WATER SUPPLY PIPE SHALL BE INSULATED IN ACCORDANCE WITH TABLE C403.2.9.
- ON BOTH THE INLET AND OUTLET PIPING OF A STORAGE HOT WATER HEATER, THE FIRST 8 FEET OF PIPING OR PIPING FROM WATER HEATER TO HEAT TRAP SHALL BE INSULATED.
- HEAT TRACED PIPING SHALL BE INSULATED IN THE SAME MANNER AS NON HEAT TRACED PIPING OR PER THE HEAT TRACE MANUFACTURER'S INSTRUCTIONS.
- TUBULAR PIPING INSULATION SHALL NOT BE REQUIRED FOR THE FOLLOWING:
 - THE TUBING FROM THE CONNECTION AT THE TERMINATION OF THE FIXTURE SUPPLY PIPING TO A PLUMBING FIXTURE OR PLUMBING APPLIANCE.
 - VALVES, PUMPS, STRAINERS, AND THREADED UNIONS IN PIPING THAT IS 1 INCH OR LESS IN NOMINAL DIAMETER.
 - PIPING FROM USER-CONTROLLED SHOWER AND BATH MIXING VALVES TO THE WATER OUTLETS.
 - COLD WATER PIPING OF A DEMAND RECIRCULATION WATER SYSTEM.
 - TUBING FROM A HOT DRINKING-WATER HEATING UNIT TO THE WATER OUTLET.
 - PIPING AT LOCATIONS WHERE A VERTICAL SUPPORT OF THE PIPING IS INSTALLED.
 - PIPING SURROUNDED BY BUILDING INSULATION WITH A THERMAL RESISTANCE (R-VALUE) OF NOT LESS THAN R-3.
 - HOT WATER PIPING THAT IS PART OF THE FINAL PIPE RUN TO THE PLUMBING FIXTURE AND IS NOT PART OF THE HEATED-WATER CIRCULATION SYSTEM CIRCULATION PATH IS NOT REQUIRED TO MEET THE MINIMUM INSULATION REQUIREMENTS OF C404.6.
- PER 2018 UPC SECTION 312.6 NO WATER, SOIL, OR WASTE PIPE SHALL BE INSTALLED OR PERMITTED OUTSIDE OF A BUILDING, IN ATTICS OR CRAWL SPACES, OR IN AN EXTERIOR WALL UNLESS, WHERE NECESSARY, ADEQUATE PROVISION IS MADE TO PROTECT SUCH PIPE FROM FREEZING. ALL HOT AND COLD WATER PIPES OUTSIDE THE CONDITIONED SPACE SHALL BE PROVIDED WITH INSULATION WITH A MINIMUM R-VALUE OF R-3.
- HEAT TRACING SHALL BE PROVIDED FOR COLD WATER AND IRRIGATION WATER IN UNCONDITIONED SPACES. CONTACT ENGINEERING IF NECESSARY. PER 2019 CEC SECTION C403.12.3 FREEZE PROTECTION SYSTEMS, SUCH AS HEAT TRACING OF OUTDOOR PIPING, SHALL INCLUDE AUTOMATIC CONTROLS CONFIGURED TO SHUT OFF THE SYSTEMS WHEN OUTDOOR AIR TEMPERATURES ARE ABOVE 40°F.
- PER 2019 CEC TABLE C403.2.9 INSULATION FOR HOT WATER AND HOT WATER RECIRCULATION SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21-0.28 (BTU·IN./H·FT²·°F) AT OPERATING TEMPERATURE.
- INSULATION R-VALUE SHALL MEET THE MINIMUM REQUIREMENT. THICKNESS IS BASED ON GRAINGER SAMPLE DATA FOR K-FLEX(PVC/NBR) AND OWENS CORNING(FIBER GLASS).
- ALL ADA P-TRAPS, HOT WATER SUPPLY TUBING, AND SHUT-OFF COCKS SHALL BE PROTECTED WITH APPROVED COVERS TO PREVENT SCALDING.
- REQUIRED BY ENGINEERING BASED ON BEST PRACTICE.
- INSULATION IS NOT REQUIRED ON PLASTIC COLD WATER PIPING.

HANGER SPACING FOR WATER PIPING

ALL SUSPENDED WATER SUPPLY PIPE SHALL BE SUPPORTED AS FOLLOWS PER 2018 UPC TABLE 313.3:

	MAX. HORIZONTAL SPACING	MAX. VERTICAL SPACING
COPPER PIPE ≤1 1/2"	6 FT.	10 FT.
COPPER PIPE >2"	10 FT.	10 FT.
COPPER TUBING ≤1 1/2"	6 FT.	10 FT.
COPPER TUBING >2"	10 FT.	10 FT.
CPVC ≤ 1"	3 FT.	10 FT.
CPVC > 1 1/2"	4 FT.	10 FT.

HANGER SPACING FOR WASTE AND VENT PIPING

ALL SUSPENDED SANITARY AND VENT PIPE SHALL BE SUPPORTED AS FOLLOWS PER 2018 UPC TABLE 313.3:

	MAX. HORIZ. SPACING	MAX. VERT. SPACING
ABS	4 FT.	10 FT.
PVC (TYPE DWV)	4 FT.	10 FT.
CAST-IRON HUBLESS*	EVERY 15 FT.	
*CAST-IRON OVER 4" SHALL BE SUPPORTED AT EVERY JOINT		

PLUMBING FIXTURE FLOW RATES PER 2018 UPC CH. 4

FIXTURE TYPE	FLOW RATE	NOTES
SHOWERHEADS	1.8 GPM @ 80 PSI	
LAVATORY FAUCETS, RESIDENTIAL	1.2 GPM @ 60 PSI	1
LAVATORY FAUCETS, NON-RESIDENTIAL	0.5 GPM @ 60 PSI	2
KITCHEN FAUCETS	1.8 GPM @ 60 PSI	3
GRAVITY TANK-TYPE WATER CLOSETS	1.28 GALLONS/FLUSH	4
FLUSHOMETER TANK WATER CLOSETS	1.28 GALLONS/FLUSH	4
FLUSHOMETER VALVE WATER CLOSETS	1.28 GALLONS/FLUSH	4
ELECTROMECHANICAL HYDRAULIC WATER CLOSETS	1.28 GALLONS/FLUSH	4
URINALS	0.5 GALLONS/FLUSH	

NOTES:

- LAVATORY FAUCETS SHALL NOT HAVE A FLOW RATE LESS THAN 0.8 GPM AT 20 PSI.
- WHERE COMPLYING FAUCETS ARE UNAVAILABLE, AERATORS RATED AT 0.35 GPM OR OTHER MEANS MAY BE USED TO ACHIEVE REDUCTION.
- KITCHEN FAUCETS MAY TEMPORARILY INCREASE FLOW ABOVE THE MAXIMUM RATE, BUT NOT ABOVE 2.2 GPM @ 60 PSI AND MUST DEFAULT TO A MAXIMUM FLOW RATE OF 1.8 GPM @ 60 PSI.
- INCLUDES SINGLE AND DUAL FLUSH WATER CLOSETS WITH AN EFFECTIVE FLUSH OF 1.6 GALLONS OR LESS. SINGLE FLUSH TOILETS - THE EFFECTIVE FLUSH VOLUME SHALL NOT EXCEED 1.6 GALLONS. THE EFFECTIVE FLUSH VOLUME IS THE AVERAGE FLUSH VOLUME WHEN TESTED IN ACCORDANCE WITH ASME A112.19.2 DUAL FLUSH TOILETS - THE EFFECTIVE FLUSH VOLUME SHALL NOT EXCEED 1.6 GALLONS. THE EFFECTIVE FLUSH VOLUME IS DEFINED AS THE COMPOSITE, AVERAGE FLUSH VOLUME OF TWO REDUCED FLUSHES AND ONE FULL FLUSH. FLUSH VOLUMES WILL BE TESTED IN ACCORDANCE WITH ASME A112.19.2 AND ASME A112.19.14.

NOTE TO CONTRACTOR

DRAWINGS ARE DIAGRAMMATIC, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT, AND EQUIPMENT REQUIRED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENT. REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS. REFER TO MANUFACTURER'S STANDARD INSTALLATION DRAWINGS FOR EQUIPMENT CONNECTIONS AND INSTALLATION REQUIREMENTS. PROVIDE DUCTWORK, CONNECTIONS, ACCESSORIES, OFFSETS, AND MATERIALS NECESSARY FOR A COMPLETE SYSTEM.

CONTRACTOR SUBSTITUTIONS & REVISIONS

PLEASE SUBMIT PROPOSALS FOR SUBSTITUTIONS OR REVISIONS FOR REVIEW AND APPROVAL PRIOR TO ORDERING MATERIAL OR DOING WORK. FOR EQUIPMENT THAT IS SCHEDULED BY MANUFACTURER'S NAME AND CATALOG DESIGNATIONS, THE MANUFACTURER'S PUBLISHED DATA AND/OR SPECIFICATION FOR THAT ITEM ARE CONSIDERED PART OF SPECIFICATION. ENGINEERING COSTS FOR REVISING MEP PLANS SHALL BE ADDRESSED IN THE COST ANALYSIS OF THE SUBSTITUTION PROPOSAL. CONTRACTOR TO COORDINATE WITH ENGINEER AND DETERMINE ASSOCIATED DESIGN AND PERMITTING COSTS. CONTRACTOR SHALL BE RESPONSIBLE FOR OTHER COSTS ASSOCIATED WITH UNFORESEEN ISSUES RESULTING FROM SUBSTITUTIONS OR REVISIONS.

PRE-CONSTRUCTION MEETING NOTES

CONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH THE ENGINEER FOR THE PURPOSE OF REVIEWING THE WORK PRIOR TO ORDERING ANY EQUIPMENT OR PERFORMING ANY WORK. THE MEETING SHALL BE LOCATED AT THE PROJECT SITE ON A DATE AND TIME TO BE MUTUALLY AGREED. THE MEETING WILL BE A WORKING SESSION. THE MEETING WILL BE FACILITATED BY THE ENGINEER AND THE AGENDA WILL INCLUDE A DETAILED REVIEW OF THE PLANS AND SPECIFICATIONS, CROSS CHECK WITH OTHER TRADES FOR COORDINATION ISSUES, REVIEW OF PROPOSED PRODUCTS, REVIEW OF PLANNED MEANS AND METHODS, AND ON-SITE INVESTIGATION OF FIELD CONDITIONS RELATIVE TO EXISTING CONDITIONS THAT COULD AFFECT THE WORK. PERSONS ATTENDING THE MEETING SHALL BE KNOWLEDGEABLE OF THE PROJECT AND SHALL BE THE SPECIFIC PERSONS INTENDED TO CONTINUE WITH THE PROJECT THROUGH TO COMPLETION. IF REQUIRED, REVISED PLANS WILL BE ISSUED THROUGH OFFICIAL CHANNELS. CHANGES IN THE BID PRICE WILL BE DISCUSSED, BUT NO CHANGE ORDERS WILL BE ISSUED UNLESS PROCESSED THROUGH OFFICIAL CHANNELS. IT SHALL BE UNDERSTOOD THAT THE ENGINEER HAS NO AUTHORITY TO ISSUE CHANGE ORDERS.

THE FOLLOWING TRADES SHALL BE REPRESENTED FOR THE MINIMUM TIME INDICATED:

MECHANICAL SHEET METAL	4 HOURS
PLUMBING/PIPING	4 HOURS
ELECTRICAL	4 HOURS
SPRINKLER	2 HOURS
GENERAL CONTRACTOR	ALL SESSIONS

PLUMBING NOTES


- CONNECTIONS: PROVIDE PLUMBING FIXTURE CONNECTIONS TO BUILDING WASTE, VENT, COLD WATER, AND HOT WATER SYSTEM IN ACCORDANCE WITH DRAWINGS, MANUFACTURER'S RECOMMENDATIONS, AND LOCAL CODES. CONNECT TO EACH FIXTURE, EQUIPMENT, ETC. WITH ALL ACCESSORIES, VALVES, VACUUM BREAKERS, REGULATORS, UNIONS, ETC. AS REQUIRED AND AS RECOMMENDED BY THE MANUFACTURERS. REFER TO PLUMBING FIXTURE CONNECTION SCHEDULE ON PLANS.
- HOT AND COLD: WATER PIPING CONNECTION TO EACH FIXTURE SHALL BE COLD WATER ON THE RIGHT HAND SIDE AND HOT WATER ON THE LEFT HAND SIDE.
- HOT WATER: NON-CIRCULATING HOT WATER PIPE SHALL NOT EXCEED 10' UNLESS OTHERWISE SHOWN ON DRAWINGS.
- VENT STACKS: COORDINATE VENT STACK WITH HVAC EQUIPMENT TO MAINTAIN MINIMUM 10' CLEARANCE FROM OUTSIDE AIR INTAKES.
- CLEANOUTS: PROVIDE CLEANOUTS PER CURRENT UPC AND AS REQUIRED BY LOCAL JURISDICTIONS. CLEANOUTS SHALL BE LOCATED IN WALLS/FLOORS WHERE THEY ARE NOT HIGHLY VISIBLE. FLOOR CLEANOUTS IN CARPETED AREAS TO BE FITTED WITH CARPET INSERTS. LOCATIONS SHALL BE SUBMITTED TO ARCHITECT FOR APPROVAL. NOTE: NOT ALL CLEANOUTS ARE SHOWN ON THE PLUMBING DRAWINGS.
- SUDS RELIEF: PROVIDE SUDS RELIEF IN ACCORDANCE WITH 2018 UPC SECTION 711.0, STATE AND LOCAL CODES.
- SHUT-OFFS: PROVIDE 1/4 TURN BALL VALVE ANGLE STOP SHUT-OFF VALVES AND BRAIDED STAINLESS STEEL FLEX CONNECTORS AT HOT AND COLD WATER SUPPLY TO EACH FIXTURE. EXCEPTION: PROVIDE SCREWDRIVER STOPS AT BATH/SHOWERS.
- TUB SPOUTS SHALL BE THREADED (NO PUSH-ON FITTINGS).
- TRAP ARMS: PROVIDE TRAP ARMS SUCH THAT THE MAXIMUM LENGTH WILL NOT EXCEED CODE REQUIREMENTS.
- ADA INSULATION: AT PLUMBING PIPING EXPOSED UNDER LAVATORIES, INSULATE THE EXPOSED PIPING AND TRAPS WITH PRODUCT SPECIFICALLY DESIGNED FOR THIS APPLICATION MEETING ADA REQUIREMENTS. PROVIDE HANDI-LAV GUARD OR EQUIVALENT. OFFSET P-TRAPS TO CLEAR WHEELCHAIR ACCESS.
- GAS EQUIPMENT: GAS EQUIPMENT SHALL BE INSTALLED PER EQUIPMENT LISTINGS, APPLICABLE SFGC, SPC, LOCAL CODES & NFPA STANDARDS.
- GAS CONNECTIONS: INSTALL FLEXIBLE QUICK DISCONNECT ASSEMBLIES FOR ALL GAS FIRED KITCHEN EQUIPMENT PER APPLICABLE SFGC, SPC, LOCAL CODES & NFPA STANDARDS. PROVIDE LOCKABLE GAS SHUT-OFF VALVES FOR FIREPLACES & BBQS IN UNATTENDED PUBLIC LOCATIONS IN THE BUILDING.
- GAS PIPING CONNECTIONS TO WATER HEATERS, BOILERS AND FURNACES SHALL HAVE DIRT LEGS AND UNIONS PROVIDED ON APPLIANCE SIDE OF SHUTOFF VALVE.
- GAS PIPING INSTALLATION: STEEL OR MALLEABLE IRON FUEL LINES 2" OR SMALLER SHALL BE ASSEMBLED USING THREAD SEALANT SUITABLE FOR NATURAL GAS. GAS PIPING LARGER THAN 2" SHALL HAVE WELDED FITTINGS.
- GAS PIPING UNDERGROUND: WHERE INSTALLED BELOW GRADE THROUGH THE OUTER FOUNDATION OR BASEMENT WALL OF A BUILDING, SHALL BE ENCASED IN A PROTECTIVE PIPE SLEEVE. THE ANNULAR SPACE BETWEEN THE GAS PIPING AND THE SLEEVE SHALL BE SEALED.
- GAS PIPING ABOVE GROUND: WHERE PASSING THROUGH AN OUTSIDE WALL, GAS PIPING SHALL BE PROTECTED AGAINST CORROSION BY COATING OR WRAPPING WITH AN INERT MATERIAL. WHERE PIPING IS ENCASED IN A PROTECTIVE PIPE SLEEVE, THE ANNULAR SPACE BETWEEN THE PIPING AND THE SLEEVE SHALL BE SEALED.
- GAS PIPE SUPPORT: FUEL LINES SHALL BE SUPPORTED OR STRAPPED, AND SHALL BE PLUMB AND SQUARE.
- GAS PIPING ON ROOFTOPS SHALL BE SUPPORTED AND ANCHORED TO THE ROOF.
- GAS PIPING SHALL NOT BE BURIED UNDER A BUILDING, SLAB OR OTHER STRUCTURE.
- GAS PIPING PROTECTIVE COATING: PAINT ALL EXTERIOR EXPOSED GAS PIPING WITH TWO COATS OF RUST INHIBITIVE PAINT. COLOR: GRAY.
- WATER HAMMER ARRESTORS: PROVIDE AT THE END OF HOT AND COLD WATER LINES SERVING TWO OR MORE FIXTURES; SIZE IN ACCORDANCE WITH PLUMBING AND DRAINAGE INSTITUTE (PDI) REQUIREMENTS. WATER HAMMER ARRESTORS ARE REQUIRED FOR QUICK CLOSING VALVES, SUCH AS LAUNDRY WASHERS, FLUSH VALVES (PUBLIC TOILETS), ETC.
- TRAP PRIMERS AS SPECIFIED: PROVIDE TRAP PRIMERS AND PIPING FOR FLOOR DRAINS, FLOOR SINKS, AREA DRAINS & HUB DRAINS. ARRANGE PIPING TO ACHIEVE EQUAL FLOW TO EACH DRAIN AND FLOOR SINK FOR TRAP PRIMERS SERVING MULTIPLE DRAINS AND FLOOR SINKS. COORDINATE EXACT LOCATIONS WITH ARCHITECT & ELECTRICAL ENGINEER.
- P-TRAPS: ALL EXPOSED P-TRAPS SHALL BE CHROME-PLATED BRASS. P-TRAPS SERVING HANDICAPPED COUNTER TOP LAVATORIES SHALL BE INSULATED.
- THROUGHOUT THE PROJECT PROVIDE BALL VALVES. GATE VALVES SHALL NOT BE USED. NO EXCEPTIONS.
- HOT WATER RECIRCULATING BALANCING VALVES SHOULD BE BELL & GOSSETT CIRCUIT SETTER (WATTS OR EQUAL) WITH INTEGRAL READOUT PORTS, ADJUSTMENT KNOB, DRAIN CONNECTION, AND POSITIVE SHUTOFF.
 - ICE MACHINES AND ICE MAKERS
 - CARBONATED BEVERAGE DISPENSING SYSTEMS
 - COFFEE BREWERS
 - ESPRESSO MACHINES
 - WATER FILTERS
 - STEAM OR HOT WATER BOILERS
 - IRRIGATION SYSTEM
 - FIRE PROTECTION SYSTEM
 - CHEMICAL TREATMENT SYSTEM
 - SOAP/CHEMICAL DISPENSER SYSTEM
 - COMMERCIAL WASHER

APPLICABLE CODES

THE FOLLOWING PROJECT DESIGN IS BASED ON THE FOLLOWING CODES:


- 2018 INTERNATIONAL BUILDING CODE (IBC)
- 2018 INTERNATIONAL MECHANICAL CODE (IMC)
- 2018 UNIVERSAL PLUMBING CODE (UPC)
- 2018 WASHINGTON STATE ENERGY CODE (WSEC) - COMMERCIAL PROVISIONS

NO.	DATE	DESCRIPTION	REVISIONS



JM	JM	RJ	JR
DRAWN:	DESIGNED:	CHECKED:	APPROVED:

BRADLEY HEIGHT APARTMENTS - BUILDING D
 PROJECT: 202 27TH AVE SE
 PUYALLUP, WA 98374
 19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343



DATE: 10/11/2023


SHEET TITLE:
PLUMBING NOTES AND TABLES

SHEET NO.
POD.01

PLUMBING CALCULATIONS

CALCULATIONS BASED ON 2018 UPC															
1 Bedroom Units (1 Bath)															
FITTURE	FIXTURE UNITS										TOTAL QTY OF FIXTURES	TOTAL FIXTURE UNITS			
	TOTAL	CW	HW	WV	B	1	2	3	R	# OF FIXTURES PER UNIT		SERVICE	CW ONLY	HW ONLY	WV ONLY
WATER CLOSET	2.5	2.5	0	3	4	8	8	8	0	1	28	70	70	0	84
LAVATORY	1	0.75	0.75	1	4	8	8	8	0	1	28	28	21	21	28
BATHTUB	4	3	3	2	4	8	8	8	0	1	28	112	84	84	56
CLOTHES WASHER	4	3	3	3	4	8	8	8	0	1	28	112	84	84	84
KITCHEN SINK W/ DISHWASHER	3	2.25	2.25	2	4	8	8	8	0	1	28	84	63	63	56
TOTAL:											406	322	252	308	
2 Bedroom Unit (2 Bath)															
FITTURE	FIXTURE UNITS										TOTAL QTY OF FIXTURES	TOTAL FIXTURE UNITS			
	TOTAL	CW	HW	WV	B	1	2	3	R	# OF FIXTURES PER UNIT		SERVICE	CW ONLY	HW ONLY	WV ONLY
WATER CLOSET	2.5	2.5	0	3	2	4	4	4	0	2	28	70	70	0	84
LAVATORY	1	0.75	0.75	1	2	4	4	4	0	2	28	28	21	21	28
BATHTUB	4	3	3	2	2	4	4	4	0	2	28	112	84	84	56
CLOTHES WASHER	4	3	3	3	2	4	4	4	0	1	14	56	42	42	42
KITCHEN SINK W/ DISHWASHER	3	2.25	2.25	2	2	4	4	4	0	1	14	42	31.5	31.5	28
TOTAL:											308	248.5	178.5	238	
Public Fixtures															
FITTURE	FIXTURE UNITS										TOTAL QTY OF FIXTURES	TOTAL FIXTURE UNITS			
	TOTAL	CW	HW	WV	B	1	2	3	R	# OF FIXTURES PER UNIT		SERVICE	CW ONLY	HW ONLY	WV ONLY
HOSE BIB	2.5/1	2.5/1	0	0	3	1	0	0	0	0	4	5.5	5.5	0	0
4" FLOOR DRAIN	0	0	0	8	1	0	0	0	0	0	1	0	0	0	8
TOTAL:											5.5	5.5	0	8	
TOTAL FIXTURE UNITS:	719.5	576	430.5	554											
PEAK FLOW:	164.6GPM														
SUPPLY WASTE	3"	6"													
REQUIRED SERVICE SIZE IN BUILDING:															

BRADLEY HEIGHTS APARTMENTS - WATER SUPPLY PRESSURE CALCULATIONS ARE BASED ON 2018 UPC APPENDIX A	
FROM STREET TO RBPB	
STREET PRESSURE, PSI	75
MINIMUM STREET PRESSURE, PSI	75
<i>ASSUME +/- 5 PSI FLUCTUATION</i>	
EQUIPMENT LOSSES, PSI	
WATER METER LOSS	4
BACKFLOW PREVENTER	10
SITE SERVICE LINE (ESTIMATE)	
PIPING SYSTEM LENGTH, FEET	50
FITTING ALLOWANCE, FEET	12.5
<i>FROM STREET TO RBPB</i>	
ZONE FRICTION LOSS FACTOR, PSI/100'	7.0
TOTAL ZONE FRICTION LOSS, PSI	4.38
MINIMUM PRESSURE AT RBPB, PSI	56.63
FROM RBPB TO FURTHEST APARTMENT UNIT	
MINIMUM PRESSURE AT END PREVIOUS ZONE, PSI	56.6
EQUIPMENT LOSSES, PSI	
THERMOSTATIC MIXING VALVE LOSS	4
STATIC HEAD, PSI	
TOTAL ELEVATION GAIN, FT	30
PIPING FRICTION LOSSES	
PIPING SYSTEM LENGTH, FEET	150
FITTING ALLOWANCE, FEET	22.5
ZONE FRICTION LOSS FACTOR, PSI/100'	7.0
TOTAL ZONE FRICTION LOSS, PSI	12.075
MINIMUM PRESSURE AT FURTHEST APARTMENT UNIT, PSI	27.6
FROM FURTHEST APARTMENT UNIT TO FURTHEST FIXTURE	
MINIMUM PRESSURE AT FURTHEST APARTMENT UNIT, PSI	27.6
PIPING FRICTION LOSSES	
RISER TO MANIFOLD, FEET	4
FITTING ALLOWANCE, FEET	6
<i>FROM MANIFOLD TO FURTHEST FIXTURE</i>	
ZONE FRICTION LOSS FACTOR, PSI/100'	14.0
TOTAL ZONE FRICTION LOSS, PSI	6.3
MINIMUM PRESSURE AT FURTHEST FIXTURE, PSI	21.3



DRAWN: JM	DESIGNED: JM	CHECKED: RJ	APPROVED: JR
-----------	--------------	-------------	--------------

BRADLEY HEIGHT APARTMENTS - BUILDING D
 202 27TH AVE SE
 PUYALLUP, WA 98374

19401 40TH AVE W. SUITE 302
 LYNWOOD, WA 98036
 PHONE: (206)364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
PLUMBING CALCULATIONS

SHEET NO.
POD.02

NO.	DATE	DESCRIPTION	REVISIONS

PLUMBING SCHEDULES

PIPE MATERIALS

PIPE TYPE	MATERIAL	JOINT	NOTES
WATER DISTRIBUTION PIPING	COPPER, TYPE L.	SOLDERED	2
APARTMENT WATER PIPING	PEX-A	EXPANSION OR PUSH-FIT FITTINGS	2
WASTE AND VENT PIPING	SCHEDULE 40 SOLID CORE PVC	SOLVENT CEMENT	1,3
CONDENSATE DRAIN PIPING	COPPER, TYPE M.	SOLDERED OR PROPPRESS FITTINGS	

NOTES:

- ALL SANITARY SYSTEM MATERIALS SHALL BE LISTED BY AN APPROVED LISTING AGENCY.
- PROVIDE THERMAL EXPANSION LOOPS FOR ALL WATER PIPING IN ACCORDANCE WITH MANUFACTURER INSTRUCTIONS.
- PROVIDE CAST IRON PIPING FOR WASTE DISCHARGE EXCEEDING 110 DEGREES FAHRENHEIT.

PIPE SIZING SCHEDULE - COPPER TYPE L AT 7.0 PSI/100 FEET

PIPE SIZE	COLD WATER, FLUSH TANK			HOT WATER			COLD WATER, FLUSH VALVE		
	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS
1/2"	3.0	2.8	4.0	3.0	2.8	4.0	---	---	---
3/4"	9.0	7.5	5.2	8.5	7.0	4.9	---	---	---
1"	22.0	16.0	6.4	16.0	12.2	5.0	---	---	---
1-1/4"	45.0	27.0	7.3	27.0	18.5	5.0	9	27	7.3
1-1/2"	100.0	43.0	8.0	43.0	26.0	5.0	30	42.5	8
2"	230.0	75.0	8.0	112.0	45.0	5.0	125.0	74.0	8.0
2-1/2"	440.0	116.0	8.0	215.0	72.0	5.0	340.0	116.0	8.0
3"	750.0	160.0	8.0	350.0	100.0	5.0	680.0	160.0	8.0
4"	1600.0	280.0	8.0	800.0	175.0	5.0	1600.0	280.0	8.0
6"	5250.0	650.0	8.0	2750.0	400.0	5.0	5250.0	650.0	8.0

PIPE SIZING SCHEDULE - PEX AT 14.0 PSI/100 FEET

PIPE SIZE	COLD WATER, FLUSH TANK			HOT WATER			COLD WATER, FLUSH VALVE		
	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS	FIXTURE UNITS	FLOW, GPM	VELOCITY, FPS
1/2"	3.0	3.0	5.5	3.0	3.4	6.1	---	---	---
3/4"	9.0	7.8	7.1	11.0	8.5	7.7	1.0	7.8	7.1
1"	21.0	15.3	8.4	20.0	14.6	8.0	2.0	15.3	8.4
1-1/4"	44.0	26.1	9.6	33.0	21.8	8.0	9.0	26.1	9.6
1-1/2"	77.0	37.9	10.0	54.0	30.3	8.0	24.0	37.9	10.0
2"	199.0	65.0	10.0	134.0	52.0	8.0	91.0	65.0	10.0
2-1/2"	375.0	99.0	10.0	270.0	79.2	8.0	239.0	99.0	10.0
3"	589.0	140.8	10.0	443.0	112.6	8.0	494.0	140.8	10.0

REDUCED PRESSURE BACKFLOW ASSEMBLY

EQUIP NO.	QTY	SERVICE	INLET/OUTLET SIZE	BASIS OF DESIGN	NOTES
RPBP-1	1	DOMESTIC WATER	3"	ZURN WILKINS 375	1,2

NOTES:

- INSTALL IN ACCORDANCE WITH MANUFACTURER INSTRUCTIONS.
- ALL DOMESTIC WATER EQUIPMENT SHALL BE NSF-61 LISTED.

HYBRID ELECTRIC HEAT PUMP WATER HEATER

EQUIP NO.	SERVICE	UNIFORM ENERGY FACTOR	GPH RECOVERY AT 90°F TR	STORAGE (GAL)	INLET/OUTLET CONNECTION	OPERATING WEIGHT (LBS)	ELECTRICAL	BASIS OF DESIGN	NOTES
HPWH-1	APARTMENT UNITS	4.00	27	80	3/4"	912	208V/1P/21A	RHEEM PROPH80	1,2,3,4

NOTES:

- ELECTRICAL REQUIREMENTS ARE BASED ON NON-SIMULTANEOUS OPERATION.
- FOR WATER HEATER PIPING DIAGRAM SEE DETAIL 1/P7.00.
- ALL DOMESTIC WATER EQUIPMENT SHALL BE NSF-61 LISTED.
- PROVIDE INLET AND OUTLET DUCTS FOR HEAT PUMP WATER HEATERS. SEE MECHANICAL DRAWINGS FOR ROUTING AND TERMINATION.


EXPANSION TANK

EQUIP NO.	SERVICE	CAPACITY GAL.	PRE-CHARGE PRESSURE, PSI	TANK SIZE		OPERATING WEIGHT, LBS	BASIS OF DESIGN	NOTES
				DIAMETER	HEIGHT			
ET-1	DOMESTIC HOT WATER	4.5	50	11	15	9	THERM-X-TROL ST-12	1

NOTES:

- INSTALL PER MANUFACTURER'S RECOMMENDATIONS

NO.	DATE	DESCRIPTION	REVISIONS



ROBISON ENGINEERING, INC.

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PH: 206-864-3343
REG PROJECT NO: 773006
CONTACT: AIME ESPINELLI

DRAWN: JM	DESIGNED: JM	CHECKED: RJ	APPROVED: JR
-----------	--------------	-------------	--------------

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206/364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
PLUMBING SCHEDULES

SHEET NO.
POD.03



GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU

FLAG NOTES


NOT USED

BACKWATER VALVE ANALYSIS - SS POC:
 IF UPSTREAM MANHOLE RIM ELEVATION IS HIGHER THAN FINISH FLOOR ELEVATION CONTACT ENGINEER FOR FURTHER EVALUATION.

UNDERSLAB WASTE & VENT PLAN
 SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM	DESIGNED:	JM	CHECKED:	RJ	APPROVED:	JR
--------	----	-----------	----	----------	----	-----------	----

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
UNDERSLAB WASTE & VENT PLAN

SHEET NO.
P2D.00



GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU

FLAG NOTES


NOT USED

BASEMENT WASTE & VENT PLAN

SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W. SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206/364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
BASEMENT WASTE & VENT PLAN

SHEET NO.
P2D.01



GENERAL NOTES


1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.

PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU



FLAG NOTES

NOT USED

LEVEL 1 WASTE & VENT PLAN
SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
202 27TH AVE SE
PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
LEVEL 1 WASTE & VENT PLAN

SHEET NO.
P2D.02



GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU

FLAG NOTES


NOT USED

LEVEL 2 WASTE & VENT PLAN

SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM	DESIGNED:	JM	CHECKED:	RJ	APPROVED:	JR
--------	----	-----------	----	----------	----	-----------	----

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 206-364-3343
 860 PROJECT NO. 777006
 CONTACT: AIMEE SPINELLI

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
LEVEL 2 WASTE & VENT PLAN

SHEET NO.
P2D.03



GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU

FLAG NOTES


NOT USED

LEVEL 3 WASTE & VENT PLAN

SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM	DESIGNED:	JM	CHECKED:	RJ	APPROVED:	JR
--------	----	-----------	----	----------	----	-----------	----

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 206-864-3364
 861 PROJECT NO. 777006
 CONTACT: ARIAN ESPINELLI

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
LEVEL 3 WASTE & VENT PLAN

SHEET NO.
P2D.04



GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 5/P7.01.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	172 DFU	256 DFU
6"	1,380 DFU	576 DFU	1,380 DFU
8"	3,600 DFU	2,112 DFU	3,600 DFU

FLAG NOTES


NOT USED

ROOF WASTE & VENT PLAN

SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR


BRADLEY HEIGHT APARTMENTS - BUILDING D
 PROJECT: 202 27TH AVE SE
 PUYALLUP, WA 98374

ROBISON ENGINEERING, INC.
 19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

DATE: 10/11/2023

SHEET TITLE:
ROOF WASTE & VENT PLAN

SHEET NO.
P2D.05




GENERAL NOTES

1. PROVIDE EXPANSION LOOPS FOR ALL WATER PIPING PER THE MANUFACTURER'S INSTRUCTIONS. SEE DETAIL 3/P7.01.
2. INSTALL HEAT TRACE ON SUPPLY PIPE IN NON CONDITIONED SPACES.


FLAG NOTES

NOT USED

BASEMENT PLUMBING SUPPLY PLAN
SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JIM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR


PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
202 27TH AVE SE
PUYALLUP, WA 98374

ROBISON ENGINEERING, INC
19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-864-3343

DATE: 10/11/2023

SHEET TITLE:
BASEMENT PLUMBING SUPPLY PLAN

SHEET NO.
P3D.01





GENERAL NOTES

1. PROVIDE EXPANSION LOOPS FOR ALL WATER PIPING PER THE MANUFACTURER'S INSTRUCTIONS. SEE DETAIL 3/P7.01.
2. INSTALL HEAT TRACE ON SUPPLY PIPE IN NON CONDITIONED SPACES.

FLAG NOTES #

NOT USED

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JIM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
 202 27TH AVE SE
 PUYALLUP, WA 98374

ROBISON
ENGINEERING, INC


19401 40TH AVE W. SUITE 302
 LYNNWOOD, WA 98036
 206-866-3343
 PHONE: 206/364-3343


DATE: 10/11/2023

SHEET TITLE:
**LEVEL 1
PLUMBING
SUPPLY PLAN**

SHEET NO.
P3D.02

LEVEL 1 PLUMBING SUPPLY PLAN
SCALE: 1/8" = 1'-0"






GENERAL NOTES

1. PROVIDE EXPANSION LOOPS FOR ALL WATER PIPING PER THE MANUFACTURER'S INSTRUCTIONS. SEE DETAIL 3/P7.01.
2. INSTALL HEAT TRACE ON SUPPLY PIPE IN NON CONDITIONED SPACES.


FLAG NOTES

NOT USED

LEVEL 2 PLUMBING SUPPLY PLAN
SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JIM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
202 27TH AVE SE
PUYALLUP, WA 98374


19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
206-866-3342 TEL
PHONE: 206/364-3343

ROBISON
ENGINEERING, INC

DATE: 10/11/2023

SHEET TITLE:
LEVEL 2
PLUMBING
SUPPLY PLAN

SHEET NO.
P3D.03




GENERAL NOTES

1. PROVIDE EXPANSION LOOPS FOR ALL WATER PIPING PER THE MANUFACTURER'S INSTRUCTIONS. SEE DETAIL 3/P7.01.
2. INSTALL HEAT TRACE ON SUPPLY PIPE IN NON CONDITIONED SPACES.


FLAG NOTES

NOT USED

LEVEL 3 PLUMBING SUPPLY PLAN
SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
202 27TH AVE SE
PUYALLUP, WA 98374

ROBISON ENGINEERING, INC
19401 40TH AVE. W. SUITE 302
LYNNWOOD, WA 98036
PHONE: 206/866-3343

DATE: 10/11/2023

SHEET TITLE:
**LEVEL 3
PLUMBING
SUPPLY PLAN**

SHEET NO.
P3D.04

GENERAL NOTES


 = WASTE & VENT RISER IDENTIFICATION (I.E. RISER "#"). REFER TO P200 SERIES FOR RISER DIAGRAMS.

- SUD RELIEF PIPING WITH LENGTH OF 8FT WILL BE USED.
- WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

ABBREVIATION LEGEND:

LV = LAVATORY	(1 DFU)
BT = BATHTUB	(2 DFU)
SH = SHOWER	(2 DFU)
KS = KITCHEN SINK WITH DISHWASHER	(2 DFU)
WM = WASHING MACHINE	(3 DFU)
WC = WATER CLOSET	(3 DFU)
UR = URINAL	(2 DFU)
FD = FLOOR DRAIN	(2 DFU)
FS = FLOOR SINK	(4 DFU)
HD = HUB DRAIN	(4 DFU)



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM
DESIGNED:	JM
CHECKED:	RJ
APPROVED:	JR

BRADLEY HEIGHT APARTMENTS - BUILDING D

PROJECT: 202 27TH AVE SE
PUYALLUP, WA 98374

19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: 206/364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
WASTE RISER
DIAGRAMS

SHEET NO.
P4D.00

GENERAL NOTES


 = WASTE & VENT RISER IDENTIFICATION (I.E. RISER "#"). REFER TO P200 SERIES FOR RISER DIAGRAMS.

- SUD RELIEF PIPING WITH LENGTH OF 8FT WILL BE USED.
- WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING 4" AND LARGER MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.


PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1½"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

ABBREVIATION LEGEND:

LV = LAVATORY	(1 DFU)
BT = BATHTUB	(2 DFU)
SH = SHOWER	(2 DFU)
KS = KITCHEN SINK WITH DISHWASHER	(2 DFU)
WM = WASHING MACHINE	(3 DFU)
WC = WATER CLOSET	(3 DFU)
UR = URINAL	(2 DFU)
FD = FLOOR DRAIN	(2 DFU)
FS = FLOOR SINK	(4 DFU)
HD = HUB DRAIN	(4 DFU)



NO.	DATE	DESCRIPTION	REVISIONS



DRAWN: JM	DESIGNED: JM	CHECKED: RJ	APPROVED: JR
-----------	--------------	-------------	--------------

BRADLEY HEIGHT APARTMENTS - BUILDING D

PROJECT: 202 27TH AVE SE
PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.


DATE: 10/11/2023

SHEET TITLE:
WASTE RISER
DIAGRAMS


SHEET NO.
P4D.01




PIPE SLEEVES THROUGH WALLS
SCALE: NONE




RISER PIPE SUPPORT
SCALE: NONE




VENT TERMINATION CLEARANCE
SCALE: NONE



PIPE SLAB PENETRATION
SCALE: NONE



VENT THROUGH ROOF
SCALE: NONE



REDUCED PRESSURE BACKFLOW PREVENTER
SCALE: NONE

EQUIPMENT SCHEDULE

WATER METERS (NEXT CENTURY MULTI-JET WATER METER MODEL M201CH, 3/4")


TRANSCIVER: WIRELESS METERING DATA TRANSCIVER DUAL INPUT WITH DISPLAY, WITH BATTERIES, TEHAMA WIRELESS MODEL TW-165A-PP.

WIRELESS REPEATERS: TEHAMA COMPATIBLE REPEATERS; QUANTITY TWO. TEHAMA WIRELESS TW-191X.


UDATA CONCENTRATING ACCESS POINT (DCAP): TEHAMA WIRELESS TW-203X-T-150.
 • DCAP TO BE INSTALLED ON MAIN COMM/DATA BOARD AND POWER SUPPLY PLUGGED INTO RECEPTACLE.
 • PROVIDE ETHERNET OR WIFI ACCESS FOR INTERNET ACCESS TO DCAP.

NOTES:

1. PROVIDE COLD WATER METER AND REMOTE TRANSCIVER FOR EACH APARTMENT.
2. SECURE METER TO FLOOR/CEILING ASSEMBLY.
3. REFER TO P5 SERIES FOR PIPE SIZES.
4. TRANSITION TO PEX PIPING WITHIN EACH UNIT.




UNIT SUB-METERING AND PEX MANIFOLD
SCALE: NONE



HORIZONTAL WET VENTING
SCALE: NONE

NO.	DATE	DESCRIPTION	REVISIONS



JM	JM	RJ	JR
DRAWN:	DESIGNED:	CHECKED:	APPROVED:

PROJECT: BRADLEY HEIGHT APARTMENTS - BUILDING D
 202 27TH AVE SE
 PUYALLUP, WA 98374


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023


SHEET TITLE: **DETAILS**

SHEET NO. **P7D.00**




HUB DRAIN
SCALE: NONE

6




TRAP PRIMER
SCALE: NONE

5




ISLAND SINK INSTALLATION
SCALE: NONE

4




EXPANSION LOOP CONFIGURATIONS
SCALE: NONE

3



SUDS RELIEF
SCALE: NONE



2



TYPICAL VALVE PLACEMENT
SCALE: NONE

1

NO.	DATE	DESCRIPTION	REVISIONS



DRAWN:	JM	DESIGNED:	JM	CHECKED:	RJ	APPROVED:	JR
--------	----	-----------	----	----------	----	-----------	----

PROJECT: **BRADLEY HEIGHT APARTMENTS - BUILDING D**
202 27TH AVE SE
PUYALLUP, WA 98374

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343

ROBISON ENGINEERING, INC.

DATE: 10/11/2023

SHEET TITLE:
DETAILS

SHEET NO.
P7D.01