

LAND USE & WSEC INFORMATION

PARCEL SUMMARY

P/N 0420264021:

TAX DESCRIPTION - Section 26 Township 20 Range 04 Quarter 44 - & 35 20 4E D 1/21 BEG INTER S LI SEC 26 WITH E 1/16 LI SD SEC TH S ALG 1/16 LI SEC 35 95.4 FT TH E 258.26 FT TH N TO SLY LI CO RD TH NWLY ALG SD SLY LI CO RD TO E 1/16 LI SEC 26 TH S ALG SD 1/16 LI TO BEG EXC AREA - 95,396 SF, 2.190 ACRES

P/N 0420351030:

TAX DESCRIPTION - BEG AT 1/16 SEC COR 1321.48 FT W OF COR COM TO SECS 25, 26, 35 & 36 TH S ALG 1/16 LI 95.4 FT TO POB TH E 258.26 FT TH S 100 FT TH W 258.26 FT TH N 100 FT TO POB EXC RDS AREA - 25,700 SF, 0.590 ACRES

P/N 0420351029:

TAX DESCRIPTION - Section 35 Township 20 Range 04 Quarter 11 : COM 1/16 SEC COR 1321.48 FT W OF COR MON COMMON TO SECS 25, 26, 35 & 36 TH S ALG 1/16 SEC LI 195.4 FT TO POB TH E 258.26 FT TH S 100 FT TH W 258.26 FT TH N 100 FT TO POB EXC RDS EXC SHAW CO RD AREA - 25,265 SF, 0.58 ACRES

P/N 0420351026:

TAX DESCRIPTION - Section 35 Township 20 Range 04 Quarter 11 : COM AT 1/16 COR 1321.48 FT W OF COR MON COMMON TO SECS 25, 26, 35 & 36 TH S ALG 1/16 SEC LI 295.4 FT TO POB TH E 258.35 FT TH S 100 FT TH W 258.35 FT TH N 100 FT TO POB EXC W 15 FT CO RD EXC SHAW CO RD AREA - 25,265 SF, 0.58 ACRES

P/N 0420264053:

TAX DESCRIPTION - Section 35 Township 20 Range 04 Quarter 11 Section 26 Township 20 Range 04 Quarter 44 L 4 OF DBLR 2003-03-31-5001 DESC AS FOLL THAT POR OF SE OF SE & NE OF NE OF SEC 35 DESC AS COM AT NE COR OF W 1/2 OF SD NE OF NE PT BEARS N 88 DEG 32 MIN 51 SEC AREA - 202,648 SF, 4.652 ACRES

P/N 0420351066:

TAX DESCRIPTION - Section 35 Township 20 Range 04 Quarter 11 L 3 OF DBLR 2003-03-31-5001 DESC AS FOLL THAT POR OF NE OF NE DESC AS COM AT NE COR OF W 1/2 OF NE OF NE PT BEARS N 88 DEG 32 MIN 51 SEC W 640.11 FT FROM MON OF NE COR TH S 01 DEG 15 MIN 04 SEC W 491.43 FT T AREA - 58,789 SF, 1.35 ACRES

P/N 0420264054:

TAX DESCRIPTION - Section 26 Township 20 Range 04 Quarter 44 L 5 OF DBLR 2003-03-31-5001 DESC AS FOLL THAT POR OF SE OF SE & NE OF NE OF SEC 35 DESC AS BEG AT NE COR OF W 1/2 OF SD NE OF NE PT BEARS N 88 DEG 32 MIN 51 SEC W 640.11 FT FROM MON OF NE COR SD SEC 35 TH S AREA - 43,335 SF, 0.995 ACRES

ZONING

DESIGNATION: RM-20, HIGH DENSITY MULTI-FAMILY RESIDENTIAL

USE: DWELLING, MULTIPLE-FAMILY
 MINIMUM LOT AREA: 4,000 SF
 MINIMUM LOT DIMENSIONS: 40 FT X 70 FT
 MINIMUM SETBACKS: 20 FT FRONT, 25 FT MAJOR ARTERIAL, 20 FT REAR, 15 FT SIDE
 MAXIMUM HEIGHT: 36 FT
 BASE DENSITY: 16 du/ac, BONUS UP TO 22 du/ac (193 units / 8.66 ac = 21.9 du/ac)
 MAXIMUM LOT COVERAGE: 55%
 MAXIMUM FAR: 3

NUMBER OF BUILDINGS:

PHASE 1:	5
PHASE 2:	4
TOTAL:	9

RESIDENTIAL VEHICLE PARKING ANALYSIS

DIMENSIONS:

STANDARD: 9'-x-20' 8' x 18'
 COMPACT: 8'-x-17' 7' x 15'

PHASE 1

PHASE 1 REQUIRED: 2 STALLS PER UNIT = 120 x 2 = 240
PHASE 1 PROVIDED = 242
 EXCESS STALLS: 240 - 242 = 2

COMPACT MIN. = 30% OF REQUIRED = **240 x 0.30 = 72**
 COMPACT MAX. = 50% OF REQUIRED = 240 x 0.50 = 120
COMPACT PROVIDED: 75

PHASE 2

PHASE 2 REQUIRED: 2 STALLS PER UNIT = 59 x 2 = 116
 PHASE 2 PROVIDED = 125
 EXCESS STALLS: 125 - 116 = 9

COMPACT MIN. = 30% OF REQUIRED = 116 x 0.30 = 35
 COMPACT MAX. = 50% OF REQUIRED = 116 x 0.50 = 58
 COMPACT STALLS PROVIDED: 32

TOTAL - PHASE 1 & PHASE 2

REQUIRED: 2 STALLS PER UNIT = 179 x 2 = 358
 ON-SITE VEHICLE STALLS PROVIDED: 259 + 125 = 384
 EXCESS STALLS: 384-358 = 26

COMPACT MIN. = 30% OF REQUIRED = 358 x 0.30 = 107
 COMPACT MAX. = 50% OF REQUIRED = 358 x 0.50 = 179
COMPACT STALLS PROVIDED: 135

TOTAL ACCESSIBLE STALL REQUIREMENT

PHASE 1 ACCESSIBLE STALLS
 PHASE 1 REQUIRED: 259 x 0.02 = 5
 PHASE 1 PROVIDED: 22 > 5 (COMPLIANT)
 PHASE 1 VAN REQUIRED: 3 (1 PER EVERY 6 ACCESSIBLE STALLS)
PHASE 1 VAN PROVIDED: 5 > 3

PHASE 2 ACCESSIBLE STALLS
 PHASE 2 REQUIRED: 125 x 0.02 = 3
 PHASE 2 PROVIDED: 12 > 3
 PHASE 2 VAN REQUIRED: 1 (1 PER EVERY 6 ACCESSIBLE STALLS)
 PHASE 2 VAN PROVIDED: 3 > 1

TOTAL ACCESSIBLE STALLS
 TOTAL REQUIRED: 389 x 0.02 = 8
 TOTAL PROVIDED: 34 > 8
 PHASE 2 VAN REQUIRED: 4 (1 PER EVERY 6 ACCESSIBLE STALLS)
 PHASE 2 VAN PROVIDED: 8 > 4

COMMERCIAL VEHICLE PARKING ANALYSIS

Lot No. 1

TENANT IMPROVEMENT SPACE 'T.I. 1' = 5000/300 = 17 REQUIRED
 PROPOSED PARKING STALLS: 30
 STANDARD STALLS: 16
 COMPACT STALLS: 14
 ADA REQUIRED: 2 (1 VAN)

Lot No. 2

TENANT IMPROVEMENT SPACE 'T.I. 2' = 2172/300 = 07
 TENANT IMPROVEMENT SPACE 'T.I. 3' = 1872/100 = 19
 TENANT IMPROVEMENT SPACE 'T.I. 4' = 1800/100 = 18
 34 REQUIRED

PROPOSED PARKING STALLS: 44

STANDARD STALLS: 27
 COMPACT STALLS: 15
 ADA REQUIRED: 2 (1 VAN)

T.I.3 USE:

(22) Restaurants, bars, taverns and other similar establishments whose primary business is the on-site sale and consumption of food and beverages: one space for each 100 square feet of gross floor area;

T.I.1 and T.I.2 USE:

(23) Retail commercial, general sales, personal service, shopping centers, malls and other similar establishments shall provide one space for each 300 square feet of gross floor area

EV CHARGING STATIONS

WAC 51-50-0427 ELECTRIC VEHICLE CHARGING INFRASTRUCTURE: REQUIRED: 2 (10% of stall provided)

PHASE 1 EV CHARGING STATIONS STALLS

PHASE 1 REQUIRED: 259 x 0.10 = 26
 PHASE 1 PROVIDED: 26 ≥ 26 (COMPLIANT)
 PHASE 1 ADA REQUIRED: 22 x 0.10 = 2
 PHASE 1 ADA PROVIDED: 12 ≥ 2 (COMPLIANT)

PHASE 2 EV CHARGING STATIONS STALLS

PHASE 2 REQUIRED: 125 x 0.10 = 13
 PHASE 2 PROVIDED: 12 > 13 (COMPLIANT)
 PHASE 2 ADA REQUIRED: 12 x 0.10 = 1
 PHASE 2 ADA PROVIDED: 4 > 1 (COMPLIANT)

WSEC

BUILDING ENVELOPE REQUIREMENTS

ZONE	4C - MARINE
PATH	PRESCRIPTIVE
ROOFS - ATTIC AND OTHER	R-VALUE = 49
FENESTRATION	U-FACTOR = 0.30
FENESTRATION SHGC	NO REQUIREMENTS
SKYLIGHTS	U-FACTOR = N/A
WOOD FRAMED WALLS	R-VALUE = 21 INT
MASS WALL R-VALUE	N/A
FLOOR	R-VALUE: 30
SLAB, R-VALUE & DEPTH	10, 2-FT

APPLICABLE 2018 WSEC BUILDING ENVELOPE NOTES :

- AN IDENTIFICATION MARK SHALL BE APPLIED TO ALL INSULATION MATERIALS PER C303.1.
- ALL FENESTRATION PRODUCTS SHALL BE LABELED WITH RATED U-FACTOR, SHGC, VT, LEAKAGE RATING PER C303.1.3 AND C402.4.3.

REFER TO TABLE R402.4.1.1 OF THE 2018 RESIDENTIAL WSEC FOR AIR BARRIER AND INSULATION INSTALLATION REQUIREMENTS.

ENERGY CREDITS

NOTE: EACH RESIDENCE QUALIFIES AS A SMALL DWELLING UNIT WITH 4.5 CREDITS REQUIRED PER THE 2018 WSEC. THE FOLLOWING CREDITS HAVE BEEN SELECTED.

FUEL NORMALIZATION CREDITS - Option #2 = 1.0
 For an initial heating system using a heat pump that meets federal standards for the equipment listed in Table C403.3.2(1)C or C403.3.2(2)

3. HIGH EFFICIENCY HVAC EQUIPMENT OPTIONS = 3.0

3.6 - Ductless split system heat pumps with no electric resistance heating in the primary living areas. A ductless heat pump system with a minimum HSPF of 10 shall be sized and installed to provide heat to entire dwelling unit at the design outdoor air temperature.

5. EFFICIENT WATER HEATING OPTIONS = 2.5


5.5 - For R-2 Occupancy, electric heat pump water heater(s), meeting the standards for Tier III of NEEA's advanced water heating specification, shall supply domestic hot water to all units. If one water heater is serving more than one dwelling unit, all hot water supply and recirculation piping shall be insulated with R-8 minimum pipe insulation.

TOTAL: 6.5 credits



SYNTHESIS 9, LLC
 823 N. D ST
 TACOMA, WA 98403

REUSE OF DOCUMENTS
 THE DOCUMENT HAS THE DESIGNER'S ORIGINAL DESIGN INCORPORATED HEREIN AS PERMITS OF PROFESSIONAL SERVICE ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.






EAST TOWN CROSSING
 BUILDING 'E'
 PIONEER & SHAW PUYALLUP WA

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	LAND USE & WSEC INFORMATION
PROJECT #:	2016
SHEET:	AG1.2


AGENCY REVIEW | 24.03.11

EXISTING LOT



2 SOUTH ELEVATION TRANSPARENCY
SCALE: 3/32" = 1'-0"

3 NORTH ELEVATION TRANSPARENCY
SCALE: 3/32" = 1'-0"



1 FRONTAGE CALCULATIONS
SCALE: 1" = 30'

NO.	REVISIONS

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: FRONTAGE CALCULATIONS
PROJECT #: 2016
SHEET:

AGENCY REVIEW | 24.03.11

FLOOR | CEILING | ROOF ASSEMBLIES

	<p>TYPICAL INTERIOR ASSEMBLY 1-HR FIRE RATED & STC 50 (MINIMUM) ASSEMBLY REFER TO GA FILE NO. FC 5112 (PROPRIETARY)</p> <p>FLOOR COVERING PER ASSEMBLY OPTIONS 1 1/4" PROPRIETARY FLOOR TOPPING 1/8" PROPRIETARY SOUND REDUCTION MAT PLYWOOD SHEATHING PER STRUCTURAL FLOOR I-JOISTS PER STRUCTURAL @ 16" O.C. 3-1/2" (MIN.) GLASS FIBER BATTS @ TOP OF CAVITY 1/2" RESILIENT FURRING CHANNELS @ 16" O.C. (RUN PERPENDICULAR TO JOISTS) (2) LAYERS 5/8" PROPRIETARY TYPE "X" GWB (W.R. IN WET AREAS)</p> <p>* DROPPED CEILING ADD AIR SPACE 2X FRAMING @ 16" O.C. PER STRUCTURAL - TO ACCOMMODATE MECHANICAL EQUIPMENT. 1/2" G.W.B.</p>
	<p>TYPICAL EXTERIOR DECK ASSEMBLY 1-HR FIRE RATED REFER TO ICC-ES EVALUATION REPORT #ESR-2201</p> <p>DECK COATING SYSTEM: SLOPE 1/4" PER FOOT, MINIMUM (ALX BY WEST COAST) 3/4" PLYWOOD SHEATHING PER STRUCTURAL (SOLID BLOCK ALL JOINTS FOR DECK COATING) 2 x FLOOR JOISTS PER STRUCTURAL @ 16" O.C. (CROSS VENTILATED AIR SPACE) CEMENT BOARD SOFFIT AT LANDINGS</p>
	<p>TYPICAL ROOF CEILING ASSEMBLY 1-HR FIRE RATED REFER TO GA FILE NO. FC RC2602</p> <p>ROOFING PER ROOF PLAN UNDERLAYMENT PER ROOFING SYSTEM 1/2" SHEATHING PER STRUCTURAL PRE-MFR WOOD TRUSSES PER STRUCTURAL @ 16" O.C. R-49 BATT INSULATION (2) LAYERS 5/8" TYPE "X" GWB (W.R. IN WET AREAS)</p> <p>* DROPPED CEILING ADD AIR SPACE 2X FRAMING @ 16" O.C. PER STRUCTURAL - TO ACCOMMODATE MECHANICAL EQUIPMENT. 1/2" G.W.B.</p>
	<p>FLOOR / CEILING ASSEMBLY 1-HR FIRE RATED ASSEMBLY REFER TO GA FILE NO. FC 5529</p> <p>SINGLE-PLY ROOF MEMBRANE SYSTEM 1/2" PLYWOOD 2x10 JOISTS @ 16" O.C. (2) LAYERS 5/8" W.R., TYPE "X" GWB</p>

WALL ASSEMBLIES

** SEE ASSEMBLY NOTES ON THIS SHEET & A6.6 FOR FIRE STOP DETAILS AT PENETRATIONS THROUGH RATED ASSEMBLIES.
DOUBLE 2x BASE PLATE WITH GYPCRETE TO THE TOP OF THE FIRST PLATE.

	<p>EXTERIOR WALL FIRE BARRIER 1-HR FIRE RATED ASSEMBLY; REFER TO GA. NO. WP 8105 (ON THIS SHEET)</p> <p>CLADDING WATER RESISTANT BARRIER 5/8" DENSGLASS 1/2" SHEATHING, WHEN APPLICABLE PER STRUCTURAL 2 X 6 WOOD STUDS @ 16" O.C. WITH R-21 BATT INSULATION 5/8" TYPE "X" GWB (W.R. IN WET AREAS) VAPOR BARRIER PAINT</p>
	<p>EXTERIOR WALL CLADDING WATER RESISTANT BARRIER 1/2" SHEATHING, PER STRUCTURAL 2 X 6 WOOD STUDS @ 16" O.C. WITH R-21 BATT INSULATION 5/8" TYPE "X" GWB (W.R. IN WET AREAS) VAPOR BARRIER PAINT</p>
	<p>1-HR FIRE RATED ASSEMBLY REFER TO GA. NO. WP 3605 (ON THIS SHEET)</p> <p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 2 X 6 WOOD STUDS @ 16" O.C. WITH R-21 BATT INSULATION 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>APARTMENT UNIT DEMISING WALL FIRE PARTITION 1-HR FIRE RATED & STC 50 (MIN.) ASSEMBLY; REFER TO GA. NO. WP 3242 (ON THIS SHEET)</p> <p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 1/2" SHEATHING PER STRUCTURAL, WHEN APPLICABLE 2 X 6 WOOD STUDS @ 16" O.C. WITH 5-1/2" SOUND BATTS 1/2" SHEATHING PER STRUCTURAL, WHEN APPLICABLE 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 5-1/2" ROCK WOOL OR SOUND BATTS 2 X 6 WOOD STUDS @ 24" O.C. 9.25" AIR SPACE 2 X 6 WOOD STUDS @ 24" O.C. 5-1/2" ROCK WOOL OR SOUND BATTS 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 2 X 6 WOOD STUDS @ 16" O.C. WITH 5-1/2" SOUND BATTS 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 2 X 4 WOOD STUDS @ 16" O.C. 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 2 X 4 WOOD STUDS @ 16" O.C. WITH 3-1/2" SOUND BATTS 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 2 X 4 WOOD STUDS @ 16" O.C. 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 1/2" PLYWOOD PER STRUCTURAL 2 X 4 STUDS @ 16" O.C. 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>1-HR FIRE RATED & STC 50 (MIN.) ASSEMBLY; REFER TO GA. NO. WP 3241, 3242 or 3243</p> <p>5/8" TYPE "X" GWB (W.R. @ WET AREAS) 1/2" RESILIENT FURRING CHANNELS @ 16" O.C. 2 X 4 WOOD STUDS @ 16" O.C. WITH 3-1/2" ROCK WOOL 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>INTERIOR PLUMBING WALL FURRING ADDED TO PROPOSED WALL</p> <p>OTHER PROPOSED WALL AIR SPACE; SEPARATE AS NECESSARY 2 X 4 WOOD STUDS @ 16" O.C. WITH 3-1/2" ROCK WOOL 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>
	<p>INTERIOR WALL FURRING ADDED TO PROPOSED WALL</p> <p>OTHER PROPOSED WALL AIR SPACE; SEPARATE AS NECESSARY 2 X 4 WOOD STUDS @ 16" O.C.; LAY FLAT OR RIP AS NEEDED 5/8" TYPE "X" GWB (W.R. @ WET AREAS)</p>

ASSEMBLY NOTES

- WALLS, PARTITIONS AND FLOOR/CEILING ASSEMBLIES ENCLOSING THE APARTMENT UNITS SHALL HAVE A SOUND TRANSMISSION CLASS (STC) OF NOT LESS THAT 50 FOR AIRBORNE NOISE WHEN TESTED IN ACCORDANCE WITH ASTM E90. PENETRATIONS OR OPENINGS IN CONSTRUCTION ASSEMBLIES FOR PIPING, ELECTRICAL DEVICES, RECESSED CABINETS, BATHTUBS SOFFITS OR HEATING, VENTILATING OR EXHAUST DUCTS SHALL BE SEALED, LINED, INSULATED OR OTHERWISE TREATED TO MAINTAIN THE REQUIRED STC. UNIT ENTRY DOORS SHALL BE TIGHT-FITTING TO THE FRAME AND SILL.
- REFER TO THE "FIRE-RESISTANCE-RATED CONSTRUCTION NOTES ON SHEET #AG1.2.
- REFER TO THE "FIRE RATED ASSEMBLY" DIAGRAM ON SHEET #AG1.2 FOR INFORMATION ON WHICH WALLS ARE SPECIFICALLY REQUIRED TO HAVE A FIRE-RATING. AS NOTED IN THAT DIAGRAM, NOT ALL WALLS ARE REQUIRED TO HAVE A FIRE RATING EVEN THOUGH THE WALL TYPE ASSEMBLY HAS THE SAME GENERAL CONFIGURATION OF COMPONENTS.
- ELECTRICAL OUTLET BOXES SHALL NOT BE PLACED BACK-TO-BACK AND SHALL BE OFFSET BY NOT LESS THAN 12-INCHES FROM OUTLETS IN THE OPPOSITE WALL SURFACE. THE BACK AND THE SIDES OF BOXES SHALL BE SEALED WITH 1/8-INCH RESILIENT SEALANT AND BACKED BY AT LEAST 2-INCH THICK MATERIAL FIBER INSULATION PER IBC 1207.3.
- SPACES OR SHAFTS CONTAINING VENTILATING EQUIPMENT OR OTHER MECHANICAL EQUIPMENT SHALL BE SEPARATED BOTH VERTICALLY AND HORIZONTALLY FROM THE ADJOINING DWELLING UNIT BY CONSTRUCTION DESIGNED TO PROVIDE A MINIMUM STC RATING OF 50.
- DESIGN AND MATERIALS FOR SOUND TRANSMISSION CONTROL SHALL NOT IMPAIR THE FIRE-RESISTANT INTEGRITY OF SEPARATING WALLS OR FLOOR/CEILING ASSEMBLIES.
- WRAP ALL PLUMBING PIPE WITH SOUND ATTENUATION BATTS.
- ROOF ASSEMBLIES TO INCLUDE CLASS C ROOF COVERING THROUGHOUT AND FIRE-RETARDANT-TREATED WOOD SHEATHING FOR A DISTANCE OF 4 FEET OF THE EXTERIOR WALL.
- IN GENERAL, THE CONTRACTOR SHALL REVIEW SECTION 1, GENERAL EXPLANATORY NOTES OF THE GYPSUM ASSOCIATION - 600 - 2009 FIRE RESISTANCE DESIGN MANUAL (19TH EDITION) OR LATER.
- PER IBC 718.2.2 FIRE-BLOCKING SHALL BE PROVIDED IN ALL FURRED SPACES: VERTICALLY AT CEILING AND FLOOR LEVELS, AND HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
- PER SECTION 1, GENERAL EXPLANATORY NOTE #22 OF THE GYPSUM ASSOCIATION - 600 - 2009 FIRE RESISTANCE DESIGN MANUAL (19TH EDITION) NOTE THE FOLLOWING: WHEN NOT SPECIFIED AS A COMPONENT OF A FIRE-RESISTANCE RATED WALL OR PARTITION SYSTEM, WOOD STRUCTURAL PANELS SHALL BE PERMITTED TO BE ADDED TO ONE OR BOTH SIDES. SUCH PANELS SHALL BE PERMITTED TO BE APPLIED EITHER AS A BASE LAYER DIRECTLY TO THE FRAMING (UNDER THE GYPSUM BOARD), AS A FACE LAYER (OVER THE FACE LAYER OF GYPSUM BOARD), OR BETWEEN LAYERS OF GYPSUM BOARD IN MULTI-LAYER SYSTEMS. WHEN SUCH PANELS ARE APPLIED UNDER THE GYPSUM BOARD OR BETWEEN LAYERS OF GYPSUM BOARD, THE LENGTH OF THE FASTENERS SPECIFIED FOR THE ATTACHMENT OF THE GYPSUM BOARD APPLIED OVER THE WOOD STRUCTURAL PANELS SHALL BE INCREASED BY NOT LESS THAT THE THICKNESS OF THE WOOD STRUCTURAL PANELS. FASTENER SPACING FOR THE GYPSUM BOARD AND THE NUMBER OF LAYERS OF GYPSUM BOARD SHALL BE AS SPECIFIED IN THE SYSTEM DESCRIPTION.
- PER SECTION 1, GENERAL EXPLANATORY NOTE #15 OF THE GYPSUM ASSOCIATION - 600 - 2009 FIRE RESISTANCE DESIGN MANUAL (19TH EDITION) NOTE THE FOLLOWING: GREATER STUD SIZES (DEPTHS) SHALL BE PERMITTED TO BE USED IN METAL- OR WOOD-STUD SYSTEMS. METAL STUDS OF HEAVIER GAGE THAN THOSE TESTED SHALL BE PERMITTED, THE ASSIGNED RATING OF ANY LOAD-BEARING SYSTEM SHALL ALSO APPLY TO THE SAME SYSTEM USED A NON-LOAD-BEARING SYSTEM. INDICATED STUD SPACINGS ARE MAXIMUMS.



SYNTHESIS 9, LLC
5214 D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE ORIGINAL DESIGN
INCORPORATED HEREIN AS PERMITTED BY THE
PROFESSIONAL SERVICES ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.




EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	ASSEMBLY TYPES
PROJECT #:	2016
SHEET:	


AG1.4

AGENCY REVIEW | 24.03.11


ACCESSIBLE DOOR CLEARANCE




FRONT APPROACH, PULL SIDE




FRONT APPROACH, PUSH SIDE




FRONT APPROACH, POCKET




HINGE APPROACH, PULL SIDE




HINGE APPROACH, PUSH SIDE




POCKET OR HINGE APPROACH




HINGE APPROACH, PUSH SIDE




LATCH APPROACH, PULL SIDE



STOP OR LATCH APPROACH




LATCH APPROACH, PUSH SIDE




PUSH SIDE, W/ CLOSER & LATCH

402.2.2 CLEAR WIDTH
 DOORWAYS SHALL HAVE A CLEAR OPENING WIDTH OF 32 INCHES MINIMUM. CLEAR OPENING WIDTH OF DOORWAYS WITH SWINGING DOORS SHALL BE MEASURED BETWEEN THE FACE OF THE DOOR AND STOP, WITH THE DOOR OPEN 90 DEGREES. OPENINGS MORE THAN 24 INCHES IN DEPTH AT DOORS AND DOORWAYS WITHOUT DOORS SHALL PROVIDE A CLEAR OPENING WIDTH OF 36 INCHES MINIMUM. THERE SHALL BE NO PROJECTIONS INTO THE CLEAR OPENING WIDTH LOWER THAN 34 INCHES ABOVE THE FLOOR. PROJECTIONS INTO THE CLEAR OPENING WIDTH BETWEEN 34 INCHES AND 80 INCHES ABOVE THE FLOOR SHALL NOT EXCEED 4 INCHES.

- EXCEPTIONS:
1. DOOR CLOSERS AND DOOR STOPS SHALL BE PERMITTED TO BE 78 INCHES MINIMUM ABOVE THE FLOOR.
 2. IN ALTERATIONS, A PROJECTION OF 5/8" MAXIMUM INTO THE REQUIRED CLEAR OPENING WIDTH SHALL BE PERMITTED FROM THE LATCH SIDE STOP.



(A) HINGE DOOR



(B) SLIDING DOOR


CLEAR WIDTH OF OPENINGS

REVISIONS


NO.	DATE	DESCRIPTION

REVISIONS


DRAWN BY: BL / CM
 CHECKED BY: BL
 DATE: 24.03.11
 TITLE: ACCESSIBLE ENTRANCES
 PROJECT #: 2016
 SHEET:



1 RATED WALLS LEVEL 2 & 3
 SCALE: 3/32" = 1'-0"



2 RATED WALLS LEVEL 1
 SCALE: 3/32" = 1'-0"



3 RATED ASSEMBLIES SECTION
 SCALE: 3/32" = 1'-0"

RATED ASSEMBLY DIAGRAM LEGEND

- 1-HR RATED PARTITION WALL ASSEMBLY AND/OR 1-HR RATED FLOOR/CEILING ASSEMBLY OR 1-HR CEILING/ROOF ASSEMBLY
- EXTERIOR WALL
 1-HR RATED WALL ASSEMBLY WITH OPENINGS LIMITED TO 10% WHEN DISTANCE TO PROPERTY LINE IS BETWEEN 5-FT TO 10-FT, NO OPENINGS WHEN DISTANCE LESS THAN 5-FT. WALL SHALL BE RATED FOR EXPOSURE TO FIRE FROM BOTH SIDES
- EXIT PASSAGEWAY
 1-HR RATED, FIRE BARRIER, CONTINUOUS TO FLOOR DECKS WITH 1-HR RATED OPENINGS & 1-HR RATED CEILING/ROOF ASSEMBLY

REVISIONS	
AGENCY REVIEW 24.03.11	DRAWN BY: BL / CM
	CHECKED BY: BL
	DATE: 24.03.11
	TITLE: CODE DIAGRAMS
	PROJECT #: 2016
	SHEET:
	AG1.7

ACCESSIBLE MAILBOX REQUIREMENTS


905.1 General. Accessible storage facilities shall comply with ICC A117.1, Section 905.
905.2 Clear Floor Space. A clear floor space complying with ICC A117.1, Section 305 shall be provided.
905.3 Height. Accessible storage elements shall comply with at least one of the reach ranges specified in ICC A117.1, Section 308.
905.4 Operable Parts. Operable parts of storage facilities shall comply with ICC A117.1, Section 309.

309.4 Operation. Operable parts shall be operable with one hand and shall not require tight grasping, pinching, or twisting of the wrist. The force required to activate operable parts shall be 5.0 pounds maximum.

308.2 Forward Reach.
308.2.1 Unobstructed. Where a forward reach is unobstructed, the high forward reach shall be 48 inches maximum and the low forward reach shall be 15 inches minimum above the floor.
308.3 Side Reach.
308.3.1 Unobstructed. Where a clear floor space allows a parallel approach to an element and the side reach is unobstructed, the high side reach shall be 48 inches maximum and the low side reach shall be 15 inches minimum above the floor.

LAND USE SITE LIGHTING REQUIREMENTS


1. Light trespass. Light trespass from sites in non-residential zoning districts shall not exceed 3 lux (0.3 foot candles) at parcel boundaries with residential zoning districts. This luminance value shall be measured at the eye in a plane perpendicular to the line-of-sight when looking at the brightest source in the field of view at any point on the property line of any residential parcel.
2. Residential light pollution. To ensure control of and to minimize glare, any lighting within 100 feet of an R District shall use luminaires which meet the Illuminating Engineering Society's cutoff light distribution specification.
3. General light pollution. To control and minimize glare, all other luminaires for area and/or off-street parking shall meet the Illuminating Engineering Society's semi-cutoff light distribution specification. Lighting shall be directed toward the site, with cutoff shields or other means, to prevent spillover glare to adjacent properties or vehicular traffic. Luminaires with a light source not greater than 1800 lumens (100 watt incandescent) are exempt from this requirement.



TYPICAL AT EACH APARTMENT BUILDING
A stand of trees with a canopy of 1,000 square feet (as measured in frontal view rather than top view) located no farther than 20 feet from a facade of the building, consisting of either existing trees, or planted trees.
(Per PMC 20.26.200 (4) (b) (v))


4 OVERALL SITE PLAN - PHASE 2
SCALE: 1" = 40'

2 SITE SIGNAGE
SCALE: 1" = 1'-0"



REVISIONS

DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	SITE PLAN - REF ONLY
PROJECT #:	2016
SHEET:	




1 LEVEL 1 - OVERALL PLAN
SCALE: 1/8" = 1'-0"



SYNTHESIS 9, LLC
521A D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DRAWING DESIGN
INCORPORATED HEREIN AS INSTRUMENTS OF
PROFESSIONAL SERVICE ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



**EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA**

REVISIONS

NO.	DATE	DESCRIPTION

REVISIONS

DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	LEVEL 1 - OVERALL PLAN
PROJECT #:	2016
SHEET:	


A1.0

AGENCY REVIEW | 24.03.11




SYNTHESIS 9, LLC
8214 5TH ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE EXHIBITS HEREON
INCORPORATED HERIN AS REFERENCE TO
PROFESSIONAL SERVICES ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA



1 LEVEL 2 - OVERALL PLAN
SCALE: 1/8" = 1'-0"

REVISIONS	

AGENCY REVIEW | 24.03.11
DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: LEVEL 2 - OVERALL PLAN
PROJECT #: 2016
SHEET:


A1.1

S9

SYNTHESIS 9, LLC
523 N. D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE EXHIBITS ORIGINALLY INCORPORATED HEREIN AS INSTRUMENTS OF PROFESSIONAL SERVICE ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.

9251 REGISTERED ARCHITECT
PETER W. WATSON
STATE OF WASHINGTON



1 ROOF - OVERALL PLAN
SCALE: 1/8" = 1'-0"


**EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA**

REVISIONS	

AGENCY REVIEW | 24.03.11

DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	ROOF - OVERALL PLAN
PROJECT #:	2016
SHEET:	

A1.3



1 LEVEL 1 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"


REVISIONS

NO.	DESCRIPTION

REVISIONS

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: LEVEL 1 - ENLARGED LEFT
PROJECT #: 2016
SHEET:

AGENCY REVIEW | 24.03.11




1 LEVEL 1 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"



SYNTHESIS 9, LLC
5214 8 ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS
INCORPORATED HEREIN ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DATE	DESCRIPTION

REVISIONS

DRAWN BY: BL / CM

CHECKED BY: BL

DATE: 24.03.11


TITLE: LEVEL 1 - ENLARGED RIGHT

PROJECT #: 2016

SHEET:

A1.5

AGENCY REVIEW | 24.03.11



1 LEVEL 2 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"

EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DATE	DESCRIPTION

REVISIONS


DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: LEVEL 2 - ENLARGED LEFT
PROJECT #: 2016
SHEET:

AGENCY REVIEW | 24.03.11



SYNTHESIS 9, LLC
521A D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE EXHIBITS HERETO
INCORPORATED HEREIN ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.




EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA

NO.	REVISIONS

NO.	REVISIONS


DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: LEVEL 2 - ENLARGED RIGHT
PROJECT #: 2016
SHEET:

A1.7



1 LEVEL 2 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"

AGENCY REVIEW | 24.03.11



1 LEVEL 3 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"

REVISIONS

NO.	DESCRIPTION
-----	-------------

REVISIONS

NO.	DESCRIPTION
-----	-------------

DRAWN BY: BL / CM

CHECKED BY: BL

DATE: 24.03.11


TITLE: LEVEL 3 - ENLARGED LEFT

PROJECT #: 2016

SHEET:

A1.8

AGENCY REVIEW | 24.03.11



1 LEVEL 3 PLAN - ENLARGED
SCALE: 1/4" = 1'-0"

REVISIONS

NO.	DESCRIPTION	DATE

REVISIONS


DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	LEVEL 3 - ENLARGED RIGHT
PROJECT #:	2016
SHEET:	

AGENCY REVIEW | 24.03.11




SYNTHESIS 9, LLC
1314 S ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS
INCORPORATED HEREIN ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA



1 ROOF - ENLARGED
SCALE: 1/4" = 1'-0"

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	ROOF PLAN - ENLARGED LEFT
PROJECT #:	2016
SHEET:	

AGENCY REVIEW | 24.03.11

A1.10



SYNTHESIS 9, LLC
5214 S ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS INCORPORATED HEREIN ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DESCRIPTION

REVISIONS

DRAWN BY: BL / CM

CHECKED BY: BL


DATE: 24.03.11

TITLE: ROOF PLAN - ENLARGED RIGHT

PROJECT #: 2016


SHEET:

A1.11




1 ROOF - ENLARGED
SCALE: 1/4" = 1'-0"

AGENCY REVIEW | 24.03.11



1 LEVEL 1 REFLECTED CEILING PLAN
SCALE: 1/8" = 1'-0"




REVISIONS

NO.	DESCRIPTION	DATE

REVISIONS

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: LEVEL 1 REFLECTED CEILING PLAN
PROJECT #: 2016
SHEET:



1 LEVEL 3 REFLECTED CEILING PLAN
SCALE: 1/8" = 1'-0"

EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DESCRIPTION	DATE


REVISIONS

DRAWN BY: BL / CM
 CHECKED BY: BL
 DATE: 24.03.11
 TITLE: LEVEL 3 REFLECTED CEILING PLAN
 PROJECT #: 2016
 SHEET:

A1.14



1 WEST ELEVATION
 SCALE: 1/8" = 1'-0"



3 SOUTH ELEVATION TRANSPARENCY
 SCALE: 3/32" = 1'-0"

BUILDING REFERENCE NOTES

- 01 WINDOW OR DOOR ASSEMBLY; PROVIDE FIRE-RATED ASSEMBLIES WHERE REQUIRED.
- 02 ASPHALT SHINGLES OVER UNDERLAYMENT
- 03 EXTERIOR CLADDING; NOTE ALL EXTERIOR WALL ASSEMBLIES INCORPORATE A 'RAINSCREEN' SYSTEM
 - 03-A HARDIE-PLANK WITH 7" EXPOSURE
 - 03-B HARDIE-PANEL WITH PRIMED-TO-BE-PAINTED ALUMINUM REVEALS (OR APPROVED SUBSTITUTE) COLOR 1
 - 03-C HARDIE-PANEL WITH PRIMED-TO-BE-PAINTED ALUMINUM REVEALS (OR APPROVED SUBSTITUTE) COLOR 2
- 04 WINDOW TREATMENT - WINDOWS SET IN CEMENT FIBERBOARD CLADDING SHALL HAVE 4" WIDE (MINIMUM) CEMENT BOARD WINDOW AND DOOR TRIM
- 05 42" TALL, PRE-FINISHED ALUMINUM GUARDRAILS W/ FACE-MOUNT CONNECTION TO STRUCTURE
- 06 LONG-TERM BICYCLE PARKING STALL; WITH WALL MOUNT BRACKET; SEE PRODUCT INFORMATION DETAILS
- 07 6" C.I.P. CONCRETE SLAB; SET ON 6 MIL PLASTIC VAPOR BARRIER AND 4" (MIN.) AGGREGATE BASE COARSE; SEE STRUCTURAL FOR RELATED INFORMATION
- 08 SINGLE-PLY ROOFING MEMBRANE
- 09 PRIMED, TO BE PAINTED, GUTTER / DOWNSPOUT
- 10 PEDESTRIAN DECK-COATING SYSTEM
- 11-A NOT USED
- 11-B NOT USED
- 12 BAFFLED RIDGE VENT OR BAFFLED SIDEWALL VENT



2 SOUTH ELEVATION
 SCALE: 1/8" = 1'-0"

EAST TOWN CROSSING
 BUILDING 'E'
 PIONEER & SHAW PUYALLUP, WA

REVISIONS

NO.	DESCRIPTION

REVISIONS


DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	BUILDING ELEVATIONS
PROJECT #:	2016
SHEET:	

A2.0

AGENCY REVIEW | 24.03.11



1 EAST ELEVATION
 SCALE: 1/8" = 1'-0"



3 NORTH ELEVATION TRANSPARENCY
 SCALE: 3/32" = 1'-0"


- BUILDING REFERENCE NOTES**
- 01 WINDOW OR DOOR ASSEMBLY; PROVIDE FIRE-RATED ASSEMBLIES WHERE REQUIRED.
 - 02 ASPHALT SHINGLES OVER UNDERLAYMENT
 - 03 EXTERIOR CLADDING; NOTE ALL EXTERIOR WALL ASSEMBLIES INCORPORATE A 'RAINSCREEN' SYSTEM
 - 03-A HARDIE-PLANK WITH 7" EXPOSURE
 - 03-B HARDIE-PANEL WITH PRIMED-TO-BE-PAINTED ALUMINUM REVEALS (OR APPROVED SUBSTITUTE) COLOR 1
 - 03-C HARDIE-PANEL WITH PRIMED-TO-BE-PAINTED ALUMINUM REVEALS (OR APPROVED SUBSTITUTE) COLOR 2
 - 04 WINDOW TREATMENT - WINDOWS SET IN CEMENT FIBERBOARD CLADDING SHALL HAVE 4" WIDE (MINIMUM) CEMENT BOARD WINDOW AND DOOR TRIM
 - 05 42" TALL, PRE-FINISHED ALUMINUM GUARDRAILS W/ FACE-MOUNT CONNECTION TO STRUCTURE
 - 06 LONG-TERM BICYCLE PARKING STALL; WITH WALL MOUNT BRACKET; SEE PRODUCT INFORMATION DETAILS
 - 07 6" C.I.P. CONCRETE SLAB; SET ON 6 MIL PLASTIC VAPOR BARRIER AND 4" (MIN.) AGGREGATE BASE COARSE; SEE STRUCTURAL FOR RELATED INFORMATION
 - 08 SINGLE-PLY ROOFING MEMBRANE
 - 09 PRIMED, TO BE PAINTED, GUTTER / DOWNSPOUT
 - 10 PEDESTRIAN DECK-COATING SYSTEM
 - 11-A NOT USED
 - 11-B NOT USED
 - 12 BAFFLED RIDGE VENT OR BAFFLED SIDEWALL VENT




2 NORTH ELEVATION
 SCALE: 1/8" = 1'-0"

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	BUILDING ELEVATIONS
PROJECT #:	2016
SHEET:	

AGENCY REVIEW | 24.03.11



1 BUILDING SECTION 1
SCALE: 1/8" = 1'-0"




2 BUILDING SECTION 2 **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"

REVISIONS


NO.	DATE	DESCRIPTION

REVISIONS


DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	BUILDING SECTIONS
PROJECT #:	2016
SHEET:	




2 **BUILDING SECTION 4** **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"



1 **BUILDING SECTION 3** **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"




4 **BUILDING SECTION 6** **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"




3 **BUILDING SECTION 5** **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"

REVISIONS



1 BUILDING SECTION 7 **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"



2 BUILDING SECTION 8 **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.
SCALE: 1/8" = 1'-0"


EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DESCRIPTION


REVISIONS

DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	BUILDING SECTIONS
PROJECT #:	2016
SHEET:	



1 BUILDING SECTION 9 **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.

SCALE: 1/8" = 1'-0"



2 BUILDING SECTION 10 **SEE ALL SECTIONS FOR CALL OUTS IN COMMON.


SCALE: 1/8" = 1'-0"

EAST TOWN CROSSING
 BUILDING 'E'
 PIONEER & SHAW PUYALLUP WA


NO.	REVISIONS

DRAWN BY: BL / CM
 CHECKED BY: BL
 DATE: 24.03.11
 TITLE: BUILDING SECTIONS
 PROJECT #: 2016
 SHEET:


AGENCY REVIEW | 24.03.11




4 TYPE 12-1 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




3 TYPE 12-1 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




2 TYPE 12-1 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




7 TYPE 12-1 BATH
SCALE: 3/8" = 1'-0"




6 TYPE 12-1 BATH
SCALE: 3/8" = 1'-0"




5 TYPE 12-1 BATH
SCALE: 3/8" = 1'-0"



10 TYPE 12-3 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




9 TYPE 12-3 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




8 TYPE 12-3 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'

DWELLING UNIT ACCESSIBILITY NOTES:




1. THE ACCESSIBLE PRIMARY ENTRANCE SHALL BE ON AN ACCESSIBLE ROUTE FROM PUBLIC AND COMMON AREAS. WITHIN THE UNIT, AT LEAST ONE ACCESSIBLE ROUTE SHALL CONNECT ALL SPACES AND ELEMENTS. THE ACCESSIBLE ROUTE SHALL HAVE A CLEAR WIDTH OF AT LEAST 36-INCHES, EXCEPT THAT SEGMENTS LESS THAN 24-INCHES IN LENGTH MAY HAVE A CLEAR WIDTH OF 32-INCHES.
2. IN THE TYPE 'A' UNIT, TURNING SPACES SHALL BE REQUIRED IN ALL ROOMS. TURNING SPACE SHALL BE 60-INCH IN DIAMETER.
3. THE CORRIDOR SIDE OF THE PRIMARY ENTRANCE DOOR TO TYPE 'B' UNITS SHALL HAVE MANEUVERING CLEARANCES COMPLYING WITH ANSI 404, ICC A117.1.
4. IN TYPE 'A' UNITS, ALL DOORWAYS INTENDED FOR PASSAGE SHALL HAVE MANEUVERING CLEARANCES COMPLYING WITH ANSI 404, ICC A117.1.
5. CHANGES IN LEVEL OF 1/4-INCH OR LESS ARE PERMITTED TO BE VERTICAL. CHANGES IN LEVEL BETWEEN 1/4-INCH AND 1/2-INCH SHALL BE BEVELED WITH A SLOPE OF 1:2. THRESHOLDS SHALL NOT BE GREATER THAN 1/2-INCH, EXCEPT THAT THEY MAY BE 3/4-INCH AT EXTERIOR SLIDING DOORS.
6. IN TYPE 'A' UNITS, LIGHTING CONTROLS, ELECTRICAL SWITCHES AND RECEPTACLE OUTLETS, ENVIRONMENTAL CONTROLS, APPLIANCE CONTROLS, OPERATING HARDWARE FOR OPERABLE WINDOWS, PLUMBING FIXTURE CONTROLS, AND USER CONTROLS FOR SECURITY OR INTERCOM SYSTEMS SHALL BE PROVIDED WITH A CLEAR FLOOR SPACE AND BE PLACED WITHIN ONE OF THE REACH RANGES SPECIFIED IN SECTION 308, ICC A117.1. THEY SHALL BE OPERABLE WITH ONE HAND AND SHALL NOT REQUIRE TIGHT GRASPING, PINCHING OR TWISTING OF THE WRIST. THE MAXIMUM FORCE REQUIRED TO ACTIVATE THE PARTS SHALL BE 5-POUNDS.
7. IN TYPE 'B' UNITS, LIGHTING CONTROLS, ELECTRICAL SWITCHES AND RECEPTACLE OUTLETS, ENVIRONMENTAL CONTROLS, APPLIANCE CONTROLS, OPERATING HARDWARE FOR OPERABLE WINDOWS, PLUMBING FIXTURE CONTROLS, AND USER CONTROLS FOR SECURITY OR INTERCOM SYSTEMS SHALL BE PROVIDED WITH A CLEAR FLOOR SPACE AND SHALL BE PLACED WITHIN ONE OF THE REACH RANGES SPECIFIED IN ANSI 308, ICC 117.1.
8. "CLEAR FLOOR SPACE" IS 30-INCHES BY 48-INCHES PER ANSI 305.3. BATHROOMS AND KITCHENS REQUIRE CLEAR FLOOR SPACES, CLEARANCES AROUND, BETWEEN AND ADJACENT TO FIXTURES, APPLIANCES, CABINETS, COUNTERS AND WALLS, AND OTHER ITEMS SHOWN IN THE DRAWINGS.
9. OPERABLE PARTS SHALL BE PLACED BETWEEN 15-INCHES AND 48-INCHES ABOVE THE FLOOR IN AN AREA WITH UNOBSTRUCTED FORWARD OR SIDE REACH. WHEN THERE IS AN OBSTRUCTION OF 24-INCHES MAXIMUM WIDTH AND 34-INCHES MAXIMUM HEIGHT, THE OPERABLE PARTS SHALL BE NO HIGHER THAN 46-INCHES ABOVE THE FLOOR. WHEN THERE IS AN OBSTRUCTION OF 25-INCHES MAXIMUM WIDTH IN A SPACE ALLOWING FORWARD APPROACH, THE OPERABLE PARTS SHALL BE NO HIGHER THAN 44-INCHES ABOVE THE FLOOR PER ANSI 308, ICC A117.1.
10. IN TYPE 'A' UNITS, WASHING MACHINES AND CLOTHES DRYERS REQUIRE A CLEAR FLOOR SPACE, POSITIONED FOR PARALLEL APPROACH, CENTERED ON EACH APPLIANCE. ALL OPERABLE PARTS SHALL COMPLY WITH SECTION 309, ICC A117.1, INCLUDING THE REACH RANGES SPECIFIED IN ANSI 308, ICC 117.1. TOP LOADING MACHINES SHALL HAVE THE DOOR TO THE LAUNDRY COMPARTMENT 36-INCHES MAXIMUM ABOVE THE FLOOR. FRONT LOADING MACHINES SHALL HAVE THE BOTTOM OF THE OPENING TO THE LAUNDRY COMPARTMENT BETWEEN 15-INCHES AND 34-INCHES ABOVE THE FLOOR.
11. IN TYPE 'B' UNITS, WASHING MACHINES AND CLOTHES DRYERS REQUIRE A CLEAR FLOOR SPACE, POSITIONED FOR PARALLEL APPROACH, CENTERED ON EACH APPLIANCE.
12. IN TYPE 'B' UNITS, WASHING MACHINES AND CLOTHES DRYERS REQUIRE A CLEAR FLOOR SPACE, POSITIONED FOR PARALLEL APPROACH, CENTERED ON EACH APPLIANCE.
13. CABINETY IS PERMITTED UNDER WORK SURFACES & SINK WHEN THE CABINETY CAN BE REMOVED WITHOUT THE REMOVAL OR REPLACEMENT OF WORK SURFACE OR SINK, FLOOR FINISH EXTENDS UNDER CABINETY AND WALLS BEHIND AND SURROUNDING CABINETY ARE FINISHED.
14. TYPE 'B' UNIT BATHROOMS ARE OPTION A.



3. CABINETY IS PERMITTED UNDER WORK SURFACE SINK WHEN THE CABINETY CAN BE REMOVED WITHOUT REMOVAL OR REPLACEMENT OF WORK SURFACE OR SIF FLOOR FINISH EXTENDS UNDER CABINETY AND WALLS BEHIND AND SURROUNDING CABINETY ARE FINISHED.
4. WHEN BASE CABINETS ARE TO BE REMOVED AT LOWERED WORK SURFACES AND SINKS, KNEE AND TOE CLEARANCES SHALL BE PROVIDED.
5. IN TYPE 'B' UNITS, REINFORCEMENT FOR A 24" REAR WALL GRAB BAR, CENTERED ON THE FIXTURE, AT WATER CLO: WHEN THERE IS INSUFFICIENT WALL SPACE FOR THE 36" BAR.
6. IN TYPE 'B' UNITS, REINFORCEMENT FOR A SWING UP GR BAR PER ANSI A117.1 1004.11.1 WHERE A SIDE WALL IS AVAILABLE FOR A 42-INCH GRAB BAR.
7. IN TYPE 'B' UNITS, REINFORCEMENT FOR A VERTICAL GR BAR AT WATER CLOSETS IS NOT REQUIRED.



1 TYPE A & B BATHROOM FIXTURES & APPLIANCES
SCALE: 3/8" = 1'-0"



S9

SYNTHESIS 9, LLC
521A D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE ORIGINAL DESIGN INCORPORATED HEREIN AS PERMITTED BY PROFESSIONAL SERVICES ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.

REGISTERED ARCHITECT
TRACY MANN
STATE OF WASHINGTON
9251

EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA

REVISIONS	


AGENCY REVIEW | 24.03.11

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: INTERIORS
PROJECT #: 2016
SHEET:
A5.0


REVISIONS

REVISIONS


DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: INTERIOR ELEVATIONS
PROJECT #: 2016
SHEET:




1 TYPE 12-3M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




2 TYPE 12-3M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




3 TYPE 12-3M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




4 TYPE 12-3M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




5 TYPE 12-3M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




7 TYPE 12-1M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




8 TYPE 12-1M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




9 TYPE 12-1M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




10 TYPE 12-1M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




11 TYPE 12-1M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




13 TYPE 12-5M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




14 TYPE 12-5M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




15 TYPE 12-5M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




16 TYPE 12-5M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




17 TYPE 12-2 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




18 TYPE 12-2 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




19 TYPE 12-2 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




20 TYPE 12-2 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




21 TYPE 12-2 BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




22 TYPE 12-3 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




23 TYPE 12-3 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'A'




6 TYPE 12-2M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




2 TYPE 12-5 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




1 TYPE 12-5 KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




10 TYPE 12-2M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'



9 TYPE 12-2M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'



8 TYPE 12-2M BATH
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'




7 TYPE 12-2M KITCHEN
SCALE: 3/8" = 1'-0"
ADA TYPE 'B'

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	INTERIOR ELEVATIONS
PROJECT #:	2016
SHEET:	


AGENCY REVIEW | 24.03.11

FOUNDATION DETAIL REFERENCE NOTES


- 01 WALL PER PLAN
- 02 VAPOR PERMEABLE AIR BARRIER / W.R.B. FIELD MEMBRANE
- 03 CONTINUOUS, SELF-ADHERED MEMBRANE (S.A.M.) ALONG TOP EDGE OF METAL FLASHING
- 04 BELOW GRADE WATER-PROOFING SYSTEM W/ DRAINAGE MAT AND FILTER FABRIC PROTECTION LAYER
- 05 22 GAUGE, SHEET METAL FLASHING, W/ HEMMED EDGE; SET ON SEALANT & EXTEND 6" UP UNDER W.R.B. OR TO WINDOW OPENING
- 06 FILTER FABRIC OVER MINIMUM 1/2-INCH DRAINAGE MATRIX
- 07 METAL LATHE WITH BOND & SCRATCH COAT
- 08 NOT USED
- 09 6 MIL PLASTIC VAPOR BARRIER
- 10 NOT USED
- 11 R-10 POLYISO INSULATION; UNDER ENTIRE SLAB AT CONDITIONED AREAS AND CONFIGURED AS SHOWN TO TOP OF FOOTING OR 2-FT IN LENGTH.
- 12 NOT USED
- 13 CEMENT FIBERBOARD PANEL OR LAP-SIDING SIDING - HARDIE PANEL OR APPROVED SUBSTITUTE
- 14 NOT USED
- 15 NOT USED
- 16 ANCHOR BOLT & TREATED SILL PLATE(S) PER STRUCTURAL
- 17 CONCRETE & REINFORCING PER STRUCTURAL (TYPICAL)
- 18 12-INCH WIDE GRACE VYCOR SILL PAN / FLASHING W/ END DAMS. AT EACH SILL CORNER, INSTALL VYCORNERS AND CORNER PATCHES PER THE MFR'S RECOMMENDATIONS; WRAP UP THE STEEL ANGLE TO CREATE A DAM
- 19 CONT. BACK DAM ANGLE, MIN. 1-INCH TALL WITH VINYL ASSEMBLY FASTENED THROUGH ANGLE PER MFR. RECOMMENDATIONS.
- 20 4" PERF. FOOTING DRAIN AND 4" TIGHT-LINE DRAIN. SET IN DRAIN ROCK AND WRAP IN FILTER FABRIC; SEE CIVIL DRAWINGS FOR RELATED INFORMATION
- 21 3/8" SEALANT JOINT WITH BACKER ROD.
- 22 PRIMED COUNTER-FLASHING ABOVE TRIM; PROVIDE 1/4-INCH PER FOOT SLOPE TO HEMMED EDGE
- 23 GALV. METAL SILL PAN AT ANY DOOR WITH A THRESHOLD
- 24 VINYL WINDOW FRAME W/ FLANGE
- 25 PRIMED COUNTER-FLASHING ABOVE TRIM; PROVIDE 1/4-INCH PER FOOT SLOPE TO HEMMED EDGE
- 26 INSTALL PLASTIC HORSESHOE SHIMS @ EACH SILL FLANGE FASTENER
- 27 1/4-INCH WITH CAULK (ONE PART URETHANE SEALANT)
- 28 VYCOR-PLUS BY GRACE AT MUD SILL W/ 1/4-INCH DOWNTURN ON EXTERIOR SIDE WHEN FEASIBLE




3 FOUNDATION DETAIL - 03
SCALE: 1 1/2" = 1'-0"




2 FOUNDATION DETAIL - 02
SCALE: 1 1/2" = 1'-0"




1 FOUNDATION DETAIL - 01
SCALE: 1 1/2" = 1'-0"



6 FOUNDATION DETAIL - 06
SCALE: 1 1/2" = 1'-0"



5 FOUNDATION DETAIL - 05
SCALE: 1 1/2" = 1'-0"



4 FOUNDATION DETAIL - 04
SCALE: 1 1/2" = 1'-0"

S9

SYNTHESIS 9, LLC
621 N. D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS INCORPORATED HEREIN AS INSTRUMENTS OF PROFESSIONAL SERVICE ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.

REGISTERED ARCHITECT
TRACY MANNING
STATE OF WASHINGTON
9251


**EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA**

REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	DETAILS
PROJECT #:	2016
SHEET:	A6.0


AGENCY REVIEW | 24.03.11

DETAIL REFERENCE NOTES


- 01 WALL PER PLAN
- 02 VAPOR PERMEABLE AIR BARRIER / WATER RESISTANT BARRIER FIELD MEMBRANE
- 03 AIR BARRIER / WATER RESISTANT BARRIER PRESTRIP WITH CONTINUOUS A.B. / W.R.B. SEALANT BETWEEN FIELD MEMBRANE (AS SHOWN)
- 04 FLOOR / CEILING ASSEMBLY PER PLAN
- 05 PRE-FINISHED ALUMINUM OR VINYL CONTINUOUS STRIP VENT. SEE REFLECTED CEILING PLANS FOR LOCATIONS AND LENGTHS
- 06 1-1/4" x 5-1/2" CEMENT FIBERBOARD TRIM AROUND OPENING - HARDIE TRIM OR APPROVED SUBSTITUTE; NOTE THAT 4" WIDE MINIMUM TRIM REQUIRED AT ALL WINDOWS U.N.O. PER TMC.
- 07 NOT USED
- 08 VINYL WINDOW OR SLIDING DOOR FRAME WITHOUT FLANGE AND ON 1/4-INCH INTERMITTENT SHIMS FOR DRAINAGE.
- 09 CEMENT FIBERBOARD CLADDING PER ELEVATIONS; LAP W/ 7-1/4" EXPOSURE OR PANEL WITH REVEAL ACCESSORIES - HARDIE PLANK OR APPROVED SUBSTITUTE
- 10 NOT USED
- 11 CORRUGATED, PRE-FINISHED METAL SIDING; EXPOSED FASTENERS WITH NEOPRENE GASKETS; NU-WAVE BY AEPSPAN
- 12 NOT USED
- 13 FLEXIBLE, SELF-ADHERED A.B. / W.R.B. SILL MEMBRANE; PER INSTALLATION INSTRUCTIONS ON SHEET A6.4.
- 14 CONT. BACK DAM ANGLE, MIN. 1-INCH TALL WITH VINYL ASSEMBLY FASTENED THROUGH ANGLE PER MFR. RECOMMENDATIONS.
- 15 ONE PART URETHANE SEALANT OVER BACKER ROD; FOAM BACKER ROD W/ BOND BREAKER JACKET - OVERSIZE ROD 25% LARGER THAN WIDTH OF JOINT; CLEAN SUBSTRATE USING A "TWO CLOTH" METHOD PER SEALANT MANUFACTURER - PRIME PER MFR ONLY WHERE REQUIRED.
- 16 CONTINUOUS AIR BARRIER SEALANT OVER BACKER ROD (WHEN SHOWN) TIED TO CONTINUOUS SEAL AT WINDOW PERIMETER.
- 17 1/4-INCH WITH PAINTABLE CAULK
- 18 NOT USED
- 19 NOT USED
- 20 PRIMED COUNTER-FLASHING ACCESSORY ABOVE TRIM w/ RIP SLOPE IN TOP OF TRIM AND 1/4-INCH CAULK AT JOINT; PROVIDE 1/4-INCH PER FOOT SLOPE.
- 21 PRE-FINISHED SHEET METAL SILL FLASHING W/ 1/2-INCH HEMMED DRIP EDGE WITH END DAMNS INTO BED JOINT AT JAMB VENEER TRIM BEYOND
- 22 PRIMED SHEET METAL HEAD FLASHING W/ 1/2" HEMMED DRIP EDGE & END DAMS. EXTEND 6-INCHES MINIMUM UP UNDER THE A.B. / W.R.B. AND OVERLAP JAMB TRIM
- 23 PRE-FINISHED SHEET METAL JAMB FLASHING TRIM
- 24 EXTRUDED ALUMINUM HORIZONTAL TRIM ACCESSORY (BY EXTREMETRIM OR APPROVED); PAINT PER MFR'S RECOMMENDATIONS; APPROXIMATE CONFIGURATION AS SHOWN.
- 25 5 x 5 x 5/16" x 5" TALL GALV. STEEL ANGLE CLIP; (2) AT EACH SIDE OF GUARDRAIL ASSEMBLY; NOTE THAT THE ATTACHMENT TO THE WALL STRUCTURE SHALL BE CONCEALED BEHIND CLADDING.
- 26 1/4" THICK NEOPRENE PAD BETWEEN VERTICAL ALUMINUM GUARDRAIL POST AND GALV. STEEL CLIP.
- 27 PRE-FINISHED ALUMINUM GUARDRAIL ASSEMBLY; FACE-MOUNT ATTACHMENT PER STRUCTURAL.
- 28 FLEXIBLE, SELF-ADHERED A.B. / W.R.B. MEMBRANE; USE 12-INCH WIDE GRACE VYCK SILL PAN FLASHING W/ END DAMS. WRAP UP SIDEWALL 4" MIN. ABOVE TOP OF FINISH FLOOR




3 SIDING TRANSITION DETAIL
SCALE: 3" = 1'-0"




6 ROOF ACCESS DETAIL
SCALE: 1 1/2" = 1'-0"




2 FLOOR-CEILING ASSEMBLY CONTINUITY
SCALE: 1 1/2" = 1'-0"





5 ROOFTOP EQUIPMENT MOUNT CURB
SCALE: 1 1/2" = 1'-0"



1 TYPICAL DRAFT STOP
SCALE: 1 1/2" = 1'-0"




4 FIRE RATING CONTINUITY
SCALE: 1 1/2" = 1'-0"



SYNTHESIS 9, LLC
521 N. D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS
INCORPORATED HEREIN AS REFERENCES TO
PROFESSIONAL SERVICES ARE THE PROPERTY OF
SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR
REPRODUCED IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.



EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP, WA

REVISIONS

NO.	DATE	DESCRIPTION


AGENCY REVIEW | 24.03.11

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: DETAILS
PROJECT #: 2016
SHEET:


A6.1

ROOF | CEILING DETAIL REFERENCE NOTES


- 01 WALL PER PLAN; COORDINATE FIRE RATING & SHEAR WALL REQUIREMENTS WITH CODE REQUIREMENTS AS NOTED ON SHEET A0.01
- 02 W.R.B. (TYVEK OR APPROVED SUBSTITUTE)
- 03 CONTINUOUS, SELF-ADHERED MEMBRANE (S.A.M.) ALONG TOP EDGE OF METAL FLASHING
- 04 NOT USED
- 05 ROOF FASCIA - 1.5" X 5.5" CEMENT FIBERBOARD TRIM
- 06 ROOF FASCIA - 1.5" X 7.25" CEMENT FIBERBOARD TRIM
- 07 2" Ø SCREENED VENTING AT BLOCKING; (3) PER TRUSS BAY (MIN.) FOR VENTILATION
- 08 PRIMED-TO-BE-PAINTED, ALUMINUM GUTTER & DOWNSPOUT
- 09 22 GAUGE, SHEET METAL EDGE FLASHING, W/ HEMMED EDGE; AT EAVE, EXTEND UP UNDER ROOFING UNDERLAYMENT 6" MINIMUM; AT RAKE OVERLAP THE ROOFING UNDERLAYMENT 4" MINIMUM.
- 10 ASPHALT SHINGLE ROOFING OVER ROOFING UNDERLAYMENT
- 11 MAINTAIN 1" MINIMUM AIRSPACE
- 12 1/4-INCH WITH CAULK (ONE PART URETHANE SEALANT)
- 13 CEMENT FIBERBOARD PANEL OR LAP-SIDING SIDING - HARDIE PANEL OR APPROVED SUBSTITUTE
- 14 NOT USED
- 15 2" Ø SCREENED VENTING AT 8" O.C.
- 16 3/8" SEALANT JOINT WITH BACKER ROD.
- 17 PRE-FINISHED ALUMINUM OR VINYL, CONTINUOUS STRIP VENT; SEE REFLECTED CEILING PLANS FOR LOCATIONS AND LENGTHS
- 18 PRE-FINISHED, SIDEWALL SHEET METAL FLASHING; EXTEND 6" MINIMUM UP UNDER W.R.B.
- 19 BAFFLED SIDEWALL VENT W/ 9 sq. in. PER LINEAR FOOT VENTILATION OR BAFFLED RIDGE VENT W/ 18 sq. in. PER LINEAR FOOT VENTILATION




8 ROOF DETAIL - 08
SCALE: 1 1/2" = 1'-0"




2 ROOF DETAIL - 02
SCALE: 1 1/2" = 1'-0"




1 ROOF DETAIL - 01
SCALE: 1 1/2" = 1'-0"




7 ROOF DETAIL - 07
SCALE: 1 1/2" = 1'-0"




4 ROOF DETAIL - 04
SCALE: 1 1/2" = 1'-0"



6 ROOF DETAIL - 06
SCALE: 1 1/2" = 1'-0"



5 ROOF DETAIL - 05
SCALE: 1 1/2" = 1'-0"



3 ROOF DETAIL - 03
SCALE: 1 1/2" = 1'-0"

S9

SYNTHESIS 9, LLC
621 N. D ST
TACOMA, WA 98403

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS INCORPORATED HEREIN AS INSTRUMENTS OF PROFESSIONAL SERVICE ARE THE PROPERTY OF SYNTHESIS 9, LLC AND ARE NOT TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF SYNTHESIS 9, LLC.

REGISTERED ARCHITECT
Frank M. Lindsay
SHEET 16 OF 17
STATE OF WASHINGTON

EAST TOWN CROSSING
BUILDING 'E'
PIONEER & SHAW PUYALLUP WA


REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	DETAILS
PROJECT #:	2016
SHEET:	

AGENCY REVIEW | 24.03.11


A6.2

DETAIL REFERENCE NOTES


- 01 WALL PER PLAN
- 02 VAPOR PERMEABLE AIR BARRIER / WATER RESISTANT BARRIER FIELD MEMBRANE
- 03 AIR BARRIER / WATER RESISTANT BARRIER PRESTRIP WITH CONTINUOUS A.B. / W.R.B. SEALANT BETWEEN FIELD MEMBRANE (AS SHOWN)
- 04 FLOOR / CEILING ASSEMBLY PER PLAN
- 05 PRE-FINISHED ALUMINUM OR VINYL, CONTINUOUS STRIP VENT, SEE REFLECTED CEILING PLANS FOR LOCATIONS AND LENGTHS
- 06 1-1/4" x 5-1/2" CEMENT FIBERBOARD TRIM AROUND OPENING - HARDIE TRIM OR APPROVED SUBSTITUTE; NOTE THAT 4" WIDE MINIMUM TRIM REQUIRED AT ALL WINDOWS U.N.O. PER TMC.
- 07 NOT USED
- 08 VINYL WINDOW OR SLIDING DOOR FRAME WITHOUT FLANGE AND ON 1/4-INCH INTERMITTENT SHIMS FOR DRAINAGE.
- 09 CEMENT FIBERBOARD CLADDING PER ELEVATIONS; LAP W/ 7/16" EXPOSURE OR PANEL WITH REVEAL ACCESSORIES - HARDIE PLANK OR APPROVED SUBSTITUTE
- 10 NOT USED
- 11 CORRUGATED, PRE-FINISHED METAL SIDING; EXPOSED FASTENERS WITH NEOPRENE GASKETS; NU-WAVE BY AEPSPAN
- 12 NOT USED
- 13 FLEXIBLE, SELF-ADHERED A.B. / W.R.B. SILL MEMBRANE; PER INSTALLATION INSTRUCTIONS ON SHEET A6.4.
- 14 CONT. BACK DAM ANGLE, MIN. 1-INCH TALL WITH VINYL ASSEMBLY FASTENED THROUGH ANGLE PER MFR. RECOMMENDATIONS.
- 15 ONE PART URETHANE SEALANT OVER BACKER ROD; FOAM BACKER ROD W/ BOND BREAKER JACKET - OVERSIZE ROD 25% LARGER THAN WIDTH OF JOINT; CLEAN SUBSTRATE USING A "TWO CLOTH" METHOD PER SEALANT MANUFACTURER - PRIME PER MFR ONLY WHERE REQUIRED.
- 16 CONTINUOUS AIR BARRIER SEALANT OVER BACKER ROD (WHEN SHOWN) TIED TO CONTINUOUS SEAL AT WINDOW PERIMETER.
- 17 1/4-INCH WITH PAINTABLE CAULK
- 18 NOT USED
- 19 NOT USED
- 20 PRIMED COUNTER-FLASHING ACCESSORY ABOVE TRIM w/ RIP SLOPE IN TOP OF TRIM AND 1/4-INCH CAULK AT JOINT, PROVIDE 1/4-INCH PER FOOT SLOPE.
- 21 PRE-FINISHED SHEET METAL SILL FLASHING W/ 1/2-INCH HEMMED DRIP EDGE WITH END DAMNS INTO BED JOINT AT JAMB VENEER TRIM BEYOND
- 22 PRIMED SHEET METAL HEAD FLASHING W/ 1/2" HEMMED DRIP EDGE & END DAMS. EXTEND 6-INCHES MINIMUM UP UNDER THE A.B. / W.R.B. AND OVERLAP JAMB TRIM
- 23 PRE-FINISHED SHEET METAL JAMB FLASHING TRIM
- 24 EXTRUDED ALUMINUM HORIZONTAL TRIM ACCESSORY (BY EXTREMETRIM OR APPROVED); PAINT PER MFR'S RECOMMENDATIONS; APPROXIMATE CONFIGURATION AS SHOWN.
- 25 5 x 5 x 5/16" x 5" TALL GALV. STEEL ANGLE CLIP: (2) AT EACH SIDE OF GUARDRAIL ASSEMBLY; NOTE THAT THE ATTACHMENT TO THE WALL STRUCTURE SHALL BE CONCEALED BEHIND CLADDING.
- 26 1/4" THICK NEOPRENE PAD BETWEEN VERTICAL ALUMINUM GUARDRAIL POST AND GALV. STEEL CLIP.
- 27 PRE-FINISHED ALUMINUM GUARDRAIL ASSEMBLY; FACE-MOUNT ATTACHMENT PER STRUCTURAL.
- 28 FLEXIBLE, SELF-ADHERED A.B. / W.R.B. MEMBRANE; USE 12-INCH WIDE GRACE VYOOK SILL PAN FLASHING W/ END DAMS. WRAP UP SIDEWALL 4" MIN. ABOVE TOP




3 GUARDRAIL MOUNT DETAIL
SCALE: 3" = 1'-0"




6 GUARDRAIL AT STAIR
SCALE: 1" = 1'-0"




2 STAIR DETAIL
SCALE: 3" = 1'-0"



5 STAIR DETAIL
SCALE: 3" = 1'-0"



1 TYPICAL HANDRAIL PLAN & SECTION
SCALE: 3" = 1'-0"




4 STAIR DETAIL
SCALE: 3" = 1'-0"


REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	DETAILS
PROJECT #:	2016
SHEET:	

GENERAL WATERPROOFING NOTES:


1. CONTRACTOR SHALL FOLLOW SYNTHESIS 9, LLC SPECIFIED WATERPROOFING SYSTEMS AND INCORPORATION THEREOF. CONTRACTOR SHALL VERIFY THE MATERIAL COMPATIBILITY OF ALL WATERPROOFING COMPONENTS, SUCH AS SEALANTS, CLOSED CELL BAKER ROD, SELF-ADHERING MEMBRANE, ETC., UTILIZED IN CONJUNCTION WITH OTHER WATERPROOFING OR BUILDING SYSTEM COMPONENTS, SHOULD THE CONTRACTOR DECIDE TO REQUEST MATERIAL SUBSTITUTION FROM THOSE SPECIFIED BY SYNTHESIS 9, LLC.
2. PRIOR TO PURCHASING AND ERECTION, THE CONTRACTOR SHALL PROVIDE SYNTHESIS 9, LLC FOR THEIR APPROVAL. SHOP DRAWINGS AND SPECS FOR ALL METAL FLASHINGS AND COUNTER-FLASHINGS IN AN ATTEMPT TO DEMONSTRATE THEIR UNDERSTANDING OF THE DETAILS.
3. CONTRACTOR IS SOLELY RESPONSIBLE FOR QUALITY CONTROL AND ASSURANCE OF THE WORK PERFORMED BY THE CONTRACTOR, ITS AGENTS, EMPLOYEES, OR ANY SUBCONTRACTOR EMPLOYED OR OTHERWISE PAID BY THE CONTRACTOR. CONTRACTOR IS FURTHER RESPONSIBLE FOR PROPER INTEGRATION OF BUILDING COMPONENTS TO PROVIDE A WEATHER-RESISTIVE BUILDING SYSTEM AS INTENDED BY THE DETAILS PROVIDED BY SYNTHESIS 9, LLC.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE MEANS AND METHODS OF WORK AND SHALL CARRY OUT ALL WORK IN COMPLIANCE WITH THE BEST INDUSTRY STANDARDS AND IN COMPLIANCE WITH PUBLISHED MANUFACTURER'S INSTALLATION INSTRUCTIONS AND STANDARDS REFERENCED IN THE SPECIFICATIONS.
5. MOCKUP OF ALL BUILDING ENVELOPE COMPONENTS SUCH AS WINDOWS, DOORS, WRB, CLADDING, AND PENETRATION INSTALLATIONS MUST BE CARRIED OUT PRIOR TO COMMENCEMENT OF EXTERIOR ENVELOPE WORK.
6. SYNTHESIS 9, LLC DETAILS MAY NOT BE MODIFIED, REVISED, OR ELIMINATED BY THE CONTRACTOR WITHOUT PRIOR WRITTEN CONSENT OF SYNTHESIS 9, LLC.
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY AND SCHEDULE SYNTHESIS 9, LLC PERSONNEL FOR INSPECTION AND APPROVAL OF THE WORK PERFORMED WITH RESPECT TO EACH OF THE WATERPROOFING COMPONENTS.
8. UNLESS OTHERWISE NOTED, ALL EXPOSED METAL FLASHINGS AND COUNTER-FLASHINGS SHALL BE MADE OF MINIMUM 24 GA PRE-FINISHED SHEET METAL. METAL FLASHING SHALL CONFORM TO SMACNA, NRCA, BUILDING CODE AND OTHER RELEVANT CODES AND INDUSTRY STANDARDS. THE VERTICAL LEGS OF SAID FLASHINGS SHALL BE MINIMUM SIX INCHES LONG. THE JOINTS OF PRE-FINISHED METAL FLASHINGS SHALL BE BENT IN PLACE SUCH AS TO PREVENT MOISTURE MIGRATION PAST THE END DAMS. ALL CONCEALED METAL FLASHING AND COUNTER-FLASHING PIECES SHALL BE 24 GA G-90 GALVANIZED SHEET METAL OR SCHEDULE 307 STAINLESS STEEL. JOINTS OF ALL FLASHING PIECES OTHER THAN PRE-FINISHED METAL MUST BE WELDED OR SOLDERED. ALL METAL FLASHING SYSTEMS SHALL BE MANUFACTURED & INSTALLED IN ACCORDANCE WITH THE ARCHITECTURAL SHEET METAL MANUAL PUBLISHED BY SMACNA. UNLESS OTHERWISE NOTED, ALL METAL HEAD FLASHINGS SHALL HAVE A MINIMUM 1/2"-TALL END-DAMS. UNLESS OTHERWISE NOTED, ALL SILL PAN FLASHINGS SHALL HAVE END- AND BACK-DAMS. UNLESS OTHERWISE NOTED, ALL FLASHINGS AND COUNTER FLASHINGS (METAL AND OTHERWISE) SHALL BE SET IN A CONTINUOUS BEAD OF NON-SKINNING BUTYL SEALANT OR APPROVED EQUAL.
9. UNLESS OTHERWISE NOTED, ENGINEERED SEALANT JOINTS SHALL BE 1/2-INCH MINIMUM WIDE BY 1/4-INCH MINIMUM DEEP IN AN ATTEMPT TO MAINTAIN A 2:1 RATIO. SEALANTS SHALL BE ONE-PART SILICONE SEALANT & SINGLE-PART POLYURETHANE FOR SURFACE APPLICATION AND NON-SKINNING BUTYL FOR INSTALLATION BETWEEN CONCEALED MATERIAL INTERFACES. ACCEPTABLE SEALANTS INCLUDE BUT NOT LIMITED TO DOW CORNING 790 AND 795 SILICONE BUILDING SEALANT, SIKAFLEX 15 LM, AND SONOLASTIC 150 VLM.
10. WEATHER-RESISTIVE BARRIER (WRB) SHALL BE COMPRISED OF (1) LAYER OF HIGH-PERFORMANCE VAPROSHIELD-WRAPSHIELD BREATHABLE UNDERLAYMENT MANUFACTURED BY VAPROSHIELD, LLC. NO SUBSTITUTION IS ALLOWED WITHOUT PRIOR APPROVAL FROM SYNTHESIS 9, LLC AND THE OWNER.
11. WINDOW AND DOOR UNITS INSTALLED WITHIN THE EXTERIOR WALL SYSTEM MAY NEED TO E FURRED OUT TO ALLOW FOR PROPER DRAINAGE. IF THIS IS THE CASE, THE FURRING MATERIAL SHALL BE PVC BATTENS OR PRESSURE-TREATED SOLID BLOCKING.
12. THE ROUGH OPENING FOR WINDOWS MUST BE 1/2" WIDER AND 1/2"+ TALLER THAN THE WIDTH & HEIGHT OF THE WINDOW UNIT AS THE SILL PAN WILL LEFT THE WINDOW UNITS BY APPROXIMATELY 1/8" TO 1/4" OFF THE SILL.
13. UNLESS OTHERWISE NOTED ON THE PLANS, ALL WOOD BLOCKINGS SHALL BE PRESSURE-TREATED LUMBER IF SUCH MATERIAL IS CUT ONSITE. CUT ENDS MUST BE TREATED WITH STANDARD WOOD PRIMERS IMMEDIATELY.
14. FURRING BATTENS SHALL BE EITHER 1X4 CEDAR OR BORATE-TREATED LUMBER OR 3/4" BY 1-7/8" PVC VAPROBATTEN MANUFACTURED BY VAPROSHIELD LLC. FURRING BATTENS SHALL ONLY BE INSTALLED VERTICALLY. FURRING BATTENS MUST BE INSTALLED DIRECTLY OVER STUDS SPACED NO MORE THAN 16" O.C. FURRING BATTENS MUST BE SECURELY ATTACHED TO THE STUDS USING APPROVED FASTENERS. ENSURE THAT THE FASTENERS FOR SIDING INSTALLATION ARE LONG ENOUGH TO PENETRATE THROUGH THE FURRING BATTENS, SHEATHING(S) AND INTO STUDS A MINIMUM OF 1/2". WHERE DISSIMILAR MATERIALS ABUT, INSTALL FURRING BATTENS DIRECTLY BEHIND MATERIAL TRANSITIONS. CUT ENDS OF BORATE TREATED LUMBER MUST BE TREATED WITH STANDARD WOOD PRIMERS IMMEDIATELY.
15. INSECT SCREENS SHALL BE PROVIDED AT TOP & BOTTOM OF THE WALLS AS WELL AS TOP & BOTTOM OF ANY AND ALL WALL PENETRATIONS. IT SHALL BE EITHER 3/4" MINIMUM VAPROVENT STRIP / VAPROVENT HOOK STRIP OR METAL BUG SCREEN. THE SCREEN / STRIP MUST BE INSTALLED CONTINUOUSLY.
16. WINDOW AND DOOR PENETRATION WRAPS SHALL CONSIST OF VAPROSHIELD-WRAPSHIELD MANUFACTURED BY VAPROSHIELD LLC. INSTALL PENETRATION WRAPS PER MANUFACTURER'S RECOMMENDATIONS AS WELL AS THE WATERPROOFING DETAILS. USE FACTORY PRE-FORMED CORNERS. USE APPROPRIATE PRIMER FOR APPLICATIONS AT EXTERIOR SHEATHING OR WHERE THE SURFACE TEMPERATURE IS BELOW 40-DEGREE FAHRENHEIT PURSUANT TO THE MANUFACTURER'S INSTRUCTIONS.
17. UNLESS OTHERWISE NOTED, SELF-ADHERING MEMBRANE (S.A.M.) SHALL BE MINIMUM OF 9" WIDE WRAPSHIELD S.A.M. MANUFACTURED BY VAPROSHIELD LLC; OR THERMFLASH. USE APPROPRIATE PRIMER FOR APPLICATIONS AT EXTERIOR SHEATHING OR WHERE THE SURFACE TEMPERATURE IS BELOW 40-DEGREES FAHRENHEIT PER MANUFACTURER'S RECOMMENDATIONS.
18. WHERE THROUGH WALL PENETRATIONS OCCUR (e.g., HOSE BIBS, PIPES, ELECTRICAL BOXES, LIGHT FIXTURES, ETC.) INSTALL 30-MIL THERM FLASH PENETRATION WRAP & BUTYL TAPE AS WELL AS WRB APRONS PER WATERPROOFING DETAILS.
17. AT ALL CONSTRUCTION & COLD JOINTS, APPLY APPROVED BENTONITE WATERSTOP. BASIS OF DESIGN IS CETCO VOLCLAY RX-101 WATERSTOP. CONCRETE SHALL BE TOOLED, CLEANED, AND PRIMED BEFORE INSTALLING WATERSTOP MEDIUM.
18. THE ROOFING FOR LOW-SLOPE ROOF SHALL BE A 60 MIL PVC, SINGLE-PLY ROOFING SYSTEM. BASIS OF DESIGN IS **JOHNS-MANVILLE**. INSTALL CRICKETS ON ROOF SURFACES WHERE NEEDED TO ALLOW FOR PROPER SLOPE AND DRAINAGE. WHERE PARAPET WALLS OCCUR, ROOF MEMBRANE SHALL WRAP OVER TOP PLATE AND WRAP OVER WRB 5" MINIMUM. INSTALL MEMBRANE IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS & NRCA ROOFING, AS WELL AS WATERPROOFING DETAILS PROVIDED. INSTALL FLASHINGS & COUNTER-FLASHINGS AT ALL TRANSITIONS AND JUNCTIONS IN ACCORDANCE WITH THE WATERPROOFING DETAIL PROVIDED HEREIN AS WELL AS NRCA, SMACNA AND THE BUILDING CODE REQUIREMENTS.
19. THE ROOFING FOR SLOPED ROOF AREAS SHALL BE AN ASPHALT SHINGLE OVER UNDERLAYMENT ROOFING SYSTEM. BASIS OF DESIGN IS **GAF, TIMBERLINE NS SHINGLE**. INSTALL CRICKETS ON ROOF SURFACES WHERE NEEDED TO ALLOW FOR PROPER SLOPE AND DRAINAGE. INSTALL SYSTEM IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, NRCA ROOFING, AS WELL AS WATERPROOFING DETAILS PROVIDED. INSTALL FLASHINGS & COUNTER-FLASHINGS AT ALL TRANSITIONS AND JUNCTIONS IN ACCORDANCE WITH THE WATERPROOFING DETAIL PROVIDED HEREIN AS WELL AS NRCA, SMACNA AND THE BUILDING CODE REQUIREMENTS.
20. COPING FLASHING SHALL BE ATTACHED WITH CONTINUOUS CLEAT ON THE OUTSIDE FACE OF PARAPET WHICH WILL BE ATTACHED TO THE PLATE @ 24" O.C. NO PENETRATION IS ALLOWED IN TOP OF COPINGS. ALL SEAM JOINTS MUST BE 3/4" TALL STANDING SEAM. ALL COPINGS SHALL BE MINIMUM 24 GA PREFINISHED SHEET METAL UNLESS OTHERWISE NOTED. COORDINATE DIMENSIONS & SLOPES OF COPING WITH OTHER DETAILS AND PLANS.
21. FIBER-CEMENT SIDING SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF JAMES HARDIE INSTALLATION INSTRUCTIONS OR AS PER THE OTHER F.C. MANUFACTURER'S REQUIREMENTS AS WELL AS WATER PROOFING DETAILS PROVIDED HEREIN. INSTALL A LAYER OF APPROVED PROTECTION MEMBRANE (e.g., FLASHING SHEET OR W.R.B.) BEHIND ALL BUTT JOINTS.
22. METAL ROOF PANELS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. ROOF PANELS SHALL BE INSTALLED OVER ONE LAYER OF 30# ROOF FELT AND ONE LAYER OF HIGH-TEMP GRACE ULTRA.
23. ALL FASTENERS SHALL BE EITHER STAINLESS STEEL OR DOUBLE-DIPPED, HOT-DIPPED OR HEAVY-DIPPED GALVANIZED CONFORMING TO ASTM A153. ELECTRO-GALVANIZED FASTENERS MUST NOT BE USED UNDER ANY CIRCUMSTANCES.
24. UNDER SLAB VAPOR BARRIER SHALL BE A CLASS B 15 MIL GEOMEMBRANE CONFORMING TO ASTM E-1745. BASIS OF DESIGN IS STEGO WRAP 15MIL WITH STEGO TAPE, MANUFACTURED BY STEGO INDUSTRIES.
25. MAINTAIN A MINIMUM OF 6" SEPARATION BETWEEN FINISH GRADE AND UNTREATED FRAMING MATERIALS.
38. SLOPE ALL DECKS, WALKS, AND PATIOS AWAY FROM THE BUILDING WITH A MINIMUM SLOPE OF 1/4" PER FOOT. INSTALL CRICKETS ON DECK SURFACES WHERE NEEDED TO ALLOW FOR PROPER SLOPE AND DRAINAGE. AT A MINIMUM 1/4" PER 1' SLOPE MUST BE PROVIDED TOWARD ROOF GUTTERS, DRAINS OR SCUPPERS.
26. ANY DISCREPANCY NOTED BY THE CONTRACTOR MUST BE BROUGHT TO THE ATTENTION OF SYNTHESIS 9, LLC IMMEDIATELY. WHERE DISCREPANCY OCCURS BETWEEN VARIOUS CONTRACT DOCUMENTS, CONTRACTOR SHALL FOLLOW THE MOST STRINGENT REQUIREMENT FOR EACH CATEGORY.
27. CONTRACTOR SHALL SUPPLY AND INSTALL FLASHINGS AND COUNTER-FLASHINGS AT ALL TRANSITIONS AND JUNCTIONS PURSUANT TO THE REQUIREMENTS OF THE BUILDING CODE, INDUSTRY STANDARDS INCLUDING SMACNA, EVEN IF SUCH FLASHING IS NOT SPECIFICALLY CALLED OUT FOR IN A DETAIL PROVIDED FOR HEREIN.
28. IT IS ASSUMED THAT THE EXTERIOR ENVELOPE SYSTEM IS A NON-AIR-BARRIER SYSTEM.
29. WEATHER EXPOSED CONCRETE WALLS & BRICK VENEER UNITS SHALL BE TREATED AS PER PLANS WITH ONE OF THE FOLLOWING PRODUCTS: (A) WATER REPELLANT: BASF - HYDROZO CLEAR 40 VOC; (B) NON-SACRIFICIAL GRAFFITI RESIST. COATING: PERMASHIELD; (C) SACRIFICIAL GRAFFITI RESIST. COATING: VS-1200 VANDAL SHIELD. APPLY SEALERS IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.




3 FLASHING @ LIGHT FIXTURE
SCALE: 3" = 1'-0"




2 JUNCTION BOX PENETRATION
SCALE: 3" = 1'-0"



5 DOOR HEAD AT EXTERIOR WALL
SCALE: 3" = 1'-0"



4 FLASHING AT HOSE BIB
SCALE: 3" = 1'-0"








6 DOOR JAMB AT EXTERIOR WALL
SCALE: 3" = 1'-0"

REVISIONS

NO.	DATE	DESCRIPTION





REVISIONS

DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: DETAILS
PROJECT #: 2016
SHEET:




- SILL PLAN NOTES:**
1. ALL PANS AT MASONRY TO BE STAINLESS STEEL OR 24 GA GALV. PRE-FINISHED.
 2. RESIDENTIAL WINDOW WALL SYSTEMS TO HAVE ALUMINUM PANS & FLASHINGS PER DETAILS TO MATCH WINDOW FRAME COLORS.
 3. SEAL OR SOLDER JOINTS AT END- & BACK DAMS TO FORM A WATERTIGHT PAN ASSEMBLY. SEAL BACK TO END DAM TRANSITIONS.
 4. COORDINATE BACK DAM HEIGHT WITH THRESHOLD AND/OR INTERIOR FINISHES PER ARCH PLANS.
 5. PROVIDE HEMMED EDGE AT ALL EXPOSED EDGES.


- WRAP & WRB NOTE:**
1. FASTEN WINDOW / DOOR WRAP & WRB PER WATERPROOFING DETAILS PROVIDED HEREIN WITH STAINLESS STEEL STAPLES WITH 7/16" CROWNS.
 2. WHERE STEEL STUD FRAMING OCCURS, USE APPROVED ADHESIVE TO PROPERLY ATTACHED WINDOW / DOOR WRAP THERETO.
 3. WHERE CONCRETE SURFACES OCCUR, USE VAPROSHIELD SELF-ADHERING MEMBRANE FOR WINDOW / DOOR WRAPS AND WRB.




1 FLANGED WINDOW WRAP
 SCALE: 3/8" = 1'-0"




4 TYPICAL WINDOW SILL
 SCALE: 3" = 1'-0"



3 TYPICAL WINDOW JAMB
 SCALE: 3" = 1'-0"




2 TYPICAL WINDOW HEAD
 SCALE: 3" = 1'-0"




REVISIONS	
REVISIONS	
DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	DETAILS
PROJECT #:	2016
SHEET:	

NON-FLANGED DOOR BEFORE WATER-RESISTIVE BARRIER (WRB) IS INSTALLED


STEP 1
ATTACH APRON WRB UNDER SILL (S). APRON SHOULD EXTEND AT LEAST 10" BEYOND SIDES OF ROUGH OPENING JAMBS (OR TO FIRST STUD IN OPEN STUD CONSTRUCTION), AND FAR ENOUGH BELOW THE ROUGH OPENING TO OVERLAP THE SILL PLAN OR THE WRB BELOW. THE TOP OF THE APRON SHOULD BE SECURELY ATTACHED TO THE WALL AND THE BOTTOM OF THE APRON SHOULD BE LEFT UNSECURED SO IT CAN OVERLAP THE WRB WHICH WILL BE INSTALLED AFTER THE DOOR.




STEP 5 FOR NON-FLANGED DOORS
A. PREPARE HEAD FLASHING BY CUTTING A PIECE OF STRAIGHT FLASH VF AT LEAST 12" LONGER THAN THE HEAD LENGTH.
B. REMOVE THE RELEASE PAPER FROM ONE SIDE OF STRAIGHT FLASH VF.
C. CENTER THE STRAIGHT FLASH VF ALONG THE LENGTH OF THE DOOR AND POSITION SO THAT IT CONTACTS THE DOOR FRAME.
D. BEGINNING AT THE JUNCTION OF THE JAMB AND HEAD AND AWAY FROM THE CORNERS CUT THE STRAIGHT FLASH VF ALONG THE CORNER AT A 45 DEGREE ANGLE.
E. FOLD THE NEWLY CREATED FLASHING FLAPS DOWN PARALLEL TO THE DOOR FRAME.
F. FOLD REMAINING HEAD FLASHING ONTO THE JAMB.





STEP 9
A. INSTALL DOOR ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS.
B. REMOVE THE REMAINING RELEASE PAPER FROM THE STRAIGHT FLASH VF JAMB FLASHING AND PRESS FIRMLY TO ADHERE TO THE WRB.
C. REMOVE THE RELEASE PAPER AT THE HEAD AND ADHERE IT TO THE EXTERIOR SHEATHING OR FRAMING MEMBERS.
OPTIONAL: COVER EXPOSED BUTYL WITH STRAIGHT FLASH, FLASHING TAPE, OR TYVEK TAPE.




STEP 2
A. CUT PIECE OF FLEX WRAP NF AT LEAST 12" LONGER THAN THE WIDTH OF THE SILL (S).
B. FLEX WRAP NF HAS PERFORATED RELEASE PAPER TO HELP WITH THE FORMATION OF THE BACK DAM. TO ENSURE THAT THE PERFORATION TEARS CLEANLY, FOLD THE PERFORATION 180 DEGREES AND CREASE THE FLASHING.
C. REMOVE THE TWO WIDEST PIECES OF RELEASE PAPER LEAVING THE NARROWEST RELEASE PAPER ON THE FLASHING. WHEN THE FINISHED FLOOR IS APPLIED, THE RELEASE PAPER CAN BE REMOVED AND THE BACK DAM CAN BE COMPLETED.




STEP 6
A. PREPARE JAMB FLASHING BY CUTTING A PIECE OF STRAIGHT FLASH VF AT LEAST 6" LONGER THAN THE JAMB LENGTH.
B. REMOVE THE RELEASE PAPER FROM ONE SIDE OF STRAIGHT FLASH VF.
C. POSITION SO THAT THE STRAIGHT FLASH VF CONTACTS THE DOOR FRAME UP TO THE EXTERIOR FACE OF THE DOOR. ENSURE THAT THE JAMB FLASHING IS POSITIONED 1 1/2" BELOW TOP OF HEAD FLASHING.
D. BEGINNING AT THE JUNCTION OF THE JAMB AND HEAD AND AWAY FROM THE CORNERS CUT THE STRAIGHT FLASH VF ALONG THE CORNER AT A 45 DEGREE ANGLE.
E. FOLD THE NEWLY CREATED FLASHING FLAPS DOWN PARALLEL TO THE DOOR FRAME.
F. FOLD REMAINING JAMB FLASHING ONTO THE JAMB.




STEP 10 (OPTIONAL - RECOMMENDED BEST PRACTICE)
A. CUT A PIECE OF METAL OR VINYL DRIP CAP SLIGHTLY LONGER THAN THE WIDTH OF THE DOOR AND PLACE A BEAD OF RECOMMENDED SEALANT ON THE REAR SIDE. INSTALL THE DRIP CAP TIGHT AGAINST THE DOOR HEAD AND COVER THE TOP EDGE WITH FLASHING TAPE.



STEP 7
A. BEGINNING AT THE JUNCTION OF THE JAMB AND HEAD AND AT THE SILL AND JAMB AND AWAY FROM THE CORNERS, CUT THE STRAIGHT FLASH VF ALONG THE CORNERS AT A 45 DEGREE ANGLE AND FOLD IT OVER FLAT TO ADHERE IT AGAINST THE HEAD FLASHING.
B. FOLD NEWLY CREATED FLAP DOWN PARALLEL TO THE DOOR FRAME.
C. FOLD FLASHING FLAPS TO THE DOOR FRAME AND ADHERE.
D. REPEAT ON OPPOSITE JAMB.
E. CUT TWO 3" x 3" FLEX WRAP NF SQUARES AND ADD PATCHES TO CORNER OF THE DOOR. STAPLE PATCHES IN CORNERS TO SECURE THE WOODEN HEAD AND JAMBS.




STEP 11
AFTER INSTALLING WRB, CUT AS SHOWN TO EXPOSE DOOR AND APRON. DO NOT CUT THROUGH THE FLASHING SYSTEMS PRODUCTS OR APRON.




STEP 3 (OPTIONAL BACK DAM)
INSTALL THE SILL FLASHING AS INDICATED LEAVING 1" OF FLEX WRAP NF WITH RELEASE PAPER EXTENDING IT PAS THE DOOR THRESHOLD ON THE INSIDE. WHEN THE 1" OF RELEASE PAPER IS REMOVED, THERE SHOULD BE 3/4" OF FLASHING TO FORM THE BACK DAM.


OPTION 2: SOME FLOORING CANNOT ACCOMMODATE A BACK DAM. IN THAT CASE FOLD THE 1" BACK DAM ON TOP OF FLEX WRAP NF IN THE SILL. DOOR WILL BE INSTALLED ON TOP OF THE 1" FOLD TO CREATE A BACK DAM.




STEP 8 (OPTIONAL - HIGH PRESSURE SKIRT)
A. CREATE THE HIGH PRESSURE SKIRT BY CUTTING A PIECE OF WRB 1" WIDER THAN THE WIDTH OF THE DOOR OPENING AND APPROXIMATELY 10" IN HEIGHT.
B. CUT A PIECE OF STRAIGHT FLASH VF TO THE SAME WIDTH OF SKIRT. REMOVE RELEASE PAPER FROM ONE SIDE OF STRAIGHT FLASH VF AND ADHERE TO WRB. THE SKIRT MAY BE MADE WITH STRAIGHT FLASH VF OR FLASHING TAPE.
C. REMOVE THE RELEASE PAPER FROM THE OTHER SIDE OF STRAIGHT FLASH VF AND ADHERE TO BUTYL ADHESIVE AT THE SILL SKIRT TO THE UNDERSIDE OF THE DOOR THRESHOLD BEHIND THE JAMB FLASHING.
D. SECURE EDGES OF THE OPTIONAL SKIRT WITH TWO 4" PIECES OF STRAIGHT FLASH OR FLASHING TAPE.
E. TAPE THE BOTTOM OF THE OPTIONAL SKIRT TO ALLOW FOR DRAINAGE AND TO MINIMIZE WIND DAMAGE DURING CONSTRUCTION.
F. IF SEALANT IS APPLIED TO THE SILL, INSURE (2) 2" GAPS TO ALLOW FOR DRAINAGE FOR EVERY 4' OF DOOR USING RECOMMENDED SEALANT.



STEP 12
A. TAPE SEAMS AS SHOWN. DO NOT TAPE AT BOTTOM OF OPENING. AT THE HEAD, CONTINUOUS TAPE SEAMS AS SHOWN WITH TYVEK TAPE. SKIP-TAPING AT THE HEAD IS ACCEPTABLE IF AN AIR BARRIER IS NOT REQUIRED OR IF ADDITIONAL DRAINAGE IS DESIRED.
B. LAP BOTTOM OF APRON AND THE WRB OVER BUILDING MATERIALS FOR PROPER SHINGLING.




STEP 13
A. WHEN THE INTERIOR FLORING IS READY TO INSTALL, REMOVE RELEASE PAPER AND USE FOLDING OPTION ONE OR TWO TO FORM THE BACK DAM.
B. INSTALL RECOMMENDED SEALANT (AND BACKER ROD AS NECESSARY) AROUND THE OPENING AT THE INTERIOR. IT IS ALSO ACCEPTABLE TO USE RECOMMENDED FOAM. THE SEAL CREATED BY THE SEALANT (AND BACKER ROD AS NECESSARY) OR FOAM WILL ALSO SERVE AS A BACK DAM. SEALANT SHOULD BE TOOLED FLAT TO ALLOW THE NATURAL CURING PROCESS TO CREATE A CONCAVE SHAPE. BE SURE THAT HTE SEALANT PENETRATES THE GROVES OF THE FLEX WRAP NF AROUND THE SILL.




REVISIONS

NO.	DESCRIPTION	DATE


DRAWN BY: BL / CM
CHECKED BY: BL
DATE: 24.03.11
TITLE: DETAILS
PROJECT #: 2016
SHEET:




3 VENT PENETRATIONS
SCALE: 3/8" = 1'-0"




1 TARGET FLASHING INSTALLATION FOR PENETRATIONS > 6"
SCALE: 1" = 1'-0"




2 WRB INSTALLATION
SCALE: 1/2" = 1'-0"



6 THROUGH WALL FLASHING
SCALE: 3\"/>



5 BUILDING OVERHANG
SCALE: 3\"/>



4 VENT SHROUDS
SCALE: 1 1/2\"/>

REVISIONS

NO.	DESCRIPTION

REVISIONS

DRAWN BY:	BL / CM
CHECKED BY:	BL
DATE:	24.03.11
TITLE:	DETAILS
PROJECT #:	2016
SHEET:	

DESIGN CRITERIA

BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE (IBC) AS AMENDED BY THE LOCAL JURISDICTION. VERTICAL LOADS ROOF LIVE LOAD: 25 PSF (SNOW) ROOF DEAD LOAD: 25 PSF RESIDENTIAL FLOOR LIVE LOAD: 40 PSF (REDUCIBLE) : 60 PSF (FOR DECKS) STAIRWAY LANDING AREAS: 150 PSF (INCLUDING Ip=1.5) FLOOR DEAD LOAD: 30 PSF (INCLUDES 1 1/2" GYP TOPPING) SNOW DESIGN DATA (ASCE 7-16) WIND DESIGN DATA (ASCE 7-16) FLAT SNOW LOAD: N/A BASIC WIND SPEED (ASD) V= 85MPH SNOW EXPOSURE FACTOR, Ce=1.0, ULTIMATE WIND SPEED V= 110MPH SNOW IMPORTANCE FACTOR, Is=1.0, RISK CATEGORY: II EXPOSURE: B THERMAL FACTOR, Ct=1.1 IMPORTANCE FACTOR, Iw=1.0 TOPOGRAPHIC FACTOR, Kzt= 1.0

SEISMIC DESIGN DATA (ASCE7-16) SEISMIC RESPONSE SYSTEM: WOOD SHEAR WALLS EQUIVALENT LATERAL FORCE PROCEDURE (ASCE 7-16) RISK CATEGORY: II SEISMIC IMPORTANCE FACTOR, Ie= 1.0 MAPPED SPECTRAL RESPONSE ACCELERATION: Ss=1.24, S1=0.476 DESIGN SPECTRAL RESPONSE ACCELERATION: Sds=0.831, Sd1=0.476 SITE CLASS: D SEISMIC DESIGN CATEGORY: D SEISMIC RESPONSE COEFFICIENT: Cs= 0.091 DESIGN BASE SHEAR: 111,513# SOIL PROPERTIES: BEARING CAPACITY: 2,000 PSF LATERAL CAPACITY: 250 PSF/FT

GENERAL REQUIREMENTS

- 1. STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH THE SPECIFICATIONS AND OTHER PROJECT DRAWINGS BY OTHER DISCIPLINES. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE CODES LISTED ABOVE.
2. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND ELEVATIONS RELATING TO EXISTING CONDITIONS BY MAKING FIELD SURVEYS AND MEASUREMENTS PRIOR TO COMMENCING FABRICATION OR CONSTRUCTION.
3. THE GENERAL CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION METHODS USED WILL NOT CAUSE DAMAGE TO ADJACENT BUILDINGS, UTILITIES, OR OTHER PROPERTY. THIS REQUIREMENT IS PARTICULARLY IMPORTANT DURING FOUNDATION INSTALLATION.
4. THE GENERAL CONTRACTOR IS ADVISED TO CONSIDER PERFORMING PHOTOGRAPHIC SURVEYS AND OTHER DOCUMENTATION OF THE CONDITION OF ADJACENT BUILDINGS AND OTHER STRUCTURES BEFORE THE START OF CONSTRUCTION.
5. THE GENERAL CONTRACTOR SHALL OBTAIN COPIES OF THE LATEST CONTRACT DOCUMENTS, INCLUDING ALL ADDENDA, AND PROVIDE THE RELEVANT PORTIONS TO ALL SUB-CONTRACTORS AND SUPPLIERS PRIOR TO SUBMITTAL OF SHOP DRAWINGS AND FABRICATION AND ERECTION OF STRUCTURAL MEMBERS.
6. THE GENERAL CONTRACTOR SHALL COMPARE AND COORDINATE THE DRAWINGS OF ALL DISCIPLINES AND REPORT ANY DISCREPANCIES BETWEEN THE DRAWINGS TO THE ARCHITECT AND ENGINEER.
7. DETAILS LABELED "TYPICAL" SHALL APPLY TO ALL SITUATIONS THAT ARE THE SAME OR SIMILAR TO THOSE SPECIFICALLY DETAILED. SEE DETAIL TITLES FOR APPLICABILITY OF A PARTICULAR DETAIL. TYPICAL DETAILS SHALL APPLY WHETHER OR NOT THEY ARE SPECIFICALLY KEYED AT EACH LOCATION. THE ENGINEER SHALL HAVE FINAL AUTHORITY TO DETERMINE APPLICABILITY OF TYPICAL DETAILS.
8. WHERE CONFLICTS EXIST BETWEEN STRUCTURAL DOCUMENTS THE STRICTEST REQUIREMENTS, AS INDICATED BY THE STRUCTURAL ENGINEER SHALL GOVERN.
9. THE GENERAL CONTRACTOR SHALL REVIEW AND DETERMINE THAT DIMENSIONS ARE COORDINATED BETWEEN ARCHITECTURAL AND STRUCTURAL DRAWINGS PRIOR TO FABRICATION OR START OF CONSTRUCTION.
10. NO STRUCTURAL MEMBER SHALL BE CUT OR NOTCHED OR OTHERWISE REDUCED IN STRENGTH UNLESS APPROVED BY THE STRUCTURAL ENGINEER.
11. THE GENERAL CONTRACTOR SHALL COORDINATE ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS FOR ANCHORED, EMBEDDED OR SUPPORTED ITEMS. NOTIFY THE ARCHITECT / ENGINEER OF ANY DISCREPANCIES.

CONSTRUCTION RESPONSIBILITY

- 1. THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE COMPLETED STRUCTURE, AND ARE NOT INTENDED TO INDICATE THE METHOD OR MEANS OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, PROCEDURES, TECHNIQUES, SEQUENCES, AND FOR JOB SAFETY.
2. THE ENGINEER DOES NOT HAVE CONTROL OR CHARGE OF, AND SHALL NOT BE RESPONSIBLE FOR, CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, OR PROCEDURES, FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK, FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR, SUBCONTRACTOR, OR ANY OTHER PERSONS PERFORMING ANY OF THE WORK, OR FOR THE FAILURE OF ANY OF THEM TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. PERIODIC SITE OBSERVATION VISITS MAY BE PROVIDED BY THE STRUCTURAL ENGINEER. THE SOLE PURPOSE OF THESE OBSERVATIONS IS TO REVIEW THE GENERAL CONFORMANCE OF THE CONSTRUCTION WITH THE STRUCTURAL CONTRACT DOCUMENTS. THESE LIMITED OBSERVATIONS SHOULD NOT BE CONSTRUED AS CONTINUOUS OR EXHAUSTIVE TO VERIFY THAT ALL CONSTRUCTION IS IN COMPLIANCE WITH THE CONSTRUCTION DOCUMENTS. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PERFORMING ALL WORK IN COMPLIANCE WITH THE CONSTRUCTION DOCUMENTS.

ABBREVIATIONS

Table with 4 columns: Abbreviation, Description, Abbreviation, Description. Includes terms like A.F.F., CLR., C, CONC., CONT., C.J., E.W., GLB, LBW, HD, MFR., MIN., MTL., N.T.S.

DEFERRED SUBMITTALS

THE FOLLOWING IS A LIST OF ITEMS THAT ARE NOT INCLUDED IN THIS PLAN AND SHOULD BE PROVIDED BY THE BUILDER AT TIME OF APPLICATION FOR PERMIT OR AS A DEFERRED SUBMITTAL ITEM:

- ALTERNATIVE I-JOIST/BEAM MANUFACTURER PLANS
• PRE-ENGINEERED TRUSS DESIGNS AND LAYOUTS

SITE WORK

PER KRAZAN & ASSOCIATES, INC. REPORT DATED APRIL 11, 2019, FOUNDATION DESIGN IS BASED ON AN ASSUMED AVERAGE SOIL BEARING OF 2,000 PSF. EXTERIOR FOOTINGS SHALL BEAR 18" & INTERIOR FOOTINGS SHALL BEAR 12" (MINIMUM) BELOW FINISHED GRADE. ALL FOOTINGS TO BEAR ON FIRM UNDISTURBED EARTH BELOW ORGANIC SURFACE SOILS OR ON STRUCTURAL FILL PER THE GEOTECHS RECOMMENDATIONS.

CONCRETE

Table with 5 columns: ITEM, DESIGN f'c (PSI), MAX. W/C RATIO, MAX. AGGREGATE SIZE, MIN. CEMENT (SACKS/YARD). Rows include FOUNDATIONS, STEM WALLS, SLAB ON GRADE.

- REINFORCING STEEL SHALL BE ASTM A615 GRADE 40 FOR #4 BARS AND SMALLER AND GRADE 60 FOR #5 BARS AND LARGER.
• MINIMUM SPLICE LENGTHS SHALL BE: 24" FOR #4, 30" FOR #5, 42" FOR #6
• CONCRETE COVER SHALL BE: 3" CAST AGAINST EARTH, 2" EXPOSED TO EARTH/WEATHER, 3/4" NOT EXPOSED TO EARTH/WEATHER.
• CORNER BARS ARE REQUIRED FOR ALL HORIZONTAL BARS IN FOOTINGS AND WALLS.
• ALL CONCRETE HAS BEEN DESIGNED FOR 2,500 PSI CONCRETE SO NO SPECIAL INSPECTION IS REQUIRED.

FRAMING

- ALL NAILING TO COMPLY WITH REQUIREMENTS OF IBC 2303.6 AND FASTENED PER TABLE 2304.10.1.
• ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED. FIELD CUT ENDS, NOTCHES, AND DRILLED HOLES OF PRESSURE TREATED LUMBER SHALL BE RETREATED IN THE FIELD IN ACCORDANCE WITH AWPA M4.
• FASTENERS FOR PRESSURE PRESERVATIVE AND FIRE RETARDANT TREATED WOOD SHALL BE OF HOT-DIPPED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE OR COPPER.
• MAINTAIN 8" MINIMUM CLEARANCE BETWEEN WOOD AND EARTH.
• MAINTAIN 12" MINIMUM CLEARANCE BETWEEN FLOOR BEAMS AND EARTH.
• MAINTAIN 18" MINIMUM CLEARANCE BETWEEN FLOOR JOISTS AND EARTH.

LUMBER GRADES

FRAMING LUMBER SHALL COMPLY WITH THE LATEST EDITION OF THE GRADING RULES OF THE WESTERN PRODUCTS ASSOCIATION OR THE WEST COAST LUMBER INSPECTION BUREAU. ALL SAWN LUMBER SHALL BE STAMPED WITH THE GRADE MARK OF AN APPROVED LUMBER GRADING AGENCY AND SHALL HAVE THE FOLLOWING UNADJUSTED DESIGN MINIMUM PROPERTIES:

Table with 2 columns: JOISTS, BEAMS, STUDS, POSTS and their respective WOOD TYPE, HF #2, Fb, Fv, Fc, E values.

FASTENERS

ALL NAILS SPECIFIED ON THIS PLAN SHALL BE COMMON OR GALVANIZED BOX (UNLESS NOTED OTHERWISE) OF THE DIAMETER AND LENGTH LISTED BELOW OR AS PER APPENDIX L OF THE NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS). ALL FASTENERS PLACE IN PRESSURE TREATED OR FIRE TREATED LUMBER/SHEATHING SHALL BE GALVANIZED.

- 8D COMMON (0.131" DIA., 2-1/2" LENGTH)
• 8D BOX (0.113" DIA., 2-1/2" LENGTH)
• 10D COMMON (0.148" DIA., 3" LENGTH)
• 10D BOX (0.128" DIA., 3" LENGTH)
• 16D COMMON (0.162" DIA., 3-1/2" LENGTH)
• 16D SINKER (0.148" DIA., 3-1/4" LENGTH)
• 5D COOLER (0.086" DIA., 1-5/8" LENGTH)
• 6D COOLER (0.092" DIA., 1-7/8" LENGTH)

SHEATHING

TYPICAL ROOF SHEATHING SHALL BE APA RATED 7/16" SHEATHING WITH A SPAN INDEX OF 24/16. FLOOR SHEATHING SHALL BE APA RATED 3/4" T&G SHEATHING WITH A SPAN INDEX OF 48/24 UNLESS NOTED OTHERWISE. STAGGER END LAPS AT ROOF AND FLOOR SHEATHING. WALL SHEATHING SHALL BE APA RATED 7/16" SHEATHING WITH A SPAN INDEX OF 24/0 UNLESS NOTED OTHERWISE.

GLULAM BEAMS (GLB)

GLULAM BEAMS SHALL BE 24F-V4 FOR SINGLE SPANS AND 24F-V8 FOR CONTINUOUS OR CANTILEVER SPANS WITH THE FOLLOWING MINIMUM PROPERTIES: Fb=2400 PSI, Fv=240 PSI, Fc=650 PSI (PERPENDICULAR), E=1,800,000 PSI.

ENGINEERED WOOD BEAMS AND I-JOIST

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND SPECIFICATIONS FOR APPROVAL BY BUILDING OFFICIAL. DESIGN, FABRICATION AND ERECTION IN ACCORDANCE WITH THE LATEST ICC EVALUATION REPORT.

BEAMS DESIGNATED AS "PSL" SHALL HAVE THE MINIMUM PROPERTIES: Fb=2900 PSI, Fv=290 PSI, Fc=750 PSI (PERPENDICULAR), E=2,000,000 PSI. BEAMS DESIGNATED AS "LVL" SHALL HAVE THE MINIMUM PROPERTIES: Fb=2600 PSI, Fv=285 PSI, Fc=750 PSI (PERPENDICULAR), E=1,900,000 PSI. BEAMS DESIGNATED AS "LSL" SHALL HAVE THE MINIMUM PROPERTIES: Fb=1700 PSI, Fv=400 PSI, Fc=680 PSI (PERPENDICULAR), E=1,300,000 PSI.

PRE-ENGINEERED ROOF TRUSSES

PRE-ENGINEERED ROOF TRUSSES IS A DEFERRED SUBMITTAL ITEM AND IS TO BE DESIGNED, FABRICATED AND INSTALLED PER THE LATEST TRUSS PLATE INSTITUTE STANDARDS, AND IBC SECTION 2303.4. PREFABRICATED ITEMS TO BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER. THE FABRICATOR SHALL PROVIDE ALL CONNECTION DESIGN, DETAILS AND INSTALLATION INSTRUCTIONS, WHICH SHALL BE AVAILABLE ON SITE FOR INSPECTION. WHERE TRUSSES ARE NOT PROVIDED TO COMPLETE THE ROOF SYSTEM, OVERFRAMING MEMBERS AND CONNECTIONS SHALL BE PROVIDED. OVERFRAMING DETAILS SHALL BE INCLUDED IN THE TRUSS SHOP DRAWINGS IN ORDER TO PROVIDE LOADING CONDITIONS CONSISTENT WITH THE MODELING OF THE TRUSSES. THE OVERFRAMING AND RELATED DETAILS SHALL BE DESIGNED BY THE TRUSS ENGINEER. TRUSSES (OR DRAG TRUSSES) ALIGNING WITH SHEAR WALLS SHALL BE SPECIAL TRUSSES THAT HAS BEEN DESIGNED TO TRANSFER THE SPECIFIC WIND AND SEISMIC LOADS SHOWN ON THE PLANS. THE TRUSS SHALL BE DESIGNED TO TRANSFER THE LOAD BETWEEN THE ROOF SHEATHING AND THE SHEAR WALL BELOW. THE TRUSS SHALL BE DESIGNED TO TRANSFER A MINIMUM OF 100 PLF ALONG THE LENGTH OF THE TRUSS. TEMPORARY AND PERMANENT BRACING REQUIRED FOR THE STABILITY OF THE TRUSS ELEMENTS UNDER GRAVITY LOADS AND IN-PLANE WIND OR SEISMIC LOADS SHALL BE DESIGNED BY THE TRUSS ENGINEER WHERE THE TOP CHORD IS NOT DIRECTLY ATTACHED TO THE ROOF SHEATHING. THE TRUSS ENGINEER SHALL DESIGN AND SHOW THE PLACEMENT OF ALL REQUIRED TOP CHORD BRACING AND CONNECTIONS ON THE TRUSS SHOP DRAWINGS. ANY BRACING LOADS TRANSFERRED TO THE MAIN BUILDING SYSTEM SHALL BE IDENTIFIED AND SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW. DESIGN CALCULATIONS AND SHOP DRAWINGS SHALL BE SUBMITTED FOR REVIEW BY THE ENGINEER OF RECORD PRIOR TO SUBMITTING TO THE BUILDING OFFICIAL FOR APPROVAL. ROOF TRUSS TOP CORD MUST BE HF#2 OR BETTER.

SPECIAL INSPECTIONS

SOILS (PER IBC 1705.6): CONTINUOUS SPECIAL INSPECTION SHALL BE REQUIRED FOR MATERIAL, DENSITIES AND LIFT THICKNESS DURING PLACEMENT AND COMPACTION OF COMPACTED STRUCTURAL FILL AND PERIODIC SPECIAL INSPECTION IS REQUIRED TO VERIFY SHALLOW FOUNDATIONS BEARING MATERIAL MEETS DESIGNED BEARING CAPACITY, VERIFYING EXCAVATION ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL, PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIAL AND TO INSPECT SUBGRADE MATERIAL PRIOR TO COMPACTED FILL PLACEMENT TO VERIFY THE SITE HAS BEEN PREPARED PROPERLY.

WOOD CONSTRUCTION (PER IBC 1705.5) AND WIND RESISTANCE (PER IBC 1705.11): PERIODIC SPECIAL INSPECTION IS REQUIRED TO VERIFY NAILING, BOLTING, ANCHORING AND OTHER FASTENING OF ELEMENTS OF SHEAR WALLS WITH NAIL SPACING 4" AND LESS, DRAG STRUTS, BRACES AND HOLD DOWNS.

POST-INSTALLED ANCHORS

- 1. POST-INSTALLED ANCHORS SHALL ONLY BE USED WHERE SPECIFIED ON THE DRAWINGS. CONTRACTOR SHALL OBTAIN APPROVAL FROM ENGINEER OF RECORD (EOR) PRIOR TO USING POST-INSTALLED ANCHORS FOR MISSINGS OR MISPLACED ANCHORS.
2. CARE SHALL BE GIVEN TO AVOID CONFLICTS WITH EXISTING REINFORCING WHEN DRILLING HOLES. HOLES SHALL BE DRILLED AND CLEANED PER THE MANUFACTURER'S INSTRUCTIONS. ANCHORS SHALL BE INSTALLED PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AT NOT LESS THAN MINIMUM EDGE DISTANCES AND/OR SPACING INDICATED IN THE MANUFACTURER'S LITERATURE.
3. SPECIAL INSPECTION SHALL BE PROVIDED FOR ALL ADHESIVE AND MECHANICAL ANCHOR INSTALLATIONS AS REQUIRED BY THE EOR. INDEPENDENT ON-SITE PROOF LOAD TESTING SHALL BE PERFORMED AS REQUIRED BY THE EOR. CONTACT EOR FOR NUMBER OF ANCHORS REQUIRED TO BE TESTED AND REQUIRED PROOF LOAD MAGNITUDE.
4. UNLESS NOTED OTHERWISE ON DOCUMENTS, ACCEPTABLE PRODUCTS SHALL BE AS LISTED BELOW:
A. MECHANICAL ANCHORS INTO CONCRETE:
1. USE THE FOLLOWING (UNO):
A. SIMPSON TITEN HD (ICC-ES AC193 AND ACI 355.2) FOR CRACKED & UNCRACKED CONCRETE PER (ICC-ES ESR-2713)
B. HILTI KWIK BOLT TZ CARBON AND STAINLESS STEEL ANCHORS (ICC-ES ESR1917)
C. RED HEAD TRUBOLT + WEDGE ANCHORS (ICC-ES ESR2427)
D. SIMPSON STRONG-TIE STRONG-BOLT (STB) (ICC-ES ESR1771)(FL8668)
2. USE THE FOLLOWING ONLY WHERE SPECIFICALLY CALLED OUT ON THE DOCUMENTS:
A. HILTI HDA (ICC-ES ESR1546)
B. HILTI HSL-3 ANCHOR (ICC-ES ESR1545)
C. SIMPSON STRONG-TIE TITEN HD (THD) (ICC-ES ESR2713)(FL2304)
B. MECHANICAL ANCHORS INTO MASONRY LINTELS OR GROUT FILLED CELLS:
1. USE THE FOLLOWING (UNO):
A. SIMPSON TITEN HD (ICC-AC AC106) FOR MASONRY PER (ICC-ES ESR-1056)
B. HILTI KWIK BOLT 3 MASONRY ANCHORS (ICC-ES ESR1385)
C. SIMPSON STRONG-TIE WEDGE-ALL ANCHOR(WA) (IC80-ES ER-3631) (FL5415)
2. USE THE FOLLOWING ONLY WHERE SPECIFICALLY CALLED OUT ON THE DOCUMENTS:
A. HILTI HUS-H SCREW ANCHOR (ICC-ES ESR2369)
B. SIMPSON STRONG-TIE TITEN HD (THD) (ICC-ES ESR1056)(FL2304)
C. ADHESIVE ANCHORS INTO CONCRETE:
1. USE THE FOLLOWING (UNO):
A. HILTI HIT-RE 500-SD ADHESIVE (ICC-ES ESR2322)
B. RED HEAD EPCON G5 ADHESIVE (ICC-ES ESR1137)(FL6582)
C. SIMPSON STRONG-TIE SET-XP EPOXY-TIE ADHESIVE (SETXP) (ICC-ES ESR2508)
2. USE THE FOLLOWING ONLY WHERE SPECIFICALLY CALLED OUT ON THE DOCUMENTS:
A. HILTI HIT HY 150 MAX ADHESIVE (ICC-ES ESR2262)
D. ADHESIVE ANCHORS INTO MASONRY LINTELS OR GROUT FILLED CELLS:
1. USE THE FOLLOWING (UNO):
A. HILTI HIT HY-150 MAX ADHESIVE (ICC-ES ESR1967)
B. SIMPSON STRONG-TIE SET EPOXY-TIE ADHESIVE (SET) (ICC-ES ESR1772)(FL5550)



PIERUCCIOLI E&C, LLC
CHON PIERUCCIOLI, PE
STEIN, BENNETT ST.
TACOMA, WA 98402

RELEASE OF DOCUMENTS
THIS DOCUMENT HAS BEEN REVIEWED AND APPROVED BY THE ENGINEER OF RECORD FOR THE PROJECT AND IS THE PROPERTY OF PIERUCCIOLI E&C, LLC. IT IS TO BE USED ONLY FOR THE PROJECT AND NOT TO BE REPRODUCED OR COPIED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF PIERUCCIOLI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

Table with 2 columns: REVISIONS, Description. Row 1: 01, ---

Table with 2 columns: REVISIONS, Description. Includes fields for DRAWN BY: CP, CHECKED BY: CP, DATE: 2024.01.12, TITLE: STRUCTURAL NOTES, PROJECT #: ---, SHEET:

S1.0



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3701 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGN AND CONSTRUCTION OF THE PROJECT ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

01

REVISIONS

DRAWN BY: CP

CHECKED BY: CP


DATE: 2024.01.12

TITLE: FOUNDATION PLAN

PROJECT #: ----

SHEET:

S3.1



FOUNDATION PLAN
1/8" = 1'-0"

**SPECIAL INSPECTION IS
REQUIRED FOR
FOUNDATION SOIL BEARING**

FOOTING SCHEDULE

36	POST ON 36" SQUARE X 8" THICK CONC. FOOTING W/ 4-#4 BARS E.W.
42	POST ON 42" SQUARE X 8" THICK CONC. FOOTING W/ 5-#4 BARS E.W.

NOTES:

1. USE MIN. 6" WIDE POST BELOW BEAM SPLICES
2. USE 4X4 POST BELOW 4X BEAMS, U.N.O.
3. USE 6X6 POST BELOW 6X BEAMS, U.N.O.
4. PT POST SHALL BE USED IN EXTERIOR CONDITIONS

NOTES:

1. PER KRAZAN & ASSOCIATES, INC. REPORT DATED APRIL 11, 2019, FOUNDATION DESIGN IS BASED ON AN ASSUMED AVERAGE SOIL BEARING OF 2,000 PSF. EXTERIOR FOOTINGS SHALL BEAR 18" & INTERIOR FOOTINGS SHALL BEAR 12" (MINIMUM) BELOW FINISHED GRADE. ALL FOOTINGS TO BEAR ON FIRM UNDISTURBED EARTH BELOW ORGANIC SURFACE SOILS OR ON STRUCTURAL FILL PER THE GEOTECHS RECOMMENDATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY THAT THE SITE SOILS PROVIDE THIS MINIMUM BEARING CAPACITY.
2. EXTERIOR FOOTINGS TO BE A MINIMUM OF 18" BELOW FINISHED GRADE BEARING ON NATIVE UNDISTURBED SOIL OR STRUCTURAL FILL.
3. INTERNAL FOOTINGS TO BE A MINIMUM OF 12" BELOW FINISHED GRADE BEARING ON NATIVE UNDISTURBED SOIL OR STRUCTURAL FILL.
4. INTERIOR S.O.G. SHALL BE 4" THICK SLAB ON GRADE OVER INSULATION (PER ARCH.), OVER VAPOR BARRIER (PER ARCH.) OVER 4" COMPACTED SAND OR GRAVEL. SLAB SHALL BE REINFORCED WITH 6X6 W2.9XW2.9 WELDED WIRE, #3 BARS @ 24" O.C., OR HELIX FABRIC (5# PER CUBIC YARD).
5. EXTERIOR SLAB SHALL BE 4" THICK SLAB ON GRADE SLOPED AT 1% AWAY FROM BUILDING..
6. CONTROL JOISTS SHALL BE 15' O.C. MAX.
7. SEE SHEAR WALL PLAN ON SHEET S4.6 FOR HOLD DOWN AND ANCHOR BOLT LOCATIONS NOT SHOWN HERE.



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3128 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGN AND CONTENTS THEREOF ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE TO BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

01

REVISIONS

DRAWN BY: CP

CHECKED BY: CP


DATE: 2024.01.12

TITLE: FRAMING PLAN

PROJECT #: ---

SHEET:

S3.2



POST SCHEDULE

POST NUMBER	POST TYPE	ALTERNATIVE BUILT-UP POST
44	4X4 DF#2	(3) 2X4 DF#2 STUDS
46	4X6 DF#2	(3) 2X6 DF#2 STUDS
48	4X8 DF#2	(5) 2X4 DF#2 STUDS
64	4X6 DF#2	(4) 2X4 DF#2 STUDS
66	6X6 DF#2	(4) 2X6 DF#2 STUDS
68	6X8 DF#2	(5) 2X6 DF#2 STUDS

SEE SHEAR WALL PLANS FOR HOLD DOWN LOCATIONS THAT REQUIRE DF#2 STUDS

LEVEL 2 FRAMING PLAN
1/8" = 1'-0"

- NOTES:
- USE MIN. 6" WIDE POST BELOW BEAM SPLICES
 - USE 4X4 DF#2 POST BELOW 4X BEAMS, U.N.O.
 - USE 6X6 DF#2 POST BELOW 6X BEAMS, U.N.O.

- NOTES:
- ALL COLUMNS NOT SPECIFIED OR OTHERWISE NOTED ON THE PLANS ARE LAMINATED TOGETHER PER "TYPICAL BUILT-UP COLUMN DETAIL" ON SHEET S4.2. SOLID WOOD COLUMNS MAY BE SUBSTITUTED FOR BUILT-UP COLUMNS BY PROVIDING AN EQUIVALENT CROSS SECTIONAL AREA.
 - ALL BEAMS SHALL HAVE A MINIMUM OF 3X BUILT-UP COLUMN WITH CONTINUOUS LOAD PATH TO FOUNDATION.
 - ALL HEADERS UNLESS SPECIFIED ON THE PLANS ARE TO BE 4X10 DF-L #2 WITH AT LEAST ONE CRIPPLE AND ONE STUD FOR EACH END FOR OPENINGS LESS THAN OR EQUAL TO 5'-0" WIDE AND TWO CRIPPLES AND ON KING STUD FOR ALL OTHERS.
 - ALL TJI FLOOR JOIST HUNG FROM FLUSH BEAMS SHALL BE HUNG WITH IUS SERIES HANGERS.
 - ALL RIM JOIST SHALL BE 1 1/2" X 11 1/2" LSL U.N.O. SEE SHEAR WALL TABLE TO AREAS REQUIRING THICKER RIM JOIST.
 - FLOOR SHEATHING SHALL BE 3/4" T&G (48/24) GLUED AND NAILED WITH 10d @ 4" O.C. ALONG PANEL EDGES AND 12" O.C. FIELD. STAGGER END LAPS. NAILS SHALL EMBED 1 1/2" MINIMUM INTO FLOOR JOIST. THIS LEVEL REQUIRES BLOCKING AT ALL SHEATHING PANEL EDGES.
 - SHORT MID LANDING STAIR STRINGERS SHALL BE PT4X12 HF#2.
 - LONG GROUND FLOOR STAIR STRINGERS SHALL BE PT3 1/2" X 12" GLB.
 - EXTERIOR WALLS TO BE 2X6 AT 16" O.C., U.N.O.
 - INTERIOR PARTITIONS TO BE 2X4 AT 16" O.C. (2X6 @ PLUMBING WALLS OR PER ARCH.) U.N.O.
 - FLOOR JOISTS AND BEAMS OF EQUAL OR BETTER CAPACITY MAY BE SUBSTITUTED FOR THOSE SHOWN ON THIS PLAN, "EQUAL" IS DEFINED AS HAVING MOMENT CAPACITY, SHEAR CAPACITY, AND STIFFNESS WITHIN 3% OF THE SPECIFIED JOISTS OR BEAMS.



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
378 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT HAS BEEN REUSED BY THE DESIGN PROFESSIONAL SERVICE, AND THE PROPERTY OF PIERUCCIONI E&C, LLC, IS HEREBY REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

01

REVISIONS

DRAWN BY: CP

CHECKED BY: CP


DATE: 2024.01.12

TITLE: FRAMING PLAN

PROJECT #: ----

SHEET:

S3.3




POST SCHEDULE

POST NUMBER	POST TYPE	ALTERNATIVE BUILT-UP POST
44	4X4 DF#2	(3) 2X4 DF#2 STUDS
46	4X6 DF#2	(3) 2X6 DF#2 STUDS
64	4X6 DF#2	(4) 2X4 DF#2 STUDS
66	6X6 DF#2	(4) 2X6 DF#2 STUDS
68	6X8 DF#2	(5) 2X6 DF#2 STUDS

- NOTES:
- USE MIN. 6" WIDE POST BELOW BEAM SPLICES
 - USE 4X4 DF#2 POST BELOW 4X BEAMS, U.N.O.
 - USE 6X6 DF#2 POST BELOW 6X BEAMS, U.N.O.

- NOTES:
- ALL COLUMNS NOT SPECIFIED OR OTHERWISE NOTED ON THE PLANS ARE LAMINATED TOGETHER PER "TYPICAL BUILT-UP COLUMN DETAIL" ON SHEET S4.2. SOLID WOOD COLUMNS MAY BE SUBSTITUTED FOR BUILT-UP COLUMNS BY PROVIDING AN EQUIVALENT CROSS SECTIONAL AREA.
 - ALL BEAMS SHALL HAVE A MINIMUM OF 3X BUILT-UP COLUMN WITH CONTINUOUS LOAD PATH TO FOUNDATION.
 - ALL HEADERS UNLESS SPECIFIED ON THE PLANS ARE TO BE 4X10 DF-L #2 WITH AT LEAST ONE CRIPPLE AND ONE STUD FOR EACH END FOR OPENINGS LESS THAN OR EQUAL TO 5'-0" WIDE AND TWO CRIPPLES AND ON KING STUD FOR ALL OTHERS.
 - ALL TJI FLOOR JOIST HUNG FROM FLUSH BEAMS SHALL BE HUNG WITH IUS SERIES HANGERS.
 - ALL RIM JOIST SHALL BE 1 1/4" X 11 3/4" LSL U.N.O. SEE SHEAR WALL TABLE TO AREAS REQUIRING THICKER RIM JOIST.
 - FLOOR SHEATHING SHALL BE 3/8" T&G (48/24) GLUED AND NAILED WITH 10d @ 6" O.C. ALONG PANEL EDGES AND 12" O.C. FIELD. STAGGER END LAPS. NAILS SHALL EMBED 1 1/2" MINIMUM INTO FLOOR JOIST.
 - SHORT MID LANDING STAIR STRINGERS SHALL BE PT4X12 HF#2.
 - LONG GROUND FLOOR STAIR STRINGERS SHALL BE PT3 1/2" X 12" GLB.
 - EXTERIOR WALLS TO BE 2X6 AT 16" O.C., U.N.O.
 - INTERIOR PARTITIONS TO BE 2X4 AT 16" O.C. (2X6 @ PLUMBING WALLS OR PER ARCH.) U.N.O.
 - FLOOR JOISTS AND BEAMS OF EQUAL OR BETTER CAPACITY MAY BE SUBSTITUTED FOR THOSE SHOWN ON THIS PLAN, "EQUAL" IS DEFINED AS HAVING MOMENT CAPACITY, SHEAR CAPACITY, AND STIFFNESS WITHIN 3% OF THE SPECIFIED JOISTS OR BEAMS.

LEVEL 3 FRAMING PLAN
1/8" = 1'-0"




POST SCHEDULE

POST NUMBER	POST TYPE	ALTERNATIVE BUILT-UP POST
44	4X4 DF#2	(3) 2X4 DF#2 STUDS
46	4X6 DF#2	(3) 2X6 DF#2 STUDS
64	4X6 DF#2	(4) 2X4 DF#2 STUDS
66	6X6 DF#2	(4) 2X6 DF#2 STUDS
68	6X8 DF#2	(5) 2X6 DF#2 STUDS

- NOTES:**
- USE MIN. 6" WIDE POST BELOW BEAM SPLICES
 - USE 4X4 DF#2 POST BELOW 4X BEAMS, U.N.O.
 - USE 6X6 DF#2 POST BELOW 6X BEAMS, U.N.O.

- NOTES:**
- ALL COLUMNS NOT SPECIFIED OR OTHERWISE NOTED ON THE PLANS ARE LAMINATED TOGETHER PER "TYPICAL BUILT-COLUMN DETAIL" ON SHEET S4.2. SOLID WOOD COLUMNS MAY BE SUBSTITUTED FOR BUILT-UP COLUMNS BY PROVIDING AN EQUIVALENT CROSS SECTIONAL AREA.
 - ALL HEADERS UNLESS SPECIFIED ON THE PLANS ARE TO BE 4X10 DF-L #2 WITH AT LEAST ONE CRIPPLE AND ONE STUD FOR EACH END FOR OPENINGS LESS THAN OR EQUAL TO 5'-0" WIDE AND TWO CRIPPLES AND ON KING STUD FOR ALL OTHERS.
 - ROOF SHEATHING SHALL BE 1/2" CDX OR 7/16" OSB NAILED WITH 8d @ 6" O.C. ALONG PANEL EDGES, AND 12" O.C. FIELD. SPAN INDEX SHALL BE 24/0. STAGGER END LAPS. NAILS SHALL MINIMUM 1 1/2" EMBED INTO ROOF STRUCTURE BELOW.
 - BEARING WALLS ARE INDICATED AS SHADED WALLS
 - PROVIDE VENTED BLOCKING AT REQUIRED TRUSS/RAFTER BAYS
 - SHADED AREAS INDICATE OVERFRAMING. ROOF OVER FRAMING (IRC SECTION R802.3): RAFTERS SHALL BE FRAMED TO 2X RIDGE BOARD PER PLAN. RIDGE BOARD SHALL NOT BE LESS IN DEPTH THAN THE CUT END OF THE RAFTER. AT ALL VALLEYS AND HIPS THERE SHALL BE A 2X VALLEY OR HIP RAFTER AND NOT LESS IN DEPTH THAN THE CUT END OR THE RAFTER. (FULL COVERAGE AT RIDGE, HIPS AND VALLEYS).
 - ALL MANUFACTURED TRUSSES:
 - * SHALL NOT BE FIELD ALTERED WITHOUT ENGINEER'S APPROVAL
 - * SHALL HAVE DESIGN DETAILS AND DRAWINGS ON SITE FOR FRAMING INSPECTION
 - * SHALL BE INSTALLED AND BRACED TO MANUFACTURER'S SPECIFICATION
 - * SHALL CARRY MANUFACTURER'S STAMP ON EACH TRUSS
 - IF AN ENGINEERED ROOF FRAMING LAYOUT IS PROVIDED BY THE TRUSS SUPPLIER, THAT TRUSS LAYOUT SHALL SUPERCEDE THE TRUSS LAYOUT INDICATED IN THE PLANS. PROVIDE TRUSS LAYOUT AND SPECS ON SITE FOR INSPECTION.
 - PROVIDE SOLID FRAMING EQUAL TO THE WIDTH OF THE MEMBER BEING SUPPORTED (U.N.O.)

LOWER ROOF FRAMING PLAN
1/8" = 1'-0"



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
378 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGN DETAILS OF PROFESSIONAL SERVICE ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE NOT TO BE COPIED, REPRODUCED OR IN ANY MANNER USED WITHOUT THE WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA


REVISIONS

01

REVISIONS

DRAWN BY: CP
CHECKED BY: CP
DATE: 2024.01.12
TITLE: FRAMING PLAN
PROJECT #: ---
SHEET:

S3.4



UPPER ROOF FRAMING PLAN
 1/8" = 1'-0"

- NOTES:**
- ALL COLUMNS NOT SPECIFIED OR OTHERWISE NOTED ON THE PLANS ARE LAMINATED TOGETHER PER "TYPICAL BUILT-COLUMN DETAIL" ON SHEET S4.2. SOLID WOOD COLUMNS MAY BE SUBSTITUTED FOR BUILT-UP COLUMNS BY PROVIDING AN EQUIVALENT CROSS SECTIONAL AREA.
 - ALL HEADERS UNLESS SPECIFIED ON THE PLANS ARE TO BE 4X10 DF-L #2 WITH AT LEAST ONE CRIPPLE AND ONE STUD FOR EACH END FOR OPENINGS LESS THAN OR EQUAL TO 5'-0" WIDE AND TWO CRIPPLES AND ON KING STUD FOR ALL OTHERS.
 - ROOF SHEATHING SHALL BE 1/2" CDX OR 7/16" OSB NAILED WITH 8d @ 6" O.C. ALONG PANEL EDGES, AND 12" O.C. FIELD. SPAN INDEX SHALL BE 24/0. STAGGER END LAPS. NAILS SHALL MINIMUM 1 1/2" EMBED INTO ROOF STRUCTURE BELOW.
 - BEARING WALLS ARE INDICATED AS SHADED WALLS
 - PROVIDE VENTED BLOCKING AT REQUIRED TRUSS/RAFTER BAYS
 - ALL MANUFACTURED TRUSSES:
 - * SHALL NOT BE FIELD ALTERED WITHOUT ENGINEER'S APPROVAL
 - * SHALL HAVE DESIGN DETAILS AND DRAWINGS ON SITE FOR FRAMING INSPECTION
 - * SHALL BE INSTALLED AND BRACED TO MANUFACTURER'S SPECIFICATION
 - * SHALL CARRY MANUFACTURER'S STAMP ON EACH TRUSS
 - IF AN ENGINEERED ROOF FRAMING LAYOUT IS PROVIDED BY THE TRUSS SUPPLIER, THAT TRUSS LAYOUT SHALL SUPERCEDE THE TRUSS LAYOUT INDICATED IN THE PLANS. PROVIDE TRUSS LAYOUT AND SPECS ON SITE FOR INSPECTION.
 - PROVIDE SOLID FRAMING EQUAL TO THE WIDTH OF THE MEMBER BEING SUPPORTED (U.N.O.)



PIERUCCIONI E&C, LLC
 CHON PIERUCCIONI, PE
 3726 N. BENNETT ST.
 TACOMA, WA 98407

REUSE OF DOCUMENTS
 THIS DOCUMENT IS THE PROPERTY OF PIERUCCIONI E&C, LLC. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. ANY REUSE OR MODIFICATION OF THIS DOCUMENT WITHOUT THE WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC IS PROHIBITED.

EAST TOWN CROSSING
 BUILDING "E"
 PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DESCRIPTION
01	---

REVISIONS

DRAWN BY:	CP
CHECKED BY:	CP
DATE:	2024.01.12
TITLE:	FRAMING PLAN
PROJECT #:	---
SHEET:	---


S3.5



PIERUCCI E&C, LLC
CHON PIERUCCI, PE
378 N. BENNETT ST.
TACOMA, WA 98402

REUSE OF DOCUMENTS
THIS DOCUMENT HAS BEEN REPRODUCED FROM THE ORIGINAL DOCUMENT OF PIERUCCI E&C, LLC. THE REPRODUCED DOCUMENT IS THE PROPERTY OF PIERUCCI E&C, LLC AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF PIERUCCI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA



SPECIAL INSPECTIONS ARE REQUIRED FOR SHEAR WALLS: $\triangle W2$ $\triangle W3$ $\triangle W4$

LEVEL 1 SHEAR WALL PLAN
1/8" = 1'-0"

- NOTES:
1. ALL EXTERIOR WALL SHALL BE SHEAR WALL TYPE W1 UNLESS NOTED OTHERWISE.

HOLD DOWN SCHEDULE

SIMPSON PRODUCT	FASTENERS		ANCHOR BOLTS
	SCREWS OR BOLTS	NAILS	
HDU4-SDS2.5	(10) 3/4" X 2 3/4" SDS INTO POST PER PLAN	--	SB 3/8" X 24 (18" EMBED)
HDU14-SDS2.5	(36) 3/4" X 2 3/4" SDS INTO POST PER PLAN	--	SB 1X30 (24" EMBED)

SHEAR WALL AND ANCHOR TABLE

WALL TYPE	APA RATED SHEATHING (b), (c)	MINIMUM NOMINAL THICKNESS (IN) (j)	MINIMUM NAIL PENETRATION IN FRAMING (IN) (i)	STUD & BLOCKING SIZE @ ADJOINING EDGES (k)	REQUIRED RIM JOIST THICKNESS	EDGE NAIL SIZE AND SPACING, COMMON OR GALV. BOX (d)	RIM JOIST OR BLOCK CONNECTION TO TOP PLATE (e), (f)	2x BOTTOM PLATE ATTACHMENT TO WOOD BELOW (g), (i)	ANCHOR BOLT SILL PLATE ATTACHMENT TO CONCRETE BELOW (h)	CAPACITY (PLF) SEISMIC/WIND
W1	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/4" LSL	8d@6" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 20" O.C. OR A35 @ 16" O.C.	(1) 16d @ 8" O.C.	3/8" @ 48" O.C.	242/339
W2	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/4" LSL	8d@4" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 14" O.C. OR A35 @ 11" O.C.	(1) 16d @ 6" O.C.	3/8" @ 36" O.C.	353/495
W3	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/4" LSL	8d@3" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 11" O.C. OR A35 @ 8" O.C.	(1) 16d @ 4" O.C.	3/8" @ 24" O.C.	456/637
W4 (a)	OSB	7/16 (j)	1 3/8	3x	3x OR 1 3/4" LSL	8d@2" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 8" O.C. OR A35 @ 6" O.C.	(2) 16d @ 6" O.C.	3/8" @ 24" O.C.	595/832

- (a) FRAMING AT ADJACENT PANELS SHALL BE 3" NOMINAL OR GREATER AND NAILS SHALL BE STAGGERED.
 (b) WHERE SHEATHING IS APPLIED ON BOTH SIDES OF WALL, PANEL EDGE JOINTS ON 2x FRAMING SHALL BE STAGGERED SO THAT JOINTS ON THE OPPOSITE SIDE ARE NOT LOCATED ON THE SAME STUDS.
 (c) BLOCKING IS REQUIRED AT ALL PANEL EDGES.
 (d) PROVIDE SHEAR WALL SHEATHING AND NAILING FOR THE ENTIRE LENGTH OF THE WALLS INDICATED ON THE PLANS. ENDS OF FULL HEIGHT WALLS ARE DESIGNATED BY EXTERIOR OF THE BUILDING, CORRIDORS, WINDOW, OR DOORWAYS OR AS DESIGNATED ON THE PLANS. SEE PLANS FOR HOLD DOWN POSTS. SHEATHING EDGE NAILING IS REQUIRED AT ALL HOLD DOWN POSTS. EDGE NAILING MAY ALSO BE REQUIRED TO EACH STUD USED IN BUILT-UP HOLD DOWN POSTS.
 (e) BASED ON 0.131X 1 1/4" LONG NAILS USED TO ATTACH FRAMING CLIPS DIRECTLY TO FRAMING. USE 0.131X 2 1/2" NAILS WHERE INSTALLED OVER SHEATHING. USE A35 OR RBC CLIPS IN LIEU OF LTP'S FOR ROOF BLOCKING TO TOP PLATE.
 (f) LTP4'S ARE NOT REQUIRED WHERE THE LOWER WALL SHEATHING IS OVERLAPPED ONTO THE RIM JOIST A MINIMUM OF 1 1/2" AND NAILED TO THE RIM JOIST PER THE SHEAR WALL PERIMETER NAIL SPACING. LTP4'S MAY BE SUBSTITUTED W/ A35'S.
 (g) CONTINUOUS SHEATHING IS REQUIRED OVER THE BOTTOM PLATE TO THE BOTTOM OF THE RIM JOIST OR SILL PLATE WITH EDGE NAILING AT EACH. WHERE TWO ROWS OF NAILING ARE REQUIRED AT RAISED FLOORS, PROVIDE BLOCKING PER PLAN, AND ATTACH WITH LTP4 PER SCHEDULE.
 (h) ANCHOR BOLTS SHALL BE PROVIDED WITH STEEL PLATE WASHERS 0.229"x3"x3". EMBED ANCHOR BOLTS MINIMUM 7" INTO THE CONCRETE. PLATE WASHERS SHALL EXTEND TO WITHIN 1" OF THE SILL PLATE EDGE ON THE SHEATHED WALL FACE.
 (i) PRESSURE TREATED MATERIALS CAN CAUSE EXCESSIVE CORROSION IN THE FASTENERS. PROVIDE HOT-DIPPED GALVANIZED (ELECTROPLATING IS NOT ACCEPTABLE) NAILS AND CONNECTOR PLATES (FRAMING ANGLES, ETC.) FOR ALL CONNECTORS IN CONTACT WITH PRESSURE TREATED FRAMING MEMBERS.
 (j) ALL SHEAR WALL STUDS MUST BE SPACED NO MORE THAN 16" O.C.
 (k) 3x MEMBERS MAY BE SUBSTITUTED WITH 2 STUDS NAILED TOGETHER PER TYPICAL BUILT-UP COLUMN DETAIL (SEE DETAILS).

REVISIONS

NO.	DESCRIPTION
01	---


DRAWN BY: CP
 CHECKED BY: CP
 DATE: 2024.01.12
 TITLE: SHEAR WALL PLAN
 PROJECT #: ---
 SHEET:

S3.6



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3728 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGN AND CONSTRUCTION DETAILS ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF PIERUCCIONI E&C, LLC.



STRAP SCHEDULE

SIMPSON PRODUCT	FASTENERS		END LENGTH
	SCREWS OR BOLTS	NAILS	
MST60	--	(46) 16d INTO 2 STUDS	--
MST72	--	(62) 16d INTO 2 STUDS	--
CMST12	--	(84) 10d INTO 2 STUDS	38"

THRU FLOOR HOLD DOWN SCHEDULE

SIMPSON PRODUCT	FASTENERS		ANCHOR BOLTS
	SCREWS OR BOLTS	NAILS	
(2) HDU8-SDS2.5	(20) 1/4" X 2 1/2" SDS INTO POST PER PLAN	--	5/8" THREADED ROD

(a) THESE HOLD DOWNS ARE THRU FLOOR HOLD DOWN. TOTAL OF 2 HOLD DOWNS ARE REQUIRED (SEE DETAIL 2/S4.2).

SHEAR WALL AND ANCHOR TABLE

WALL TYPE	APA RATED SHEATHING (b), (c)	MINIMUM NOMINAL THICKNESS (IN) (j)	MINIMUM NAIL PENETRATION IN FRAMING (IN) (i)	STUD & BLOCKING SIZE @ ADJOINING EDGES (k)	REQUIRED RIM JOIST THICKNESS	EDGE NAIL SIZE AND SPACING, COMMON OR GALV. BOX (d)	RIM JOIST OR BLOCK CONNECTION TO TOP PLATE (e), (f)	2x BOTTOM PLATE ATTACHMENT TO WOOD BELOW (g), (l)	ANCHOR BOLT SILL PLATE ATTACHMENT TO CONCRETE BELOW (h)	CAPACITY (PLF) SEISMIC/WIND
W1	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/2" LSL	8d @ 6" O.C. EDGE 8d @ 12" O.C. FIELD	LTP4 @ 20" O.C. OR A35 @ 16" O.C.	(1) 16d @ 8" O.C.	5/8" @ 48" O.C.	242/339
W2	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/2" LSL	8d @ 4" O.C. EDGE 8d @ 12" O.C. FIELD	LTP4 @ 14" O.C. OR A35 @ 11" O.C.	(1) 16d @ 6" O.C.	5/8" @ 36" O.C.	353/495
W3	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/2" LSL	8d @ 3" O.C. EDGE 8d @ 12" O.C. FIELD	LTP4 @ 11" O.C. OR A35 @ 8" O.C.	(1) 16d @ 4" O.C.	5/8" @ 24" O.C.	456/637

- FRAMING AT ADJACENT PANELS SHALL BE 3" NOMINAL OR GREATER AND NAILS SHALL BE STAGGERED.
- WHERE SHEATHING IS APPLIED ON BOTH SIDES OF WALL, PANEL EDGE JOINTS ON 2x FRAMING SHALL BE STAGGERED SO THAT JOINTS ON THE OPPOSITE SIDE ARE NOT LOCATED ON THE SAME STUDS.
- BLOCKING IS REQUIRED AT ALL PANEL EDGES.
- PROVIDE SHEAR WALL SHEATHING AND NAILING FOR THE ENTIRE LENGTH OF THE WALLS INDICATED ON THE PLANS. ENDS OF FULL HEIGHT WALLS ARE DESIGNATED BY EXTERIOR OF THE BUILDING, CORRIDORS, WINDOW, OR DOORWAYS OR AS DESIGNATED ON THE PLANS. SEE PLANS FOR HOLD DOWN POSTS. SHEATHING EDGE NAILING IS REQUIRED AT ALL HOLD DOWN POSTS. EDGE NAILING MAY ALSO BE REQUIRED TO EACH STUD USED IN BUILT-UP HOLD DOWN POSTS.
- BASED ON 0.131X 1 1/2" LONG NAILS USED TO ATTACH FRAMING CLIPS DIRECTLY TO FRAMING. USE 0.131X 2 1/2" NAILS WHERE INSTALLED OVER SHEATHING. USE A35 OR RBC CLIPS IN LIEU OF LTP'S FOR ROOF BLOCKING TO TOP PLATE.
- LTP4'S ARE NOT REQUIRED WHERE THE LOWER WALL SHEATHING IS OVERLAPPED ONTO THE RIM JOIST A MINIMUM OF 1 1/2" AND NAILED TO THE RIM JOIST PER THE SHEAR WALL PERIMETER NAIL SPACING. LTP4'S MAY BE SUBSTITUTED W/ A35'S.
- CONTINUOUS SHEATHING IS REQUIRED OVER THE BOTTOM PLATE TO THE BOTTOM OF THE RIM JOIST OR SILL PLATE WITH EDGE NAILING AT EACH. WHERE TWO ROWS OF NAILING ARE REQUIRED AT RAISED FLOORS, PROVIDE BLOCKING PER PLAN, AND ATTACH WITH LTP4 PER SCHEDULE.
- ANCHOR BOLTS SHALL BE PROVIDED WITH STEEL PLATE WASHERS 0.229"x3"x3". EMBED ANCHOR BOLTS MINIMUM 7" INTO THE CONCRETE. PLATE WASHERS SHALL EXTEND TO WITHIN 1/2" OF THE SILL PLATE EDGE ON THE SHEATHED WALL FACE.
- PRESSURE TREATED MATERIALS CAN CAUSE EXCESSIVE CORROSION IN THE FASTENERS. PROVIDE HOT-DIPPED GALVANIZED (ELECTROPLATING IS NOT ACCEPTABLE) NAILS AND CONNECTOR PLATES (FRAMING ANGLES, ETC.) FOR ALL CONNECTORS IN CONTACT WITH PRESSURE TREATED FRAMING MEMBERS.
- ALL SHEAR WALL STUDS MUST BE SPACED NO MORE THAN 16" O.C.
- 3X MEMBERS MAY BE SUBSTITUTED WITH 2 STUDS NAILED TOGETHER PER TYPICAL BUILT-UP COLUMN DETAIL (SEE DETAILS).

SPECIAL INSPECTIONS ARE REQUIRED FOR SHEAR WALLS:

LEVEL 2 SHEAR WALL PLAN
1/8" = 1'-0"

- NOTES:
1. ALL EXTERIOR WALL SHALL BE SHEAR WALL TYPE W1 UNLESS NOTED OTHERWISE.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

NO.	DATE	DESCRIPTION
01	----	----

DRAWN BY: CP
CHECKED BY: CP
DATE: 2024.01.12
TITLE: SHEAR WALL PLAN
PROJECT #: ----
SHEET:


S3.7



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
378 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT HAS BEEN REPRODUCED FROM THE ORIGINAL DESIGN OF PROFESSIONAL SERVICES AND THE PROPERTY OF PIERUCCIONI E&C, LLC. IT IS THE USER'S RESPONSIBILITY TO OBTAIN THE WRITTEN PERMISSION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA



LEVEL 3 SHEAR WALL PLAN
1/8" = 1'-0"

- NOTES:
1. ALL EXTERIOR WALL SHALL BE SHEAR WALL TYPE W1 UNLESS NOTED OTHERWISE.

STRAP SCHEDULE

SIMPSON PRODUCT	FASTENERS		END LENGTH
	SCREWS OR BOLTS	NAILS	
MST37	--	(22) 16d INTO 2 STUDS	--
MST48	--	(34) 16d INTO 2 STUDS	--

THRU FLOOR HOLD DOWN SCHEDULE

SIMPSON PRODUCT	FASTENERS		ANCHOR BOLTS
	SCREWS OR BOLTS	NAILS	
(2) HDU2-SDS2.5 (a)	(6) 1/4" X 2 1/2" SDS INTO POST PER PLAN	--	5/8" TREADED ROD
(2) HDU4-SDS2.5 (a)	(10) 1/4" X 2 1/2" SDS INTO POST PER PLAN	--	5/8" TREADED ROD

(a) THESE HOLD DOWNS ARE THRU FLOOR HOLD DOWN. TOTAL OF 2 HOLD DOWNS ARE REQUIRED (SEE DETAIL 2/S4.2).

SHEAR WALL AND ANCHOR TABLE

WALL TYPE	APA RATED SHEATHING (b), (c)	MINIMUM NOMINAL THICKNESS (IN) (j)	MINIMUM NAIL PENETRATION IN FRAMING (IN) (i)	STUD & BLOCKING SIZE @ ADJOINING EDGES (k)	REQUIRED RIM JOIST THICKNESS	EDGE NAIL SIZE AND SPACING, COMMON OR GALV. BOX (d)	RIM JOIST OR BLOCK CONNECTION TO TOP PLATE (e), (f)	2x BOTTOM PLATE ATTACHMENT TO WOOD BELOW (g), (i)	ANCHOR BOLT SILL PLATE ATTACHMENT TO CONCRETE BELOW (h)	CAPACITY (PLF) SEISMIC/WIND
W1	OSB	7/16 (j)	1 3/8	2x	2x OR 1 1/4" LSL	8d@6" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 20" O.C. OR A35 @ 16" O.C.	(1) 16d @ 8" O.C.	5/8" @ 48" O.C.	242/339

FRAMING AT ADJACENT PANELS SHALL BE 3" NOMINAL OR GREATER AND NAILS SHALL BE STAGGERED. WHERE SHEATHING IS APPLIED ON BOTH SIDES OF WALL, PANEL EDGE JOINTS ON 2x FRAMING SHALL BE STAGGERED SO THAT JOINTS ON THE OPPOSITE SIDE ARE NOT LOCATED ON THE SAME STUDS.
BLOCKING IS REQUIRED AT ALL PANEL EDGES
PROVIDE SHEAR WALL SHEATHING AND NAILING FOR THE ENTIRE LENGTH OF THE WALLS INDICATED ON THE PLANS. ENDS OF FULL HEIGHT WALLS ARE DESIGNATED BY EXTERIOR OF THE BUILDING, CORRIDORS, WINDOW, OR DOORWAYS OR AS DESIGNATED ON THE PLANS. SEE PLANS FOR HOLD DOWN POSTS. SHEATHING EDGE NAILING IS REQUIRED AT ALL HOLD DOWN POSTS. EDGE NAILING MAY ALSO BE REQUIRED TO EACH STUD USED IN BUILT-UP HOLD DOWN POSTS.
BASED ON 0.131X 1 1/4" LONG NAILS USED TO ATTACH FRAMING CLIPS DIRECTLY TO FRAMING. USE 0.131X 2 1/2" NAILS WHERE INSTALLED OVER SHEATHING. USE A35 OR RBC CLIPS IN LIEU OF LTP'S FOR ROOF BLOCKING TO TOP PLATE.
LTP4'S ARE NOT REQUIRED WHERE THE LOWER WALL SHEATHING IS OVERLAPPED ONTO THE RIM JOIST A MINIMUM OF 1 1/4" AND NAILED TO THE RIM JOIST PER THE SHEAR WALL PERIMETER NAIL SPACING. LTP4'S MAY BE SUBSTITUTED W/ A35'S.
CONTINUOUS SHEATHING IS REQUIRED OVER THE BOTTOM PLATE TO THE BOTTOM OF THE RIM JOIST OR SILL PLATE WITH EDGE NAILING AT EACH. WHERE TWO ROWS OF NAILING ARE REQUIRED AT RAISED FLOORS, PROVIDE BLOCKING PER PLAN, AND ATTACH WITH LTP4 PER SCHEDULE.
ANCHOR BOLTS SHALL BE PROVIDED WITH STEEL PLATE WASHERS 0.229"x3"x3". EMBED ANCHOR BOLTS MINIMUM 7" INTO THE CONCRETE. PLATE WASHERS SHALL EXTEND TO WITHIN 1/2" OF THE SILL PLATE EDGE ON THE SHEATHED WALL FACE.
PRESSURE TREATED MATERIALS CAN CAUSE EXCESSIVE CORROSION IN THE FASTENERS. PROVIDE HOT-DIPPED GALVANIZED (ELECTROPLATING IS NOT ACCEPTABLE) NAILS AND CONNECTOR PLATES (FRAMING ANGLES, ETC.) FOR ALL CONNECTORS IN CONTACT WITH PRESSURE TREATED FRAMING MEMBERS.
ALL SHEAR WALL STUDS MUST BE SPACED NO MORE THAN 16" O.C.
3X MEMBERS MAY BE SUBSTITUTED WITH 2 STUDS NAILED TOGETHER PER TYPICAL BUILT-UP COLUMN DETAIL. (SEE DETAILS).

REVISIONS

01

REVISIONS

DRAWN BY: CP

CHECKED BY: CP

DATE: 2024.01.12

TITLE: SHEAR WALL PLAN

PROJECT #: ---


SHEET:



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3720 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGN AND CONTENTS THEREOF ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA



UPPER ROOF SHEAR WALL PLAN
1/8" = 1'-0"

NOTES:
1. ALL EXTERIOR WALL SHALL BE SHEAR WALL TYPE W1 UNLESS NOTED OTHERWISE.

SHEAR WALL AND ANCHOR TABLE

WALL TYPE	APA RATED SHEATHING (b), (c)	MINIMUM NOMINAL THICKNESS (IN) (f)	MINIMUM NAIL PENETRATION IN FRAMING (IN) (i)	STUD & BLOCKING SIZE @ ADJOINING EDGES (k)	REQUIRED RIM JOIST THICKNESS	EDGE NAIL SIZE AND SPACING, COMMON OR GALV. BOX (d)	RIM JOIST OR BLOCK CONNECTION TO TOP PLATE (e), (f)	2x BOTTOM PLATE ATTACHMENT TO WOOD BELOW (g), (i)	ANCHOR BOLT SILL PLATE ATTACHMENT TO CONCRETE BELOW (h)	CAPACITY (PLF) SEISMIC/WIND (j)
W1	OSB	7/16 (f)	1 3/8	2x	2x OR 1 1/4" LSL	8d@6" O.C. EDGE 8d@12" O.C. FIELD	LTP4 @ 20" O.C. OR A35 @ 16" O.C.	(1) 16d @ 8" O.C.	5/8" @ 48" O.C.	242/339

- (a) FRAMING AT ADJACENT PANELS SHALL BE 3" NOMINAL OR GREATER AND NAILS SHALL BE STAGGERED.
- (b) WHERE SHEATHING IS APPLIED ON BOTH SIDES OF WALL, PANEL EDGE JOINTS ON 2x FRAMING SHALL BE STAGGERED SO THAT JOINTS ON THE OPPOSITE SIDE ARE NOT LOCATED ON THE SAME STUDS.
- (c) BLOCKING IS REQUIRED AT ALL PANEL EDGES
- (d) PROVIDE SHEAR WALL SHEATHING AND NAILING FOR THE ENTIRE LENGTH OF THE WALLS INDICATED ON THE PLANS. ENDS OF FULL HEIGHT WALLS ARE DESIGNATED BY EXTERIOR OF THE BUILDING, CORRIDORS, WINDOW, OR DOORWAYS OR AS DESIGNATED ON THE PLANS. SEE PLANS FOR HOLD DOWN POSTS. SHEATHING EDGE NAILING IS REQUIRED AT ALL HOLD DOWN POSTS. EDGE NAILING MAY ALSO BE REQUIRED TO EACH STUD USED IN BUILT-UP HOLD DOWN POSTS.
- (e) BASED ON 0.131x 1 1/4" LONG NAILS USED TO ATTACH FRAMING CLIPS DIRECTLY TO FRAMING. USE 0.131x 2 1/2" NAILS WHERE INSTALLED OVER SHEATHING. USE A35 OR RBC CLIPS IN LIEU OF LTP'S FOR ROOF BLOCKING TO TOP PLATE.
- (f) LTP4'S ARE NOT REQUIRED WHERE THE LOWER WALL SHEATHING IS OVERLAPPED ONTO THE RIM JOIST A MINIMUM OF 1 1/2" AND NAILED TO THE RIM JOIST PER THE SHEAR WALL PERIMETER NAIL SPACING. LTP4'S MAY BE SUBSTITUTED W/ A35'S.
- (g) CONTINUOUS SHEATHING IS REQUIRED OVER THE BOTTOM PLATE TO THE BOTTOM OF THE RIM JOIST OR SILL PLATE WITH EDGE NAILING AT EACH. WHERE TWO ROWS OF NAILING ARE REQUIRED AT RAISED FLOORS, PROVIDE BLOCKING PER PLAN, AND ATTACH WITH LTP4 PER SCHEDULE.
- (h) ANCHOR BOLTS SHALL BE PROVIDED WITH STEEL PLATE WASHERS 0.229"x3"x3". EMBED ANCHOR BOLTS MINIMUM 7" INTO THE CONCRETE. PLATE WASHERS SHALL EXTEND TO WITHIN 1/2" OF THE SILL PLATE EDGE ON THE SHEATHED WALL FACE.
- (i) PRESSURE TREATED MATERIALS CAN CAUSE EXCESSIVE CORROSION IN THE FASTENERS. PROVIDE HOT-DIPPED GALVANIZED (ELECTROPLATING IS NOT ACCEPTABLE) NAILS AND CONNECTOR PLATES (FRAMING ANGLES, ETC.) FOR ALL CONNECTORS IN CONTACT WITH PRESSURE TREATED FRAMING MEMBERS.
- (j) ALL SHEAR WALL STUDS MUST BE SPACED NO MORE THAN 16" O.C.
- (k) 3x MEMBERS MAY BE SUBSTITUTED WITH 2 STUDS NAILED TOGETHER PER TYPICAL BUILT-UP COLUMN DETAIL (SEE DETAILS).

REVISIONS

01	---
----	-----

REVISIONS

DRAWN BY:	CP
CHECKED BY:	CP
DATE:	2024.01.12
TITLE:	SHEAR WALL PLAN
PROJECT #:	---
SHEET:	



PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3720 N. BENNETT ST.
TACOMA, WA 98407

REUSE OF DOCUMENTS
THIS DOCUMENT AND THE DESIGNATIONS OF PROFESSIONAL LICENSE ARE THE PROPERTY OF PIERUCCIONI E&C, LLC AND ARE NOT TO BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

01	---
----	-----

REVISIONS

DRAWN BY: CP

CHECKED BY: CP


DATE: 2024.01.12

TITLE: FOUNDATION DETAILS

PROJECT #: ---

SHEET:

S4.1





PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3701 N. BENNETT ST.
TACOMA, WA 98407

RELEASE OF DOCUMENTS
THIS DOCUMENT IS THE SOLE PROPERTY OF
PIERUCCIONI E&C, LLC. THE PROPERTY OF
ANY OTHER PARTY IS HEREBY DENIED. THE USE OF
THIS DOCUMENT IN WHOLE OR IN PART WITHOUT THE
WRITTEN AUTHORIZATION OF PIERUCCIONI E&C, LLC IS
PROHIBITED.

EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

REVISIONS

01

REVISIONS

DRAWN BY: CP

CHECKED BY: CP
















DATE: 2024.01.12


TITLE: FRAMING DETAILS

PROJECT #: ----

SHEET:

S4.2





EAST TOWN CROSSING
BUILDING "E"
PIONEER & SHAW PUYALLUP WA

PIERUCCIONI E&C, LLC
CHON PIERUCCIONI, PE
3120 N. BENNETT ST.
TACOMA, WA 98407

REVISIONS

NO.	DATE	DESCRIPTION
01	---	---

REVISIONS

DRAWN BY: CP
CHECKED BY: CP
DATE: 2024.01.12
TITLE: FRAMING DETAILS
PROJECT #: ---
SHEET:

S4.3

ENERGY CODE NOTES

WSEC SECTION R406: ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS

EACH DWELLING UNIT IN A RESIDENTIAL BUILDING SHALL COMPLY WITH SUFFICIENT CREDIT OPTIONS FROM SECTION R406. CREDIT FROM BOTH SECTIONS R406.2 AND R406.3 ARE REQUIRED:

- #1. SMALL DWELLING UNIT: 3.0 CREDITS
DWELLING UNITS LESS THAN 1500 SQUARE FEET IN CONDITIONED FLOOR AREA WITH LESS THAN 300 SQUARE FEET OF FENESTRATION AREA. ADDITIONS TO EXISTING BUILDING THAT ARE GREATER THAN 500 SQUARE FEET OF HEATED FLOOR AREA BUT LESS THAN 1500 SQUARE FEET.
- #2. MEDIUM DWELLING UNIT: 6.0 CREDITS
ALL DWELLING UNITS THAT ARE NOT INCLUDED IN #1, #3 OR #4.
- #3. LARGE DWELLING UNIT: 7.0 CREDITS
DWELLING UNITS EXCEEDING 5000 SQUARE FEET OF CONDITIONED FLOOR AREA.
- #4. DWELLING UNITS SERVING R-2 OCCUPANCIES: 4.5 CREDITS
- #5. ADDITIONS LESS THAN 500 SQUARE FEET: 1.5 CREDITS

TABLE R406.2 FUEL NORMALIZATION CREDITS

SYSTEM TYPE	DESCRIPTION	CREDITS	CREDIT TAKEN
1	COMBUSTION HEATING EQUIPMENT MEETING MINIMUM FEDERAL EFFICIENCY STANDARDS FOR THE EQUIPMENT LISTED IN TABLE C403.3.2(4) OR C403.3.2(5)	0.0	-
2	FOR AN INITIAL HEATING SYSTEM USING A HEAT PUMP THAT MEETS FEDERAL STANDARDS FOR EQUIPMENT LISTED IN TABLE C403.3.2(2)(C) OR C403.3.2(2) OR AIR TO WATER HEAT PUMP UNITS THAT ARE CONFIGURED TO PROVIDE BOTH HEATING AND COOLING AND ARE RATED IN ACCORDANCE WITH AHRI 550 / 590	1.0	1.0
3	FOR HEATING SYSTEM BASED ON ELECTRIC RESISTANCE ONLY (EITHER FORCED AIR OR ZONAL)	-1.0	-
4	FOR HEATING SYSTEM BASED ON ELECTRIC RESISTANCE WITH A DUCTLESS MINI-SPLIT HEAT PUMP SYSTEM IN ACCORDANCE WITH SECTION R403.7.1 INCLUDING THE EXCEPTION	N/A	-
5	ALL OTHER HEATING SYSTEMS	-1.0	-
TOTAL CREDITS			1.0

TABLE R406.3 ENERGY CREDITS

OPTION	DESCRIPTION	CREDITS	CREDIT TAKEN
EFFICIENT BUILDING ENVELOPE OPTIONS			
1	OPTION 1.1	0.5	-
	OPTION 1.2	1.0	-
	OPTION 1.3	N/A	-
	OPTION 1.4	1.0	-
	OPTION 1.5	1.5	-
	OPTION 1.6	2.0	-
	OPTION 1.7	0.5	-
AIR LEAKAGE CONTROL AND EFFICIENT VENTILATION OPTIONS			
2	OPTION 2.1	1.0	-
	OPTION 2.2	1.5	-
	OPTION 2.3	2.0	-
	OPTION 2.4	2.5	-
HIGH EFFICIENCY HVAC EQUIPMENT OPTIONS			
3	OPTION 3.1	1.0	-
	OPTION 3.2	N/A	-
	OPTION 3.3	1.0	-
	OPTION 3.4	2.0	-
	OPTION 3.5	N/A	-
	OPTION 3.6	3.0	3.0
HIGH EFFICIENCY HVAC DISTRIBUTION SYSTEM OPTIONS			
4	OPTION 4.1	0.5	-
	OPTION 4.2	N/A	-
EFFICIENT WATER HEATING OPTIONS			
5	OPTION 5.1	0.5	-
	OPTION 5.2	0.5	-
	OPTION 5.3	1.0	-
	OPTION 5.4	2.0	-
	OPTION 5.5	2.5	2.5
	OPTION 5.6	3.0	-
RENEWABLE ELECTRIC ENERGY OPTION			
6	OPTION 6.1	1.0	-
	APPLIANCE PACKAGE OPTION		
7	OPTION 7.1	1.5	-
	TOTAL CREDITS FROM TABLE R406.3		
TOTAL CREDITS FROM TABLE R406.2			1.0
TOTAL CREDITS			6.5

WHOLE HOUSE VENTILATION NOTES

EACH DWELLING UNIT OR SLEEPING UNIT SHALL BE EQUIPPED WITH A WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM THAT COMPLIES WITH SECTIONS 403.4.1 THROUGH 403.4.6. EACH DWELLING UNIT OR SLEEPING UNIT SHALL BE EQUIPPED WITH LOCAL EXHAUST COMPLYING WITH SECTION 403.4.7. ALL OCCUPIED SPACES, INCLUDING PUBLIC CORRIDORS, OTHER THAN GROUP R DWELLING UNITS AND/OR SLEEPING UNITS, THAT SUPPORT THESE GROUP R OCCUPANCIES, SHALL MEET THE VENTILATION REQUIREMENTS OF SECTION 402 OR THE MECHANICAL VENTILATION REQUIREMENTS OF SECTIONS 403.1 THROUGH 403.3.

THE WHOLE HOUSE VENTILATION SYSTEM SHALL CONSIST OF ONE OR MORE SUPPLY FANS, ONE OR MORE EXHAUST FANS, OR AN ERV/HRV WITH INTEGRAL FANS; AND THE ASSOCIATED DUCTS AND CONTROLS. LOCAL EXHAUST FANS SHALL BE PERMITTED TO SERVE AS PART OF THE WHOLE-HOUSE VENTILATION SYSTEM WHEN PROVIDED WITH THE PROPER CONTROLS IN ACCORDANCE WITH SECTION 403.4.5. THE SYSTEMS SHALL BE DESIGNED AND INSTALLED TO SUPPLY AND EXHAUST THE MINIMUM OUTDOOR AIRFLOW RATES PER SECTION 403.4.2 AS CORRECTED BY THE BALANCED AND/OR DISTRIBUTED WHOLE-HOUSE VENTILATION SYSTEM COEFFICIENTS IN ACCORDANCE WITH SECTION 403.4.3 WHERE APPLICABLE.

THE DWELLING UNIT WHOLE-HOUSE MECHANICAL VENTILATION MINIMUM OUTDOOR AIRFLOW RATE SHALL BE DETERMINED IN ACCORDANCE WITH EQUATION 4-10 OR TABLE 403.4.2.

RESIDENTIAL DWELLING AND SLEEPING UNITS IN GROUP R-2 OCCUPANCIES SYSTEM SHALL INCLUDE SUPPLY AND EXHAUST FANS AND BE A BALANCED WHOLE-HOUSE VENTILATION SYSTEM IN ACCORDANCE WITH SECTION 403.4.6.3. THE SYSTEM SHALL INCLUDE A HEAT OR ENERGY RECOVERY VENTILATOR WITH A SENSIBLE HEAT RECOVERY EFFECTIVENESS AS PRESCRIBED IN SECTION C403.3.6 OF THE WASHINGTON STATE ENERGY CODE. THE WHOLE-HOUSE VENTILATION SYSTEM SHALL OPERATE CONTINUOUSLY AT THE MINIMUM VENTILATION RATE DETERMINED IN ACCORDANCE WITH SECTION 403.4. THE WHOLE-HOUSE SUPPLY FAN SHALL PROVIDE DUCTED OUTDOOR VENTILATION AIR TO EACH HABITABLE SPACE WITHIN THE RESIDENTIAL UNIT.

CONTROLS FOR THE WHOLE-HOUSE VENTILATION SYSTEM SHALL COMPLY WITH THE FOLLOWING:

- THE WHOLE-HOUSE VENTILATION SYSTEM SHALL BE CONTROLLED WITH MANUAL SWITCHES, TIMERS OR OTHER MEANS THAT PROVIDE FOR AUTOMATIC OPERATION OF THE VENTILATION SYSTEM THAT HAVE READY ACCESS FOR THE OCCUPANT.
- THE WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM SHALL BE PROVIDED WITH CONTROLS THAT ENABLE MANUAL OVERRIDE OFF OF THE SYSTEM BY THE OCCUPANT DURING PERIODS OF POOR OUTDOOR AIR QUALITY. CONTROLS SHALL INCLUDE PERMANENT TEXT OR A SYMBOL INDICATING THEIR FUNCTION. RECOMMENDED CONTROL PERMANENT LABELING TO INCLUDE TEXT SIMILAR TO THE FOLLOWING; "LEAVE ON UNLESS OUTDOOR AIR QUALITY IS VERY POOR." MANUAL CONTROLS SHALL HAVE READY ACCESS FOR THE OCCUPANT.
- WHOLE-HOUSE VENTILATION SYSTEMS SHALL BE CONFIGURED TO OPERATE CONTINUOUSLY EXCEPT WHERE INTERMITTENT OFF CONTROLS ARE PROVIDED IN ACCORDANCE WITH SECTION 403.4.6.5 AND ALLOWED BY SECTION 403.4.4.2.

WHOLE HOUSE VENTILATION SUPPLY AND EXHAUST FANS SPECIFIED IN THIS SECTION SHALL HAVE A MINIMUM EFFICACY AS PRESCRIBED IN THE WASHINGTON STATE ENERGY CODE. THE FANS SHALL BE RATED FOR SOUND AT A MAXIMUM OF 1.0 SOME AT DESIGN AIRFLOW AND STATIC PRESSURE CONDITIONS. DESIGN AND INSTALLATION OF THE SYSTEM OR EQUIPMENT SHALL BE CARRIED OUT IN ACCORDANCE WITH MANUFACTURERS' INSTALLATION INSTRUCTIONS

A BALANCED WHOLE HOUSE VENTILATION SYSTEM SHALL INCLUDE BOTH SUPPLY AND EXHAUST FANS. THE SUPPLY AND EXHAUST FANS SHALL HAVE AIRFLOW THAT IS WITHIN 10 PERCENT OF EACH OTHER. THE TESTED AND BALANCED TOTAL MECHANICAL EXHAUST AIRFLOW RATE IS WITHIN 10 PERCENT OR 5 CFM, WHICHEVER IS GREATER, OF THE TOTAL MECHANICAL SUPPLY AIRFLOW RATE. THE FLOW RATE TEST RESULTS SHALL BE SUBMITTED AND POSTED IN ACCORDANCE WITH SECTION 403.4.6.6. THE EXHAUST FAN SHALL MEET THE REQUIREMENTS OF SECTION 403.4.6.2. THE SUPPLY FAN SHALL MEET THE REQUIREMENTS OF SECTION 403.4.6.3. FOR R-2 DWELLING AND SLEEPING UNITS, THE SYSTEM IS REQUIRED TO HAVE BALANCED WHOLE-HOUSE VENTILATION BUT IS NOT REQUIRED TO HAVE DISTRIBUTED WHOLE-HOUSE VENTILATION WHERE THE NOT DISTRIBUTED SYSTEM COEFFICIENT FROM TABLE 403.4.3 IS UTILIZED TO CORRECT THE WHOLE-HOUSE MECHANICAL VENTILATION RATE. THE SYSTEM SHALL BE DESIGNED AND BALANCED TO MEET THE PRESSURE EQUALIZATION REQUIREMENTS OF SECTION 501.4. INTERMITTENT DRYER EXHAUST, INTERMITTENT RANGE HOOD EXHAUST, AND INTERMITTENT TOILET ROOM EXHAUST AIRFLOW RATES ABOVE THE RESIDENTIAL DWELLING OR SLEEPING UNIT MINIMUM VENTILATION RATE ARE EXEMPT FROM THE BALANCED AIRFLOW CALCULATION.

FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATIONS


PER 2018 IMC 401.4.3, ITEM 3, EXCEPTION, SEPARATION IS NOT REQUIRED BETWEEN INTAKE AIR OPENINGS AND LIVING SPACE RELIEF AIR EXHAUST AIR OPENINGS OF AN INDIVIDUAL DWELLING UNIT OR SLEEPING UNIT, NOT TO INCLUDE COMMON AREAS OUTSIDE OF THE DWELLING OR SLEEPING UNIT, WHERE A FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATION FITTING, LISTED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, IS USED TO SEPARATE THE AIR STREAMS. A MINIMUM OF 5 FEET HORIZONTAL SEPARATION BETWEEN OTHER ENVIRONMENTAL AIR EXHAUST OUTLETS AND OTHER DWELLING OR SLEEPING UNIT FACTORY-BUILT INTAKE/EXHAUST COMBINATION TERMINATION FITTINGS SHALL BE MAINTAINED.

CALCULATIONS

RESIDENTIAL VENTILATION CALCULATIONS						
UNIT TYPE	UNIT SQUARE FOOTAGE PER ARCHITECTURAL PLANS	NUMBER OF BEDROOMS	2015 IMC CRITERIA (1)			TOTAL CFM PROVIDED BY WHOLE HOUSE VENTILATION SYSTEM
			FLOOR AREA, SQFT	NUMBER OF BEDROOMS	REQUIRED CFM (2)	
11-3/21-3	634	1	501-1,000	0-1	30	50
11-7/21-9/31-9	659	1	501-1,000	0-1	30	50
11-8/21-4/31-4	679	2	501-1,000	2	35	50
21-2/31-2	958	2	501-1,000	2	35	50
12-1	1,021	2	1,001-1,500	2	40	50
12-3	1,000	2	501-1,000	2	35	50
12-5	957	2	501-1,000	2	35	50
22-1/32-1	1,022	2	1,001-1,500	2	40	50
22-2/32-2	958	2	501-1,000	2	35	50
22-5/32-5	958	2	501-1,000	2	35	50
22-6/32-6	1,000	2	501-1,000	2	35	50
31-3	645	1	501-1,000	0-1	30	50

NOTE: (1) VENTILATION CRITERIA IS PER THE 2018 IRC, TABLE 1505.4.3(1).
(2) MINIMUM OSA FOR CONTINUOUSLY OPERATING FAN(S).

NO.	DATE	DESCRIPTION



DRAWN: OP	DESIGNED: ABE	CHECKED: PR	APPROVED: JMR
-----------	---------------	-------------	---------------

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343
REPROJECT NO.: 810010
CONTACT: ARK@ESPINELI

DATE:
3/8/2024

SHEET TITLE:
TABLES & CALCULATIONS

SHEET NO.
M0.2

SCHEDULES

ENERGY RECOVERY VENTILATOR

EQUIP NO.	SERVICE	MOUNTING/ DISCHARGE	FAN		ELECTRICAL			SENSIBLE HEAT RECOVERY EFFICIENCY	BASIS OF DESIGN (1)(2)(3)
			AIRFLOW, CFM	ESP. IN WG	VOLTAGE	AMPS	MOCP		
ERV-1	RESIDENTIAL UNIT	HORIZONTAL	PER PLANS	0.4	120V/1P	1.1	15	0.69	ALDES E130-HF-N (4)
ERV-2	RESIDENTIAL UNIT	HORIZONTAL	PER PLANS	0.4	120V/1P	1.1	15	0.69	ALDES E130-HF-N-M (4)

- NOTES:
- (1) INSTALL IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION REQUIREMENTS.
 - (2) UNIT SHALL RUN CONTINUOUSLY.
 - (3) UNIT SHALL HAVE A MINIMUM MERV 8 FILTER.
 - (4) PROVIDE MANUFACTURER'S OPTIONAL WALL MOUNT SPEED CONTROLLER, PART NUMBER 611229. SPEED CONTROLLER SHALL BE MOUNTED NEXT TO THE LIGHT SWITCH FOR THE BATHROOM.

FAN SCHEDULE

EQUIP NO.	SERVICE	TYPE	AIRFLOW, CFM	ESP. IN WG	ELECTRICAL		OPERATION	WEIGHT, LBS	BASIS OF DESIGN (1)
					VOLTAGE	HP			
BEF-1	BATHROOM	CEILING MOUNTED	50	0.25	115V/1P	FHP	(2)	10	PANASONIC FV-0511VQ1 (3)
TF-1	TRANSFER FAN	IN WALL	50	0.1	120V/1P	[4.4]	(5)	8.82	PANASONIC FV-0510V51 (4)
TF-2	TRANSFER FAN	CEILING MOUNTED	50	0.1	120V/1P	[4.4]	(5)	8.82	PANASONIC FV-0510V51 (4)

- NOTES:
- (1) PROVIDE BACKDRAFT DAMPERS ON EXHAUST FANS.
 - (2) FAN SHALL BE ACTIVATED VIA WALL SWITCH.
 - (3) PROVIDE MANUFACTURER'S OPTIONAL CEILING RADIATION DAMPER.
 - (4) PROVIDE TRANSFER REGISTER BOX. BOD PANASONIC FV-JD
 - (5) FAN TO BE CONTROLLED BY WALL MOUNTED THERMOSTAT.

DIFFUSER SCHEDULE

CALLOUT	DESCRIPTION	AIRFLOW RANGE, CFM	FACE SIZE, IN	BASIS OF DESIGN
HRG-1	HARD LID RETURN GRILLE	0-700	12X12	TITUS 350ZRL
SSG-1	SIDEWALL SUPPLY GRILLE	0-150	10X4	SHOEMAKER 950
HSM-1	HARD LID SUPPLY GRILLE	0-150	10X4	SHOEMAKER 950

ELECTRIC HEATERS

EQUIP NO.	SERVICE	MOUNTING/ DISCHARGE	HEATING		ELECTRICAL		BASIS OF DESIGN (3)
			KW	VOLTAGE	VOLTAGE		
EWH-0.5	PER PLANS	WALL	0.5	208V/1P	208V/1P		(1)(2)
EWH-0.75	PER PLANS	WALL	0.75	208V/1P	208V/1P		(1)(2)
EWH-1.0	PER PLANS	WALL	1.0	208V/1P	208V/1P		(1)(2)
EWH-1.5	PER PLANS	WALL	1.5	208V/1P	208V/1P		(1)(2)
EWH-2.0	PER PLANS	WALL	2.0	208V/1P	208V/1P		(1)(2)

- NOTES: (1) BROAN, KING, CADET OR EQUIVALENT.
 (2) PROVIDE INTEGRAL THERMOSTAT.
 (3) ALL ELECTRIC HEATERS TO BE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR.

SPLIT SYSTEM HEAT PUMP SCHEDULE - INDOOR UNIT

EQUIP NO.	SERVICE	MOUNTING/ DISCHARGE	FAN		ELECTRICAL			BASIS OF DESIGN (1)(2)(4)	CONNECTED OUTDOOR UNIT
			AIRFLOW, CFM	ESP. IN WG	VOLTAGE	MCA	MOCP		
FCU-X	RES. UNIT	HIGH WALL	716	N/A	(3)	(3)	(3)	DAIKIN FTXB18BXVJU	HP-1


- NOTES:
- (1) INSTALL IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION REQUIREMENTS.
 - (2) PROVIDE MANUFACTURER'S OPTIONAL CONDENSATE PUMP WITH RESERVOIR AND SENSOR.
 - (3) INDOOR UNIT POWERED FROM OUTDOOR UNIT.
 - (4) "X" DENOTES THE UNIT BEING SERVED.

SPLIT SYSTEM HEAT PUMP SCHEDULE - OUTDOOR UNIT

EQUIP NO.	SERVICE	CAPACITY, TONS	TOTAL COOLING CAPACITY, BTUH	SEER	TOTAL HEATING CAPACITY, BTUH	HSPF	ELECTRICAL			DIMENSIONS, INCHES			WEIGHT, LBS	BASIS OF DESIGN (1)(2)(3)(4)(5)(6)	CONNECTED FAN COIL UNIT
							VOLTAGE	MCA	MOCP	H	W	D			
HP-1	RES. UNIT	1.5	18,000	18.8	17,900	10.0	208V/1P	16.55	20	27 ¹¹ / ₁₆	36 ⁷ / ₈	13 ¹ / ₂	97	DAIKIN RXB18BXVJU	FCU-1

- NOTES:
- (1) INSTALL IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION REQUIREMENTS.
 - (2) ARI LISTED WITH ALL STANDARD FEATURES. INSTALLATION ACCESSORIES AND COMPRESSOR SHORT CYCLING PROTECTION, FILTER DRIVER, REFRIGERANT LINE FILTER, LIQUID SOLENOID VALVE, AND SAFETY PRESSURE SWITCHES. INSTALL REFRIGERANT TUBING AND LENGTH IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 - (3) PROVIDE ALL REQUIRED ACCESSORIES FOR LOW-AMBIENT.
 - (4) ROUTING OF REFRIGERANT LINES FROM INDOOR TO OUTDOOR UNITS NOT SHOWN ON PLANS. CONTRACTOR TO FIELD COORDINATE ROUTING.
 - (5) REFRIGERANT SHALL BE R-410A.
 - (6) "X" DENOTES THE UNIT BEING SERVED.

NO.	DATE	DESCRIPTION



DRAWN: OP	DESIGNED: ABE	CHECKED: PR	APPROVED: JMR
-----------	---------------	-------------	---------------

PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W., SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 864-3343
 RE: PROJECT NO.: 810010
 CONTACT: ARK/ESP/INELI

ROBISON ENGINEERING, INC.

DATE:
3/8/2024

SHEET TITLE:
MECHANICAL SCHEDULES

SHEET NO.
M0.3

WSEC FORMS

3/8/24, 3:14 PM waenergycodes.com/print_project_summary_form.php?k=aWQ9MjMyNDAmZnZpPTE3JmN0aT00Ng==&print=1

System/Equip ID	Area(s) Served	Location In Project Documents - Plan/Detail #
HP-1	Apartment Units	M0.3
System/Equip ID for a single or multiple items? Multiple items w/ identical heating & cooling capacity		
Heating Section/Auxiliary Heating Type: Electric resistance (or None)		
Air-side economizer exception applied: Exp 5(2) - Group R cooling units ≥ 20,000 < 54,000 Btu/h (Note equip location limitations)		
Proposed Low OSA Temp Efficiency: WSEC Equip Efficiency Reference Table - Cooling: Table C403.3.2(2) - Unitary and Applied Heat Pumps		
WSEC Equip Efficiency Reference Table - Heating: Table C403.3.2(2) - Unitary and Applied Heat Pumps		

https://waenergycodes.com/print_project_summary_form.php?k=aWQ9MjMyNDAmZnZpPTE3JmN0aT00Ng==&print=1 2/2

3/8/24, 3:14 PM waenergycodes.com/print_project_summary_form.php?k=aWQ9MjMyNDAmZnZpPTE3JmN0aT00Ng==&print=1

MECHANICAL COMPLIANCE SUMMARY			
2018 WSEC Compliance Forms for Commercial Buildings including Group R2, R3 & R4 over 3 stories and all R1 Administered by: ©2024 NEEA, All rights reserved			
Project Title		East Town Crossing Building E - 2018 WSEC	
Project Address		Pioneer & Shaw Puyallup, WA 98372	
Applicant Name		Arik Espineli	
Applicant Phone		206-364-3343	
Applicant Email		aespineli@robisonengineering.com	
For questions about this report, contact WSEC Commercial Technical Support at 360-539-5300 or via email at com.techsupport@waenergycodes.com			
General Occupancy		All Group R - R2, R3 & R4 over 3 stories and all R1	
General Building Use Type		Multifamily/Residential	
Building Cond. Floor Area		27,753	
Project Cond. Floor Area		27,753	
Floors Above Grade		3	
Compliance Method		Compliance Method 1 - General	

General Project Types	New Building	New Building or Addition Mechanical Scope	Single Zone Systems & Equipment	Alteration Mechanical Scope	Building Cond. Floor Area	Project Cond. Floor Area	Floors Above Grade	Compliance Method
					27,753	27,753	3	Compliance Method 1 - General

Mechanical Compliance Scope and Method	Project Type	Mechanical Scope	Economizer Exception(s) Applied?	DOAS Ventilation Provided?	Higher Equipment Efficiency Option Applied?	Equipment Efficiency Compliance Verification
	New Building	Single Zone Systems & Equipment	Yes	Yes	Yes	COMPLIES

Additional Efficiency Credits Included (AEC)	Higher equipment efficiency and fan FEG	Does project include DOAS equipment?	Yes
Does building include occupancy classifications requiring DOAS? Based on project scope do TSPR requirements apply?	No	Does project include DOAS equipment?	Yes
	No	Do all systems comply with Appendix D standard reference design or qualify for an exception to TSPR?	No

Scope & Space Conditioning: NEW BUILDING - SINGLE ZONE SYSTEMS & EQUIPMENT Compliance Verification: COMPLIES

Single Zone Air Systems Category - Heat pump, unitary, thru-wall, SDHV


System/Equip ID	Quantity of Items	Supply Airflow Control	Ventilation Standard	Ventilation CFM (Total if Multiple Items)	Ventilation Air Source	Paired with DOAS	Ventilation energy recovery	Energy Recovery Efficiency (%)
HP-1	36	Constant volume	IMC Ventilation		Other System		Provided but not required	69

System/Equip ID	Cooling System/Equip Type	Specific Type	Cooling Capacity per Item (Btu/h)	AEC Efficiency Multiplier	Econo Exception Multiplier (E1 & PL)	Combined Efficiency Multiplier (AEC & Econo)	Proposed Cooling Efficiency	CE Units	Proposed Part Load Efficiency	PL Units	Efficiency Compliance Verification
HP-1	Heat pump, air cooled	Split system	18,000	1.15	1.15	1.3225	18.8	SEER		HEER	COMP_PIES

System/Equip ID	Heating System/Equip Type	Specific Type	Heat Pump Heating Capacity (Btu/h)	Cooling Capacity (Btu/h)	AEC Efficiency Multiplier	Proposed Heat Pump Heating Efficiency	HSPF	Proposed Low OSA Temp Efficiency	LTH Units	Efficiency Compliance Verification
HP-1	Heat pump, air cooled, heating	Split system	17,900	18,000	1.15	10.0	HSPF		COP	COMPLIES

https://waenergycodes.com/print_project_summary_form.php?k=aWQ9MjMyNDAmZnZpPTE3JmN0aT00Ng==&print=1 1/2

NO.	DATE	DESCRIPTION



DRAWN: OP	DESIGNED: ABE	CHECKED: PR	APPROVED: JMR
-----------	---------------	-------------	---------------


PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 364-3343
RE: PROJECT NO.: 810010
CONTACT: ARIK.ESPINELI

DATE: 3/8/2024

SHEET TITLE: WSEC FORMS

SHEET NO. M0.4




LEGEND
 ○ = BUILDING NUMBER
 BLDG 2 = BUILDING TYPE
 (BUILDING TYPE "2" FOR EXAMPLE)

PHASE 2

SITE PLAN
 SCALE: 1" = 30'

NO.	DATE	DESCRIPTION



DRAWN: OP	CHECKED: JMR
DESIGNED: ABE	APPROVED: JMR


PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

CONTACT: ARK/ESPINELLI

DATE: 3/8/2024

SHEET TITLE: SITE PLAN

SHEET NO. M1.0





RESIDENTIAL UNIT NOTES:

UNIT A = UNIT TYPE A (FOR EXAMPLE)
 REFER TO DWG M300,
 DETAIL 1.

FOR DUCT SIZES WITHIN THE RESIDENTIAL
 UNITS, REFER TO THE ENLARGED UNIT
 PLANS ON DWGS M300-M303.

BUILDING TYPE 1
LEVEL 1 FLOOR PLAN
 SCALE: 1/8" = 1'-0"

NO.	DATE	DESCRIPTION



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	PR
APPROVED:	JMR

PROJECT: **EAST TOWN CROSSING BUILDING E**
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 364-3343
 REPROJECT NO. 810010
 CONTACT: ARK.ESPINELLI



DATE:
3/8/2024

SHEET TITLE:
**HVAC PLAN -
LEVEL 1**

SHEET NO.
M2.0





RESIDENTIAL UNIT NOTES:

UNIT A = UNIT TYPE A (FOR EXAMPLE)
 REFER TO DWG M300,
 DETAIL 1.

FOR DUCT SIZES WITHIN THE RESIDENTIAL
 UNITS, REFER TO THE ENLARGED UNIT
 PLANS ON DWGS M300-M303.

BUILDING TYPE 1
 LEVEL 2 FLOOR PLAN
 SCALE: 1/8" = 1'-0"

NO.	DATE	REVISIONS DESCRIPTION



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	PR
APPROVED:	JMR

PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 964-3343
 RE: PROJECT NO. 810010
 CONTACT: ARK@ESPINELI.COM

ROBISON ENGINEERING, INC.

DATE:
 3/8/2024

SHEET TITLE:
 HVAC PLANS -
 LEVEL 2

SHEET NO.
M2.1





RESIDENTIAL UNIT NOTES:

UNIT A = UNIT TYPE A (FOR EXAMPLE)
 REFER TO DWG M300,
 DETAIL 1.

FOR DUCT SIZES WITHIN THE RESIDENTIAL
 UNITS, REFER TO THE ENLARGED UNIT
 PLANS ON DWGS M300-M303.

BUILDING TYPE 1
 LEVEL 3 FLOOR PLAN
 SCALE: 1/8" = 1'-0"

NO.	DATE	REVISIONS DESCRIPTION



DRAWN: OP	DESIGNED: ABE	CHECKED: PR	APPROVED: JMR
-----------	---------------	-------------	---------------


PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W. SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 964-3343
 RE: PROJECT NO. 810010
 CONTACT: ARK.ESPINELLI



DATE:
 3/8/2024

SHEET TITLE:
 HVAC PLANS -
 LEVEL 3

SHEET NO.
M2.2



NO.	DATE	DESCRIPTION



DRAWN: OP	CHECKED: JMR
DESIGNED: ABE	APPROVED: JMR

PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 964-3343
 RE/PROJECT NO.: 810010
 CONTACT: ARK@ESPINELI.COM

DATE:
3/8/2024

SHEET TITLE:
HVAC PLANS - ROOF

SHEET NO.
M2.3


BUILDING TYPE 1
 ROOF
 SCALE: 1/8" = 1'-0"



UNIT 106
TYPE 12-3 LEVEL: 1
BEDS: 2
A: 1,008 sq ft
ADA TYPE 'A'

UNIT 12-3,12-3M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"


3
M3.0



UNIT 107
TYPE 12-1 LEVEL: 1
BEDS: 2
A: 1,108 sq ft
ADA TYPE 'A'

UNIT 12-1,12-1M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"


1
M3.0



UNIT 102
TYPE 12-5 LEVEL: 1
BEDS: 2
A: 1,081 sq ft
ADA TYPE 'B'

UNIT 12-5,12-5M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"

4
M3.0



UNIT 108
TYPE 12-2 LEVEL: 1
BEDS: 2
A: 878 sq ft
ADA TYPE 'B'

UNIT 12-2, 12-2M, 22-5, 22-5M, 32-5, 32-5M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"

2
M3.0

RESIDENTIAL UNIT NOTES:

- PENETRATIONS OF THE RATED WALL ASSEMBLIES SHALL BE PROTECTED IN ACCORDANCE WITH IBC SECTION 717. REFER TO ARCHITECTURAL PLANS FOR PENETRATION DETAILS.
- PER OWNER, THE FOLLOWING RANGE HOODS ARE BEING INSTALLED: STANDARD UNITS (MICRO/HOOD COMBO): FRIGIDAIRE LFMV1846VF ADA UNITS (HOOD ONLY): GE JX3240DJWW PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, DUCT CONNECTION TO HOODS ARE 6". MINIMUM SIZE ROUND DUCT FOR HOOD VENTING SHALL BE 7".
- EXHAUST FAN EF-1 SHALL SERVE AS THE WHOLE HOUSE VENTILATION FAN. REFER TO M003 FOR REQUIREMENTS.
- DRYER VENTING: PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, THE MAXIMUM LENGTH OF THE DRYER VENTS IS AS FOLLOWS (REFER TO DWG M400, DETAIL 1):

STANDARD DRYER:
GE GUV27ESSM

NUMBER OF 90° ELBOWS OR TURNS	MAXIMUM LENGTH (FT)
0	200
1	185
2	175
3	165
4	155
5	145



ADA DRYER:
GE GFV55ESSN

NUMBER OF 90° ELBOWS OR TURNS	MAXIMUM LENGTH (FT)
0	200
1	185
2	175
3	165
4	155

FLAG NOTES: \triangle

- 4" POC TO DRYER. PROVIDE METAL DRYER BOX WHERE DUCT IS ROUTED IN 2X6 FRAMED WALL. REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WSMC 504.8.4.1 FOR THE MAXIMUM ALLOWED LENGTH OF THE DRYER VENT. PROVIDE PERMANENT PLACARD OF TYPE PLAC34 SHOWING NET EQUIVALENT LENGTH. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- LOUVERED DOOR. REFER TO ARCHITECTURAL PLANS FOR DETAILS.
- DRYER EXHAUST VENT SHALL BE PROTECTED WITH FIRE WRAP FROM DRYER TO EXTERIOR WALL TERMINATION POINT. REFER TO DWG M401, DETAIL 1 FOR FIRE WRAP DETAILS. FIRE WRAP SHALL BE UNIFRAX FYREWRAPE DPS.
- DUCT ROUTED IN LINED JOIST BAY
- CLOSETS CONTAINING DRYERS SHALL BE PROVIDED WITH LOUVERED DOOR OR 100 SQ. IN FREE-AREA OPENING ABOVE DOOR. OPENING PROVIDES PATH FOR EXHAUST AIR DURING WASHER OPERATION PER WSMC TABLE 403.3.1.1 NOTE (I) AND MAKEUP AIR DURING DRYER OPERATION PER 504.6.
- 4" DRYER EXHAUST TERMINATION WALL CAP. PROVIDE BACKDRAFT DAMPER AT TERMINATION. DO NOT INSTALL SCREENS ON DRYER EXHAUST TERMINATIONS. CLEARANCES PER GENERAL NOTE 1.
- POC TO DOMESTIC KITCHEN RANGE HOOD. SEE PLANS FOR SIZE. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
- DOMESTIC KITCHEN RANGE HOOD EXHAUST TERMINATION WALL CAP WITH SCREEN. PROVIDE BACKDRAFT DAMPER AT TERMINATION. CLEARANCES PER GENERAL NOTE 1.
- LOWERED SOFFIT FOR MECHANICAL EQUIPMENT.

NO.	DATE	DESCRIPTION



DRAWN: OP	DESIGNED: ABE	CHECKED: PR	APPROVED: JMR
-----------	---------------	-------------	---------------

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 ACOTWAY W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 964-3343
REPROJECT NO.: 810010
CONTACT: ARK.ESPINELLI

ROBISON ENGINEERING, INC.

DATE:
3/8/2024


SHEET TITLE:
HVAC ENLARGED PLANS

SHEET NO.
M3.0




UNIT 22-6, 22-6M, 32-6, 32-6M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"

3
M3.1



UNIT 22-1, 22-1M, 32-1, 32-1M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"

1
M3.1



UNIT 22-2, 22-2M, 32-2, 32-2M
ENLARGED PLAN
SCALE: 1/4" = 1'-0"

2
M3.1

RESIDENTIAL UNIT NOTES:

1. PENETRATIONS OF THE RATED WALL ASSEMBLIES SHALL BE PROTECTED IN ACCORDANCE WITH IBC SECTION 717. REFER TO ARCHITECTURAL PLANS FOR PENETRATION DETAILS.
2. PER OWNER, THE FOLLOWING RANGE HOODS ARE BEING INSTALLED: STANDARD UNITS (MICRO/HOOD COMBO): FRIGIDAIRE LFMV1846VF ADA UNITS (HOOD ONLY): GE JX3240DJWW PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, DUCT CONNECTION TO HOODS ARE 6". MINIMUM SIZE ROUND DUCT FOR HOOD VENTING SHALL BE 7".
3. EXHAUST FAN EF-1 SHALL SERVE AS THE WHOLE HOUSE VENTILATION FAN. REFER TO M003 FOR REQUIREMENTS.
4. DRYER VENTING: PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, THE MAXIMUM LENGTH OF THE DRYER VENTS IS AS FOLLOWS (REFER TO DWG M400, DETAIL 1):

STANDARD DRYER:
GE GUV27ESSM

NUMBER OF 90° ELBOWS OR TURNS	MAXIMUM LENGTH (FT)
0	200
1	185
2	175
3	165
4	155
5	145



ADA DRYER:
GE GFV55ESSN

NUMBER OF 90° ELBOWS OR TURNS	MAXIMUM LENGTH (FT)
0	200
1	185
2	175
3	165
4	155

FLAG NOTES: #

1. 4" POC TO DRYER. PROVIDE METAL DRYER BOX WHERE DUCT IS ROUTED IN 2X6 FRAMED WALL. REFER TO MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WSMC 504.8.4.1 FOR THE MAXIMUM ALLOWED LENGTH OF THE DRYER VENT. PROVIDE PERMANENT PLACARD OF TYPE PLAC34 SHOWING NET EQUIVALENT LENGTH. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
2. LOUVERED DOOR. REFER TO ARCHITECTURAL PLANS FOR DETAILS.
3. DRYER EXHAUST VENT SHALL BE PROTECTED WITH FIRE WRAP FROM DRYER TO EXTERIOR WALL TERMINATION POINT. REFER TO DWG M401, DETAIL 1 FOR FIRE WRAP DETAILS. FIRE WRAP SHALL BE UNIFRAX FYREWRAPE DPS.
4. DUCT ROUTED IN LINED JOIST BAY
5. CLOSETS CONTAINING DRYERS SHALL BE PROVIDED WITH LOUVERED DOOR OR 100 SQ. IN FREE-AREA OPENING ABOVE DOOR. OPENING PROVIDES PATH FOR EXHAUST AIR DURING WASHER OPERATION PER WSMC TABLE 403.3.1.1 NOTE (1) AND MAKEUP AIR DURING DRYER OPERATION PER 504.6.
6. 4" DRYER EXHAUST TERMINATION WALL CAP. PROVIDE BACKDRAFT DAMPER AT TERMINATION. DO NOT INSTALL SCREENS ON DRYER EXHAUST TERMINATIONS. CLEARANCES PER GENERAL NOTE 1.
7. POC TO DOMESTIC KITCHEN RANGE HOOD. SEE PLANS FOR SIZE. DUCT SHALL REMAIN SEPARATE FROM OTHER EXHAUST SYSTEMS UP TO TERMINATION.
8. DOMESTIC KITCHEN RANGE HOOD EXHAUST TERMINATION WALL CAP WITH SCREEN. PROVIDE BACKDRAFT DAMPER AT TERMINATION. CLEARANCES PER GENERAL NOTE 1.
9. LOWERED SOFFIT FOR MECHANICAL EQUIPMENT.

NO.	DATE	DESCRIPTION



OP	ABE	JMR
DESIGNED:	ABE	APPROVED:
CHECKED:	PR	

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 ACOTHAVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 964-3343
REPROJECT NO.: 810010
CONTACT: ARK.ESPINELLI

ROBISON ENGINEERING, INC.

DATE:
3/8/2024

SHEET TITLE:
HVAC ENLARGED PLANS

SHEET NO.
M3.1

ADA DRYER

GFV55ESSN

GE® Long Vent 7.8 cu. ft. Capacity Front Load Electric Dryer

DIMENSIONS AND INSTALLATION INFORMATION (IN INCHES)


ELECTRIC DRYER RATING	
120V/240V	5600W, 25A, 60Hz
120V/208V	4300W, 23A, 60Hz

EXHAUST OPTIONS: 4-way via rear, right, left and bottom.

CIRCUIT REQUIREMENTS: An individual, properly grounded branch circuit, protected by a 30-amp circuit breaker or a time-delay fuse, is required.

NOTE: Dryer wall outlet must be located within 36" of service cord entry and accessible when dryer is mounted in position.

INSTALLATION INFORMATION: For complete information, see installation instructions packed with your dryer.



For answers to your Monogram, GE Café® Series, GE Profile® Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



Specification Revised 11/19

GFV55ESSN

GE® Long Vent 7.8 cu. ft. Capacity Front Load Electric Dryer

DRYER EXHAUSTING INFORMATION - METAL DUCT ONLY

For complete information, see installation instructions packed with your dryer.

DUCTING MATERIALS: For best performance, this dryer should be vented with 4" diameter all rigid metal exhaust duct. If rigid metal duct cannot be used, then UL-listed flexible metal (semi-rigid) ducting can be used (Kit WX08X10077). In special installations, it may be necessary to connect the dryer to the house vent using a flexible metal (foil-type) duct. A UL-listed flexible metal (foil-type) duct may be used ONLY in installations where rigid metal or flexible metal (semi-rigid) ducting cannot be used AND where a 4" diameter can be maintained throughout the entire length of the transition duct. Please see installation instruction packed with your dryer for complete instructions when using flexible metal (foil type) ducting.

EXHAUST LENGTH CALCULATION:

- Determine the number of 90° turns needed for your installation. If you exhaust to the side or bottom of dryer, add one turn.
- The maximum length of 4" rigid (aluminum or galvanized) duct which can be tolerated is shown in the table.

A turn of 45° or less may be ignored. Two 45° turns within the duct length should be treated as a 90° elbow.


A turn over 45° should be treated as a 90° elbow. Dryers must be exhausted to the outside.

CAUTION: For personal safety do not terminate exhaust into a chimney, under any enclosed house floor (crawl space), or into an attic, since the accumulated lint could create a fire hazard or moisture could cause damage. Never terminate the exhaust into a common duct or plenum with a kitchen exhaust, since the combination of lint and grease could create a fire hazard.

Exhaust ducts should be terminated in a dampered wall cap to prevent back drafts, bird nesting, etc. The wall cap must also be located at least 12" above the ground or any other obstruction with the opening pointed down.

FOR MORE INFORMATION ON VENTING KITS AND ACCESSORIES, PLEASE CALL 1-800-GE-CARES.

Domestic dryer models	Number of 90° turns	Best performance Maximum length of 4" dia. rigid metal duct Exhaust hood type	
		A 4" opening	B 2-1/2" opening
	0	200 ft.	175 ft.
	1	185 ft.	165 ft.
	2	175 ft.	155 ft.
	3	165 ft.	145 ft.
	4	155 ft.	135 ft.



For answers to your Monogram, GE Café® Series, GE Profile® Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



Specification Revised 11/19

STANDARD DRYER

GUV27ESSM

GE® Unitized Spacemaker® 3.8 DOE Cu. Ft. Stainless Steel Washer and 5.9 Cu. Ft. Long Vent Electric Dryer


DIMENSIONS AND INSTALLATION INFORMATION (IN INCHES)

ELECTRICAL REQUIREMENTS: This appliance should be connected to an individual, properly-grounded branch circuit with 120/240V or 120/208V single-phase 60 Hz electrical service and should be protected by 30-amp time-delay fuses or circuit breakers KW Rating per voltage (240/208). This appliance is manufactured with neutral connected to the frame. Power cord should be purchased separately. Dryers must be exhausted to the outside.

INSTALLATION INFORMATION: For complete information, see installation instructions packed with the product.

Installation Instructions

27" NOMINAL PRODUCT DIMENSIONS



For answers to your Monogram, GE Café® Series, GE Profile® Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



Specification Revised 11/17

GUV27ESSM

GE® Unitized Spacemaker® 3.8 DOE Cu. Ft. Stainless Steel Washer and 5.9 Cu. Ft. Long Vent Electric Dryer

DIMENSIONS AND INSTALLATION INFORMATION (IN INCHES)

For complete information, see installation instructions packed with your dryer.

DUCTING MATERIALS:

For best performance, this dryer should be vented with 4" diameter all rigid metal exhaust duct. If rigid metal duct cannot be used, then UL-listed flexible metal (semi-rigid) ducting can be used (Kit WX08X10077). In special installations, it may be necessary to connect the dryer to the house vent using a flexible metal (foil-type) duct. A UL-listed flexible metal (foil-type) duct may be used ONLY in installations where rigid metal or flexible metal (semi-rigid) ducting cannot be used AND where a 4" diameter can be maintained throughout the entire length of the transition duct. Please see installation instruction packed with your dryer for complete instructions when using flexible metal (foil type) ducting.

EXHAUST LENGTH CALCULATION:

- Determine the number of 90° turns needed for your installation. If you exhaust to the side or bottom of dryer, add one turn.
- The maximum length of 4" rigid (aluminum or galvanized) duct which can be tolerated is shown in the table.

For every extra 90° elbow, reduce the allowable vent system length by 10 ft. Two 45° elbows will be treated like one 90° elbow. For the side exhaust installations, add one 90° elbow to the chart. The total vent system length includes all the straight portions and elbows of the system (transition duct included).

Dryers must be exhausted to the outside.

CAUTION: For personal safety do not terminate exhaust into a chimney, under any enclosed house floor (crawl space), or into an attic, since the accumulated lint could create a fire hazard or moisture could cause damage. Never terminate the exhaust into a common duct or plenum with a kitchen exhaust, since the combination of lint and grease could create a fire hazard.

Exhaust ducts should be terminated in a dampered wall cap to prevent back drafts, bird nesting, etc. The wall cap must also be located at least 12" above the ground or any other obstruction with the opening pointed down.



For answers to your Monogram, GE Café® Series, GE Profile® Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.




Specification Revised 11/17

GUV27 DRYER EXHAUST LENGTH



No. of 90° Elbows	RECOMMENDED MAXIMUM LENGTH	
	Rigid Metal	Rigid Metal
0	200 Feet	175 Feet
1	185 Feet	165 Feet
2	175 Feet	155 Feet
3	165 Feet	145 Feet
4	155 Feet	135 Feet
5	145 Feet	125 Feet

SAMPLE LABEL



NOTE: DRYER MAKE AND MODEL SHOWN ARE THE BASIS OF DESIGN FOR DETERMINING MAXIMUM DRYER VENT LENGTHS. IF A DIFFERENT MAKE/MODEL IS USED, NOTIFY THE ENGINEER AND ARCHITECT IMMEDIATELY TO VERIFY VENT LENGTHS AND TO DETERMINE IF DRYER BOOSTER FANS WILL BE NECESSARY. PER IMC 504.8.5, CONTRACTOR SHALL PROVIDE A LABEL OR PLACARD WITHIN 6 FEET OF THE EXHAUST DUCT CONNECTION THAT LISTS THE EQUIVALENT LENGTH OF THE DRYER EXHAUST DUCT. SEE SAMPLE LABEL FOR DETAILS.

REVISIONS	DESCRIPTION
NO.	DATE



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	PR
APPROVED:	JMR

PROJECT: EAST TOWN CROSSING BUILDING E MULTIFAMILY DEVELOPMENT PIONEER WAY & SHAW RD. PUYALLUP, WA


18401 ACOTHAVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 964-3343
RE/PROJECT NO.: 810010
CONTACT: ARK@ESPINELI

ROBISON ENGINEERING, INC

DATE: 3/8/2024

SHEET TITLE: DETAILS & DIAGRAMS

SHEET NO. M4.0



- Floor-Ceiling Assembly** – The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual 1500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction details of the floor-ceiling assembly are summarized below:
 - Flooring System** – Lumber or plywood subfloor with finish floor of lumber, plywood or **Floor Topping Mixture** as specified in the individual Floor-Ceiling Design. Max area of floor opening is 150 in.2 (0.098 m²) with a max 1.5 in. (38 mm) annular space between wrapped duct and framing members.
 - Wood Joists** – Nom 10 in. (254 mm) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or **Structural Wood Members** with bridging as required and with ends firestopped. Additional framing members installed to form a square enclosure around the perimeter of the opening in the floor and ceiling.
 - Furring Channels** – (Where required - not shown) - Resilient galv steel furring installed perpendicular to wood joists between gypsum board and wood joists as specified in the individual Floor-Ceiling Design. Furring channels spaced max 24 in. (610 mm) OC. If furring channels are used within the assembly, additional furring channels to be installed around the periphery of the opening.
 - Gypsum Board*** – Nom 4 ft (1.2 m) wide by 5/8 in. (15.9 mm) thick as specified in the individual Floor-Ceiling Design. Gypsum board secured to wood joists or furring channels as specified in the individual Floor-Ceiling Design. Max area of ceiling opening is 150 in.2 (0.098 m²) with a max 1.5 in. (38 mm) annular space between duct and framing members.
- Steel Air Duct** – Max 7 in. (178 mm) diam by min 0.0157 in. (No. 30 gauge or 0.40 mm) thick galv steel air duct to be centered within the firestop system. Max one steel air duct to be installed within opening. Steel duct to be rigidly supported on top side of floor-ceiling assembly.
 - Steel Air Duct** – Max 10 x 4 in. (254 x 102 mm) rectangular by min 0.022 in. (no. 26 gauge or 0.56 mm) thick galv steel air duct to be centered within the firestop system. Max one steel air duct to be installed within opening. Steel duct to be rigidly supported on top side of floor-ceiling assembly.
- Fire-resistive System** – The fire resistive system shall consist of the following:
 - Firestop System** – When the ventilation duct passes through a fire rated floor assembly, the through openings shall be firestopped in accordance with System No. F-C-7057.
 - Batts and Blankets*** – 1/2 in. (13 mm) thick, 8 pcf (128 kg/m³) or nom 1-1/2 in.

(38 mm) thick, 6 pcf (96 kg/m³) with foil-scrim facers. The steel duct shall be wrapped with one layer of duct wrap installed with 1 in. (25 mm) transverse and longitudinal overlaps or lightly butted compression joints in accordance with the manufacturer's installation instructions. A min 12 in. high collar consisting of an additional layer of 1/2 in. (13 mm) thick, 8 pcf (128 kg/m³) or nom 1-1/2 in. (38 mm) thick, 6 pcf (96 kg/m³) duct wrap, installed over the duct wrap flush with the top surface of the floor and extending upward. All seams and edges shall be sealed with min 3 in. (76 mm) wide pressure sensitive aluminum foil tape.

UNIFRAX I L L C – FyreWrap® DPS or FyreWrap® Elite 1.5

C. **Steel Tie Wire** – Min No. 18 Gauge (0.040 in. or 1 mm) galvanized steel wire formed into a loop on one end, with the other end passed through the loop, pulled hand tight and bent over. Tie wires spaced a max 12 in. (305 mm) OC.

*Bearing the UL Classification Mark

Last Updated on 2013-10-29

[Questions?](#) [Print this page](#) [Terms of Use](#) [Page Top](#)

© 2013 UL LLC

When the UL Leaf Mark is on the product, or when the word "Environment" is included in the UL Mark, please search the [UL Environment database](#) for additional information regarding this product's certification.

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings); 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: © 2013 UL LLC."

UL ONLINE CERTIFICATIONS DIRECTORY

Assembly No. V-32
HNJ.V-32
Ventilation Duct Assemblies

Page Bottom

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.


Ventilation Duct Assemblies

See General Information for Ventilation Duct Assemblies

Assembly No. V-32

October 29, 2013

Duct A	Fire Resistance Rating
	1 Hr



FyreWrap® DPS Insulation
Dryer Protection System

Introduction

Unifrax's FyreWrap® DPS Insulation is a high-temperature insulation blanket specifically designed. UL tested and certified to provide a single layer, one-hour rated flexible enclosure around dryer and residential kitchen exhaust ductwork.


Dryer Exhaust Applications

FyreWrap DPS is an innovative product that provides a safe and cost-effective means to achieve a one-hour fire resistance rated zero clearance enclosure for routing dryer ductwork, from start to finish, through rated wood truss/joist construction as prescribed by the International Building and Mechanical Codes.

- FyreWrap DPS Insulation offers the following product features:
- Lightweight, flexible product form
 - Scrim encapsulated
 - Easy to cut, fabricate, wrap around ducts, pipes or cables
 - Thin, single-layer design
 - High-temperature, low bioperseptance fiber

Product Components

Core Material: FyreWrap DPS Insulation incorporates Insulfrax® Thermal Insulation as its core material. Insulfrax is a high-temperature insulation made from a calcium, magnesium, silica chemistry designed to enhance biodegradability. It provides excellent insulation in a noncombustible blanket product form.



FyreWrap® DPS Insulation – Dryer Protection System

Encapsulating Material: The core insulation blanket is completely encapsulated in an aluminum foil, fiberglass reinforced scrim covering. This scrim provides additional handling strength as well as protection from moisture absorption and tearing.

Typical Product Parameters

Thickness	1/2"
Density	8pcf
Scrim Encapsulated	
Covering	16" w x 25' L
Product Availability	24" w x 25' L
	26" w x 25' L
	48" w x 25' L

Typical System Properties

ISO 6944	UL Assembly No. V-32, ULC Assembly No. FRD-29
UL 1479 (ASTM E814), CAN/ULC S115	UL Assembly Nos. F-C-7057, F-C-7058
Intertek Laboratories (CPL) Listed	Applied Fire Protection, File 16341-3
ASTM E 136 Noncombustibility Test	Passes
ASTM E84, UL 723, ULC S102.2	UL File No. R14514
	Unfaced Blanket
Flame Spread Rating:	Zero
Smoke Developed Rating:	Zero

Data are average results of tests conducted under standard procedures and are subject to variation. Results should not be used for specification purposes.

Refer to the product Safety Data Sheet (SDS) No. M0456 for recommended work practices and other product safety information.



UL ONLINE CERTIFICATIONS DIRECTORY



UL Product iQ
UL'S NEXT GENERATION CERTIFICATIONS SEARCH
The same trusted data in a modern search engine.

NOW AVAILABLE
LEARN MORE

System No. F-C-7057
XHEZ, F-C-7057
Through-penetration Firestop Systems

Page Bottom

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

XHEZ - Through-penetration Firestop Systems

XHEZ7 - Through-penetration Firestop Systems Certified for Canada

See General Information for Through-penetration Firestop Systems

See General Information for Through-penetration Firestop Systems Certified for Canada

System No. F-C-7057

March 27, 2017

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating – 1 Hr	F Rating – 1 Hr
T Rating – 1 Hr	FT Rating – 1 Hr
	FH Rating – 1 Hr
	FTH Rating – 1 Hr

Installation

FyreWrap DPS Insulation consists of a single-layer system applied directly on to the surface of the duct or combustible item.


Dryer Applications

Install the insulation around the duct to provide a 1" longitudinal compression joint or overlap. Adjacent pieces of insulation should be installed with a 1" perimeter compression joint or material overlap. The 16" wide DPS product facilitates linear installation around 4" diameter dryer ductwork without material cutting or scrap. The same technique can be used with wrapping 26" wide FyreWrap DPS on 7" diameter dryer ductwork. To temporarily secure the insulation, optional use of foil tape is permitted. Seal all cut edges with aluminum foil tape to ensure there is no

exposed fiber. 18 gauge steel tie wire should be utilized for permanent attachment. Locate the wire 1/2" from the blanket edge and on maximum 12" centers. Twist tension the wire to firmly hold the wrap system in place, but not so tight as to cut or damage the blanket. Installation details are provided below for additional illustration.

Unifrax has a wide range of FyreWrap fire protection materials available to provide passive fire protection solutions in a variety of applications in the commercial building, industrial facility and transportation industries.

For additional information about product performance or for assistance identifying the recommended product for your fire protection application, please contact Unifrax at 716-768-6500 and ask for Fire Protection Application Engineering.



From C-605 Effective 6/16 © 2017 Unifrax I LLC All Rights Reserved Printed in USA Page 2 of 2


Unifrax I LLC
Corporate Headquarters
600 Riverwalk Parkway
Suite 120
Tonawanda, NY 14150
Telephone: 716-768-6500
Canada: 1-800-635-4464
Internet: www.unifrax.com
Email: info@unifrax.com

DUCT FIRE WRAP

DETAIL

SCALE: NONE


NO.	DATE	DESCRIPTION



DRAWN:	OP
DESIGNED:	ABE
CHECKED:	PR
APPROVED:	JMR

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYYALLUP, WA

19401 ACHTAVIE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 964-3343
REPROJECT NO.: 810010
CONTACT: ARK.ESPINELI



DATE: 3/8/2024

SHEET TITLE: DETAILS & DIAGRAMS

SHEET NO. M4.1

GENERAL NOTES

- REFERENCE TO RELATED WORK: "REF" INDICATIONS DENOTE WORK COVERED ELSEWHERE (ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL, LANDSCAPE, OR KITCHEN), OR ITEM BASED ON A SPECIFIC MANUFACTURER'S DIMENSIONS (VERIFY).
- ELECTRICAL CHARACTERISTICS: REFER TO ELECTRICAL DRAWINGS FOR ELECTRICAL CHARACTERISTICS (VOLTAGES, ETC. OF MECHANICAL EQUIPMENT, UNLESS OTHERWISE INDICATED).
- CODES: COMPLETE INSTALLATION OF THE PLUMBING SYSTEM SHALL BE PER THE APPLICABLE BUILDING, MECHANICAL, ENERGY, PLUMBING, FIRE, AND HEALTH CODES AND REGULATIONS AS ADOPTED BY THE LOCAL AHJ.
- PREPARE AND SUBMIT FOR REVIEW A SHOP DRAWING BASED ON FINAL STRUCTURAL SHOP DRAWINGS FOR LOCATING AND ROUTING ALL EQUIPMENT, PIPING, ETC.
 - COORDINATE FLOOR AND BEAM PENETRATIONS WITH STRUCTURAL.
 - COORDINATE FINAL LOCATION AND ROUTING WITH CEILING, LIGHTS, WALLS, FIRE SPRINKLER PIPING, AND OTHER TRADES WORK.
 - INCLUDE ADDITIONAL OFFSETS, ELBOWS, ROUTING, EQUIVALENT DUCT SIZING EXCHANGE, RELOCATING, ETC. AS REQUIRED FOR A COMPLETE OPERATING MECHANICAL SYSTEM.
 - PROVIDE SHOP DRAWINGS AT NO ADDITIONAL COST TO THE OWNER.
- PLUMBING CONTRACTOR SHALL LOCATE AND COORDINATE EXACT LOCATION OF ALL PLUMBING EQUIPMENT WITHIN THE STRUCTURE.
- ACCESS DOORS: COORDINATE WITH ARCHITECT AND LOCATE ALL ACCESS DOORS ON SHOP DRAWINGS PRIOR TO BEGINNING OF CONSTRUCTION. ACCESS DOORS IN FIRE RATED STRUCTURE SHALL BE FIRE RATED. VERIFY ACCESS DOOR LOCATIONS WITH GENERAL CONTRACTOR PRIOR TO BIDDING.
- ROOF PENETRATIONS: SEE ARCHITECTURAL DRAWINGS FOR ROOF CAP, ROOF CURB, ROOF DRAIN, OVERFLOW DRAINS AND VTR DETAILS.
- EXPOSED PIPING: PROVIDE CHROME PLATING FOR EXPOSED PIPING IN FINISHED ROOMS.
- PENETRATIONS: PROVIDE ESCUTCHEON PLATES FOR EXPOSED PIPING PENETRATIONS AND SHEET METAL FLASHING FOR EXPOSED DUCTWORK PENETRATIONS.
- SHAFT AND PLENUM CONNECTIONS: SEAL CONNECTIONS TO AIR SHAFTS AIRTIGHT. PROVIDE AIRTIGHT SEAL AROUND PENETRATIONS IN AIR PLENUMS.
- LIGHT FIXTURE CLEARANCE: COORDINATE LOCATIONS OF MECHANICAL WORK TO PROVIDE CLEARANCES OVER LIGHTING FIXTURES FOR REMOVAL AND REPLACEMENT.
- CABLE TRAYS: PIPING INSTALLED ADJACENT TO ELECTRICAL CABLE TRAYS SHALL ALLOW MINIMUM ACCESS OF 6" ABOVE AND TO THE SIDE OF CABLE TRAYS.
- MOTORS: COMPLY WITH ENERGY CODE ENFORCED BY AHJ FOR MINIMUM EFFICIENCIES UNDER FULL LOAD.
- ACCESS CLEARANCES FOR MAINTENANCE AND REPLACEMENT: VERIFY PHYSICAL DIMENSIONS OF EQUIPMENT TO ENSURE THAT ACCESS CLEARANCES CAN BE MET. COORDINATE LOCATIONS OF MECHANICAL WORK AND WORK OF OTHER TRADES TO PROVIDE ACCESS CLEARANCES FOR SERVICE AND MAINTENANCE.

COORDINATION REQUIREMENTS

- IRRIGATION SYSTEM: COORDINATE IRRIGATION WATER DEMAND, MINIMUM WATER PRESSURE REQUIREMENTS & CONTROL CABINET LOCATIONS WITH IRRIGATION CONTRACTOR.
- GAS: CONTRACTOR/GAS COMPANY SHALL FINALIZE GAS METER AND GAS SERVICE LOCATIONS. INSTALL SEISMIC GAS SHUT OFF VALVE PER GAS COMPANY REGULATIONS.
- UTILITIES: COORDINATE WITH SITE UTILITY CONTRACTOR AND CIVIL DRAWINGS FOR UTILITY CONNECTIONS AND EXTENSIONS.
- ROOF DRAINAGE: COORDINATE WITH GENERAL CONTRACTOR FOR ROOF DRAIN AND OVERFLOWS, SCUPPER DRAINS, AND CONDENSATE DRAINS.
- PLUMBING FIXTURES & EQUIPMENT: COORDINATE EXACT LOCATION OF ALL PLUMBING FIXTURES & EQUIPMENT WITH ARCHITECTURAL AND OTHER TRADES DOCUMENTS.
- PIPING: COORDINATE EXACT LOCATION OF ALL STRUCTURAL FRAMING & FOOTINGS AND FINALIZE THE EXACT ROUTING OF ALL PIPES WITH STRUCTURAL ENGINEER AT THE SITE PRIOR TO AND DURING THE CONSTRUCTION. COORDINATE UNDER GRADE PIPING & FOUNDATION DRAINAGE PIPING WITH CIVIL ENGINEER.
- ADJUSTMENTS: ALL EQUIPMENT, MOTORS, FANS GAS BURNERS, IGNITION DEVICES, DRIVES, ETC. SHALL BE ADJUSTED AND BALANCED TO OPERATE AT SPECIFIED RATINGS AS REQUIRED FOR THIS PROJECT SITE AND ACCOUNTING FOR ELEVATION ABOVE SEA LEVEL.
- APPROVALS: MECHANICAL AND PLUMBING EQUIPMENT SHALL BE APPROVED FOR INSTALLATION IN THE PROJECT LOCATION AND SHALL HAVE ALL CERTIFICATIONS AND RATINGS TO MEET ALL ENERGY, POLLUTION, ENVIRONMENTAL, SEISMIC, APPLICABLE CODES AND REGULATIONS. THE CONTRACTOR SHALL COORDINATE WITH MANUFACTURE SUPPLIERS AND SHALL INCLUDE ALL COSTS REQUIRED TO MEET THE BID DOCUMENTS.
- FIRE PROTECTION: CONTRACTOR SHALL PROVIDE A FULLY DESIGNED FIRE PROTECTION SPRINKLER SYSTEM IN COMPLIANCE WITH NFPA AND LOCAL CODES. PROVIDE DESIGN, PERMITS, MATERIALS, INSTALLATION, TESTING AND ALL OTHER FOR A FULLY OPERATIONAL SYSTEM. LOCATION OF ALL PIPING TO BE COORDINATED WITH OTHER TRADES.
- PRIOR TO PIPING INSTALLATION: PLUMBING CONTRACTOR TO COORDINATE PIPING LAYOUT WITH ALL OTHER TRADES.
- ACCESS: COORDINATE ALL ACCESS LOCATIONS WITH GENERAL CONTRACTOR AND ARCHITECT TO ENSURE ALL REQUIRED ACCESS HATCHES, ACCESS PANELS & ACCESS COVERS ARE PROVIDED.
- PROVIDE WATER TIGHT SEALS FOR ANY PIPING PENETRATING THE EXTERIOR FOUNDATION WALLS OR SLABS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT IMMEDIATELY.
- PROVIDE FIRE PROOFING FOR ALL PIPING PENETRATING FIRE BARRIER WALLS OR FLOOR SLABS.

SYMBOLS

GENERAL

ARCHITECTURAL BACKGROUND
NEW PIPING (HEAVY LINE)
EXISTING PIPING (THIN LINE)
EXISTING WORK TO BE REMOVED
MATCHLINE OR PROPERTY LINE
CONNECTION TO EXISTING

SECTION IDENTIFICATION

INDICATES DIRECTION OF CUTTING PLANE
LETTER INDICATES SECTION (NO. INDICATES DETAIL)
SHEET NUMBER WHERE SECTION IS DRAWN
SHEET NUMBER WHERE SECTION IS TAKEN

DETAIL IDENTIFICATION

DETAIL NUMBER
DRAWING/SHEET NUMBER

EQUIPMENT

TYPICAL EQUIPMENT DESIGNATION

PIPING

WASTE BELOW GRADE
WASTE ABOVE GRADE
PUMPED WASTE
INDIRECT WASTE
SANITARY SEWER BELOW GRADE
SANITARY SEWER ABOVE GRADE
PUMPED SANITARY SEWER
VENT
STORM DRAIN
OVERFLOW STORM DRAIN
PUMPED STORM DRAIN
CONDENSATE DRAIN
PUMPED CONDENSATE DRAIN
COLD WATER (CW)
HOT WATER (HW), POTABLE, 120°F
HOT WATER, POTABLE, TEMPERATURE OTHER THAN 120°F
HOT WATER CIRCULATING (HWC), POTABLE, 120°F
HOT WATER CIRCULATING, POTABLE, TEMPERATURE OTHER THAN 120°F
FUEL OIL FILL
FUEL OIL SUPPLY
FUEL OIL RETURN
FUEL OIL VENT
RELIEF VENT
LOW PRESSURE NATURAL GAS
MEDIUM PRESSURE NATURAL GAS
IRRIGATION (NON POTABLE)
FIRE MAIN

PIPE SYMBOLS

TOP PIPE CONNECTION
BOTTOM PIPE CONNECTION
PIPE TURNING UP
PIPE TURNING DOWN/DROP
PIPE CAP
PIPE PLUG
UNION
FLANGE
WYE STRAINER
WYE STRAINER WITH CAPPED HOSE END BLOWDOWN VALVE
BALL VALVE

GENERAL

BALL VALVE
GLOBE VALVE
CHECK VALVE
BALANCING OR PLUG VALVE
BUTTERFLY VALVE
FLEXIBLE CONNECTION IN PIPING
PRESSURE REDUCING VALVE (PRV)
AUTOMATIC CONTROL VALVE, 2-WAY
AUTOMATIC CONTROL VALVE, 3-WAY
RELIEF VALVE
BALANCING/METERING VALVE
REDUCER
DIRECTION OF FLOW
PIPE ANCHOR
PIPE ALIGNMENT GUIDE
PIPE SUPPORT
VALVE STATION OR ASSEMBLY
INDIRECT DRAIN, PIPE TO DRAIN
POINT OF CONNECTION
ROOF DRAIN, OVERFLOW DRAIN
FLOOR DRAIN
HOSE BIBB
BREAK IN PIPING OR DUCTWORK
GAS METER
INLINE WATER METER
PUMP
PRESSURE GAUGE
THERMOMETER
PRESSURE/TEMPERATURE TEST PORT
REDUCED PRESSURE BACKFLOW PREVENTER
DOUBLE CHECK VALVE ASSEMBLY
CATCH BASIN - SAND/OIL INTERCEPTOR
TRENCH DRAIN
EMERGENCY GAS SHUT-OFF VALVE
SEISMIC GAS SHUT-OFF VALVE
WASHER BOX
GREASE INTERCEPTOR

NOTE TO CONTRACTOR

DRAWINGS ARE DIAGRAMMATIC, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT, AND EQUIPMENT REQUIRED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENT. REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS. REFER TO MANUFACTURER'S STANDARD INSTALLATION DRAWINGS FOR EQUIPMENT CONNECTIONS AND INSTALLATION REQUIREMENTS. PROVIDE DUCTWORK, CONNECTIONS, ACCESSORIES, OFFSETS, AND MATERIALS NECESSARY FOR A COMPLETE SYSTEM.


ABBREVIATIONS

ABV	ABOVE	FLR	FLOOR	OPD	OVER PRESSURE DEVICE
AD	AREA DRAIN	FPM	FEET PER MINUTE	OPNG	OPENING
AFF	ABOVE FINISHED FLOOR	FPS	FEET PER SECOND	P	PUMP
AHJ	AUTHORITY HAVING JURISDICTION	FS	FLOOR SINK	PD	PRESSURE DROP, PLANTER DRAIN
BFF	BELOW FINISHED FLOOR	FT	FEET	POC	POINT OF CONNECTION
BFP	BACKFLOW PREVENTER	FU	FIXTURE UNITS	PRV	PRESSURE REDUCING VALVE
BOH	BACK OF HOUSE	G	GAS (LOW PRESSURE)	PS	PRESSURE RELIEF VALVE
BP	BOOSTER PUMP	GAL	GALLONS	PSIG	PUMPED STORM DRAINAGE
BT	BATHTUB	GD	GARAGE DRAIN		POUNDS PER SQUARE INCH GAUGE
BTUH	BRITISH THERMAL UNIT PER HOUR	GM	GAS METER	PSD	PUMPED STORM DRAINAGE
BV	BALANCING VALVE	GPG	GRAINS PER GALLON	PSS	PUMPED SANITARY SEWER
C	COMMON	GPM	GALLONS PER MINUTE	PSW	PUMPED SANITARY WASTE
CAP	CAPACITY	GV	GATE VALVE	PW	PUMPED WASTE
CB	CATCH BASIN	GW	GAS WATER HEATER	RD	ROOF DRAIN
CD	CONDENSATE DRAIN	HB	HOSE BIBB	REF	REFERENCE
CFF	CAPPED FOR FUTURE	HD	HEAD	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
CFM	CUBIC FEET PER MINUTE	HDR	HUB DRAIN	RPM	REVOLUTIONS PER MINUTE
CI	CAST IRON	HEDV	HOSE END DRAIN VALVE	S	SINK
CLG	CEILING, COOLING	HORIZ	HORIZONTAL	SCH	SCHEDULE
CLW	CLOTHES WASHER	HP	HORSEPOWER	SCW	SOFTENED COLD WATER
CO	CLEANOUTS	HPCW	HIGH PRESSURE COLD WATER	SD	STORM DRAIN
COMB	COMBUSTION	HW	HOT WATER	SEP	SEWAGE EJECTOR PUMP
CONT	CONTINUE, CONTROL	HWC	HOT WATER RE-CIRCULATION	SF	SQUARE FOOT
CONTR	CONTRACTOR	HWCP	HOT WATER CIRCULATION PUMP	SGSV	SEISMIC GAS SHUT-OFF VALVE
COTG	CLEANOUTS TO GRADE	HWR	HOT WATER RETURN	SH	SHOWER
CP	CIRCULATING PUMP	HWST	HOT WATER STORAGE TANK	SO	STORM OVERFLOW
CV	CHECK VALVE	HX	HEAT EXCHANGER	SP	STATIC PRESSURE/SUMP PUMP
CW	COLD WATER	ICW	INDUSTRIAL COLD WATER	SUDS	SUDS RELIEF
D	DIAMETER	ID	INDIRECT DRAIN, INSIDE DIAMETER	SR	STAINLESS STEEL/SANITARY SEWER
DB	DRY BULB, DECIBEL	IE	INVERT ELEVATION	SSS	SIDE SANITARY SEWER
DF	DRINKING FOUNTAIN	IHW	INDUSTRIAL HOT WATER	STD	STANDARD
DFU	DRAIN FIXTURE UNITS	IN	INCH	SQ	SQUARE
DI	DUCTILE IRON	KS	KITCHEN SINK	TD	TRENCH DRAIN
DIM	DIMENSION	KW	KILOWATT	TMV	THERMOSTATIC MIXING VALVE
DN	DOWN	L	LONG, LENGTH	TP	TRAP PRIMER
DS	DOWN SPOUT	LAV	LAVATORY	TYP	TYPICAL
DWG	DRAWING	LB	POUND	UH	UNIT HEATER
(E)	EXISTING	M	METER	UON	UNLESS OTHERWISE NOTED
EFF	EFFICIENCY	MBH	THOUSAND BTU PER HOUR	UR	URINAL
ELEC	ELECTRIC	MECH	MECHANICAL	V	VENT
EQUIV	EQUIVALENT	MCA	MIN. CIRCUIT AMPACITY	VTR	VENT THRU ROOF
EWC	ELECTRIC WATER COOLER	MOC	MAX. OVER CURRENT PROTECTION	W	WASTE, WATT, WIDE
EW	ELECTRIC WATER HEATER	MPG	MEDIUM PRESSURE GAS	WC	WATER CLOSET
EXT	EXTERIOR, EXTERNAL	MTD	MOUNTED	WCO	WALL CLEANOUTS
FCO	FLOOR CLEANOUTS	(N)	NEW	WHD	WALL HYDRANT
FD	FLOOR DRAIN	NC	NORMALLY CLOSED	WM	WASHING MACHINE
FDC	FIRE DEPARTMENT CONNECTION	NO	NORMALLY OPEN	WSFU	WATER SUPPLY FIXTURE UNITS
FF	FINISHED FLOOR	OD	OUTSIDE DIMENSION/DIAMETER		
			OVERFLOW DRAIN/DECK DRAIN		

DRAWING INDEX

DWG	DESCRIPTION	INCLUDED IN SET
P0.00	LEGEND, GENERAL NOTES, AND DRAWING INDEX	X
P0.01	PLUMBING NOTES, TABLES AND CODES	X
P0.02	PLUMBING FIXTURE UNIT COUNTS AND FIXTURE/RAIN SCHEDULES	X
P0.03	PLUMBING EQUIPMENT SCHEDULES, PIPE SIZING TABLES AND PRESSURE CALCULATIONS	X
P2.E0	BUILDING E - UNDERSLAB AND LEVEL 1 PLUMBING PLANS	X
P2.E1	BUILDING E - LEVEL 2 AND LEVEL 3 PLUMBING PLANS	X
P2.E2	BUILDING E - ROOF PLUMBING PLAN	X
P3.00	ENLARGED UNIT PLANS	X
P4.00	DETAILS	X
P4.01	DETAILS	X
P4.02	DETAILS	X
P6.E0	BUILDING E - WASTE DIAGRAMS	X
P6.E1	BUILDING E - WASTE DIAGRAMS	X

NO.	DATE	DESCRIPTION



DRAWN:	JMN
DESIGNED:	JMN
CHECKED:	JMN
APPROVED:	JMN

PROJECT: **EAST TOWN CROSSING - BUILDING E**
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

DATE: 3-8-2024

SHEET TITLE: LEGEND, GENERAL NOTES, & DRAWING INDEX

SHEET NO. **P0.00**

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-864-3343

ROBISON ENGINEERING, INC

PLUMBING TABLES

PLUMBING NOTES

PIPE INSULATION SCHEDULE

Table with columns: SERVICE, OPTION 1 (MATERIAL, THICKNESS), OPTION 2 (MATERIAL, THICKNESS), VAPOR RETARDER REQUIRED, NOTES. Rows include Domestic Cold Water, Roof Drain Bodies, Domestic Hot Water, and Exposed Sanitary Drains.

NOTES:

- 1. PIPING INSULATION EXPOSED TO THE WEATHER SHALL BE PROTECTED FROM DAMAGE... ADHESIVE TAPE SHALL NOT BE PERMITTED.
- 2. PER 2015 WSEC SECTION R403.5.3 (RESIDENTIAL) INSULATION FOR HOT WATER PIPE SHALL HAVE A MINIMUM R-VALUE OF R-3.
- 3. PIPING FROM WATER HEATER TO THE TERMINATION OF HEATED WATER SUPPLY PIPE SHALL BE INSULATED IN ACCORDANCE WITH TABLE C403.2.9.

WASHINGTON STATE-COMMERCIAL ENERGY CODE EFFICIENT HEATED WATER SUPPLY PIPING

Table with columns: NOMINAL PIPE SIZE (IN), METHOD #1 - PIPE LENGTH (RECOMMENDED), METHOD #2 - PIPE VOLUME, PIPE VOLUME (FLUID OZ / FEET), MAXIMUM ALLOWABLE PIPING LENGTH (FT), NOTES. Rows show pipe sizes from 3/8 to 2 OR LARGER.

PIPING SUPPORTS (SUPPLY)

Table with columns: SUPPORT TYPE, MAX. HORIZONTAL SPACING, MAX. VERTICAL SPACING. Rows include COPPER PIPE, COPPER TUBING, CPVC.

PIPING SUPPORTS (WASTE)

Table with columns: SUPPORT TYPE, MAX. HORIZ. SPACING, MAX. VERT. SPACING. Rows include ABS, PVC (TYPE DWV), CAST-IRON (<10 FT PIPE SECTIONS), CAST-IRON (10 FT PIPE SECTIONS).

PRE-CONSTRUCTION MEETING NOTES

CONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH THE ENGINEER FOR THE PURPOSE OF REVIEWING THE WORK PRIOR TO ORDERING ANY EQUIPMENT OR PERFORMING ANY WORK. THE MEETING SHALL BE LOCATED AT THE PROJECT SITE ON A DATE AND TIME TO BE MUTUALLY AGREED.

THE FOLLOWING TRADES SHALL BE REPRESENTED FOR THE MINIMUM TIME INDICATED:

Table with columns: TRADE, HOURS. Includes MECHANICAL SHEET METAL (4 HOURS), PLUMBING/PIPING (4 HOURS), ELECTRICAL (4 HOURS), SPRINKLER (2 HOURS), GENERAL CONTRACTOR (ALL SESSIONS).

APPLICABLE CODES

THE FOLLOWING PROJECT DESIGN IS BASED ON THE FOLLOWING CODES:

- 2015 INTERNATIONAL BUILDING CODE (IBC) & WASHINGTON STATE AMENDMENTS
- 2015 INTERNATIONAL MECHANICAL CODE (IMC) & WASHINGTON STATE AMENDMENTS
- 2015 UNIFORM PLUMBING CODE (UPC) & WASHINGTON STATE AMENDMENTS
- 2018 WASHINGTON STATE ENERGY CONSERVATION CODE (WSEC)
- 2015 INTERNATIONAL FUEL GAS CODE (IFGC) & WASHINGTON STATE AMENDMENTS

CONTRACTOR SUBSTITUTIONS & REVISIONS

PLEASE SUBMIT PROPOSALS FOR SUBSTITUTIONS OR REVISIONS FOR REVIEW AND APPROVAL PRIOR TO ORDERING MATERIAL OR DOING WORK. FOR EQUIPMENT THAT IS SCHEDULED BY MANUFACTURER'S NAME AND CATALOG DESIGNATIONS, THE MANUFACTURER'S PUBLISHED DATA AND/OR SPECIFICATION FOR THAT ITEM ARE CONSIDERED PART OF SPECIFICATION.

- 1. CONNECTIONS: PROVIDE PLUMBING FIXTURE CONNECTIONS TO BUILDING WASTE, VENT, COLD WATER, AND HOT WATER SYSTEM IN ACCORDANCE WITH DRAWINGS, MANUFACTURER'S RECOMMENDATIONS, AND LOCAL CODES.
- 2. HOT AND COLD: WATER PIPING CONNECTION TO EACH FIXTURE SHALL BE COLD WATER ON THE RIGHT HAND SIDE AND HOT WATER ON THE LEFT HAND SIDE.
- 24. PROVIDE EXPANSION LOOPS/EXPANSION JOINTS IN PIPING PER 2015 UPC TABLE 313.3 AND MANUFACTURER INSTALLATION INSTRUCTIONS.
- 25. PROVIDE APPROVED PIPE HANGERS & PIPE SUPPORTS IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS AND 2015 UPC TABLES 313.3 & 313.6. SUBMIT FOR APPROVAL.



Revision table with columns: DATE, DESCRIPTION, NO., JMN. Rows 1-11.

PROJECT: EAST TOWN CROSSING - BUILDING E, MULTIFAMILY DEVELOPMENT, PIONEER WAY & SHAW RD. PUYALLUP, WA. SHEET TITLE: PLUMBING NOTES, TABLES AND CODES.

DATE: 3-8-2024

SHEET TITLE: PLUMBING NOTES, TABLES AND CODES

SHEET NO. P0.01

PLUMBING FIXTURE UNIT COUNTS AND FIXTURE / DRAIN SCHEDULES

FIXTURE SCHEDULE											
PLAN MARK	FIXTURE TYPE	SERVICE SIZE - INCHES				LOCATION	FINISH	MANUFACTURER	BASIS OF DESIGN MODEL	FLOW RATE, GPM	NOTES
		CW	HW	W	V						
BT-1	BATH-TUB	1/2	1/2	2	1-1/2	TYPICAL APARTMENT	WHITE	AQUATIC	6030SM	1.75 GPM	1-5.7
	IN-WALL VALVE						N/A	45312			
	TRIM KIT						CHROME	CFG	40311CGR		
LV-1	LAVATORY	1/2	1/2	1-1/2	TYPICAL APARTMENT	WHITE	CASCADIAN	L1560	1.2 GPM	1-5	
	FAUCET					CHROME	PFISTER	LG1420600C			
KS-1	KITCHEN SINK	1/2	1/2	2	TYPICAL APARTMENT	STAINLESS	MOEN	G20193	1.8 GPM	1-5	
	FAUCET					CHROME	PEERLESS	P188152LF			
WC-1	WATER CLOSET	1/2	---	3	TYPICAL APARTMENT	WHITE	WESTERN POTTERY	B832, -T8ULF -HP	1.28 GPF	1-6	
	SEAT					WHITE	COMFORT SEATS	C014WD			
WB-1	WASHER BOX	3/4	3/4	2	1-1/2	TYPICAL APARTMENT	WHITE	SIoux CHIEF	696-2313	N/A	1-5
HB-1	WALL HYDRANT	3/4	---	---	---	PER DWGS.	N/A	WOODFORD	B65	N/A	1-3,5,8

NOTES:

- REFER TO ARCH PLANS FOR MOUNTING HEIGHT.
- CONTRACTOR SHALL CONFIRM MAKE, MODEL, AND FINISH OF ALL FIXTURES WITH OWNER, ARCHITECT, AND INTERIOR DESIGNER PRIOR TO ORDERING.
- PROVIDE RED/HOT AND BLUE/COLD WATER INDICATORS TO ALL FIXTURES.
- ALL FIXTURE P-TRAPS SHALL BE CHROME-PLATED BRASS.
- PROVIDE DAHL 1/4-TURN BALL VALVE ANGLE STOPS WITH BRAIDED STAINLESS STEEL FLEX CONNECTORS AT HOT AND COLD WATER SUPPLY TO EACH FIXTURE EXCEPT SHOWERS AND BATHS. PROVIDE SCREWDRIVER STOPS AT SHOWERS AND BATHS.
- FLUSH TRIGGER SHALL BE ON WIDE SIDE OF ROOM.
- SHOWERS AND TUB-SHOWER COMBINATIONS SHALL BE PROVIDED WITH MIXING VALVES PER UPC SECTION 408.3.
- PROVIDE LOCKABLE BOX.

DRAINS & CLEANOUTS SCHEDULE								
PLAN MARK	FIXTURE TYPE	SERVICE SIZE - INCHES		LOCATION	FINISH	MANUFACTURER	BASIS OF DESIGN MODEL	NOTES
		W	V					
FD-1	FLOOR DRAIN	4	2	PER DWGS.	CAST IRON	JR SMITH	2010	1
FS-1	FLOOR SINK	4	2	PER DWGS.	N/A	JR SMITH	3140	1
HD-1	HUB DRAIN	2	1-1/2	PER DWGS.	STAINLESS	JR SMITH	9654	1
FCO	FLOOR CLEANOUT	PER PLANS	N/A	PER DWGS.	CAST IRON	WADE	6000	1
WCO	WALL CLEANOUT	PER PLANS	N/A	PER DWGS.	CAST IRON	WADE	8560	1

NOTES:

- CONTRACTOR SHALL CONFIRM MAKE, MODEL, AND FINISH OF ALL FIXTURES WITH OWNER, ARCHITECT, AND INTERIOR DESIGNER PRIOR TO ORDERING.


FIXTURE UNIT CALCULATIONS - BUILDING B,C,D																																																																																																	
CALCULATIONS BASED ON 2015 UPC TABLES A103.1 AND 702.1.																																																																																																	
APARTMENTS																																																																																																	
FIXTURE	FIXTURE UNITS				FLOOR				TOTAL QTY OF FIXTURES	TOTAL FIXTURE UNITS																																																																																							
	TOTAL	CW	HW	W/V	1	2	3	R		SERVICE	CW ONLY	HW ONLY	W/V ONLY																																																																																				
LAVATORY (PRIVATE)	1	0.75	0.75	1	16	16	16		48	48	36	36	48																																																																																				
WATER CLOSET (PRIVATE, TANK)	2.5	2.5	0	3	16	16	16		48	120	120	0	144																																																																																				
BATH-TUB (PRIVATE)	4	3	3	2	16	16	16		48	192	144	144	96																																																																																				
KITCHEN SINK (PRIVATE)	1.5	1.125	1.125	2	8	8	8		24	36	27	27	48																																																																																				
DISHWASHER	1.5	0	1.5	0	8	8	8		24	36	0	36	0																																																																																				
CLOTHES WASHER	4	3	3	3	8	8	8		24	96	72	72	72																																																																																				
										528	399	315	408																																																																																				
PUBLIC SPACES / MISC.																																																																																																	
FIXTURE	FIXTURE UNITS				FLOOR				TOTAL QTY OF FIXTURES	TOTAL FIXTURE UNITS																																																																																							
	TOTAL	CW	HW	W/V	1	2	3	R		SERVICE	CW ONLY	HW ONLY	W/V ONLY																																																																																				
FLOOR DRAIN (2")	0	0	0	2	2				2	0	0	0	4																																																																																				
HOSE BIB	2.5/1	2.5/1	0	0	2				2	3.5	3.5	0	0																																																																																				
										3.5	3.5	0	4																																																																																				
<table style="width: 100%; border: none;"> <tr> <td style="width: 25%;">TOTAL FIXTURE UNITS:</td> <td style="width: 10%;">TOTAL</td> <td style="width: 10%;">CW</td> <td style="width: 10%;">HW</td> <td style="width: 10%;">W/V</td> <td colspan="9"></td> </tr> <tr> <td>DOMESTIC WATER PEAK FLOW:</td> <td>531.5</td> <td>402.5</td> <td>315</td> <td>412</td> <td colspan="9"></td> </tr> <tr> <td colspan="5"></td> <td colspan="4" style="text-align: center;">REQUIRED SERVICE SIZES IN BUILDING:</td> <td colspan="5"></td> </tr> <tr> <td colspan="5"></td> <td colspan="4" style="text-align: center;">DOMESTIC WATER</td> <td colspan="5" style="text-align: center;">SEWER SIZE</td> </tr> <tr> <td colspan="5"></td> <td colspan="4" style="text-align: center;">SERVICE SIZE: 3"</td> <td colspan="5" style="text-align: center;">6"</td> </tr> <tr> <td colspan="5"></td> <td colspan="4"></td> <td colspan="5" style="text-align: center;">1/4" PER FT</td> </tr> </table>														TOTAL FIXTURE UNITS:	TOTAL	CW	HW	W/V										DOMESTIC WATER PEAK FLOW:	531.5	402.5	315	412															REQUIRED SERVICE SIZES IN BUILDING:														DOMESTIC WATER				SEWER SIZE										SERVICE SIZE: 3"				6"														1/4" PER FT				
TOTAL FIXTURE UNITS:	TOTAL	CW	HW	W/V																																																																																													
DOMESTIC WATER PEAK FLOW:	531.5	402.5	315	412																																																																																													
					REQUIRED SERVICE SIZES IN BUILDING:																																																																																												
					DOMESTIC WATER				SEWER SIZE																																																																																								
					SERVICE SIZE: 3"				6"																																																																																								
									1/4" PER FT																																																																																								

PLUMBING FIXTURE FLOW RATES PER 2015 UPC CH. 4		
FIXTURE TYPE	FLOW RATE	NOTES
SHOWERHEADS	2.5 GPM @ 80 PSI	
LAVATORY FAUCETS, RESIDENTIAL	2.2 GPM @ 60 PSI	1
LAVATORY FAUCETS, NON-RESIDENTIAL	0.5 GPM @ 60 PSI	2
KITCHEN FAUCETS	2.2 GPM @ 60 PSI	3
GRAVITY TANK-TYPE WATER CLOSETS	1.6 GALLONS/FLUSH	4
FLUSHMETER TANK WATER CLOSETS	1.6 GALLONS/FLUSH	4
FLUSHMETER VALVE WATER CLOSETS	1.6 GALLONS/FLUSH	4
ELECTROMECHANICAL HYDRAULIC WATER CLOSETS	1.6 GALLONS/FLUSH	4
URINALS	1.0 GALLONS/FLUSH	

NOTES:

- LAVATORY FAUCETS SHALL NOT HAVE A FLOW RATE LESS THAN 0.8 GPM AT 20 PSI.
- WHERE COMPLYING FAUCETS ARE UNAVAILABLE, AERATORS RATED AT 0.35 GPM OR OTHER MEANS MAY BE USED TO ACHIEVE REDUCTION.
- KITCHEN FAUCETS MAY TEMPORARILY INCREASE FLOW ABOVE THE MAXIMUM RATE, BUT NOT ABOVE 2.2 GPM @ 60 PSI AND MUST DEFAULT TO A MAXIMUM FLOW RATE OF 1.8 GPM @ 60 PSI.
- INCLUDES SINGLE AND DUAL FLUSH WATER CLOSETS WITH AN EFFECTIVE FLUSH OF 1.6 GALLONS OR LESS. SINGLE FLUSH TOILETS - THE EFFECTIVE FLUSH VOLUME SHALL NOT EXCEED 1.6 GALLONS. THE EFFECTIVE FLUSH VOLUME IS THE AVERAGE FLUSH VOLUME WHEN TESTED IN ACCORDANCE WITH ASME A112.19.2 DUAL FLUSH TOILETS - THE EFFECTIVE FLUSH VOLUME SHALL NOT EXCEED 1.6 GALLONS. THE EFFECTIVE FLUSH VOLUME IS DEFINED AS THE COMPOSITE, AVERAGE FLUSH VOLUME OF TWO REDUCED FLUSHES AND ONE FULL FLUSH. FLUSH VOLUMES WILL BE TESTED IN ACCORDANCE WITH ASME A112.19.2 AND ASME A112.19.14.

REVISIONS	NO.	DATE	DESCRIPTION



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JMN	JMN	JMN	JMN

PROJECT: EAST TOWN CROSSING - BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 964-3343

DATE:
3-8-2024

SHEET TITLE:
PLUMBING FIXTURE
UNIT COUNTS AND
FIXTURE/DRAIN
SCHEDULE

SHEET NO.
P0.02

WATER SUPPLY PIPE SIZING CALCULATIONS

TYPE L COPPER SERVICE PIPING

Robison Engineering, Inc.
19401 40th Ave. W. Suite 302
Lynnwood, WA 98087

Project Name: EAST TOWN CROSSING
Project Number: 810-010
Edited By: JD
Edit Date: 1/22/2024

SIZING IS PER 2015 UPC APPENDIX A

WATER SUPPLY PIPE SIZING CALCULATION FORM

UTILITY SUPPLY WATER PRESSURE: 55 PSI STATIC PRESSURE
ASSUMING BUILDING PRESSURE

BOOSTER PUMP: 70 PSI
OUTLET PRESSURE

WATER SOFTENER LOSS: 0 PSI
TYPICALLY 5-20 PSI, IF NO SOFTENER ENTER "0".

STATIC LIFT: 30 FEET = 13.0 PSI

THERMOSTATIC MIXING VALVE LOSS: 0 PSI

REQUIRED MINIMUM PRESSURE AT FURTHEST PLUMBING FIXTURE: 25 PSI

PRESSURE AVAILABLE TO OFFSET FRICTION LOSSES: 32.0 PSI

PIPING SYSTEM LENGTH FROM SERVICE TO FURTHEST FIXTURE: 200 FEET
FITTING ALLOWANCE: 66.6667 FEET

MAXIMUM FRICTION LOSS FACTOR: 12.0 PSI/100 FT

SELECTED FRICTION LOSS FACTOR: 12.0 PSI/100 FT
MAX CW VELOCITY 8 FPS, MAX HW VELOCITY 5 FPS.

SUPPLY PIPE SIZING SCHEDULE						Copper Type: Type L	
FLUSH TANK CW			HOT WATER			FLUSH VALVE CW	
PIPE SIZE	FLOW, GPM	VEL. FPS	FIXTURE UNITS	FLOW, GPM	VEL. FPS	FIXTURE UNITS	FIXTURE UNITS
2-1/2"	116.0	8.0	440.0	72.0	5.0	215.0	116.0
3"	160.0	8.0	750.0	100.0	5.0	350.0	160.0
4"	280.0	8.0	1600.0	175.0	5.0	800.0	280.0
6"	650.0	8.0	5250.0	400.0	5.0	2750.0	650.0

PEX PIPING

Robison Engineering, Inc.
19401 40th Ave. W. Suite 302
Lynnwood, WA 98036

Project Name: East Town Crossing
Project Number: 810-010
Edited By: JD
Edit Date: 1/22/24

SIZING IS PER 2015 UPC APPENDIX A

WATER SUPPLY PIPE SIZING CALCULATION FORM

AVAILABLE PRESSURE BEFORE BOOSTER PUMP: 55 PSI

AVAILABLE PRESSURE AFTER BOOSTER PUMP: 70 PSI

STATIC LIFT TO HIGHEST FIXTURE: 30 FEET = 13.0 PSI

REQUIRED MINIMUM PRESSURE AT FURTHEST PLUMBING FIXTURE: 25 PSI

PRESSURE AVAILABLE TO OFFSET FRICTION LOSSES: 32.0 PSI

PIPING SYSTEM LENGTH FROM SERVICE TO FURTHEST FIXTURE: 200 FEET
FITTING ALLOWANCE: 66 FEET

MAXIMUM FRICTION LOSS FACTOR: 12.0 PSI/100 FT

SELECTED FRICTION LOSS FACTOR: 12.0 PSI/100 FT
MAX HW & CW VELOCITY 8 FPS

SUPPLY PIPE SIZING SCHEDULE				PIPE MATERIAL
PIPE SIZE	FLOW, GPM	VELOCITY FPS	FIXTURE UNITS	
1/2"	3.5	8.00	3.0	PEX
3/4"	7.9	8.00	9.0	PEX
1"	14.6	8.00	20.0	PEX
1-1/4"	27.8	8.00	33.0	PEX
1-1/2"	30.3	8.00	54.0	PEX
2"	52.0	8.00	134.0	PEX
2-1/2"	79.2	8.00	270.0	PEX
3"	112.6	8.00	440.0	PEX

PLUMBING EQUIPMENT SCHEDULES

PIPE MATERIALS

PIPE TYPE	MATERIAL	JOINT	NOTES
UNDERGROUND WATER SERVICE ENTRANCE PIPING	PVC	SOLVENT CEMENT	
WATER DISTRIBUTION PIPING – MAINS ADN RISERS	SCHEDULE 80 CPVC	SOLVENT CEMENT	
WATER DISTRIBUTION PIPING – UNIT FIXTURE RUN-OUTS	PEX	EXPANSION FITTINGS	3
WASTE & VENT PIPING	SCHEDULE 40 SOLID CORE PVC OR ABS	SOLVENT CEMENT	4
STORM PIPING	SCHEDULE 40 SOLID CORE PVC OR ABS	SOLVENT CEMENT	
CONDENSATE DRAIN PIPING	CPVC OR PEX	SOLVENT CEMENT OR EXPANSION FITTINGS	

NOTES:

- ALL SANITARY SYSTEM MATERIALS SHALL BE LISTED BY AN APPROVED LISTING AGENCY.
- NOT USED
- PROVIDE THERMAL EXPANSION LOOPS FOR ALL CPVC PIPING PER MANUFACTURER REQUIREMENTS.
- NOT TO BE USED WHERE EXPOSED IN RETURN AIR PLENUM (METAL PIPING REQUIRED IN RETURN AIR PLENUMS.) USE CAST IRON FOR PIPING IN PLENUM.

WATER HEATER SCHEDULE - ELECTRIC

EQUIP. TAG	LOCATION	SERVICE	HEAT RECOVERY	STORAGE CAPACITY, GAL	INLET/OUTLET CONNECTION	HEATER, KW	OPERATING WEIGHT (LBS)	ELECTRICAL	BOD ENERGY FACTOR	BASIS OF DESIGN	NOTES
WH-1	APARTMENT	DOMESTIC HOT WATER (EA. UNIT)	21 GPH @ 90°F TR	30	3/4"	4.5	360	240V/1P	0.94	AMERICAN STANDARD EN30T-6	1,2,3,4

NOTES:

- WATER HEATER RECOVERY AND POWER REQUIREMENT ARE BASED ON NON-SIMULTANEOUS OPERATION.
- FOR WATER HEATER PIPING, SEE PIPING DIAGRAM DETAIL 1 ON P7.00.
- PROVIDE DRAIN PAN FOR WATER HEATER.

EXPANSION TANK

EQUIP. TAG	LOCATION	SERVICE	CAPACITY GAL.	TANK SIZE, IN		OPERATING WEIGHT, LBS	BASIS OF DESIGN	NOTES
				DIAMETER	HEIGHT			
ET-1	APARTMENT	DOMESTIC HOT WATER (EA. UNIT)	2	8	13	25	AMTROL ST-5	1,2

NOTES:

- INSTALL ACCORDING TO MANUFACTURER'S REQUIREMENTS
- EXPANSION TANK PRE-CHARGE PRESSURE SHALL BE SET TO INLET WATER STATIC PRESSURE AT INSTALLATION.

REDUCED PRESSURE BACKFLOW ASSEMBLY

EQUIP. TAG	SERVICE	INLET/OUTLET SIZE	DESIGN FLOW, GPM	PRESSURE DROP, PSI	MAX WATER PRESSURE, PSI	BASIS OF DESIGN	NOTES
RPBA-1	DOMESTIC WATER	3"	105	15	175	ZURN 3750SY	1,2

NOTES:

- COMPLIES WITH AWWA C551-92 STANDARDS.
- PROVIDE DRAIN TO NEAREST INDIRECT WASTE RECEPTOR.

PACKAGED BOOSTER PUMP SCHEDULE

EQUIP NO.	SERVICE	TYPE	TOTAL FLOW, GPM	PRESSURE RISE (INLET/OUTLET) PSIG	MOTOR HP (EACH)	ELECTRICAL	FLA (AMPS)	WEIGHT, LBS	BASIS OF DESIGN
BP-1	DOMESTIC WATER	DUPLEX	103	30 (40/70)	2	208V/3P	13.3	730	FLOWTHERM FMV2-3LH (1)(2)(3)

- NOTES: (1) SINGLE POINT POWER CONNECTION.
(2) PROVIDE ALL REQUIRED VALVES, PIPING, CONTROLS, ETC. FOR A COMPLETE SYSTEM.
(3) PROVIDE VFD'S FOR EACH PUMP.

NO.	DATE	DESCRIPTION



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JMN	JMN	JMN	JMN

PROJECT: EAST TOWN CROSSING - BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-964-3343




DATE:
3-8-2024

SHEET TITLE:
PLUMBING
EQUIPMENT
SCHEDULES, PIPE
SIZING TABLES AND
PRESSURE
CALCULATIONS

SHEET NO.

P0.03



NOTES:

- WASTE & VENT SIZING: WASTE & VENT PIPING SIZED PER 2018 UPC CHAPTER 7. WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT:

PIPE SIZE	VERT.	HORIZ.	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

- PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS. SEE DETAIL 2, P9.00.
- NOT ALL FIXTURE PIPING SHOWN HERE. SEE RISER DIAGRAMS AND ENLARGED PLANS FOR ADDITIONAL FIXTURE PIPING AND SUDS RELIEF REQUIREMENTS.


W# = WASTE/VENT RISER IDENTIFICATION ON SHEETS P6.B0 & P6.B1 (I.E RISER "#")

FLAG NOTES:

- REFER TO TYPICAL ENLARGED PLAN S2 ON SHEET P3.00 FOR SUPPLY PIPING ROUTING WITHIN UNIT.

BUILDING E LEVEL 1 – PLUMBING PLAN

SCALE: 1/8" = 1'-0"




NO.	DATE	DESCRIPTION



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JMN	JMN	JMN	JMN

BUILDING E UNDERSLAB – PLUMBING PLAN

SCALE: 1/8" = 1'-0"




NOTES:

- WASTE & VENT SIZING: WASTE & VENT PIPING SIZED PER 2018 UPC CHAPTER 7. WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT:

PIPE SIZE	VERT.	HORIZ.	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

- PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS. SEE DETAIL 2, P9.00.
- NOT ALL FIXTURE PIPING SHOWN HERE. SEE RISER DIAGRAMS AND ENLARGED PLANS FOR ADDITIONAL FIXTURE PIPING AND SUDS RELIEF REQUIREMENTS.


W# = WASTE/VENT RISER IDENTIFICATION ON SHEETS P6.B0 & P6.B1 (I.E RISER "#")



PROJECT: EAST TOWN CROSSING - BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA


ROBISON ENGINEERING, INC.
19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: (206) 964-3343

DATE: 3-8-2024
SHEET TITLE: BUILDING E – UNDERSLAB AND LEVEL 1 PLUMBING PLANS
SHEET NO. P2.E0



BUILDING E LEVEL 3 – PLUMBING PLAN

SCALE: 1/8" = 1'-0"



NOTES:

- WASTE & VENT SIZING: WASTE & VENT PIPING SIZED PER 2018 UPC CHAPTER 7. WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT:


PIPE SIZE	VERT.	HORIZ.	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

- PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS. SEE DETAIL 2, P9.00.
- NOT ALL FIXTURE PIPING SHOWN HERE. SEE RISER DIAGRAMS AND ENLARGED PLANS FOR ADDITIONAL FIXTURE PIPING AND SUDS RELIEF REQUIREMENTS.

W# = WASTE/VENT RISER IDENTIFICATION ON SHEETS P6.B0 & P6.B1 (I.E RISER "#")


FLAG NOTES: #

- REFER TO TYPICAL ENLARGED PLAN S1 ON SHEET P3.00 FOR SUPPLY PIPING ROUTING WITHIN UNIT.



BUILDING E LEVEL 2 – PLUMBING PLAN

SCALE: 1/8" = 1'-0"



NOTES:

- WASTE & VENT SIZING: WASTE & VENT PIPING SIZED PER 2018 UPC CHAPTER 7. WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT:

PIPE SIZE	VERT.	HORIZ.	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

- PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS. SEE DETAIL 2, P9.00.
- NOT ALL FIXTURE PIPING SHOWN HERE. SEE RISER DIAGRAMS AND ENLARGED PLANS FOR ADDITIONAL FIXTURE PIPING AND SUDS RELIEF REQUIREMENTS.

W# = WASTE/VENT RISER IDENTIFICATION ON SHEETS P6.B0 & P6.B1 (I.E RISER "#")

FLAG NOTES: #

- REFER TO TYPICAL ENLARGED PLAN S1 ON SHEET P3.00 FOR SUPPLY PIPING ROUTING WITHIN UNIT.

REVISIONS	DESCRIPTION
NO.	DATE



JMN	JMN	JMN	JMN
DRAWN:	DESIGNED:	CHECKED:	APPROVED:

PROJECT: EAST TOWN CROSSING - BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-964-3343

ROBISON ENGINEERING, INC.

DATE:
3-8-2024

SHEET TITLE:
BUILDING E –
LEVEL 2 AND
LEVEL 3 PLUMBING
PLANS

SHEET NO.
P2.E1



NOTES:

1. WASTE & VENT SIZING: WASTE & VENT PIPING SIZED PER 2018 UPC CHAPTER 7. WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT:

PIPE SIZE	VERT.	HORIZ.	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU


2. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS. SEE DETAIL 2, P9.00.
3. STORM DRAINAGE: ROOF IS SLOPED AND DRAINAGE IS VIA GUTTERS AND DOWNSPOUTS. REFER TO ARCHITECTURAL PLANS FOR DOWNSPOUTS LOCATIONS.

FLAG NOTES:

1. VENT TO ROOF. VENT TO BE 10' MINIMUM FROM ANY FRESH AIR INTAKE.

BUILDING E ROOF - PLUMBING PLAN

SCALE: 1/8" = 1'-0"



NO.	DATE	DESCRIPTION



JMN	JMN	JMN	JMN
DRAWN:	DESIGNED:	CHECKED:	APPROVED:


PROJECT: EAST TOWN CROSSING - BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUVALUP, WA

ROBISON ENGINEERING, INC.
 19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PH: 206-864-3343


DATE:
 3-8-2024

SHEET TITLE:
 BUILDING E -
 ROOF PLUMBING
 PLAN

SHEET NO.
P2.E2



TYPICAL ENLARGED
 ADA 2 BATHROOM UNIT
 SCALE: 1/4" = 1'-0"



TYPICAL ENLARGED
 2 BATHROOM UNIT
 SCALE: 1/4" = 1'-0"

- FLAG NOTES:
- COLD WATER PIPE. REFER TO FLOOR PLANS FOR CONTINUATION.
 - HOT & COLD WATER PIPING MANIFOLD. VIEGA MANABLOC MODEL V5030.5 OR EQUAL. MANIFOLD SHALL BE NSF/ANSI 61 @ 372 CERTIFIED.
 - ACCESS PANEL.

ABBREVIATION LEGEND / FIXTURE UNIT VALUES:

LV = LAVATORY	(1 WSFU)
BT = BATHTUB/SHOWER COMBO	(4 WSFU)
KS = KITCHEN SINK WITH DISHWASHER	(1.5 WSFU)
WB = WASHER BOX	(4 WSFU)
WC = WATER CLOSET	(2.5 WSFU)

NO.	DATE	DESCRIPTION



DRAWN:	JMN
DESIGNED:	JMN
CHECKED:	JMN
APPROVED:	JMN


PROJECT: **EAST TOWN CROSSING - BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343

DATE:
 3-8-2024

SHEET TITLE:
 ENLARGED UNIT PLANS

SHEET NO.
P3.00




INTERIOR WALL CLEANOUT (WCO) EXTERIOR CLEANOUT TO GRADE (COTG) (LIGHT TRAFFIC AREA) INTERIOR FLOOR CLEANOUT (FCO)

CLEANOUTS

DETAIL

SCALE: NONE

6
P4.00




HUB DRAIN

DETAIL

SCALE: NONE

5
P4.00




RISER PIPE SUPPORT


DETAIL

SCALE: NONE

4
P4.00



INTERIOR WALLS




EXTERIOR WALLS ABOVE GRADE

PIPE SLEEVES THROUGH WALLS

DETAIL

SCALE: NONE

3
P4.00




WATER HEATER SEISMIC STRAPPING

DETAIL

SCALE: NONE

2
P4.00



WATER SERVICE PIPING DIAGRAM

SCALE: NONE

1
P4.00

NO.	DATE	DESCRIPTION



NO.	DATE	DESCRIPTION

NO.	DATE	DESCRIPTION

PROJECT: **EAST TOWN CROSSING - BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343

ROBISON ENGINEERING, INC.

DATE: 3-8-2024


SHEET TITLE: DETAILS

SHEET NO. **P4.00**




**RESIDENTIAL DISHWASHER CONNECTION
DETAIL**
SCALE: NONE

6
P4.01



**TYPICAL VALVE PLACEMENT
DETAIL**
SCALE: NONE

5
P4.01




**PEX MANIFOLD
DETAIL**
SCALE: NONE

4
P4.01


NOTES:

1. MINIMUM BEND RADIUS FOR PEX PIPING IS 6 TIMES THE TUBING DIAMETER.
2. FOR UNUSED PORTS, INSTALL VALVE AND CAP FOR FUTURE USE.
3. REFER TO PLUMBING RISER DIAGRAM FOR PIPE SIZING FROM RISERS.
4. PROVIDE GROMMETS OR SLEEVES PER MANUFACTURER'S RECOMMENDATIONS WHERE PEX PASSES THROUGH METAL STUDS AND WHERE PIPE ABRASION COULD OCCUR.
5. PROVIDE SHUT OFF VALVE TO MAINS.
6. PEX RUNOUT PIPING SHALL MEET THE FOLLOWING REQUIREMENTS:
 - 6.1. MAX WATER VOLUME ALLOWED PER 2015 WSEC 403.2 FOR HOT WATER RUNOUTS IS 0.5 GALLONS.




**VENT TERMINATION
DETAIL**
SCALE: NONE

3
P4.01



**VENT TERMINATION
DETAIL**
SCALE: NONE

2
P4.01



**VENT THROUGH ROOF
DETAIL**
SCALE: NONE

1
P4.01

REVISIONS	DESCRIPTION	DATE
NO.		



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JMN	JMN	JMN	JMN

PROJECT: EAST TOWN CROSSING - BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

ROBISON ENGINEERING, INC.

DATE:
3-8-2024

SHEET TITLE:
DETAILS

SHEET NO.
P4.01

NO.	DATE	DESCRIPTION



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JWN	JWN	JWN	JWN

PROJECT: **EAST TOWN CROSSING - BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA



19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343

ROBISON ENGINEERING, INC.

DATE:
3-8-2024


SHEET TITLE:
DETAILS

SHEET NO.
P4.02



WATER HEATER
DETAIL
 SCALE: NONE


4
P4.02



INSTALL CW ROUGH-IN APPROXIMATELY 8" AFF
 (CONFIRM ELEVATION WITH ARCH PLANS).

WATER CLOSET CW SUPPLY
DETAIL
 SCALE: NONE


3
P4.02



PER UPC SECTION 908, BATHROOM GROUP
 FIXTURES SHALL BE PERMITTED TO BE
 VENTED BY A HORIZONTAL WET VENT.


PRIVATE BATHROOM WET VENTING
DETAIL
 SCALE: NONE

2
P4.02



PIPE SLAB PENETRATION
DETAIL
 SCALE: NONE

1
P4.02



RISER DIAGRAM
SCALE: NONE

RISER DIAGRAM
SCALE: NONE

RISER DIAGRAM
SCALE: NONE

GENERAL NOTES

1. PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 6/P901.
2. WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.
3. PROVIDE EXPANSION JOINTS FOR PVC WASTE AND VENT STACKS THAT EXCEED 30' PER 2018 UPC TABLE 313.3 AND MANUFACTURER INSTALLATION INSTRUCTIONS.
4. PROVIDE CLEANOUTS FOR WASTE STACKS AND KITCHEN SINK DRAINS AT THE LOWEST LEVEL PER 2018 UPC SECTION 707.0.

ABBREVIATION LEGEND:

LV = LAVATORY	(1 DFU)
BT = BATHTUB	(2 DFU)
KS = KITCHEN SINK WITH DISHWASHER	(2 DFU)
WB = WASHER BOX	(3 DFU)
WC = WATER CLOSET	(3 DFU)
FD = FLOOR DRAIN	(2 DFU)
FS = FLOOR SINK	(4 DFU)
HD = HUB DRAIN	(4 DFU)
SH = SHOWER	(2 DFU)

= WASTE/VENT RISER IDENTIFICATION (I.E. RISER "#").

FLAG NOTES

PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

NO.	DATE	DESCRIPTION



DRAWN:	DESIGNED:	CHECKED:	APPROVED:
JMN	JMN	JMN	JMN


PROJECT: EAST TOWN CROSSING - BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

ROBISON ENGINEERING, INC.
19401 40TH AVE W. SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-964-3343


DATE:
3-8-2024

SHEET TITLE:
BUILDING B -
WASTE RISER
DIAGRAMS


SHEET NO.
P6.E0




RISER DIAGRAM
SCALE: NONE



RISER DIAGRAM
SCALE: NONE



RISER DIAGRAM
SCALE: NONE



GENERAL NOTES

- PROVIDE TRAP PRIMERS FOR ALL FLOOR DRAINS PER 2018 UPC 1007.1. SEE DETAIL 6/P901.
- WASTE & VENT SIZING: WASTE & VENT PIPING IS SIZED PER 2018 UPC TABLE 703.2. DRAINAGE PIPING SHALL BE SLOPED AT 1/4" PER FOOT OR 2%. WHERE IT IS IMPRACTICAL TO OBTAIN A SLOPE OF 2% DUE TO THE DEPTH OF THE STREET SEWER OR TO STRUCTURAL FEATURES OF THE BUILDING, DRAINAGE PIPING MAY BE SLOPED AT 1/8" PER FOOT OR 1% WITH APPROVAL FROM THE AHJ.
- PROVIDE EXPANSION JOINTS FOR PVC WASTE AND VENT STACKS THAT EXCEED 30' PER 2018 UPC TABLE 313.3 AND MANUFACTURER INSTALLATION INSTRUCTIONS.
- PROVIDE CLEANOUTS FOR WASTE STACKS AND KITCHEN SINK DRAINS AT THE LOWEST LEVEL PER 2018 UPC SECTION 707.0.

PIPE SIZE	VERTICAL	HORIZONTAL	VENT
1 1/2"	2 DFU	1 DFU	8 DFU
2"	16 DFU	8 DFU	24 DFU
3"	48 DFU	35 DFU	84 DFU
4"	256 DFU	216 DFU	256 DFU
6"	1,380 DFU	720 DFU	1,380 DFU
8"	3,600 DFU	2,640 DFU	3,600 DFU

ABBREVIATION LEGEND:

LV = LAVATORY	(1 DFU)
BT = BATHTUB	(2 DFU)
KS = KITCHEN SINK WITH DISHWASHER	(2 DFU)
WB = WASHER BOX	(3 DFU)
WC = WATER CLOSET	(3 DFU)
FD = FLOOR DRAIN	(2 DFU)
FS = FLOOR SINK	(4 DFU)
HD = HUB DRAIN	(4 DFU)
SH = SHOWER	(2 DFU)

= WASTE/VENT RISER IDENTIFICATION (I.E. RISER "#").

FLAG NOTES

NO.	DATE	DESCRIPTION



JMN	JMN	JMN	JMN
DRAWN:	DESIGNED:	CHECKED:	APPROVED:

PROJECT: **EAST TOWN CROSSING - BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W. SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-964-3343

ROBISON ENGINEERING, INC.

DATE:
3-8-2024

SHEET TITLE:
BUILDING B -
WASTE RISER
DIAGRAMS

SHEET NO.
P6.E1

SYMBOLS

GENERAL

LIGHT LINE INDICATES NON-ELECTRICAL OR BACKGROUND (THIS IS NOT CONTRACTUAL DEFINITION OF WORK)
HEAVY LINE INDICATES NEW WORK (THIS IS NOT CONTRACTUAL DEFINITION OF WORK)

DETAIL IDENTIFICATION

SYMBOL

1 FLAG NOTE
REVISION NOTE
REVISION DEFINITION, AREA ENCLOSED CONTAINS DRAWING CHANGES MADE SUBSEQUENT TO PREVIOUS ISSUE

SWITCHES

\$s SWITCH, SINGLE POLE; WITH SWITCHING SUBSCRIPT
\$os OCCUPANCY SENSOR SWITCH
D SWITCH, SINGLE POLE; WITH SWITCHING SUBSCRIPT "D" INDICATES WALLBOX DIMMER
C CEILING MOUNTED OCCUPANCY SENSOR
\$1 SWITCH, TIMER.
\$3 SWITCH, THREE WAY.

RECEPTACLES

Single Receptacle, Duplex Receptacle: Wall Mounted, +18" AFF, Duplex Receptacle - Above Counter, Duplex GFCI, Duplex GFCI +42", Double Duplex Receptacle: Wall Mounted, +18" AFF, Floor Box One Duplex Receptacle, Floor Box One Duplex Receptacle + One Data, Floor Box One Duplex Receptacle + One Data + One Voice, Special Purpose Receptacle, AS NOTED

MISCELLANEOUS

JUNCTION BOX: 4SQ MOUNTED, JUNCTION BOX: 4SQ WALL MOUNTED, JUNCTION BOX: 4SQ TRACK, CONNECTION FOR LIGHTED MIRROR COORDINATE LOCATION AND ELEVATION WITH ARCHITECT PRIOR TO ROUGH-IN, THERMOSTAT

SIGNAL/COMMUNICATION

DATA OUTLET: WALL MOUNTED @ +18" AFF U.O.N., TELEPHONE/DATA OUTLET: WALL MOUNTED @ +18" AFF U.O.N., TELEVISION OUTLET: WALL MOUNTED @ +18" AFF U.O.N.

POWER

PANELBOARD, NON-FUSED DISCONNECT SWITCH (WP = NEMA 3R WHERE APPROPRIATE), FUSED DISCONNECT SWITCH, MOTOR CONNECTION (EQUIPMENT NAME, HORSEPOWER, VOLTAGE, AND PHASE INDICATED), EQUIPMENT CONNECTION (EQUIPMENT NAME, LOAD, VOLTAGE, AND PHASE INDICATED), TRANSFORMER, DRY TYPE, SHOWN TO SCALE, KW METER AND BASE

FACP FIRE ALARM SYSTEM CONTROL PANEL, P FIRE ALARM SYSTEM PULL STATION, Fire Alarm System Strobe/Speaker, Fire Alarm Photoelectric Smoke Detector and Speaker, Fire Alarm Combination Photoelectric Smoke Detector, Carbon Monoxide Detector, and Speaker, Guestroom, Carbon Monoxide Detector, Electro-Magnetic Door Holder, DSD DUCT SMOKE DETECTOR

ABBREVIATIONS

A AMPERE, AC ALTERNATING CURRENT, ABOVE COUNTER, AFF ABOVE FINISHED FLOOR, AIC AMPS INTERRUPTING CAPACITY, AL ALUMINUM, AMP AMPERE, AWG AMERICAN WIRE GAUGE, BKR BREAKER, BLDG BUILDING, C COIL OF CONDUIT, CKT CIRCUIT, CO CONDUIT/RACEWAY ONLY, CT CURRENT TRANSFORMER, Cu COPPER, CW COOL WHITE, D DIMMER, DED DEDICATED, EC ELECTRICAL CONTRACTOR, EF EXHAUST FAN, ELEC ELECTRICAL, EMT ELECTRICAL METALLIC TUBING, EQUIP EQUIPMENT, EXIST EXISTING, FAA FIRE ALARM ANNUNCIATOR, FACP FIRE ALARM CONTROL PANEL, FLUOR FLUORESCENT, GC GENERAL CONTRACTOR, GFCI GROUND FAULT CIRCUIT INTERRUPTER, GND GROUND, GRS GALVANIZED RIGID STEEL, HID HIGH INTENSITY DISCHARGE, HP HORSEPOWER, IG ISOLATED GROUND, KCMIL THOUSAND CIRCULAR MILLS, KVA KILOVOLT AMPERES, KW KILOWATT, LITG LIGHTING, LV LOW VOLTAGE, MFR MANUFACTURER, MIN MINIMUM, MLO MAIN LUGS ONLY, N NEUTRAL, NEC NATIONAL ELECTRICAL CODE (NFPA-70), NEMA NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION, NOT TO SCALE, NTS NATIONAL ELECTRICAL CODE (NFPA-70), PNL PANEL, POC POINT OF CONNECTION, PT POTENTIAL TRANSFORMER, PVC POLYVINYL CHLORIDE, PWR POWER, QTY QUANTITY, RECEPT RECEPTACLE, REF REFERENCE, RI ROUGH-IN, RM ROOM, RO RACEWAY ONLY, SHT SHEET, SPEC SPECIFICATIONS, SW SWITCH, SWBD SWITCHBOARD, SWGR SWITCHGEAR, TYP TYPICAL, UG UNDERGROUND, UL UNDERWRITERS LABORATORIES, UON UNLESS OTHERWISE NOTED, V VOLTS, W WATTS, WW WARM WHITE, WP WEATHERPROOF, W/ WITH, W/O WITHOUT, XFMR TRANSFORMER, XFR TRANSFER, Z IMPEDANCE OR ZONE

GENERAL NOTES

GENERAL
1. PROVIDE ELECTRICAL INSTALLATION IN ACCORDANCE WITH THE GOVERNING ELECTRICAL CODE, LOCAL CODES, ORDINANCES AND REQUIREMENTS OF UTILITY COMPANIES FURNISHING SERVICES TO INSTALLATION.
2. PROVIDE ALL WORK AND ITEMS NECESSARY FOR COMPLETE AND FUNCTIONAL ELECTRICAL SYSTEMS. THE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND DO NOT NECESSARILY SHOW EVERY CONDUIT, BOX, CONDUCTOR OR SIMILAR ITEMS FOR A COMPLETE INSTALLATION.
3. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID AND DETERMINE CONDITIONS WHICH MAY AFFECT BID. ANY ITEMS NOT FULLY UNDERSTOOD SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO BIDDING.
4. "REF" INDICATIONS DENOTE WORK COVERED ELSEWHERE (ARCHITECTURAL, STRUCTURAL, OR MECHANICAL).
5. REFERENCE ARCHITECTURAL DRAWING FOR EXACT LOCATION OF DEVICES. QUESTIONS CONCERNING THE LOCATION OF DEVICES AND EQUIPMENT SHALL BE DIRECTED TO THE ARCHITECT. FAILURE TO COORDINATE REQUIREMENTS SHALL IN NO WAY RESULT IN ADDITIONAL COMPENSATION BEING PROVIDED TO THE CONTRACTOR.
6. WHEREVER THE WORD "PROVIDE" IS USED, IT MEANS, "FURNISH AND INSTALL COMPLETE AND READY FOR USE."
7. COORDINATE LOCATION OF ELECTRICAL WITH OTHER TRADES.
8. REFER TO EQUIPMENT DRAWINGS FOR MECHANICAL CHARACTERISTICS (SIZE, LOCATION, ETC.) OF MECHANICAL EQUIPMENT, UNLESS OTHERWISE INDICATED. COORDINATE INSTALLATION AND LOCATION OF ALL EQUIPMENT WITH MECHANICAL CONTRACTOR. VERIFY ALL FUSE RATINGS, WIRE SIZES AND DISCONNECT SIZES PRIOR TO INSTALLATION.
MATERIALS AND METHODS
1. PROVIDE RACEWAY AND WIRING ROUTED CONCEALED WITHIN BUILDING STRUCTURE WHERE POSSIBLE. WHERE RACEWAY CANNOT BE CONCEALED, IT SHALL BE INSTALLED PER PROJECT MANAGER'S DIRECTION. ALL CONDUIT SHALL BE INSTALLED IN NEAT SYMMETRICAL LINES HORIZONTAL OR PERPENDICULAR TO BUILDING COLUMNS AND ROOF LINES. CONDUITS SHALL BE GROUPED ON COMMON SUPPORTS WHEREVER POSSIBLE.
2. EXPOSED CONDUIT ROUTING: CONDUITS MAY BE ROUTED EXPOSED IN MECHANICAL AND ELECTRICAL ROOMS ONLY. EXPOSED CONDUITS SHALL BE SECURED A MINIMUM OF 6" ABOVE FLOOR.
3. OUTDOOR EXPOSED CONDUIT ROUTING: CONDUITS ROUTED ON ROOF OR EXPOSED TO WEATHER SHALL BE GRC, PVC OR LIQUID-TIGHT FLEX. PROVIDE WATER-TIGHT CONNECTIONS AND FITTINGS.
4. CLEARANCES: VERIFY PHYSICAL DIMENSIONS OF EQUIPMENT TO ENSURE THAT ACCESS CLEARANCES CAN BE MET.
5. CONNECTIONS: PROVIDE GRS, METALLIC FLEX, OR LIQUIDTITE FLEX CONDUITS FOR CONNECTIONS TO MOTORS OR MOTORIZED EQUIPMENT.
6. WIRING: PROVIDE MINIMUM #12 AWG WIRE SIZE. IF CONDUIT IS TO BE USED MINIMUM IS TO BE 1/2". FLEXIBLE CONDUIT AND FLEXIBLE CABLE IS PERMISSIBLE THROUGHOUT THE BUILDING.
7. WIRING: PROVIDE MINIMUM #10 AWG COPPER CONDUCTOR SIZE IN 120V BRANCH CIRCUIT RUNS OVER 75' IN LENGTH.
SITE ELECTRICAL
1. TRENCHING: COORDINATE ALL TRENCHING WORK WITH OTHER UTILITY LOCATIONS AND DRAINAGE TRENCHES.
2. UNDERGROUND CONDUITS: PROVIDE PVC, SCHEDULE 40, 3/4" MINIMUM. PROVIDE GRC CONDUIT TRANSITION ELBOW WHEN TURNING UP TO ABOVE GRADE.
3. DIRECT-BURIED CONDUITS: CONDUIT FOR BRANCH CIRCUITS OUTSIDE BUILDINGS NOT BENEATH DRIVEWAYS OR PARKING AREAS SHALL BE DIRECTLY BURIED WITHOUT CONCRETE ENCASEMENT. THE DEPTH TO THE TOP OF BURIED CONDUITS SHALL BE 36". PROVIDE MARKER TAPE 12" BELOW GRADE.
4. BELOW SLAB: CONDUIT ROUTED BELOW ON-GRADE FLOOR SLABS SHALL BE INSTALLED PRIOR TO FLOOR SLAB POUR. ROUTE CONDUITS BELOW SLAB AS STRAIGHT AS POSSIBLE TO MINIMIZE BENDS.
5. ALL CONDUITS PENETRATING THE BUILDING ENVELOPE BELOW GRADE SHALL FOLLOW WATERPROOFING REQUIREMENTS IN THE ARCHITECTURAL DRAWINGS.
NEUTRALS
1. AT CONTRACTORS OPTION, NEUTRALS MAY BE SHARED ON COMBINED HOMERUNS UNLESS THE CIRCUIT HAS A GFCI BREAKER, AN ISOLATED GROUND, OR IS FROM A PANEL WITH TVSS PROTECTION. ANY NEUTRAL DOWNSTREAM FROM A DIMMER SHALL BE DEDICATED TO THE DIMMED LOAD.
2. NEUTRAL WIRES SHOWN FOR TWO AND THREE POLE MECHANICAL AND KITCHEN EQUIPMENT MAY BE OMITTED UPON VERIFICATION THAT THEY ARE NOT REQUIRED EITHER FOR OPERATION OR CONTROL CIRCUITS PER MANUFACTURER'S SPECIFICATIONS.
LIGHTING
1. PROVIDE LIGHT FIXTURES WITH PROPER FITTING FLANGES, MOUNTING SUPPORTS, AND ACCESSORY ITEMS, UL LISTED FOR CONDITIONS OF USE.
LOW VOLTAGE LIGHTING
1. PROVIDE LOW VOLTAGE TRANSFORMERS IN NEARBY ACCESSIBLE CEILING SPACE.
2. PROVIDE LOW VOLTAGE CONDUCTORS SIZED PER MANUFACTURER'S GUIDELINES TO MINIMIZE VOLTAGE DROP.
LIGHTING CONTROL
1. THE MAXIMUM LIGHTING POWER THAT MAY BE CONTROLLED FROM A SINGLE SWITCH OR AUTOMATIC CONTROL SHALL NOT EXCEED THAT WHICH IS PROVIDED BY A TWENTY AMPERE CIRCUIT LOADED TO NOT MORE THAN EIGHTY PERCENT. A MASTER CONTROL MAY BE INSTALLED PROVIDED THE INDIVIDUAL SWITCHES RETAIN THEIR CAPABILITY TO FUNCTION INDEPENDENTLY.
2. EMERGENCY FIXTURES: EMERGENCY BATTERY/CHARGER SHALL BE CONNECTED TO AN UNSWITCHED LEG OF THE DESIGNATED CIRCUIT.

GENERAL REQUIREMENTS

1. DRAWINGS ARE DIAGRAMMATIC, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT, AND EQUIPMENT REQUIRED.
2. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENT.
3. REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS.
4. REFER TO MANUFACTURER'S STANDARD INSTALLATION DRAWINGS FOR EQUIPMENT CONNECTIONS AND INSTALLATION REQUIREMENTS.
5. PROVIDE CONNECTIONS, ACCESSORIES, OFFSETS, AND MATERIALS NECESSARY FOR A COMPLETE SYSTEM.

CONTRACTOR SUBSTITUTIONS & REVISIONS

1. PLEASE SUBMIT PROPOSALS FOR SUBSTITUTIONS OR REVISIONS FOR REVIEW AND APPROVAL PRIOR TO ORDERING MATERIAL OR DOING WORK.
2. FOR EQUIPMENT THAT IS SCHEDULED BY MANUFACTURER'S NAME AND CATALOG DESIGNATIONS, THE MANUFACTURER'S PUBLISHED DATA AND/OR SPECIFICATION FOR THAT ITEM ARE CONSIDERED PART OF SPECIFICATION.
3. ENGINEERING COSTS FOR REVISING MEP PLANS SHALL BE ADDRESSED IN THE COST ANALYSIS OF THE SUBSTITUTION PROPOSAL.
4. CONTRACTOR TO COORDINATE WITH ENGINEER AND DETERMINE ASSOCIATED DESIGN AND PERMITTING COSTS. CONTRACTOR SHALL BE RESPONSIBLE FOR OTHER COSTS ASSOCIATED WITH UNFORESEEN ISSUES RESULTING FROM SUBSTITUTIONS OR REVISIONS.

PRE-CON MEETING NOTES

CONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH THE ENGINEER FOR THE PURPOSE OF REVIEWING THE WORK PRIOR TO ORDERING ANY EQUIPMENT OR PERFORMING ANY WORK. THE MEETING SHALL BE LOCATED AT THE PROJECT SITE ON A DATE AND TIME TO BE MUTUALLY AGREED. THE MEETING WILL BE A WORKING SESSION. THE MEETING WILL BE FACILITATED BY THE ENGINEER AND THE AGENDA WILL INCLUDE A DETAILED REVIEW OF THE PLANS AND SPECIFICATIONS, CROSS CHECK WITH OTHER TRADES FOR COORDINATION ISSUES, REVIEW OF PROPOSED PRODUCTS, REVIEW OF PLANNED MEANS AND METHODS, AND ON-SITE INVESTIGATION OF FIELD CONDITIONS RELATIVE TO EXISTING CONDITIONS THAT COULD AFFECT THE WORK. PERSONS ATTENDING THE MEETING SHALL BE KNOWLEDGEABLE OF THE PROJECT AND SHALL BE THE SPECIFIC PERSONS INTENDED TO CONTINUE WITH THE PROJECT THROUGH TO COMPLETION. IF REQUIRED, REVISED PLANS WILL BE ISSUED THROUGH OFFICIAL CHANNELS. CHANGES IN THE BID PRICE WILL BE DISCUSSED, BUT NO CHANGE ORDERS WILL BE ISSUED UNLESS PROCESSED THROUGH OFFICIAL CHANNELS. IT SHALL BE UNDERSTOOD THAT THE ENGINEER HAS NO AUTHORITY TO ISSUE CHANGE ORDERS.
THE FOLLOWING TRADES SHALL BE REPRESENTED FOR THE MINIMUM TIME INDICATED:

Table with 2 columns: Trade Name, Hours. Includes MECHANICAL SHEET METAL (4 HOURS), PLUMBING/PIPING (4 HOURS), ELECTRICAL (4 HOURS), SPRINKLER (2 HOURS), GENERAL CONTRACTOR (ALL SESSIONS).

DRAWING INDEX

Table with columns: DWG, DESCRIPTION, PERMIT SET, and INCLUDED IN SET. Lists drawings like LEGEND, GENERAL NOTES, DRAWING INDEX, SITE POWER PLAN, SITE LIGHTING PLAN, LIGHTING PLAN - LEVEL 1, etc.

Table with columns: REVISIONS, DESCRIPTION, DATE, NO.




Table with columns: DRAWN, DESIGNED, CHECKED, APPROVED. Lists names: LYSAK K., STEINKE M.

PROJECT: EAST TOWN CROSSING BUILDING E MULTIFAMILY DEVELOPMENT PIONEER WAY & SHAW RD. PUYALLUP, WA. Includes Robison Engineering, Inc. logo and address: 19401 40TH AVE W, SUITE 302, LYNNWOOD, WA 98036.



PERMIT SET 03/08/2024

SHEET TITLE: LEGEND, GENERAL NOTES, DRAWING INDEX

SHEET NO. E0.00




VICINITY MAP



BUILDING F & E SITE PLAN – POWER

SCALE: 1" = 30'



NO.	DATE	DESCRIPTION



DRAWN:	CHECKED: STEINKE M.
DESIGNED:	APPROVED: STEINKE M.

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-364-3343





DATE:
03-08-2024

SHEET TITLE:
SITE PLAN

SHEET NO.
E0.02




VICINITY MAP



BUILDING E SITE LIGHTING PLAN – POWER

SCALE: 1" = 30'



NO.	DATE	REVISIONS DESCRIPTION



DRAWN:	DESIGNED:	CHECKED: STEINKE M.	APPROVED: STEINKE M.
--------	-----------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-834-3343


DATE:
03-08-2024

SHEET TITLE:
LIGHTING PLAN

SHEET NO.
E0.03

GENERAL NOTES

1. MOUNTING HEIGHT (MH) LISTED IN LUMINAIRE SCHEDULE SHALL BE FROM ABOVE GRADE TO BOTTOM OF COMPLETE EXPOSED FIXTURE.
2. ALL EXTERIOR MOUNTED LIGHTING SHALL BE CONTROLLED BY PHOTOCONTROL OR ASTRONOMIC TIME-CLOCK SCHEDULING PER CALIFORNIA ENERGY CODE (CENC) REQUIREMENTS 160.5(c)2. PROVIDE MOTION SENSING CONTROLS FOR LUMINAIRES OVER 40 WATTS MOUNTED LESS THAN 24' ABOVE GRADE AND WALL MOUNTED LUMINAIRES MORE THAN 24' ABOVE GRADE.
3. ALL EXTERIOR MOUNTED LUMINAIRES SHALL FOLLOW MAXIMUM ALLOWABLE BACKLIGHT, UPLIGHT AND GLARE (BUG) RATINGS FOUND IN CALIFORNIA GREEN BUILDING STANDARDS CODE TABLE 5.106.8.
4. DURING EMERGENCY CONDITIONS EMERGENCY LIGHTING CIRCUITS SHALL BYPASS ALL LIGHTING CONTROLS IN ORDER TO ENERGIZE ALL CONNECTED LUMINAIRES AT FULL CAPACITY. PROVIDE UL924 RELAYS AS REQUIRED TO BYPASS AREA CONTROLS.
 - 4.1. EMERGENCY PATHWAY EGRESS LIGHTING: EMERGENCY LIGHTING FACILITIES SHALL BE ARRANGED TO PROVIDE INITIAL ILLUMINATION THAT IS NOT LESS THAN AN AVERAGE OF 1 FOOTCANDLE. (CBC 1008.3.5)



NO.	DATE	REVISIONS DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-834-3343

PERMIT SET
 03/08/2024

SHEET TITLE:
LIGHTING PLAN - LEVEL 1


SHEET NO.
 E1.01

LIGHTING PLAN - LEVEL 1
 SCALE: 1/8" = 1'-0"



GENERAL NOTES

1. MOUNTING HEIGHT (MH) LISTED IN LUMINAIRE SCHEDULE SHALL BE FROM ABOVE GRADE TO BOTTOM OF COMPLETE EXPOSED FIXTURE.
2. ALL EXTERIOR MOUNTED LIGHTING SHALL BE CONTROLLED BY PHOTOCONTROL OR ASTRONOMIC TIME-CLOCK SCHEDULING PER CALIFORNIA ENERGY CODE (CEC) REQUIREMENTS 160.5(c)2. PROVIDE MOTION SENSING CONTROLS FOR LUMINAIRES OVER 40 WATTS MOUNTED LESS THAN 24' ABOVE GRADE AND WALL MOUNTED LUMINAIRES MORE THAN 24' ABOVE GRADE.
3. ALL EXTERIOR MOUNTED LUMINAIRES SHALL FOLLOW MAXIMUM ALLOWABLE BACKLIGHT, UPLIGHT AND GLARE (BUG) RATINGS FOUND IN CALIFORNIA GREEN BUILDING STANDARDS CODE TABLE 5.106.8.
4. DURING EMERGENCY CONDITIONS EMERGENCY LIGHTING CIRCUITS SHALL BYPASS ALL LIGHTING CONTROLS IN ORDER TO ENERGIZE ALL CONNECTED LUMINAIRES AT FULL CAPACITY. PROVIDE UL924 RELAYS AS REQUIRED TO BYPASS AREA CONTROLS.
 - 4.1. EMERGENCY PATHWAY EGRESS LIGHTING: EMERGENCY LIGHTING FACILITIES SHALL BE ARRANGED TO PROVIDE INITIAL ILLUMINATION THAT IS NOT LESS THAN AN AVERAGE OF 1 FOOTCANDLE. (CBC 1008.3.5)



NO.	DATE	REVISIONS DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-864-3343


ROBISON ENGINEERING, INC.

PERMIT SET
03/08/2024

SHEET TITLE:
LIGHTING PLAN - LEVEL 2


SHEET NO.
E1.02

LIGHTING PLAN - LEVEL 2
SCALE: 1/8" = 1'-0" 0' 4' 8' 16'



GENERAL NOTES

1. MOUNTING HEIGHT (MH) LISTED IN LUMINAIRE SCHEDULE SHALL BE FROM ABOVE GRADE TO BOTTOM OF COMPLETE EXPOSED FIXTURE.
2. ALL EXTERIOR MOUNTED LIGHTING SHALL BE CONTROLLED BY PHOTOCONTROL OR ASTRONOMIC TIME-CLOCK SCHEDULING PER CALIFORNIA ENERGY CODE (CENC) REQUIREMENTS 160.5(c)2. PROVIDE MOTION SENSING CONTROLS FOR LUMINAIRES OVER 40 WATTS MOUNTED LESS THAN 24' ABOVE GRADE AND WALL MOUNTED LUMINAIRES MORE THAN 24' ABOVE GRADE.
3. ALL EXTERIOR MOUNTED LUMINAIRES SHALL FOLLOW MAXIMUM ALLOWABLE BACKLIGHT, UPLIGHT AND GLARE (BUG) RATINGS FOUND IN CALIFORNIA GREEN BUILDING STANDARDS CODE TABLE 5.106.8.
4. DURING EMERGENCY CONDITIONS EMERGENCY LIGHTING CIRCUITS SHALL BYPASS ALL LIGHTING CONTROLS IN ORDER TO ENERGIZE ALL CONNECTED LUMINAIRES AT FULL CAPACITY. PROVIDE UL924 RELAYS AS REQUIRED TO BYPASS AREA CONTROLS.
 - 4.1. EMERGENCY PATHWAY EGRESS LIGHTING: EMERGENCY LIGHTING FACILITIES SHALL BE ARRANGED TO PROVIDE INITIAL ILLUMINATION THAT IS NOT LESS THAN AN AVERAGE OF 1 FOOTCANDLE. (CBC 1008.3.5)



NO.	DATE	REVISIONS DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343


ROBISON ENGINEERING, INC

PERMIT SET
 03/08/2024

SHEET TITLE:
LIGHTING PLAN - LEVEL 3

SHEET NO.
 E1.03

LIGHTING PLAN — LEVEL 3
 SCALE: 1/8" = 1'-0" 0' 4' 8' 16'




PHOTOMETRIC NOTES


1. PHOTOMETRIC CALCULATIONS BASED ON AVAILABLE IES FILE FROM FIXTURE MANUFACTURER (OR EQUIVALENT). FIXTURE SUBSTITUTIONS MAY COMPROMISE FOOT CANDLE LEVELS.
2. PHOTOMETRIC CALCULATIONS MEASURED AT GRADE LEVEL FROM CEILING HEIGHT OR MOUNTING HEIGHT (MH) NOTED IN LUMINAIRE SCHEDULE.
3. SITE PHOTOMETRIC: BASED ON PROPOSED SITE LIGHTING FOR PROJECT ONLY.

Egress Photometric Schedule

AVERAGE FOOT-CANDLES	1.73
MAXIMUM FOOT-CANDLES	4.2
MINIMUM FOOT-CANDLES	0.1
MINIMUM TO MAXIMUM FC RATIO	0.03



NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA

19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343

PERMIT SET
 03/08/2024

SHEET TITLE:
PHOTOMETRIC PLAN - LEVEL 1

SHEET NO.
 E1.10

PHOTOMETRIC PLAN - LEVEL 1
 SCALE: 1/8" = 1'-0"

EXTERIOR & SITE LUMINAIRE SCHEDULE

CALLOUT	SYMBOL	MOUNTING	DESCRIPTION	MODEL	VOLTAGE	TYPE	CRI / CCT	LAMPING	WATTAGE
CP1	○	SURFACE	CARPORT LIGHT - TYPE 5 - B1 U0 G1	GARDCO: SVPG A01 830 5CD [MOUNTING] UNV	MULTIPLE	0-10V DIMMING	80 / 3000K	(1) 21W LED	21
SB1	○	3' BOLLARD	BOLLARD - TYPE 5 - B1 U0 G0	GARDCO: PUREFORM BOLLARD / PBL 36 14L 100 WW-G2 5 UNV	MULTIPLE	0-10V DIMMING	70 / 3000K	(1) 6W LED	6
SB1A	⊕	3' BOLLARD	BOLLARD - TYPE 3 - B0 U0 G0	GARDCO: PUREFORM BOLLARD / PBL 36 14L 100 WW-G2 3 UNV	MULTIPLE	0-10V DIMMING	70 / 3000K	(1) 6W LED	6
SF1	⊕	SURFACE	MONUMENT SIGN FLOOD LIGHT	TBD	120	TBD		(1) 15W LED	15
SP1	○	16' POLE	POST TOP LIGHT - TYPE 5 - B2 U3 G2	WE-EF: ZFT434LED / 115-1283	MULTIPLE	0-10V DIMMING	80 / 3000K	(1) 42W LED	42
SP2	○	16' POLE	POLE LIGHT - SPORT COURT - B1 U0 G2 - TYPE 3	SIGNIFY - GARDCO: P15 P A03 730 T3M AR1 UNV PCB [FINISH]	MULTIPLE	0-10V DIMMING	80 / 3000K	(1) 45W LED	45
SU1	⊕	TREE BAND	UPLIGHT - ACCENT	HK LIGHTING: ZXLI61 120V 5W 30K 010 / TMS120 TS - WATER TIGHT FITTING - CORD & PLUG BY ELECTRICAL	120	0-10V DIMMING		(1) 10W LED	10
SW1	⊕	SURFACE	EXTERIOR SCONCE - STAIRS - NB UP / TYPE II DOWN - MH 10'	PERFORMANCE IN LIGHTING: AMON / 070274	MULTIPLE	0-10V DIMMING	80 / 3000K	(1) 37W LED	37
SW2	⊕	SURFACE	SECURITY LIGHT - TRASH ENCLOSURES	STONCO: SL20 SCT G1 8 BK	MULTIPLE	INTEGRAL MOTION & PHOTOCCELL	70 / 3000K	(1) 20W LED	20
WP1	⊕	SURFACE	WALL PACK - PARKING - TYPE III - B2 U0 G2 - MH 18'	GARDCO: PUREFORM COMFORT OPTICS / PWS 140L 1150 WW-G2 3 X UNV	MULTIPLE	AS NEEDED	70 / 3000K	(1) 52W LED	52
WP2	⊕	SURFACE	WALL PACK - POOL - TYPE IV - B3 U0 G3 - MH 14'	GARDCO: PUREFORM COMFORT OPTICS / PWS 140L 1675 WW-G2 4 UNV	MULTIPLE	AS NEEDED		(1) 76W LED	76

- CONTRACTOR TO FURNISH AND INSTALL ALL FIXTURES.
- FIXTURE FINISHES TO BE COORDINATED WITH ARCHITECT/ID.

DWELLING UNIT LUMINAIRE SCHEDULE

CALLOUT	SYMBOL	LAMP	MOUNTING	DESCRIPTION	MODEL	VOLTAGE	WATTAGE	NOTES
T1	⊕	(1)	CEILING	SURFACE MOUNT LED LIGHT	OSTW: OW-LFMDR-14D2130-NK	120V 1P 2W	21	
T2	⊕	(1)	CEILING	SURFACE MOUNT LED	OSTW: OW-LDS01-6D1530N	120V 1P 2W	15	
T3	○	(1)	CEILING	FAN/LIGHT COMBO	KICHLER: 330017NI	120V 1P 2W	52	PROVIDE DIVA: DVFSQ-LF CONTROLLER IN UNITS DESIGNATED AS ACCESSIBLE PER ARCHITECTUAL
T4	⊕	(1)	PENDANT	LED CHANDELIER	OSTW: OW-LSFDR-12D1530-NK	120V 1P 2W	15	
T5	●	(1)	CEILING	LAUNDRY LIGHT/HOUSE FAN COMBO	BROAN: LP50100DC	120V 1P 2W	45	
T6	●	(1)	CEILING	BATH FAN/LIGHT COMBO	ORB: OSP70L	120V 1P 2W	45	
T7	⊕	(1)	WALL	LED VANITY LIGHT	KICHLER: 5337NIS	120V 1P 2W	27	(3) BULBRITE 9W LED BULBS: ITEM #774006
T8	⊕	(1)	WALL	EXT. LED SCONCE		120V 1P 2W	20	
T9	○	(1)	CEILING	SURFACE MOUNT LED	OSTW: OW-LDS0B-6D1830W	120V 1P 2W	18	
T13	□	(1)	CEILING	1.4 LED TROFFER	TBD	120V 1P 2W	40	

- CONTRACTOR TO FURNISH AND INSTALL ALL FIXTURES.
- FIXTURE FINISHES TO BE COORDINATED WITH ARCHITECT/ID.

GENERAL LIGHTING NOTES

- LIGHTING CONTROLS SHALL BE INSTALLED WHICH MEET ALL REQUIREMENTS OF LOCAL ENERGY CODES.
- EMERGENCY LIGHT FIXTURES: PROVIDE UNSWITCHED HOT FOR BATTERY CHARGER.
- LOCATIONS OF OCCUPANCY SENSORS, PHOTO SENSORS, DIMMERS, AND SWITCHES ARE DIAGRAMMATIC. CONTRACTOR TO FIELD-IDENTIFY OPTIMAL LOCATIONS AND QUANTITIES.
- ASSURE COMPATIBILITY OF DIMMERS WITH CONTROLLED LUMINAIRES PRIOR TO PURCHASING.
- AUTOMATIC LIGHTING SHUT-OFF CONTROLS SHALL BE PROVIDED BY LOCAL OCCUPANCY SENSORS AND/OR ASTRONOMIC TIME CLOCK UNLESS OTHERWISE NOTED.
- DAYLIGHT ZONES ARE REFERRED TO AS 'PRIMARY' AND 'SECONDARY' ON PLANS AND DENOTED BY DASHED LINES.
- FOR CUSTOM FF&E FIXTURES, IT IS THE MANUFACTURER'S RESPONSIBILITY TO FURNISH PRODUCTS WHICH ARE COMPLIANT WITH ALL REQUIREMENTS OF LOCAL ENERGY CODES, AS WELL AS MATCH THE ELECTRICAL SPECIFICATIONS PROVIDED IN THE LUMINAIRE SCHEDULES. PROVIDE SUBMITTAL SHOP DRAWINGS WITHIN 30 DAYS OF RECEIVING FIXTURE ORDER. SUBMITTALS SHALL CLEARLY INDICATE LAMPING AND MAXIMUM WATTAGE RATING OF LAMP SOCKETS. NON-COMPLIANT FIXTURES REJECTED BY ELECTRICAL INSPECTOR SHALL BE RETURNED TO THE MANUFACTURER FOR REWORKING AND/OR RE-LABELING.
- EMERGENCY EGRESS LIGHTING TO BE CONFIRMED AS INTENDED EGRESS DESIGN PRIOR TO PERMITTING

EXIT SIGN NOTES

DURING CONSTRUCTION, UPON COMPLETION OF A TYPICAL FLOOR FRAMING AND BEFORE WALL COVER, ELECTRICAL CONTRACTOR SHALL WALK THE EGRESS PATHS WITH THE LOCAL INSPECTOR (AHJ) TO CONFIRM THAT ALL THE EXIT SIGNS ARE LOCATED PER THE AHJ'S SATISFACTION AND IDENTIFY ANY ADDITIONAL EXIT SIGNS THAT THE AHJ WISHES TO BE INSTALLED. CONTRACTOR SHALL INCLUDE IN THEIR BASE BID UP TO 10% ADDITIONAL EXIT SIGNS (HIGH & LOW) AT NO ADDITIONAL COST. INCLUDE COST OF FIXTURES AND ASSOCIATED WIRING AND INSTALLATION.


LIGHTING CONTROL SYSTEM REQUIREMENTS

- CONTRACTOR TO PROVIDE A FULLY OPERATIONAL LIGHTING CONTROL SYSTEM.
- ELECTRICAL CONTRACTOR SHALL COORDINATE WITH A LIGHTING CONTROLS VENDOR TO OBTAIN LIGHTING CONTROL SYSTEM PACKAGE COMPLETE WITH DEVICES, WIRING DIAGRAMS, ANNOTATED PLANS INDICATING WHICH DEVICE TO BE USED IN EACH LOCATION, CONNECTION REQUIREMENTS, SET UP INSTRUCTIONS, COMMISSIONING AND CHECK-OUT FOLLOWING COMPLETION. PROVIDE ALL LOW VOLTAGE WIRING AS REQUIRED FOR CONTROL DEVICE INTERCONNECTIONS.
- INSTALLER QUALIFICATIONS: TECHNICIAN INSTALLING AND WIRING THE LIGHTING CONTROL SYSTEM SHALL HAVE INSTALLED THIS SAME SYSTEM AT LEAST ONCE PREVIOUSLY. TECHNICIAN SHALL HAVE RECEIVED TRAINING BY FACTORY REPRESENTATIVE ON THE SYSTEM BEING INSTALLED.
- PROVIDE LIGHTING CONTROL SYSTEM TO PERFORM THE FUNCTIONS DESCRIBED BELOW AND WHERE INDICATED ON PLANS. NOT ALL FEATURES ARE REQUIRED.
 - CONTROL EXTERIOR LIGHTING BASED ON ASTRONOMIC TIME-CLOCK SCHEDULING.
 - INTERIOR PRIMARY AND SECONDARY DAYLIGHT HARVESTING CONTROL PER ENERGY CODE REQUIREMENTS.
 - PROVIDE SEPARATE SWITCHING AND DIMMING CONTROL FOR LIGHTING ZONES AS INDICATED IN LIGHTING DIMMING SCHEDULE.
- DURING EMERGENCY CONDITIONS EMERGENCY LIGHTING CIRCUITS SHALL BYPASS ALL LIGHTING CONTROLS IN ORDER TO ENERGIZE ALL CONNECTED LUMINAIRES AT FULL CAPACITY. PROVIDE UL924 RELAYS AS REQUIRED TO BYPASS AREA CONTROLS.

LIGHTING CONTROLS LEGEND

⊕ ⊕	TOGGLE SWITCH FOR MANUAL ON/OFF LIGHTING CONTROL. SUBSCRIPT INDICATES WHICH FIXTURES ARE TO BE CONTROLLED BY WHICH SWITCH.
⊕ ⊕	DIMMER SWITCH FOR MANUAL MULTI-LEVEL LIGHTING CONTROL. SWITCH SHALL ALSO HAVE MANUAL ON/OFF FUNCTIONALITY. SUBSCRIPT INDICATES WHICH FIXTURES ARE TO BE CONTROLLED BY WHICH DIMMER.
OS OS	SWITCHES LABELED 'OS' SHALL TURN OFF ALL CONNECTED LUMINAIRES WITHIN 30 MINUTES OF SPACE BEING VACANT.
⊕	OCCUPANCY SENSOR SHALL AUTOMATICALLY TURN OFF ALL CONNECTED LUMINAIRES WITHIN 30 MINUTES OF SPACE BEING VACANT.
⊕	PHOTOSENSOR FOR DAYLIGHT ZONE CONTROL SHALL AUTOMATICALLY ADJUST THE LIGHT OUTPUT OF ALL CONNECTED LUMINAIRES BASED ON THE DAYLIGHT LEVEL IN THE SPACE.

NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-864-3343

ROBISON ENGINEERING, INC.

PERMIT SET
 03/08/2024

SHEET TITLE:
LIGHTING NOTES & LUMINAIRE SCHEDULE

SHEET NO.
 E1.50



SHEET NOTES:

1. PROVIDE CONDUITS WITH PULL WIRE FROM DEMARCATION OR MDF TO IDF CLOSETS FOR ALL SYSTEMS INCLUDING VOICE, DATA, TV AND SECURITY. QUANTITY AND SIZE AS DETERMINED BY LOW VOLTAGE CONSULTANT. PROVIDE SLEEVES WITH BUSHINGS AT BOTH ENDS PER LOW VOLTAGE CONSULTANT. FIRE STOP AS REQUIRED BY AHJ
2. PROVIDE CONDUIT, WIRING, CIRCUITS AND CONNECTIONS AS COORDINATED WITH SECURITY VENDOR FOR FULLY FUNCTIONING SECURITY AND ACCESS CONTROL SYSTEM. COORDINATE WITH SECURITY CONSTRUCTION DOCUMENTS TO IDENTIFY ALL CAMERA LOCATIONS, AT ALL DOORS CALLED OUT BY OWNER, AS WELL AS ROLL UP GARAGE DOORS FOR GARAGE ACCESS.
3. AMENITY SPACES, OFFICES AND PUBLIC AREAS: ROUGH-IN FOR EQUIPMENT, OUTLETS AND APPLIANCES IN AMENITY SPACES TO BE COORDINATED WITH ARCHITECT. REFER TO ARCHITECTS DRAWINGS AND ELEVATIONS.
4. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10
5. CONTRACTOR TO COORDINATE DOOR CONTROLS AND CONNECTIONS WITH DOOR VENDOR. PROVIDE RACEWAY, CONDUCTORS, POWER SUPPLY AND TERMINATIONS FOR A FULLY FUNCTIONING SYSTEM. COORDINATE WITH SECURITY VENDOR FOR MONITORING AND CONTROL AS NEEDED.
6. ELECTRICAL CONTRACTOR (EC) TO PROVIDE J-BOX/PULL BOX SO NUMBER OF BENDS IN CONDUIT DOES NOT EXCEED CODE REQUIREMENT (360 MAX TOTAL). EC TO FIELD VERIFY LOCATION OF J-BOX/PULL BOX. COORDINATE WITH ARCHITECT WHERE ACCESS PANEL IS REQUIRED.
7. PROVIDE BLOCKOUTS AND SLEEVES AS REQUIRED FOR ALL FEEDERS AND RISERS SHOWN ON 1-LINE. COORDINATE WITH STRUCTURAL. PROVIDE SUPPORT FOR VERTICAL FEEDERS AS REQUIRED BY NEC 300.19. ANY SLEEVE LOCATIONS SHOWN ARE DIAGRAMMATIC ONLY. ELECTRICAL PLANS DO NOT SHOW BRANCH CIRCUIT OR SMALL FEEDER CONDUIT RUNS. LAYOUT PER EC. FINAL VERIFICATION OF NUMBER AND LOCATION OF ALL FLOOR PENETRATIONS BY EC.

FLAG NOTES: (NOT EVERY FLAG IS USED ON EVERY SHEET)

1. PROVIDE LOCKING COVER FOR EXTERIOR & CORRIDOR RECEPTACLES. TYP.
2. LEAVE 2" OF OPEN WALL SPACE ADJACENT TO HOUSE PANEL FOR FUTURE EV PANEL.
3. PROVIDE (1) 2" CONDUIT FROM TELEPHONE VAULT AND (1) 2" CONDUIT FROM THE CABLE TV VAULT. COORDINATE WITH TELECOM UTILITY FOR TELEPHONE & CABLE TV VAULT LOCATIONS.

NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-834-3343

ROBISON ENGINEERING, INC.

PERMIT SET
 03/08/2024


SHEET TITLE:
POWER PLAN - LEVEL 1

SHEET NO.
 E3.00



SHEET NOTES:

1. PROVIDE CONDUITS WITH PULL WIRE FROM DEMARCATION OR MDF TO IDF CLOSETS FOR ALL SYSTEMS INCLUDING VOICE, DATA, TV AND SECURITY. QUANTITY AND SIZE AS DETERMINED BY LOW VOLTAGE CONSULTANT. PROVIDE SLEEVES WITH BUSHINGS AT BOTH ENDS PER LOW VOLTAGE CONSULTANT. FIRE STOP AS REQUIRED BY AHJ
2. PROVIDE CONDUIT, WIRING, CIRCUITS AND CONNECTIONS AS COORDINATED WITH SECURITY VENDOR FOR FULLY FUNCTIONING SECURITY AND ACCESS CONTROL SYSTEM. COORDINATE WITH SECURITY CONSTRUCTION DOCUMENTS TO IDENTIFY ALL CAMERA LOCATIONS, AT ALL DOORS CALLED OUT BY OWNER, AS WELL AS ROLL UP GARAGE DOORS FOR GARAGE ACCESS.
3. AMENITY SPACES, OFFICES AND PUBLIC AREAS: ROUGH-IN FOR EQUIPMENT, OUTLETS AND APPLIANCES IN AMENITY SPACES TO BE COORDINATED WITH ARCHITECT. REFER TO ARCHITECTS DRAWINGS AND ELEVATIONS.
4. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10
5. CONTRACTOR TO COORDINATE DOOR CONTROLS AND CONNECTIONS WITH DOOR VENDOR. PROVIDE RACEWAY, CONDUCTORS, POWER SUPPLY AND TERMINATIONS FOR A FULLY FUNCTIONING SYSTEM. COORDINATE WITH SECURITY VENDOR FOR MONITORING AND CONTROL AS NEEDED.
6. ELECTRICAL CONTRACTOR (EC) TO PROVIDE J-BOX/PULL BOX SO NUMBER OF BENDS IN CONDUIT DOES NOT EXCEED CODE REQUIREMENT (360 MAX TOTAL). EC TO FIELD VERIFY LOCATION OF J-BOX/PULL BOX. COORDINATE WITH ARCHITECT WHERE ACCESS PANEL IS REQUIRED.
7. PROVIDE BLOCKOUTS AND SLEEVES AS REQUIRED FOR ALL FEEDERS AND RISERS SHOWN ON 1-LINE. COORDINATE WITH STRUCTURAL. PROVIDE SUPPORT FOR VERTICAL FEEDERS AS REQUIRED BY NEC 300.19. ANY SLEEVE LOCATIONS SHOWN ARE DIAGRAMMATIC ONLY. ELECTRICAL PLANS DO NOT SHOW BRANCH CIRCUIT OR SMALL FEEDER CONDUIT RUNS. LAYOUT PER EC. FINAL VERIFICATION OF NUMBER AND LOCATION OF ALL FLOOR PENETRATIONS BY EC.

FLAG NOTES:  (NOT EVERY FLAG IS USED ON EVERY SHEET)

1. PROVIDE LOCKING COVER FOR EXTERIOR & CORRIDOR RECEPTACLES. TYP.
2. LEAVE 2" OF OPEN WALL SPACE ADJACENT TO HOUSE PANEL FOR FUTURE EV PANEL.
3. PROVIDE (1) 2" CONDUIT FROM TELEPHONE VAULT AND (1) 2" CONDUIT FROM THE CABLE TV VAULT. COORDINATE WITH TELECOM UTILITY FOR TELEPHONE & CABLE TV VAULT LOCATIONS.

NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA



19401 40TH AVE W. SUITE 302
 LYNNWOOD, WA 98036
 PHONE: (206) 964-3343


ROBISON ENGINEERING, INC

PERMIT SET
 03/08/2024

SHEET TITLE:
POWER PLAN - LEVEL 2

SHEET NO.
 E3.01

POWER PLAN - LEVEL 2 
 SCALE: 1/8" = 1'-0" 



SHEET NOTES:

1. PROVIDE CONDUITS WITH PULL WIRE FROM DEMARCATION OR MDF TO IDF CLOSETS FOR ALL SYSTEMS INCLUDING VOICE, DATA, TV AND SECURITY. QUANTITY AND SIZE AS DETERMINED BY LOW VOLTAGE CONSULTANT. PROVIDE SLEEVES WITH BUSHINGS AT BOTH ENDS PER LOW VOLTAGE CONSULTANT. FIRE STOP AS REQUIRED BY AHJ
2. PROVIDE CONDUIT, WIRING, CIRCUITS AND CONNECTIONS AS COORDINATED WITH SECURITY VENDOR FOR FULLY FUNCTIONING SECURITY AND ACCESS CONTROL SYSTEM. COORDINATE WITH SECURITY CONSTRUCTION DOCUMENTS TO IDENTIFY ALL CAMERA LOCATIONS, AT ALL DOORS CALLED OUT BY OWNER, AS WELL AS ROLL UP GARAGE DOORS FOR GARAGE ACCESS.
3. AMENITY SPACES, OFFICES AND PUBLIC AREAS: ROUGH-IN FOR EQUIPMENT, OUTLETS AND APPLIANCES IN AMENITY SPACES TO BE COORDINATED WITH ARCHITECT. REFER TO ARCHITECTS DRAWINGS AND ELEVATIONS.
4. WIRING METHOD FOR APARTMENT FEEDERS MUST BE SUITABLE FOR THE TYPE OF CONSTRUCTION. SEE NEC 334.10
5. CONTRACTOR TO COORDINATE DOOR CONTROLS AND CONNECTIONS WITH DOOR VENDOR. PROVIDE RACEWAY, CONDUCTORS, POWER SUPPLY AND TERMINATIONS FOR A FULLY FUNCTIONING SYSTEM. COORDINATE WITH SECURITY VENDOR FOR MONITORING AND CONTROL AS NEEDED.
6. ELECTRICAL CONTRACTOR (EC) TO PROVIDE J-BOX/PULL BOX SO NUMBER OF BENDS IN CONDUIT DOES NOT EXCEED CODE REQUIREMENT (360 MAX TOTAL). EC TO FIELD VERIFY LOCATION OF J-BOX/PULL BOX. COORDINATE WITH ARCHITECT WHERE ACCESS PANEL IS REQUIRED.
7. PROVIDE BLOCKOUTS AND SLEEVES AS REQUIRED FOR ALL FEEDERS AND RISERS SHOWN ON 1-LINE. COORDINATE WITH STRUCTURAL. PROVIDE SUPPORT FOR VERTICAL FEEDERS AS REQUIRED BY NEC 300.19. ANY SLEEVE LOCATIONS SHOWN ARE DIAGRAMMATIC ONLY. ELECTRICAL PLANS DO NOT SHOW BRANCH CIRCUIT OR SMALL FEEDER CONDUIT RUNS. LAYOUT PER EC. FINAL VERIFICATION OF NUMBER AND LOCATION OF ALL FLOOR PENETRATIONS BY EC.

FLAG NOTES: (NOT EVERY FLAG IS USED ON EVERY SHEET)

1. PROVIDE LOCKING COVER FOR EXTERIOR & CORRIDOR RECEPTACLES. TYP.
2. LEAVE 2" OF OPEN WALL SPACE ADJACENT TO HOUSE PANEL FOR FUTURE EV PANEL.
3. PROVIDE (1) 2" CONDUIT FROM TELEPHONE VAULT AND (1) 2" CONDUIT FROM THE CABLE TV VAULT. COORDINATE WITH TELECOM UTILITY FOR TELEPHONE & CABLE TV VAULT LOCATIONS.

NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: **EAST TOWN CROSSING BUILDING E**
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-848-3343

ROBISON ENGINEERING, INC

PERMIT SET
 03/08/2024

SHEET TITLE:
POWER PLAN - LEVEL 3


SHEET NO.
 E3.02



APARTMENT ELECTRICAL DEVICE SCHEDULE

SYMBOL	DEVICE	NOTES
⊕	RECEPTACLE, SIMPLEX	PROVIDE WHERE INDICATED.
⊕	RECEPTACLE, SIMPLEX, FLOOR MOUNT	PROVIDE WHERE INDICATED.
⊕	RECEPTACLE, DUPLEX, FLOOR MOUNT	PROVIDE WHERE INDICATED.
⊕	RECEPTACLE, DUPLEX	PROVIDE WHERE INDICATED.
⊕	RECEPTACLE, DUPLEX, SPLIT-WIRED	PROVIDE WHERE INDICATED. LOWER OUTLET CONTROLLED BY WALL SWITCH
⊕	RECEPTACLE, QUAD + TELEVISION CABLE OUTLET	PROVIDE WHERE INDICATED.
⊕	RECEPTACLE, QUAD	PROVIDE WHERE INDICATED.
▽	TELEPHONE WALL OUTLET	REFER TO LOW VOLTAGE PLANS
▽	COMM/DATA WALL OUTLET	REFER TO LOW VOLTAGE PLANS
⊕	TELEVISION CABLE OUTLET	REFER TO LOW VOLTAGE PLANS
\$	WALL SWITCH	PROVIDE WHERE INDICATED.
\$vs	WALL SWITCH VACANCY SENSOR	PROVIDE WHERE INDICATED.
\$SW	WALL SWITCH (3-WAY)	PROVIDE WHERE INDICATED.
⊕	WALL SWITCH DIMMER	PROVIDE WHERE INDICATED.
⊕	FAN CONTROL	PROVIDE WHERE INDICATED.
\$AT	SWITCH ASTRONOMICAL TIME CLOCK CONTROL	PROVIDE WHERE INDICATED.
⊕	LIGHT FIXTURE, WALL MOUNTED SCNCE	PROVIDE ROUGH IN WHERE INDICATED REFER TO LUMINAIRE SCHEDULE
⊕	LIGHT FIXTURE, CEILING MOUNTED	PROVIDE ROUGH IN WHERE INDICATED REFER TO LUMINAIRE SCHEDULE
⊕	PENDANT LIGHT FIXTURE, CEILING MOUNTED	PROVIDE ROUGH IN WHERE INDICATED REFER TO LUMINAIRE SCHEDULE
⊕	LIGHT FIXTURE, WALL MOUNTED	PROVIDE ROUGH IN WHERE INDICATED REFER TO LUMINAIRE SCHEDULE
⊕EF	FAN, CEILING MOUNTED.	FURNISHED & INSTALLED BY MECH, WIRED BY ELECTRICAL CONTRACTOR
⊕	THERMOSTAT	FURNISHED & INSTALLED BY MECH
⊕	SMOKE DETECTOR & CARBON MONOXIDE DETECTOR	PART OF DESIGN/BUILD FIRE ALARM SYSTEM. SMOKE/CO DETECTORS TO BE WIRED TO FIRE ALARM SYSTEM.
⊕DB	DOOR BELL BUTTON	PROVIDE WHERE INDICATED.
⊕DBC	DOOR BELL CHIMES	PROVIDE WHERE INDICATED.
⊕DBT	DOOR BELL TRANSFORMER	PROVIDE WHERE INDICATED.
⊕MB	MULTIMEDIA BOX	PROVIDE WHERE INDICATED.
⊕	FAN COIL UNIT	FURNISHED & INSTALLED BY MECH (ELECTRICAL PROVIDE POWER TO THE UNIT PER NEC)
⊕	PHOTOCELL	EXTERIOR WEATHERPROOF PHOTOCELL CONTROL FOR DUSK TO DAWN OPERATION
⊕	WALL SWITCH, LOW VOLTAGE BATHROOM FAN SPEED CONTROL	FURNISHED & INSTALLED BY ELEC

NOTE: NOT ALL ITEMS USED ON PROJECT.



DWELLING UNIT VENTILATION WIRING DIAGRAM
DETAIL

ELECTRIC HEATERS					
EQUIP NO.	SERVICE	MOUNTING/ DISCHARGE	HEATING KW	ELECTRICAL VOLTAGE	BASIS OF DESIGN
EWH-1	BEDROOM	WALL	1	208V/1P	KING WHF
EWH-0.75	BATHROOM	WALL	0.5	208V/1P	KING WHF

NOTES: (1) BROAN, CADET OR EQUIVALENT. (2) PROVIDE REMOTE THERMOSTAT.


APARTMENT NOTES:

- ALL ELECTRICAL WORK SHALL COMPLY WITH ALL LOCAL AND NATIONAL CODES.
- DEVICE BOXES ON OPPOSITE SIDES OF DEMISING WALLS SHALL BE IN SEPARATE STUD BAYS. PROVIDE BACKING EQUIVALENT TO LOWRY'S OUTLET BOX PADS. CONDUIT FROM ONE UNIT SHALL NOT PASS THROUGH STUDS OF A SHARED WALL(DOUBLE STUDS) FROM AN ADJACENT UNIT(BRIDGING).
- PROVIDE ARC-FAULT PROTECTION, TAMPER PROOF AND GFCI RECEPTACLES AS REQUIRED BY CODE AND LOCAL AHJ. ARC-FAULT PROTECTION MUST BE PROVIDED FOR CIRCUITS IN THE AREAS LISTED IN NEC 210.12(A).
- PROVIDE SUFFICIENT DUPLEX RECEPTACLES TO MEET NEC 210.52.
- THERMOSTATS SHALL NOT INTERFERE WITH DOOR SWINGS.
- ELECTRICAL CONTRACTOR SHALL MAKE ALL FINAL CONNECTIONS FOR KITCHEN APPLIANCES. COORDINATE ALL J-BOX LOCATIONS WITH APPLIANCE INSTALLATION INSTRUCTIONS PRIOR TO ROUGH-IN.
- ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL CORD AND PLUG ASSEMBLY FOR EACH DISPOSER.
- PROVIDE A DEDICATED 20 AMP CIRCUIT TO EACH UNIT BATHROOM RECEPTACLE. BATHROOM LIGHTS, FAN TO BE ON SAME CIRCUIT PER 210.11(C)(3) EXCEPTION.
- HOME RUNS AND LOOPS CONNECTING LIGHT FIXTURES, WIRING DEVICES, AND HVAC EQUIPMENT ON PLANS INDICATE CIRCUITING SCHEME. SEE TYPICAL PANEL SCHEDULES FOR ACTUAL CIRCUIT NUMBERS FOR TYPICAL APARTMENT.
- LIGHTS WITHIN 3' HORIZONTAL OF SHOWER OR TUB TO BE WET LOCATION RATED AND HAVE FULLY ENCLOSED TRIMS. PROVIDE GFCI PROTECTION IF THE LUMINAIRE INSTALLATION MANUAL STATES IT IS REQUIRED.
- PROVIDE SMOKE DETECTORS AND CO ALARMS AS REQUIRED. DETECTORS AND ALARMS TO BE HARDWIRED AND PROVIDED WITH BATTERY BACKUP.
- ELECTRICAL CONTRACTOR SHALL INSTALL RECEPTACLES AND TV, DATA/PHONE OUTLETS UNDER COMMON COVER PLATE WHERE POSSIBLE. PROVIDE AND INSTALL DIVIDERS AS REQUIRED FOR CABLE/POWER SEPARATION.
- SEE ARCHITECTURAL DRAWINGS FOR DIMENSIONS AND LAYOUTS OF ALL DEVICES.
- ALL WALL PENETRATIONS SHALL BE CAULKED WITH APPROVED MATERIAL TO MAINTAIN THE FIRE RATING OF ALL WALLS AND FLOORS.
- ALL CONDUIT SHALL BE INSTALLED IN NEAT SYMMETRICAL LINES HORIZONTAL OR PERPENDICULAR TO BUILDING COLUMNS AND ROOF LINES. CONDUITS SHALL BE GROUPED ON COMMON SUPPORTS WHEREVER POSSIBLE.
- REFERENCE MECHANICAL DRAWINGS FOR EXACT LOCATION OF ALL MECHANICAL EQUIPMENT.
- ELECTRICAL CONTRACTOR SHALL VERIFY ALL FUSE RATING WIRE SIZES AND DISCONNECT SIZES WITH EQUIPMENT SERVED ON THE JOB PRIOR TO INSTALLATION.
- SEE ARCHITECTURAL DRAWINGS AND ELEVATIONS FOR ADDITIONAL DETAILS AND CASEWORK DIMENSIONS.
- DEVICE LOCATIONS IN 1ST DWELLING/RESIDENT UNIT SHALL BE REVIEWED AND APPROVED BY OWNER PRIOR TO ROUGH-IN OF REMAINING UNITS
- CONFIRM FINAL LOCATION OF HEATERS AND THERMOSTATS IN FIELD PRIOR TO ROUGH-IN

ACCESSIBILITY NOTES:

- ALL SWITCHES AND CONTROLS - 15" MIN; 48" MAX TO CONTROL.
- GENERAL OUTLETS MIN 18" AFF.
- ALL SWITCHES/CONTROLS ABOVE COUNTERTOPS 48" MAX.
- ELECTRICAL SUB-PANELS IN UNITS MUST COMPLY WITH ABOVE REACH RANGES.
- SWITCHES FOR EXHAUST HOODS AND GARBAGE DISPOSALS MUST COMPLY WITH ABOVE REACH RANGES. INSTALL SWITCHES ON FACE OF CABINETS IF REQUIRED TO COMPLY.

REVISIONS	DESCRIPTION	DATE
NO.		




DRAWN: LYSAK K.
DESIGNED: LYSAK K.
CHECKED: STEINKE M.
APPROVED: STEINKE M.

PROJECT: EAST TOWN CROSSING BUILDING E
MULTIFAMILY DEVELOPMENT
PIONEER WAY & SHAW RD. PUYALLUP, WA
19401 40TH AVE W, SUITE 302
LYNNWOOD, WA 98036
PHONE: 206-835-1818
ROBISON ENGINEERING, INC.


PERMIT SET
03/08/2024

SHEET TITLE:
UNIT PLANS NOTES


SHEET NO.
E5.00




UNIT TYPICALS
 TYPE 12-5 2BR
 SCALE: 1/4" = 1'-0"



UNIT TYPICALS
 TYPE 12-1 3BR
 SCALE: 1/4" = 1'-0"



UNIT TYPICALS
 TYPE 12-2 2BR
 SCALE: 1/4" = 1'-0"



UNIT TYPICALS
 TYPE 12-3 3BR
 SCALE: 1/4" = 1'-0"

GENERAL NOTES:

1. PROVIDE AFCI BREAKERS PER NEC 210.12.
2. PROVIDE TAMPER RESISTANT RECEPTACLES PER NEC 406.12.
3. PROVIDE ADA COMPLIANT CONTROLS FOR RANGE HOODS & CEILING FANS IN UNITS DESIGNATED AS 'ACCESSIBLE' PER ARCHITECTURAL.

FLAG NOTES

1. LAUNDRY EXHAUST FAN CONTROLLED BY INTEGRAL HUMIDISTAT. PROVIDE UNSWITCHED HOT.
2. TWO-SPEED WHOLE HOUSE FAN CONTROLLED BY INTEGRAL OCCUPANCY SENSOR. HIGH SPEED OPERATION WHEN OCCUPIED, LOW SPEED OPERATION OTHERWISE. PROVIDE UNSWITCHED HOT.
3. REFER TO MECHANICAL PLANS FOR CONDENSING UNIT LOCATION

NO.	DATE	DESCRIPTION



DRAWN: LYSAK K.	DESIGNED: LYSAK K.	CHECKED: STEINKE M.	APPROVED: STEINKE M.
-----------------	--------------------	---------------------	----------------------

PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA


19401 40TH AVE W, SUITE 302
 LYNNWOOD, WA 98036
 PHONE: 206-844-3343

ROBISON ENGINEERING, INC

PERMIT SET
 03/08/2024

SHEET TITLE:
 UNIT PLANS

SHEET NO.
 E5.01



GEC DIAGRAM

GENERAL FEEDER SCHEDULE

ID	FEEDER AMPS	CONDUIT AND FEEDER	FEEDING THESE DEVICES
1	125	1-1/2" C, 2#2/0 AL, #2/0 AL N, #4 AL G	101, 102, 103, 104, 105, 106, 107, 108, 201, 202, 203, 204, 205, 206, 207, 208, 301, 302, 303, 304, 305, 306, 307, 308
10	800	(3) 3" C, 3#400kcmil AL, #400kcmil AL N, #4/0 AL G	UTIL
11	400	(2) 2-1/2" C, 3#250kcmil AL, #250kcmil AL N, #1 AL G	HOUSE
12	1000	(4) 3" C, 3#350kcmil AL, #350kcmil AL N, #4/0 AL G	MC-B
14	300	3" C, 3#350kcmil, #350kcmil N, #4G	PV

SIZING METHOD: COPPER, 60°C #12 THROUGH #1, 75°C 1/0 AND ABOVE

FEEDER SCHEDULE NOTES:

- CONDUIT FILL:
 * FOR CONDUIT SIZES 1-1/2" AND BELOW, FILL IS BASED ON EMT.
 * FOR CONDUIT SIZES 2" AND ABOVE, FILL IS BASED ON SCHEDULE 40 PVC.

IN LOCATIONS APPROVED FOR THE PURPOSE, CONTRACTOR MAY USE MC CABLE. IN LOCATIONS APPROVED FOR THE PURPOSE CONTRACTOR MAY USE OTHER CONDUIT TYPES, INCLUDING RMC, FMC AND LFMC. CONTRACTOR REQUIRED TO ENSURE CONDUIT FILL DOES NOT EXCEED 40%.

CONTRACTOR RESPONSIBLE TO ENSURE TERMINATION/LUG CAPACITY FOR ALL SCHEDULED FEEDERS.

XHHW/THHN/THWN SHALL BE USED FOR INSULATION OF THE CONDUCTOR.



PHASE 1 EV BREAKDOWN: 290 PARKING SPACES * 0.2 = 58 EV CHARGERS

Bldg	# EV chargers	208V 1PH load (KVA)	208/120V 3PH load (A)	50% load management infrastructure (KVA)	50% load management infrastructure (A)
B	6	49.92	138.57	24.96	69.29
C	6	49.92	138.57	24.96	69.29
D	6	49.92	138.57	24.96	69.29
G	20	166.4	461.9	83.2	230.95
H	4	33.28	92.38	16.64	46.19
TI.1	3	24.96	69.29	12.48	34.65
TI.2-4	13	108.16	300.24	54.08	150.12
Total	58	482.56	1339.5	241.28	669.75

FAULT CURRENT SCHEDULE

DEVICE	FAULT	AIC RATING	L-N VOLTS	UTILITY FAULT	FED FROM		FEEDER		TOTAL MOTOR FAULT
					DEVICE	FAULT	SIZE	LENGTH	
UTIL	29,711	NA	120V	29,100					611
MC-B	21,901	42,000	120V	21,286	UTIL	29,100	(4)#350kcmil AL	105'	615
HOUSE	17,917	42,000	120V	17,483	MC-B	21,286	(2)#250kcmil AL	29'	434
PV	16,302	22,000	120V	15,944	HOUSE	17,483	#350kcmil	12'	358
101	10,709	22,000	120V	10,549	MC-B	21,286	#2/0 AL	42'	160
102	11,121	22,000	120V	10,949	MC-B	21,286	#2/0 AL	39'	172
103	9,799	22,000	120V	9,662	MC-B	21,286	#2/0 AL	48'	137
104	9,351	22,000	120V	9,225	MC-B	21,286	#2/0 AL	52'	126
105	5,597	22,000	120V	5,539	MC-B	21,286	#2/0 AL	106'	58
106	6,879	22,000	120V	6,802	MC-B	21,286	#2/0 AL	81'	77
107	4,386	22,000	120V	4,342	MC-B	21,286	#2/0 AL	143'	44
108	4,426	22,000	120V	4,381	MC-B	21,286	#2/0 AL	141'	45
201	9,257	22,000	120V	9,133	MC-B	21,286	#2/0 AL	53'	124
202	9,316	22,000	120V	9,191	MC-B	21,286	#2/0 AL	52'	125
203	8,690	22,000	120V	8,578	MC-B	21,286	#2/0 AL	58'	112
204	8,266	22,000	120V	8,164	MC-B	21,286	#2/0 AL	63'	102
205	5,413	22,000	120V	5,358	MC-B	21,286	#2/0 AL	111'	55
206	5,496	22,000	120V	5,439	MC-B	21,286	#2/0 AL	109'	57
207	3,976	22,000	120V	3,936	MC-B	21,286	#2/0 AL	160'	40
208	4,749	22,000	120V	4,701	MC-B	21,286	#2/0 AL	130'	48
301	8,258	22,000	120V	8,155	MC-B	21,286	#2/0 AL	63'	103
302	8,305	22,000	120V	8,202	MC-B	21,286	#2/0 AL	62'	103
303	7,798	22,000	120V	7,705	MC-B	21,286	#2/0 AL	68'	93
304	7,453	22,000	120V	7,366	MC-B	21,286	#2/0 AL	73'	87
305	4,826	22,000	120V	4,778	MC-B	21,286	#2/0 AL	127'	48
306	5,118	22,000	120V	5,066	MC-B	21,286	#2/0 AL	119'	52
307	3,773	22,000	120V	3,735	MC-B	21,286	#2/0 AL	170'	38
308	4,463	22,000	120V	4,418	MC-B	21,286	#2/0 AL	140'	45

208Y/120V 3P 4W
 225 KVA
 FC 29,711



FLAG NOTES

- 1 UNIT FEEDERS: REFER TO METER CENTER PANEL SCHEDULE ON THIS SHEET FOR UNIT FEEDER SIZE & TYPE. TYP.
- 2 CONTRACTOR SHALL VERIFY AVAILABLE FAULT CURRENT WITH PSE SERVICE LETTER PRIOR TO ORDERING EQUIPMENT.
- 3 HOUSE PANEL METER AND MAIN BREAKER.
- 4 PROVISIONAL BREAKER SPACE AND CONDUIT FOR FUTURE PV SYSTEM. LOCATE BREAKER SPACE AT
- 5 BUSBAR SIZED PER NEC 705.12(B)(2).

ONE-LINE DIAGRAM

SCALE: NONE


REQUIRED ELECTRIC VEHICLE CHARGING INFRASTRUCTURE WAC 51-50-0429:

- WHERE PARKING IS PROVIDED, TEN PERCENT OF PARKING SPACES SHALL BE PROVIDED WITH ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.
- ELECTRICAL ROOM(S) SERVING PARKING AREAS SHALL BE DESIGNED TO ACCOMMODATE THE ELECTRICAL EQUIPMENT AND DISTRIBUTION REQUIRED TO SERVE A MINIMUM OF 20 PERCENT OF THE TOTAL PARKING SPACES WITH 208/240 V 40-AMP ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.
- MINIMUM ONE ACCESSIBLE PARKING SPACE SHALL BE SERVED BY ELECTRIC VEHICLE CHARGING INFRASTRUCTURE.

TOTAL NUMBER OF PARKING SPACES = 458; 458 x 0.2 = CAPACITY FOR 92 EV CHARGERS
 92 CHARGERS x 208V/1PH x 40A = 765.44 KVA = 2,126.22 A 3 PHASE POWER @ 120/208V

UTILIZING LOAD MANAGEMENT INFRASTRUCTURE, EV LOAD CAN BE REDUCED BY 50%. 2,126.22A/2 = 382.72 KVA (1,063.11 A) @ 208V 3 PHASE.

PER WAC 427, ELECTRICAL INFRASTRUCTURE SHALL BE DESIGNED TO ACCOMMODATE AN ADDITIONAL 1,064 AMPS OF ELECTRICAL LOAD.



DRAWN: LYSAK K.
 DESIGNED: LYSAK K.
 CHECKED: STEINKE M.
 APPROVED: STEINKE M.

PROJECT: EAST TOWN CROSSING BUILDING E
 MULTIFAMILY DEVELOPMENT
 PIONEER WAY & SHAW RD. PUYALLUP, WA



PERMIT SET
 03/08/2024

SHEET TITLE:
ONE-LINE DIAGRAM & PANELS SCHEDULES

SHEET NO.
 E6.00

