



CENTERIS SHED




Vicinity Map




PRCNC20240647

See architectural plans for insulation, cladding and finishes.



PRCNC20240647



THE APPROVED CONSTRUCTION PLANS AND ALL ENGINEERING MUST BE POSTED ON THE JOB AT ALL INSPECTIONS IN A VISIBLE AND READILY ACCESSIBLE LOCATION. PRINT IN COLOR and to SCALE.



Approval of submitted plans is not an approval of omissions or oversight by this office or noncompliance with any applicable regulations of local government. The contractor is responsible for making sure that the building complies with all applicable building codes and regulations of the local government.

See separate engineering and architectural plans.

BSE

Brien
Structural
Engineers

1316 Central Ave. S., Suite 200
Kent, WA 98032
(206) 397-0000 - www.bse-ps.com





CENTERIS SHED
1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374

Δ Issue	Date
Foundation Permit Submittal	04/05/2024
Superstructure Permit Submittal	04/18/2024
Job #	24202
Drawn	RRS
Checked	PJB

COVER SHEET

S0.0



CENTERIS SHED
1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374

Δ Issue	Date
Foundation Permit Submittal	04/05/2024
Superstructure Permit Submittal	04/18/2024
Job #	24202
Drawn	RRS
Checked	PJB

FRAMING PLANS


S1.0

FOUNDATION PLAN NOTES


- SLAB ON GRADE IS 5" THICK UNLESS NOTED OTHERWISE.
- REINFORCE SLAB ON GRADE WITH #4 @ 12" OC EW, UNO.
- PROVIDE SAW CUT JOINTS IN SLAB ON GRADE PER TYPICAL SLAB ON GRADE DETAILS. MAX SPACING SHALL BE 12" - 0" O.C. EACH WAY UNLESS SPECIFIED OTHERWISE BY ARCHITECT. SUBMIT SAW CUT PLAN TO ARCHITECT FOR REVIEW.
- REFERENCE DRAWINGS:
S3.1 FOR CONCRETE FOUNDATION DETAILS
- OVEREXCAVATION SHALL BE BACKFILLED WITH A LEAN-MIX CONCRETE (1 1/2 SACK MIN) PER GEOTECHNICAL REPORT.

COLD-FORMED STEEL FRAMING PLAN NOTES



- COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS.
- COLD-FORMED STEEL STUD WALLS SHALL ALIGN WITH TRUSS/JOIST LAYOUT AND BE SPACED AT 24" OC MAXIMUM, UNLESS NOTED OTHERWISE.
- (A) INDICATES PLYWOOD SHEAR WALL. SEE SHEAR WALL SCHEDULE ON SHEET S3.0 AT WALLS SHEATHED ON ONE FACE ONLY. PLACE SHEATHING ON THE CHEVRON TAG SIDE. ALL EXTERIOR BEARING AND NON-BEARING WALLS SHALL MEET SHEAR WALL TYPE A REQUIREMENTS UNLESS NOTED OTHERWISE.
- PLACE ALL HOLDDOWNS AND SILL ANCHORS EMBEDDED IN CONCRETE PRIOR TO CASTING OF THE CONCRETE. DRILLING SUCH ITEMS IN AFTER THE DECK IS CAST SHALL BE ASSUMED NOT FEASIBLE.
- PROVIDE 3/4" NOMINAL TONGUE & GROOVE WOOD SHEATHING OVER ALL ROOF STRUCTURE. PROVIDE #8 SMS @ 6" OC EDGE NAILING AND #8 SMS @ 10" OC FIELD NAILING, UNLESS OTHERWISE NOTED.
- ALL ROOF TRUSSES SHALL ALIGN WITH WALL STUDS.
- PROVIDE EDGE NAILING OVER ALL RM JOISTS AND TRUSS BLOCKINGS OVER SHEAR WALLS.
- REFERENCE DRAWINGS:
S3.X FOR TYPICAL CFS DETAILS



1 FOUNDATION PLAN
1/4" = 1'-0"



2 ROOF PLAN
1/4" = 1'-0"



City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic





CENTERIS SHED

1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374


Issue	Date
Foundation Permit Submittal	04/05/2024
Superstructure Permit Submittal	04/18/2024

Job #	24202
Drawn	RRS
Checked	PJB

ELEVATIONS
AND
SECTIONS



C:\Users\brandomb\Documents\24202_R2024_Centeris Shed_hbeaudette@bse-ps.com.rvt
4/18/2024 9:20:09 AM



City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic

CENTERIS SHED


1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374

Δ Issue	Date
Foundation Permit Submittal	04/05/2024
Superstructure Permit Submittal	04/18/2024


Job #	24202
Drawn	RRS
Checked	PJB

**ELEVATIONS
AND
SECTIONS**

S2.1



1 EAST-WEST SECTION
1/4" = 1'-0"



2 NORTH-SOUTH SECTION
1/4" = 1'-0"

EXTERIOR METAL STUD WALL FRAMING SCHEDULE						
WALL TYPE	STUD TYPE	SPACING	TRACKS		STUD-TO-TRACK CONNECTION	
			BOTTOM	TOP	BOTTOM	TOP
Ⓐ	600S162-54	24" OC	600T125-54	600T125-54	Ⓐ	Ⓑ


EXTERIOR METAL STUD WALL FRAMING SCHEDULE NOTES

- FULLY-SHEATH FACE OF STUDS AS NOTED ON PLANS FULL-HEIGHT OR PROVIDE BRIDGING OR SOLID BLOCKING AT 4'-0" OC MAX UNLESS NOTED OTHERWISE
- ALL STUDS SHALL FULLY BEAR AT TOP AND BOTTOM TRACK – SHIM WHERE NECESSARY. WEB STIFFENERS ARE NOT REQUIRED UNLESS OTHERWISE SPECIFIED.
- TOP/BOTTOM TRACK PENETRATIONS OR FLANGE CLIPS UP TO 2/3 (TRACK WIDTH) ARE STRUCTURALLY ACCEPTABLE 16" CLEAR FROM ANY JAMB STUDS - ADD ANCHOR ON EACH SIDE OF OPENING.
- WALL STUDS, CRIPPLE STUDS, JAMBS, HEADERS AND SILLS SHALL NOT BE SPLICED.
- ALL COLD-FORMED STEEL STUDS, TRACKS AND LIGHT GAUGE ANGLES SHALL CONFORM TO ASTM A653 SS GRADE 50 (Fy=50KSI) FOR 18, 24, 30, 36 AND 42 MILS MEMBERS AND ASTM 653 SS GRADE 33 (Fy=33KSI) FOR 43 MILS AND LIGHTER MEMBERS.
- BLOCKING SHALL MATCH GAUGE OF WALL STUD AND 1 1/2" WIDE, MINIMUM.
- CONCRETE SCREWS SHALL BE HILTI KH-EZ SCREW-TYPE CONCRETE ANCHOR OR SIMPSON TITEN HD. SEE DETAILS FOR REQUIRED DIAMETERS AND EMBEDMENTS. ALL DRILLING IN CONCRETE SHALL CONFORM TO REQUIREMENTS IN GENERAL NOTES. DO NOT DAMAGE REINFORCING IN CONCRETE SLAB OR FOUNDATION.
- SHEET-METAL SCREWS (SMS) SHALL BE SELF-TAPPING, SELF-DRILLING FASTENERS IN COMPLIANCE WITH ASTM C1513 AND SHALL HAVE A TYPE II COATING IN ACCORDANCE WITH ASTM B633.
- IT IS STRUCTURALLY ACCEPTABLE TO USE A THICKER FRAMING MEMBER PROVIDED THE WEB SIZE REMAINS UNCHANGED AND FLANGE SIZE REMAINS UNCHANGED OR IS INCREASED.



SPECIAL CFS FRAMING SHEAR WALL W/ PLYWOOD			
SHEAR WALL REQUIREMENTS			
MARK	STRUCTURAL PANEL REQUIREMENTS	EDGE SCREWS (NOTES 2, 4)	BOTTOM TRACK ANCHORS (NOTE 6)
Ⓐ	(1) SIDE 7/16" WOOD SHTG	#8 @ 6" OC	5/8"Ø ANCHOR @ 32" OC - EMBED 7" UNO

SHEAR WALL FRAMING NOTES:

- (Ⓐ) INDICATES STRUCTURAL WALL MARK. STUDS SHALL ALIGN WITH 2023 AND STUDS ABOVE. FOR NUMBER OF STUDS REQUIRED BELOW, JOIST/STUD ABOVE SEE SCHEDULE. FOR TYPICAL WALL STUD BRIDGING DETAIL AND ADDITIONAL WALL FRAMING REQUIREMENTS SEE SCHEDULE.
- ALL EXTERIOR AND INTERIOR WALLS DESIGNATED AS SHEAR WALLS SHALL BE BLOCKED AT ALL UNSUPPORTED PANEL EDGES. EDGE SCREW SPACING APPLIES TO TOP AND BOTTOM TRACK, PANEL VERTICAL AND HORIZONTAL JOINTS, WALL CORNERS, HOLD-DOWN ANCHOR STUDS, AND WALL END STUDS. SHEAR WALL STUD FLANGE WIDTH SHALL BE S162 MINIMUM. BLOCKING SHALL MATCH GAUGE OF WALL STUD x 1 1/2" WIDE MINIMUM.
- SHEATHING PANELS MAY BE INSTALLED PARALLEL OR PERPENDICULAR TO FRAMING.
- SCREWS SHALL BE SELF-DRILLING, SELF-TAPPING FLAT HEAD SCREWS WITH MINIMUM 0.292" HEAD DIAMETER. PROVIDE 3"x3"x1/4" PLATE WASHER AT EACH ANCHOR BOLT - WELD PLATE WASHER TO TRACK WITH FILLET WELD ALL AROUND. DISTANCE FROM ANCHOR TO END OF TRACK TO BE 3" MIN AND 6" MAX.
- ACCEPTABLE TO USE 5/8"Ø HILTI HUS-EZ SCREW ANCHORS WITH 3-1/2" EMBED AS AN ALTERNATE TO THE CAST-IN-PLACE ANCHOR SHOWN IN THE SCHEDULE.



1 EXTERIOR METAL STUD WALL SCHEDULES AND DETAILS



City of Puyallup Development & Permitting Services ISSUED PERMIT	
Building	Planning
Engineering	Public Works
Fire	Traffic

CENTERIS SHED




1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374

Δ Issue	Date
Foundation Permit Submittal	04/05/2024
Superstructure Permit Submittal	04/18/2024

Job #	24202
Drawn	RRS
Checked	PJB

EXTERIOR WALL SCHEDULES AND DETAILS

C:\Users\brandomb\Documents\24202_F2024_Centeris Shed_bbeaudette@bse-ps.com.rvt 4/18/2024 9:20:10 AM



CENTERIS SHED

1023 39TH AVENUE SOUTH EAST
PUYALLUP, WA 98374

NOTES:
1. QUALIFIED SHEATHING SHALL BE PLYWOOD OR OSB ONLY AND SHALL OCCUR FULL HEIGHT OF WALL. PROVIDE SOLID BLOCKING PER 2/S3.2 FOR ALL SHEAR WALLS.

FULL HEIGHT SHT. SEE NOTE 1 - ALLOWABLE TO ORIENT SHEETS HORIZONTALLY OR VERTICALLY

FASTEN W/ #8 SMS MIN @ 12" OC MAX TYP AT ALL FRAMING MEMBERS (STUDS, TRACKS, BLOCKING, CHANNELS, STRAPS, ETC.) - SEE SHEAR WALL SCHEDULE FOR EDGE SCREWING REQUIREMENTS.

1 TYPICAL SHEATHINGS AT SHEAR WALLS
NTS

NOTES:
1. ALL SHEAR WALL PANEL EDGES SHALL HAVE SOLID BLOCKING AS SHOWN.

PROVIDE BLOCKING @ 96" OC VERT MAX. TYP UNO.

TRACK BLOCKING TO MATCH WALL STUD - CLIP FLG AND BEND - INSTALL 96" OC MAX

(2) #8 EA FLANGE TYP.
(2) #8 AT CLIPED TRACK WEB TYP

2 TYPICAL BLOCKING AT PARTITIONS
NTS

TOP TRACK PER SCHEDULE

(4) #8 SDS @ LAPPED TRACK


#8 SDS @ 24" OC CONNECTING CORNER STUDS

#8 SDS @ 24" OC CONNECTING CORNER STUDS

PLAN VIEW


SHTG

7 TYPICAL STUD WALL AT CORNER
NTS




NOTES:
1. SPLICE TRACK 6" CLEAR FROM VERTICAL STUDS TYPICAL.
2. DO NOT SPLICE IN WALLS ADJACENT TO JAMBS.
3. SEE WALL SCHEDULE NOTES FOR BOT TRACK ANCHORS.


6 TYPICAL TRACK SPLICE
NTS



5 TYPICAL METAL STUD PUNCHOUT
NTS



10 54MIL TRACK BACKING
NTS



9 TYP ROOF JOIST CONNECTION
NTS

Δ Issue	Date
Superstructure Permit Submittal	04/18/2024

Job #	24202
Drawn	RRS
Checked	PJB

FRAMING DETAILS

C:\Users\brandamb\Documents\24202_R2024_Centeris Shed_bbeauaette@bse-ps.com.rvt 4/18/2024 9:20:12 AM