

CITY OF PUYALLUP **Development & Permitting Services** 333 S. Meridian, Puyallup, WA 98371 (253) 864-4165

www.cityofpuyallup.org

Permit No: PRFA20230879

FIRE ALARMS

Puyallup, WA

Job Address	Address: 1601 39TH AVE SE, PUYALLUP, WA 98374 Parcel # 0419034039	ISSUED July 30, 2024			
Owner ST OF WA PIERCE COLLEGE 9401 FARWEST DR SW TACOMA, WA 98498-1919					
Applicant ADT Commercial LLC 21312 30th Drive SE, Suite 103 Bothell, WA 98021 (425) 219-3232 Rh_bothellpermits@adt.com					
Contractor ADT COMMERCIAL FORMALLY RED HAWK FIRE 21312 30TH DR SE, STE. BOTHELL, WA 98021 NWCOMMPERMITS@ADT.COM WA L&I #:					
Description of Work INSTALL FIRE ALARM SYSTEM PIERCE COLLEGE STEM BLDG - REV (1) - 4/12/2024 - ADDITIONAL SMOKE DETECTION * REV (2) - 7/29/2024 - HEAT DETECTORS IN SKYLIGHTS AND SMOKE SPACING RELEVANT IN SOME CLASSROOMS AND HALLWAYS					
Permit Types	Fire Alarms				
Expiration Date: January 26, 2025					
Total ESU's					

Building Components:

Quantity	Units	Description		
312	DEVICES	Fire Alarm and Detection System and		
		Related Equipment, New		
248	DEVICES	Fire Alarm and Detection System and		
		Related Equipment, New		
			Total Value of Work:	\$0.00

Standard Conditions:

1. • Appointment required for all inspections am/pm is not guaranteed without appointment. Larger systems taking more than 1 hour will require 48-72hr notice prior to scheduling.

- Provide plans and permit on site for inspection.
- Complete labor and industries inspections prior to requesting city inspection.
- Exterior fire bell required outside fire sprinkler room.
- Above ceiling detection is required.
- Device maps required at the annunciator and fire alarm panel prior to calling in final. The annunciator map will need to be weatherproof.
- Total coverage is required, subject to field inspection. Comply with NFPA 72.

• Fire alarm system shall be placarded per NFPA 72. The UL certificate shall be posted at time of final inspection. The system will need to be UL certified.

- Pre-test shall be conducted with a printout for inspector at time of inspection.
- Labeling of all devices above and below ceiling required.
- Fire sprinkler tamper values and PIV will be required to be tested at inspection. Fire sprinkler contractor to be onsite.
- RTU'S and smoke dampeners will be required to be tested during inspection.
- In existing buildings all above ceiling detection is to remain. Do not remove.
- Due to unforeseeable construction design, all device locations to be field verified for compliance.

Schedule your inspection online through the city of puyallup online permit system after requesting appointment from inspector. Fire Inspections are Monday – Thursday there will be no inspections on Fridays.

David Drake 253-864-4171 ddrake@puyallupwa.gov

Permit is valid 180 days from date of issuance. Permit validity is subject to all adhering to all applicable codes, ordinances and standards, and conditions of this permit.

I certify that I am the owner of this property or the owner's authorized agent, including an appropriately licensed contractor. I have read and examined this application and furnished true and correct information. I will comply with all provisions of law and ordinances governing this type of construction work, whether specific herein or not. By submitting this application, I give the jurisdiction permission to enter the property to perform inspections. The granting of this permit does not presume or give authority to violate or cancel the provisions of any other state or local law regulating construction or the performance of construction. I understand that failure to comply with the above may result in revocation of the permit.

Applicant: ADT Commercial LLC