



MEMORANDUM

Date: November 27, 2024

Subject: Evaluation of Storage Rack Anchorage
Project: Shoe Palace - South Hill Mall
Puyallup, WA

Wright Project No: SCI242883

Attention: Elliot Flaum
Company: Shoe Palace Corporation

Copy to:



11/27/2024

ENGINEER'S SEAL

Prepared by: Jeremy Magbag
Total Pages: 2 (including this sheet)



Our office has been tasked with reviewing the anchorage of the storage racks to the existing structure per as-built conditions shown in the following sheet. Provided each corner of the storage racks are anchored to the existing slab with a minimum of (2) 3/8" Dia. Red Head Trubolt Wedge Anchors (ESR-2251) with 2 5/8" min. embedment, the anchorage of the storage racks are compliant with the 2021 Washington State Building Code. Per the information provided, the maximum dimensions of the storage racks are 8'-0" long x 2'-0" wide x 12'-0" tall.

Las Vegas
Orange County
Phoenix
Salt Lake
Dallas

2 Venture
Suite 200
Irvine, CA 92618

949.477.4001
CA@wrightengineers.com

wrightengineers.com



STORAGE RACK ANCHORAGE TO EXSITING CFS STUD WALL:
(2) 1/4" DIA. TEK SCREWS AT EACH STUD.

FLOOR PLAN

SCALE: 3/32" = 1'-0"

