FIRE ALARM CONSTRUCTION DOCUMENT SET

MERIDIAN MARKET FACP 4301 S. MERIDIAN, PUYALLUP WA FA24144

SHEET INDEX						
SHEET	REV.	DESCRIPTION				
FA001		GENERAL SHEET, LEGEND & NOTES				
FA101		DEVICE LOCATION VIEWS - FIRST LEVEL				
FA501		SCHEDULES, POWER CALCULATIONS, RISER DIAGRAMS				
FA601		PRODUCT TYPICALS				

SHEET NAMING CONVENTION					
SHEET	DESCRIPTION				
FA0XX	GENERAL SHEET, LEGEND & NOTES				
FA1XX	FA1XX DEVICE LOCATION VIEWS - FIRST FLOOR				
FA5XX	SXX SCHEDULES & RISER DIAGRAMS, POWER CALCULATIONS				
FA6XX	PRODUCT TYPICALS				

IDENTIFIER TYPES						
TYPE	DESCRIPTION					
\(\frac{1}{\times}\)	DEVICE IDENTIFIER - EXISTING, ADD, REPLACE, MOVE, DEMO					
X:XX:XXX XX	POINT OF PROTECTION IDENTIFIER / TYPE REFERENCE					
/_xx	REVISION IDENTIFIER					
Ĺ⊗	CABLE ID - SEE CABLE LEGEND					
	SHEET ID - SHEET DETAIL "A", "B", "C" / SHEET #XXXX					

DE	DEVICE IDENTIFIERS				
	TYPE	DESCRIPTION			
	ſ <u>E</u>	DEVICE EXISTING IDENTIFIER			
	√A	DEVICE ADD IDENTIFIER			
	√R R	DEVICE REPLACE IDENTIFIER			
	√ ^M	DEVICE MOVE IDENTIFIER			
	ţ□	DEVICE DEMO IDENTIFIER			

ID	AWG	COND	SHEILD	CLASS	ID	AWG	SHEILD	CLAS
						71110	OFFICIED	
Α	16	2	N	FPLR	AA			
В	16	4	N	FPLR	BB			
С	16	2	N	FPLP	CC			
D	16	4	N	FPLP	DD			
Е	14	2	N	FPLR	EE			
F	14	4	N	FPLR	FF			
G	14	2	N	FPLP	GG			
Н	14	4	N	FPLP	HH			
I	12	2	N	FPLR	II			
J	12	4	N	FPLR	JJ			
K	12	2	N	FPLP	KK			
L	12	4	N	FPLP	LL			
М	16	2	N	TFFN	MM			
N	16	4	N	TFFN	NN			
0	16	2	N	THWN	00			
Р	16	4	N	THWN	PP			
Q					QQ			
U					UU			
R					RR			
S					SS			
Т					TT			
U					UU			
V					VV			
Χ					XX			
Υ					YY			
Z					ZZ			

SCOPE OF W	ORK						
		TO REPLACE THE EX			ROL PANEL. A	LL OTHER DEVICES WILL REMAIN UNALTERED.	
SYSTEM COD	ES						
INTERNATION	AL BUILDING CODE	(IBC 2021 EDITION)		,	ADA INTERNA	FIONAL CODE ANSIE 117.1	
INTERNATION	AL FIRE CODE (IFC	2021 EDITION)		ĺ	JNDERWRITE	RS LABORATORIES, INCORPORATED	
NATIONAL FIR	E PROTECTION ASS	SOCATION (NFPA 70 2	2019 EDITION) 1	PUYALLUP MU	NICIPAL CODES	
NATIONAL FIR	E PROTECTION ASS	SOCIATION (NFPA 72	2019 EDITION	l)			
NATIONAL FIR	E PROTECTION (NF	PA 101 2019 EDITION)				
	PANCY CLASSI						
□ ASSEMBLY	• •	□ A-1	□ A-2	□ A-3	□ A-4	□ A-5	
■ BUSINESS							
☐ EDUCATION		☐ F-1	□ F-2				
	R INDUSTRIAL (F)	□ F-1	□ F-2	☐ H-3	☐ H-4	□ H-5	
☐ HIGH HAZZ		□ I-1	□ I-2	☐ I-3	□ I-4	□ 11-3	
☐ MERCANTII		□ 1-1	□ I-Z	□ 1-3	□ 1 -4		
☐ RESIDENTI		□ R-1	□ R-2	□ R-3	□ R-4		
☐ STORAGE (□ S-1	□ S-2	□ S-3	□ N-4		
	MISCELLANEOUS (U		□ 3-2	□ 3-3	□ 3-4		
□ OHLITT & N	MISCELLANEOUS (U	')					
BUILDING CO	NSTRUCTION '	TYPES					
☐ TYPE I	☐ TYPE I-A	☐ TYPE I-B					
☐ TYPE II	☐ TYPE II-A	☐ TYPE II-B					
☐ TYPE III	☐ TYPE III-A	☐ TYPE III-B					
☐ TYPE IV							
☐ TYPE V	☐ TYPE V-A	☐ TYPE V-B					
ALITONAATIO		OTFOTION					
	SPRINKLER PR						
□ NO	□ PARTIAL	■ FULL					

GENERAL NOTES

- 1. INSTALLATION SHALL BE ACCOMPLISHED IN STRICT COMPLIANCE WITH NFPA, LOCAL, AND STATE AHJ'S, NEC, AND CONTRACT DRAWINGS. 2. AS-BUILT DRAWINGS ARE REQUIRED AT THE TIME OF AHJ ACCEPTANCE. SMITH FIRE SYSTEMS REQUIRES ELECTRICAL RED LINES WITH IN TWO WEEKS PRIOR TO
- 3. AGREEMENT AND CONFIRMATION OF ALL MILESTONE EVENTS WILL BE MADE WITH SMITH FIRE SYSTEMS PROJECT MANAGER. ALL SMITH FIRE SYSTEMS FIELD SERVICES MUST BE SCHEDULED WITH SMITH FIRE SYSTEMS PROJECT MANAGER WITH A MINIMUM OF TEN BUSINESS DAY'S ADVANCE NOTICE.
- 4. A SET OF INSTALLATION AS-BUILT DRAWINGS SHOWING ACTUAL CONDUIT AND CONDUCTOR ROUTES SHALL BE KEPT BY PROJECT FOREMAN FOR USE
- 5. FIRE ALARM CONTROL PANEL SHALL NOT BE ENERGIZED WITHOUT THE PRESENCE OF A SMITH FIRE SYSTEMS ALARM TECHNICIAN.
- 6. THE FIRE ALARM SYSTEM SHALL BE MONITORED BY A UNDERWRITERS LISTED MONITORING STATION BEFORE AHJ'S TEST. 7. WIRE ROUTING IS DIAGRAMMATIC IN NATURE ONLY AND NOT INTENDED FOR ACTUAL CONDUIT ROUTING.
- 8. ALL CONDUIT SIZING AND ROUTING BY ELECTRICAL CONTRACTOR PER NEC AND AHJ.
- 9. NO LINE VOLTAGE IN SAME CONDUIT AS POWER LIMITED FIRE ALARM CABLE.
- 10. VERIFY ALL LOCATIONS OF DEVICES WITH ELECTRICAL AND ARCHITECTURAL PLANS. SCALE AND PLACE ALL DEVICES PER ELECTRICAL
- 11. FIELD VERIFY WATERFLOW SWITCHES, TAMPER SWITCHES, PRESSURE SWITCHES, SMOKE DAMPERS, AND DUCT DETECTOR LOCATIONS.
- 12. FIELD VERIFY ALL WIRING LOCATIONS AND REQUIREMENTS FOR HVAC AND FAN CONTROL.
- 13. SMOKE DETECTORS SHALL NOT BE LOCATED WITH IN 36" OF ANY AIR DIFFUSER.
- 14. WALL MOUNTED AUDIBLE/VISUAL APPLIANCES SHALL BE MOUNTED IN SUCH THAT THE ENTIRE LENS IS NOT LESS THAN 80" AND NOT GREATER THE
- 15. THE OPERABLE PART OF EACH MANUAL FIRE ALARM BOX SHALL BE NOT LESS THAN 3'-6" AND NOT MORE THAN 4'-6" ABOVE THE FINISHED FLOOR.
- 16. NO DETECTOR SHALL BE INSTALLED UNTIL AFTER FINAL CONSTRUCTION CLEAN-UP. DETECTORS THAT HAVE BEEN INSTALLED PRIOR TO CLEAN-UP MUST BE
- 17. A DEDICATED BRANCH CIRCUIT OF ONE OF THE FOLLOWING SHALL SUPPLY PRIMARY POWER.
- B) AN ENGINE-DRIVEN GENERATOR OR EQUIVALENT WHERE A PERSON SPECIFICALLY TRAINED IN ITS OPERATIONS IS ON DUTY AT ALL TIMES. E) AN ENGINE-DRIVEN GENERATOR OR EQUIVALENT ARRANGED FOR COGENERATION WITH COMMERCIAL LIGHT AND POWER WHERE A PERSON SPECIFICALLY
- 18. ALL CIRCUITS WILL BE PROPERLY TAGGED AND TESTED FOR OPENS, SHORTS, GROUNDS, AND PROPER "END-TO-LINE" RESISTANCE. EACH CIRCUITS METER READING MUST BE DOCUMENTED AND PRESENTED TO SMITH FIRE SYSTEMS ALARM TECHNICIAN UPON ARRIVAL ONSITE FOR STARTUP AND CHECKOUT.
- 19. NO TAPPING OF SIGNALING OR INITIATING ZONE CIRCUITS ARE ALLOWED. T-TAPPING OF STYLE 4 ADDRESSABLE CIRCUITS IS ALLOWED PROVIDING A SPLICE IS PROFESSIONALLY INSTALLED, POLARITY IS OBSERVED, AND SHIELDS ARE CONTINUOUS AND FREE OF GROUNDS. SHIELDS MUST BE TERMINATED AT THE FIRE ALARM CONTROL PANEL ONLY. CABLE SHIELDS SHALL BE SPLICED TOGETHER AT EVERY JUNCTION BETWEEN THE FIRE ALARM CONTROL PANEL AND THE LAST DEVICE ON EACH CABLE RUN. SHIELDS AND OTHER FIRE ALARM CONDUCTORS (EXCEPT POWER GROUNDS) SHALL BE INSULATED AND COMPLETELY FREE FROM CONDUIT OR EARTH GROUNDS. SHIELDS WILL BE TIED TO GROUND ONLY AT THE FIR ALARM CONTROL PANEL.

DRAWING ACCEPTANCE

THIS DRAWING IS TO BE USED FOR THE PURPOSE OF PLACING AND LOCATING SMITH FIRE SYSTEMS FIRE ALARM DEVICES AND IS NOT BE USED FOR ANY OTHER

RECORD DRAWINGS

ALL WORK PERFORMED IN THE FIELD SHALL BE ACCURATELY RECORDED ON THESE DRAWINGS AND RETURNED TO SMITH FIRE SYSTEMS CORPORATE OFFICE.

MONITORING COMPANY	INSTALLATION COMPANY
SOUND ELETRONICS 3409 S. 37TH ST, TACOMA, WA 98409 ACCOUNT# LACAESA459	SMITH FIRE SYSTEMS 1106 54TH AVE E, TACOMA, WA 98424

FIRE ALARM - PANELS

QTY	SYMBOL	DEVICE DESCRIPTION
1	FACP	FIRE ALARM CONTROL PANEL
	FM200	FM-200 CLEAN AGENT PANEL
	PAP	PRE-ACTION CONTROL PANEL
	EVAC	VOICE EVACUATION CONTROL PANEL
	FSE	FIRE SIGNAL EXPANDER
	ANN	REMOTE ANNUNCIATOR
	UT2	SUBSCRIBER TERMINAL UNIT
	AES	AES TRANSMITTER

FIRE	ALARM	- NOTIFICATION DEVICES
QTY	SYMBOL	DEVICE DESCRIPTION
	¤	WALL STROBE
	\(\mathbb{\pi}_{VP}\)	WALL STROBE WEATHERPROOF
	Q	CEILING STROBE
	XvP	CEILING STROBE WEATHERPROOF
	$\stackrel{\bowtie}{\triangle}$	WALL HORN-STROBE
		WALL HORN-STROBE WEATHERPROOF
	Œ	CEILING HORN-STROBE
	H)VP	CEILING HORN-STROBE WEATHERPROOF
		WALL HORN
	(I	CEILING HORN
	M	WALL MINI-SPEAKER
	2	WALL SPEAKER
	(2)	CEILING SPEAKER
	\mathbb{H}	WALL SPEAKER/STROBE
	(2 <u>)</u>	CEILING SPEAKER/STROBE
	С	WALL CHIME
	Θ	CEILING CHIME
	В	WALL BUZZER
	В	CEILING BUZZER
		BELL

FIRE ALARM - DETECTORS

QTY	SYMBOL	DEVICE DESCRIPTION
Е	⊘ P	SMOKE DETECTOR
	(S) _{AB}	SMOKE DETECTOR ABOVE CEILING
	⊘ BL	SMOKE DETECTOR BELOW CEILING
ш	2	DUCT SMOKE DETECTOR
	RTS	DUCT SMOKE DETECTOR REMOTE TEST SWITCH
	S BT	SMOKE BEAM TRANSMITTER
	⊘ BR	SMOKE BEAM RECEIVER
Ε		135° FIXED TEMP HEAT DETECTOR
	⊕ _R	135° RATE OF RISE HEAT DETECTOR
·	194* F	194° FIXED TEMP HEAT DETECTOR
·	194* R	194° RATE OF RISE HEAT DETECTOR
	190° F	190° FIXED TEMP HEAT DETECTOR
	4044	

194° LINE TYPE HEAT DETECTOR

FIRE ALARM - MODULE / RELAY

	QTY SYMBOL		DEVICE DESCRIPTION
	E F		MANUAL PULL STATION
		ММ	MINI MONITOR MODULE
	Е	М	MONITOR MODULE
		M2	TWO POINT POINT MONITOR MODULE
		M4	FOUR POINT MONITOR MODULE
		R	RELAY MODULE
		(CR)	CONTROL RELAY MODULE
		IN	INPUT MODULE
•		ID	FOUR POINT INPUT/OUTPUT RELAY MODULE
•		IM	ISOLATION MODULE
		NM	NOTIFICATION MODULE
		SM	SYNC MODULE
		DH	DOOR HOLDER

FIRE ALARM - SPRINKLER

QTY SYMBO		DEVICE DESCRIPTION
	\otimes	SPRINKLER RISER
		WATER GONG BELL
Е	FS	WATERFLOW SWITCH
	PS	PRESSURE SWITCH
E	TS	TAMPER SWITCH

FIRE ALARM - FIREMAN'S PHONE

QTY	SYMBOL	DEVICE DESCRIPTION
	ESR	ELEVATOR STATUS RECALL
	FFP	FIRE FIGHTERS PHONE
		FIRE FIGHTERS PHONE JACK
	€ _H	FIRE FIGHTERS HANDSET

FIRE ALARM - MISCELLANEOUS

I II LE ALAI IIVI - IVIIOOLLLAINEOOO					
QTY	SYMBOL	DEVICE DESCRIPTION			
Е	КН	KITCHEN HOOD			
	♦	JUNCTION BOX			
2		BATTERY			

QTY	SYMBOL	DEVICE DESCRIPTION
E	КН	KITCHEN HOOD
		JUNCTION BOX
2		BATTERY

Development & Permitting Services

	ISSUED	PERMIT
	Building	Planning
	Engineering	Public Works
	Fire	Traffic
_		

1. READ PERMIT CONDITIONS

2. Provide a pretest of all spaces prior to scheduling an inspection. This will need to be orchestrated with all tenant spaces. The pretest will be used as part of the Fire Alarm Testing. All spaces will need to provide access day of

City of Puyallup **REVIEWED** COMPLIANCE

12/10/2024

PLANS AND ALL ENGINEERING MUST BE POSTED ON THE JOB AT ALL INSPECTIONS IN A VISIBLE AND READILY ACCESSIBLE LOCATION. Approval of submitted plans is not an

THE APPROVED CONSTRUCTION


approval of omissions or oversight by this office or noncompliance with any applicable regulations of local government. The contractor is responsible for making sure that the building complies with all applicable building codes and regulations of the local government.

CONSTRUCTION SET


DESIGNER: SCOTT JERKE ISSUE DATE: 10/29/24 PROJECT #: FA24144


FIRE ALARM

GENERAL SHEET LEGEND & NOTES




City of Puyallup Development & Permitting Services ISSUED PERMIT				
Building	Planning			
Engineering	Public Works			
Fire OF V	Traffic			







SCHEDULES - SEQUENCE OP OPERATIONS MATRIX



	A A SA NO. 11 14 14		MARKET FACP			
	HON	IEYWELL IF	P-300 FACP	T	ı	1
Current Load:		Standby:		Alarm:		
Device Type	Quantity	Amps	Total	Amps	Total	
Main System Board	1	0.19000	0.1900	0.25000	0.2500	
NAC 1	0	0.00000	0.0000	0.00000	0.0000	
NAC 2	0	0.00000	0.0000	0.00000	0.0000	
IDP-PHOTO	130	0.00030	0.0390	0.00650	0.8450	
IDP-HEAT	53	0.00030	0.0159	0.00650	0.3445	
IDP-PULL	15	0.00030	0.0045	0.00030	0.0045	
IDP-MON	26	0.00040	0.0104	0.00500	0.1300	
Total Panel Loads:			0.260	Amps	1.574	Amps
Standby Current Load:	0.260	Amps	For 24 Hours =	6.235	Amp-hours	
Alarm Current Load:	1.574	Amps	For 5 Minutes=	0.132	Amp-hours	
			20% Derating=	7.641	Amp-hours	
Total S	ystem Curren	t Load:		7.641	Amp-hours	
Dotton, Doir to be Hood:	13VDC		Amp hours	10		

CONSTRUCTION SET

DESIGNER: SCOTT JERKE

ISSUE DATE:

PROJECT #:

<u>C</u>)-


POWER CALCULATIONS




RISER DIAGRAMS


SCHEDULES & CALCULATIONS

FIRE ALARM







evelopment & Permitting Services ISSUED PERMIT Public Works Engineering Traffic










FIRE ALARM - STROBE MOUNTING




PRIMARY PORT PRIMARY PORT SECONDARY PORT -- SECURITY CONTROL PANEL - FIRE ALARM CONTROL PANEL


- RJ 31X BLOCK

RJ CORD


FIRE ALARM - PULL STATION MOUNTING









FIRE ALARM - PHONE CONNECTION




FIRE ALARM - CONDUIT WALL & CEILING



FIRE ALARM - CEILING TO WALL TRANSITION AND OPEN WIRING



FIRE ALARM - DROP CEILING & J BOX





FIRE ALARM - OS&Y TAMPER GATE VALVE



FA601

FIRE ALARM

PRODUCT TYPICALS

ISSUE DATE PROJECT #: