



FIRE PROTECTION, INC.

PO BOX 12642
MILL CREEK, WA 98082

(425) 290-9600 OR 1-800-681-1125 FAX (425) 353-4546

January 31, 2025

CITY OF PUYALLUP FIRE PREVENTION

RE: FACP REPLACEMENT & WIRELESS COMMUNICATOR INSTALLATION

SCOPE OF WORK : THE EXISTING ADDRESSABLE FACP (FAREHYT IFP-100) IN BUILDING A WAS FOUND TO HAVE A FAULTY CHARGING CIRCUIT. THIS PANEL PROVIDES MONITORING TO ALL OTHER 12 BUILDINGS ONSITE VIA MINI MODULES MONITORING THE FACP AT EACH INDIVIDUAL BUILDING (FIRE, SUPERVISORY, AND TROUBLE). THE EXISTING FAULTY FACP WILL BE REPLACED WITH AN ADDRESSABLE FACP (SILENT KNIGHT SK-6808). AN AES RADIO WILL ALSO BE INSTALLED TO REPLACE THE POTS LINES FOR COMMUNICATION. FIRE PANEL BEING REPLACED IS LOCATED IN THE FIRE SPRINKLER ROOM OF BUILDING A.

ALL EXISTING DEVICES / CIRCUITS WILL BE REMAIN AND BE TIED IN AS-IS, NO CHANGES WILL BE MADE TO THE EXISTING SYSTEM. THE EXISTING BUILDING IS FULLY-SPRINKLED.

EXISTING FIRE ALARM DEVICE COUNTS : (1) ADDRESSABLE FACP, (1) AES 2.0 RADIO, (5) PULL-STATIONS, (12) SMOKE DETECTORS, (8) HEAT DETECTORS, (16) OCCUPANT NOTIFICATION DEVICES, AND (39) MODULES MONITORING THE OTHER BUILDINGS FACPs.

EXISTING FIRE SPRINKLER EQUIPMENT : (1) DRY WATERFLOW, AND (4) TAMPER SWITCHES.

INSTALLATION COMPANY

Fire Protection, Inc.
17410 Ash Way, Ste 8
Lynnwood, WA 98037
WSCL# FIREPI*021ML
UL CERT #608242-002

SITE ADDRESS

RIVER TRAIL APARTMENTS - PHASE 1
1617 E MAIN AVE
PUYALLUP, WA 98372

APPROVED UL MONITORING COMPANY

Securitas / FPI
4300 3rd Ave. SE Lacey, WA 800-429-0991

CONTRACTUAL RESPONSIBLE PARTIES

Installation, Testing, Service & Monitoring
Fire Protection, Inc.

Should you have any further questions, please feel free to contact me directly.

NICK CHANDLER, AET
NICET-III #148121
SYSTEMS ENGINEER/DESIGNER