

PRSG20250228

INSTALLATION OF SIGN



The Sign will be installed as indicated in the drawings using 8 3-1/2 galvanized bolt anchors mounted directly to the building. Power input will be AC 120 volts 20 amp and power output will be DC 12v 5 Amp max. Watts 60 and attached to the existing junction box.

Prior to installation:

Review anchor product's ICC-ES Report and install the product per the report. If the report states special inspection(s) are required - the final special inspection report must be on site during City inspections.