


- AT SL1 (566809-155297)
- INSTALL 39W LED CHFL AL ON 8' ARM
- MOUNTING HEIGHT AT 20" ABOVE COMMS
- ORIENT ARM OVER THE ROAD AS SHOWN
- INSTALL SMART NODE AND SERIAL NUMBER
- INSTALL PSE SL TAG#

-FLAGGING REQUIRED

Where a curb exists, the lateral offset of all vertical obstructions shall be a minimum of 1.5' from the face of the curb to the face of the vertical obstruction and a minimum of 3' at intersections. Where no curb exists, the lateral offset of all vertical obstructions shall be a minimum of 4' measured from the edge of pavement to the face of the obstruction.

Any public curb, gutter, or sidewalk broken now or during the course of construction shall be removed and replaced per City Standards.



All proposed franchise utilities shall be located within a recorded utility easement or in the public right-of-way as determined by the City of Puyallup. The City of Puyallup does not authorize or permit utility work on private property.

STREET LIGHT TABLE

SITE #	POLE					LUMINAIRE		WO #	BILLING SCH.	TOTAL CONN LOAD	SMART NODE
	GRID #	TAG #	TYPE	MTG HT.	ARM	WATTS	STYLE				
SL1	566809155297		EXIST WOOD	20" A.C	39W LED CHFL AL	8'	CHFL	105106826	53	120/240	

FOREMAN (CHECK BOX WHEN COMPLETED)

☐ PSE Equipment LOCKED/SECURED & Work Area left in CLEAN/SAFE Condition.

☐ Grid, Cable, and Switch numbers INSTALLED & VERIFIED.

☐ Field Changes RED-LINED on As-built.

☐ Material VERIFIED and CHANGES noted on Paperwork.

☐ Total PRIMARY Cable noted on As-built.

☐ Company ID#'s RECORDED in correct location on As-built.

☐ Indicate correct FUSE SIZE on As-built & VERIFY proper PHASE.

☐ Correct QA Checklist(s) reviewed.

☐ Deviations noted on the As-built and their reason.

☐ I certify that the work performed meets PSE's standards and procedures and that all quality requirements are met.

Foreman's Signature _____

Print Name _____ Date _____

PROJECT PHASE	NOTIF#	ORDER#
PWR	Superior	
	New Install	515850214
	St. Light	105106826
	Removal	
	Smart Node	
GAS	Temporary	141010143
	Job Order	
	Distribution	
CABLE TV	HP Main	
	HP Svc/MS	
PHONE		

Project Manager Contact Information:

Michael Hammons

425-765-1395 Cell Phone

"Locates Required" Yes ☐ No ☒

"Outages Required" Yes ☐ No ☒

"Flagging Required" Yes ☒ No ☐

PSE STREET LIGHT NOTES

- 1- ALL STREET LIGHTING POLES ARE TO BE INSTALLED PER STANDARD 6375.4800 (PAGE #2) IN THE "LINE WORK PRACTICES MANUAL".
- 2- ALL POLES (WOOD, CONCRETE OR FIBERGLASS) ARE TO BE SET PLUMB AND EMBEDDED TO THE GROUND LINE MARKED ON THE POLE.
- 3- IN ALL SHOEBOX AND COBRAHEAD INSTALLATIONS, THE LUMINAIRE MUST BE LEVELED.

Vicinity Map
47.1513 -122.2981



Owner / Developer Contact Info

Gregg Johnson (253) 330-7374

409 43rd Ave SW

Puyallup, WA, 98373 Gregg@hchomesinc.com

For contacts below dial 1-888-CALL PSE (225-5773)

CALL 811 TWO BUSINESS DAYS BEFORE YOU DIG

THIS SKETCH NOT TO BE RELIED UPON FOR EXACT LOCATION OF EXISTING FACILITIES

<input checked="" type="checkbox"/> NEW BUSINESS		<input type="checkbox"/> CORRECTIVE / 10 DAY WAIVED		REAL ESTATE/EASEMENT N/A		PERMIT N/A	
3				FUNCTION	CONTACT	PHONE NO	DATE
2				ACCOUNT MGR	Lars Larson	425-456-2701	3/4/2025
1				ENGR - POWER	Saleem Khan	(425) 446-2289	3/4/2025
REV#		BY	DESCRIPTION	ENGR - GAS			
COUNTY	PIERCE	Emer Sect	Gas Wk Ctr	POWER WK CTR	3515	DRAWN BY	Saleem Khan
1/4 SEC	OP MAP		PLAT MAP	CHECKED BY			
U-MAP NO (POWER)	A1904E033	OH CKT MAP	D1904E056	UG CKT MAP	R1904E033	CIRCUIT NO	FRU-26
				FOREMAN #1			
				FOREMAN #2			
				MAPPING			

JOINT FACILITIES ARRANGEMENTS				
UTILITIES	N/A	N/A	N/A	N/A
CONTACT	N/A	N/A	N/A	N/A
PHONE#	N/A	N/A	N/A	N/A

PSE **PUGET SOUND ENERGY**

HC Homes Duplexes

INSTALL 1 OH STREET LIGHTS

409 43rd Ave SW Puyallup, WA, 98373

DESIGNED BY: PSE

INCIDENT	MAOP
Gas Order	Elect Order
105106826	
SCALE 1"=100'	PAGE 1 of 1