

PRCNC20250094

These calculations must be on site and made available by the Permittee for all inspections.

MiTek, Inc.

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571


Re: 4623747

MKM EAST TOWN CROSSING LOT 1#

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Arlington, WA).

Pages or sheets covered by this seal: R88389159 thru R88389179

My license renewal date for the state of Washington is September 28, 2025.



EXPIRES

Zhao, Xiaoming

May 27, 2025


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

**City of Puyallup
Building
REVIEWED
FOR
COMPLIANCE**


BSnowden
07/21/2025
3:50:12 PM



Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:27 Page: 1
ID:iWiPnXMMWZOoBsgHdxnKbo_zHHIX-RfC?PsB70Hg3NSgPqnL8w3uITxbGKWrCDOI7J4zJC?f



LUMBER		Max Grav	30=288 (LC 1), 31=996 (LC 1), 32=1128 (LC 1), 33=1077 (LC 1), 34=1080 (LC 1), 35=1080 (LC 1), 36=1080 (LC 1), 37=1080 (LC 1), 38=1080 (LC 1), 40=1080 (LC 1), 41=1080 (LC 1), 42=1080 (LC 1), 43=1080 (LC 1), 44=1080 (LC 1), 45=1080 (LC 1), 46=1080 (LC 1), 47=1080 (LC 1), 48=1080 (LC 1), 49=1080 (LC 1), 50=1080 (LC 1), 51=1080 (LC 1), 52=1080 (LC 1), 53=1076 (LC 1), 54=1107 (LC 1), 55=1097 (LC 1), 56=416 (LC 20)	BOT CHORD	55-56=-320/776, 54-55=-99/215, 53-54=-99/215, 52-53=-99/215, 51-52=-99/215, 50-51=-99/215, 49-50=-99/215, 47-49=-99/215, 46-47=-99/215, 45-46=-99/215, 44-45=-99/215, 42-44=-99/215, 41-42=-99/215, 40-41=-99/215, 38-40=-99/215, 37-38=-99/215, 36-37=-99/215, 35-36=-99/215, 34-35=-99/215, 33-34=-99/215, 32-33=-99/215, 31-32=-99/215, 30-31=-47/776
TOP CHORD	2x6 DF No.2				
BOT CHORD	2x6 DF No.2				
WEBS	2x6 DF No.2 *Except* 1-55,31-29;2x4 HF No.2				
OTHERS	2x4 HF No.2				
BRACING					
TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.				
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 55-56,30-31.				
REACTIONS	(size)				
	30=49-8-4, 31=49-8-4, 32=49-8-4, 33=49-8-4, 34=49-8-4, 35=49-8-4, 36=49-8-4, 37=49-8-4, 38=49-8-4, 40=49-8-4, 41=49-8-4, 42=49-8-4, 43=49-8-4, 44=49-8-4, 45=49-8-4, 46=49-8-4, 47=49-8-4, 48=49-8-4, 49=49-8-4, 50=49-8-4, 51=49-8-4, 52=49-8-4, 53=49-8-4, 54=49-8-4, 55=49-8-4, 56=49-8-4				
	56=159 (LC 9)				
Max Horiz	30=-76 (LC 9), 31=-59 (LC 8), 32=-12 (LC 8), 33=-12 (LC 8), 34=-12 (LC 12), 35=-12 (LC 8), 36=-12 (LC 12), 37=-12 (LC 8), 38=-12 (LC 12), 40=-12 (LC 8), 41=-12 (LC 12), 42=-12 (LC 8), 43=-12 (LC 8), 44=-12 (LC 12), 45=-12 (LC 8), 46=-12 (LC 8), 47=-12 (LC 12), 48=-12 (LC 8), 49=-12 (LC 12), 50=-12 (LC 8), 51=-12 (LC 8), 52=-12 (LC 12), 53=-12 (LC 8), 54=-15 (LC 8), 55=-168 (LC 9), 56=-162 (LC 8)				
Max Uplift					
		FORCES	(lb) - Maximum Compression/Maximum Tension		
		TOP CHORD	1-2=-72/133, 2-3=-70/130, 3-4=-69/132, 4-5=-67/133, 5-6=-66/134, 6-7=-65/136, 7-9=-63/137, 9-10=-62/139, 10-11=-60/140, 11-12=-59/141, 12-13=-58/143, 13-14=-57/144, 14-15=-58/146, 15-17=-58/147, 17-18=-58/148, 18-19=-59/150, 19-20=-59/151, 20-21=-59/152, 21-23=-60/154, 23-24=-60/155, 24-25=-60/157, 25-26=-61/158, 26-27=-61/159, 27-28=-61/161, 28-29=-61/163, 1-56=-391/1108, 1-57=0/0, 29-30=-492/296, 29-58=0/0		



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com).

MiTek®
400 Sunrise Ave., Suite 270
Roseville, CA 95661
916 755 3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A01	Monopitch Supported Gable	1	1	R88389159
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:27

Page: 2

ID: iWiPnXMWZOObsqHdxnKbo_zHHIX-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDdi7J4zJC?f

WEBS 2-55=-998/143, 3-54=-1064/61,
4-53=-1037/51, 5-52=-1040/50,
6-51=-1040/50, 7-50=-1040/50,
9-49=-1040/50, 10-48=-1040/50,
11-47=-1040/50, 12-46=-1040/50,
13-45=-1040/50, 14-44=-1040/50,
15-43=-1040/50, 17-42=-1040/50,
18-41=-1040/50, 19-40=-1040/50,
20-38=-1040/50, 21-37=-1040/50,
23-36=-1040/50, 24-35=-1040/50,
25-34=-1039/50, 26-33=-1037/52,
27-32=-1085/60, 28-31=-885/104,
1-55=-1072/433, 29-31=-198/468

Horz: 57=200, 58=200 (F)

27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-29=25, 30-56=-12
Horz: 1-29=-33, 1-56=18, 1-57=71, 29-30=34, 29-58=52
Concentrated Loads (lb)
Horz: 57=-200, 58=-200 (F)

NOTES

- 1) Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 15-2-12, Exterior (2) 15-2-12 to 34-5-8, Corner (3) 34-5-8 to 49-5-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 2x4 (I) MT20 unless otherwise indicated.
- 6) Gable requires continuous bottom chord bearing.
- 7) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 8) Gable studs spaced at 2-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 162 lb uplift at joint 56, 168 lb uplift at joint 55, 15 lb uplift at joint 54, 12 lb uplift at joint 53, 12 lb uplift at joint 52, 12 lb uplift at joint 51, 12 lb uplift at joint 50, 12 lb uplift at joint 49, 12 lb uplift at joint 48, 12 lb uplift at joint 47, 12 lb uplift at joint 46, 12 lb uplift at joint 45, 12 lb uplift at joint 44, 12 lb uplift at joint 43, 12 lb uplift at joint 42, 12 lb uplift at joint 41, 12 lb uplift at joint 40, 12 lb uplift at joint 38, 12 lb uplift at joint 37, 12 lb uplift at joint 36, 12 lb uplift at joint 35, 12 lb uplift at joint 34, 12 lb uplift at joint 33, 12 lb uplift at joint 32, 59 lb uplift at joint 31 and 76 lb uplift at joint 30.
- 12) Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 13) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.
- 14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard Except:

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-29=-520, 30-56=-20
- 26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-29=25, 30-56=-12
Horz: 1-29=-33, 1-56=18, 1-57=71, 29-30=34, 29-58=52
Concentrated Loads (lb)



May 27, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:29 Page: 1
ID:bN1tnqULE_JCg3kQWVJyy0zIAZq-RfC?PsB70Hq3NSgPqnL8w3uITxbGKwRCDoi7J4zJC?f

[illegible]

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)



400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A02	Monopitch	2	3	R88389160
					Job Reference (optional)

Horz: 1-12=-4



May 27,2025


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389161
4623747	A03	Monopitch	18	1	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:29

Page: 1

ID:bN1tnqJLE_JCg3kQWVJyy0ziAZq-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?



Scale = 1:84.9																		
[1:0-6-12,0-4-4], [2:0-2-0,0-2-4], [3:0-2-4,0-2-0], [10:0-2-4,0-2-0], [11:0-2-0,0-2-4], [12:0-4-0,0-3-12], [13:0-5-0,0-1-8], [14:0-2-0,0-2-12], [15:0-1-12,0-2-8], [17:0-1-8,0-2-4], [20:0-2-4,0-2-0], [22:0-1-12,0-2-8], [23:0-2-0,0-2-0], [24:0-5-0,0-1-0]																		
Plate Offsets (X, Y):																		
Loading		(psf)	Spacing		2-0-0	CSI		DEFL			in	(loc)	l/defl	L/d	PLATES	GRIP		
TCLL		25.0	Plate Grip DOL		1.15	TC		0.85	Vert(LL)		-0.81	19-20	>731	240	M18AHS	169/162		
(Roof Snow = 25.0)			Lumber DOL		1.15	BC		0.58	Vert(CT)		-1.34	19-20	>444	180	MT20	185/148		
TCDL		10.0	Rep Stress Incr		NO	WB		0.95	Horz(CT)		0.20	13	n/a	n/a				
BCLL		0.0*	Code		IBC2021/TPI2014	Matrix-SH												
BCDL		10.0																
															Weight: 314 lb	FT = 10%		

LUMBER		1) Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 5-2-12, Exterior (2) 5-2-12 to 44-5-8, Corner (3) 44-5-8 to 49-5-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		6) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (lb/ft) Vert: 13-24=-20, 1-2=-520, 2-11=-70, 11-12=-520	
TOP CHORD	2x6 DF 2400F 2.0E	2) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.		26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60 Uniform Loads (lb/ft) Vert: 13-24=-12, 1-12=-5 Horz: 1-12=-4 Concentrated Loads (lb) Horz: 25=200, 26=200 (F)	
BOT CHORD	2x6 DF 2400F 2.0E	3) Provide adequate drainage to prevent water ponding.		27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60 Uniform Loads (lb/ft) Vert: 13-24=-12, 1-12=-5 Horz: 1-12=-4 Concentrated Loads (lb) Horz: 25=-200 (F), 26=-200	
WEBS	2x4 HF No.2 *Except* 25-24,26-13:2x6 DF No.2	4) All plates are MT20 plates unless otherwise indicated.			
BRACING		5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.			
TOP CHORD	Structural wood sheathing directly applied or 3-1-9 oc purlins, except end verticals.	6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.			
BOT CHORD	Rigid ceiling directly applied or 9-1-14 oc bracing.	7) WARNING: Required bearing size at joint(s) 24, 13 greater than input bearing size.			
WEBS	1 Row at midpt 6-17	8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 146 lb uplift at joint 24 and 146 lb uplift at joint 13.			
REACTIONS (size)		9) Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.			
	13=0-5-8, (req. 0-6-8), 24=0-5-8, (req. 0-6-7)	10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.			
	Max Horiz 24=159 (LC 9)	11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).			
	Max Uplift 13=-146 (LC 12), 24=-146 (LC 8)	LOAD CASE(S) Standard Except:			
	Max Grav 13=3930 (LC 1), 24=3899 (LC 1)				
FORCES (lb) - Maximum Compression/Maximum Tension					
TOP CHORD	1-2=-4125/530, 2-3=-7271/954, 3-5=-8928/1157, 5-6=-9151/1161, 6-8=-8136/1028, 8-10=-8136/1033, 10-11=-6014/779, 11-12=-3000/380, 1-24=-3849/341, 1-25=0/0, 12-13=-3854/344, 12-26=0/0				
BOT CHORD	23-24=-451/532, 22-23=-694/4103, 20-22=-1113/7264, 19-20=-1311/8921, 17-19=-1311/9144, 15-17=-808/6008, 14-15=-343/2979, 13-14=-37/140				
WEBS	1-23=-487/4522, 12-14=-442/4088, 2-23=-2667/365, 11-14=-2872/393, 2-22=-560/3435, 3-22=-1213/309, 3-20=-312/1815, 5-20=-604/209, 5-19=-88/246, 6-19=0/188, 6-17=-1129/195, 8-17=-494/171, 10-17=-371/2400, 10-15=-1526/343, 11-15=-531/3459				

NOTES



May 27,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:30 Page: 1
ID:bN1tnqULE JCg3kQWVJyy0ziAZq-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?c

[illegible]

May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
400 Sunrise Ave., Suite 270
Roseville, CA 95661
916 755 3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A04	Monopitch	3	3	R88389162
Job Reference (optional)					

Horz: 1-12=-4



May 27,2025


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389163
4623747	A05	Monopitch	1	4	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:31


Page: 1

ID:tx1BYLMwvCRXqbmCgbS044zHB7S-RfC?Psb70Hq3NSgPqnL8w3uITxbGKwRCDoi7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.

Alternate to 1/2" dia. bolts and washers specified in note 1:
USP WS6, SIMPSON SDS25600, SDW22638, OR TRUSSLOK TSLZ006,
1/4" X 6" LONG WOOD SCREWS SPACED @ 24" OC, 2 ROWS (ONE ROW-2X4)
DRIVEN FROM EITHER SIDE OF 4-PLY GIRDER TRUSS CAN
REPLACE THE 1/2" BOLTS @ 48" OC IN CHORD MEMBERS
AS SHOWN IN THE NOTE SECTION.



Scale = 1:96.7

[1:0-4-8,0-2-8], [2:0-1-12,0-2-4], [3:0-1-12,0-2-0], [11:0-2-12,0-2-4], [12:0-3-4,0-2-4], [15:0-4-12,0-2-8], [16:0-5-4,0-2-0], [18:0-3-8,0-2-0], [20:0-2-12,0-2-0],

Plate Offsets (X, Y): [24:0-1-12,0-2-0], [26:0-1-12,0-2-0], [27:0-2-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-1.03	23-24	>573	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.57	Vert(CT)	-1.12	23-24	>528	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	NO	WB	0.93	Horz(CT)	0.16	17	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
Weight: 1499 lb FT = 10%												

LUMBER
TOP CHORD 2x6 DF 2400F 2.0E
BOT CHORD 2x6 DF 2400F 2.0E
WEBS 2x4 HF No.2 *Except* 12-16:2x4 DF 1800F
1.6E, 8-20:2x4 DF No.2,
9-18,29-28,30-15:2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or
6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing, Except:
6-0-0 oc bracing: 17-18,16-17,15-16.

REACTIONS (size) 15=6-8-4, 16=6-8-4, 17=6-8-4,
28=0-5-8
Max Horiz 28=257 (LC 11)
Max Uplift 15=14453 (LC 1), 16=57 (LC 10),
17=381 (LC 12), 28=127 (LC 8)
Max Grav 15=230 (LC 12), 16=195 (LC 1),
17=32729 (LC 1), 28=9081 (LC 1)

FORCES (lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=11146/605, 2-3=24935/860,
3-5=32512/925, 5-6=31896/829,
6-8=24076/677, 8-9=9993/375,
9-11=512/10405, 11-12=891/24929,
12-13=664/14637, 13-14=664/14640,
1-28=9051/312, 1-29=0/0,
14-15=431/14477, 14-30=0/0
BOT CHORD 27-28=560/1090, 26-27=843/11121,
24-26=1092/24925, 23-24=1154/32472,
21-23=1046/31851, 20-21=779/24034,
18-20=370/9954, 17-18=10367/338,
16-17=24900/669, 15-16=195/47

WEBS
12-17=18133/496, 13-16=1617/134,
14-16=21142/593, 12-16=471/18834,
8-21=55/3904, 9-20=135/7477,
8-20=15801/476, 11-18=207/10085,
11-17=19273/519, 9-18=23002/641,
2-27=7522/321, 1-27=418/12625,
3-26=6086/280, 2-26=476/15107,
5-24=3387/183, 3-24=245/8325,
6-23=0/420, 5-23=685/132, 6-21=8701/316

NOTES

- 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Attach TC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 5-2-12, Exterior (2) 5-2-12 to 50-8-4, Corner (3) 50-8-4 to 55-8-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 127 lb uplift at joint 28, 381 lb uplift at joint 17, 57 lb uplift at joint 16 and 14453 lb uplift at joint 15.
- Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A05	Monopitch	1	4	R88389163
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:31
ID:tx1BYLMwvCRXqbmCgbS044zHB7S-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 2

- 11) This truss has large uplift reaction(s) from gravity load case(s). Proper connection is required to secure truss against upward movement at the bearings. Building designer must provide for uplift reactions indicated.
- 12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard Except:

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 2-31=-70, 14-31=-520, 15-28=-20
- 26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-14=25, 15-28=-12
Horz: 1-14=-33
Concentrated Loads (lb)
Horz: 29=200, 32=200 (F)
- 27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-14=25, 15-28=-12
Horz: 1-14=-33
Concentrated Loads (lb)
Horz: 29=-200 (F), 32=-200 (F)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389164
4623747	A06	Monopitch Girder	2	4	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:31

Page: 1

ID: _J9u59?B18TVsoHvqyynjzHCK5-RfC?Psb70Hq3NSgPqnl8w3uITXBGKwRcDol7J4zJC?C



Scale = 1:96.7

Plate Offsets (X, Y): [2:0-3-4,0-2-8], [22:0-1-12,0-2-0], [24:0-2-4,0-2-0], [25:0-2-4,0-2-8], [26:0-3-0,0-0-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	-1.23	19-21	>543	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.78	Vert(CT)	-1.39	19-21	>481	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	Yes	WB	0.75	Horz(CT)	0.22	14	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
											Weight: 1939 lb	FT = 10%

LUMBER

TOP CHORD 2x10 DF SS
BOT CHORD 2x8 DF SS
WEBS 2x4 DF 1800F 1.6E *Except*
27-26,28-14:2x6 DF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.

REACTIONS (size) 14=0-5-8, 26=0-5-8
Max Horiz 26=-529 (LC 30)
Max Uplift 14=-244 (LC 31), 26=-418 (LC 30)
Max Grav 14=10039 (LC 1), 26=10270 (LC 1)

FORCES (lb) - Maximum Compression/Maximum
Tension

TOP CHORD 1-2=-13967/783, 2-3=-30729/1508,
3-5=-40362/1712, 5-6=-42294/1522,
6-8=-39787/1303, 8-9=-33110/1046,
9-11=-22810/784, 11-12=-9464/486,
12-13=-9468/490, 1-26=-10232/432,
1-27=0/0, 13-14=-9908/256, 13-28=0/0

BOT CHORD 25-26=-260/1506, 24-25=-741/13941,
22-24=-1461/30711, 21-22=-1663/40326,
19-21=-1468/42267, 18-19=-1246/39762,
16-18=-954/33086, 15-16=-608/22789,
14-15=-28/293

WEBS 2-25=-8600/508, 3-24=-6551/249,
5-22=-3767/262, 6-21=-749/192,
8-19=-24/1275, 9-18=-56/3324,
11-16=-85/5198, 12-15=-2236/141,
13-15=-353/13003, 11-15=-15030/440,
9-16=-11499/386, 8-18=-7395/324,
6-19=-2752/244, 5-21=-335/2116,
3-22=-360/10470, 2-24=-943/18127,
1-25=-678/15203

NOTES

- 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x10 - 2 rows staggered at 0-6-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
Attach TC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 418 lb uplift at joint 26 and 244 lb uplift at joint 14.

10) Load case(s) 1, 30, 31 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 300 lb down and 145 lb up at 13-4-8, and 300 lb down and 145 lb up at 13-4-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard Except:

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 2-29=-70, 5-29=-520, 5-12=-295, 12-13=-520, 14-26=-20
Concentrated Loads (lb)
Vert: 30=-542 (F=-271, B=-271)
- User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-13=18, 14-26=-12, 1-26=-8



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A06	Monopitch Girder	2	4	R88389164
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:31

Page: 2

ID: _J9u59?B18TVsoHVqyynnjzHCK5-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f

Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14,
13-31=22

Concentrated Loads (lb)

Vert: 30=291 (F=145, B=145)

Horz: 27=200, 31=200 (F)

31) User defined (2): Lumber Increase=1.60, Plate
Increase=1.60

Uniform Loads (lb/ft)

Vert: 1-13=18, 14-26=-12, 1-26=-8

Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14,
13-31=22

Concentrated Loads (lb)

Vert: 30=291 (F=145, B=145)

Horz: 27=-200 (F)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389165
4623747	A07	Monopitch Girder	1	3	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,


Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:32

Page: 1

ID: SxqZ_3EzNbMA8VJpOHuwy7zHCry-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.



Scale = 1:96.7

Plate Offsets (X, Y): [2:0-2-12,0-2-8], [15:0-2-0,0-2-0], [24:0-2-12,0-2-8], [25:0-1-12,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	-0.91	21-22	>731	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.57	Vert(CT)	-1.35	19-21	>496	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.21	14	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
Weight: 1077 lb FT = 10%												

LUMBER

TOP CHORD 2x6 DF 2400F 2.0E
BOT CHORD 2x6 DF 2400F 2.0E
WEBS 2x4 HF No.2 *Except* 27-26,28-14:2x6 DF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 14=0-5-8, 26=0-5-8
Max Horiz 26=591 (LC 30)
Max Grav 14=5822 (LC 1), 26=7788 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=9339/0, 2-3=-20682/0, 3-5=-24776/0, 5-6=-23523/0, 6-8=-24352/0, 8-9=-19909/0, 9-11=-11242/0, 11-12=-4695/0, 12-13=-4712/0, 1-26=-7734/0, 1-27=0/0, 13-14=-5733/0, 13-28=0/0
BOT CHORD 25-26=-2071005, 24-25=0/9314, 22-24=0/20673, 21-22=0/24734, 19-21=0/23510, 18-19=0/24644, 16-18=0/20204, 15-16=0/11554, 14-15=-58173
WEBS 2-25=-6329/34, 3-24=-4603/0, 5-22=-2473/0, 6-21=-2637/722, 8-19=-1261/1247, 9-18=0/2357, 11-16=0/4673, 12-15=-1267/190, 13-15=0/6636, 11-15=-8811/0, 9-16=-9791/0, 8-18=-4983/0, 6-19=-2522/2978, 5-21=-1462/6415, 3-22=0/6111, 2-24=0/12432, 1-25=0/10521

NOTES

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-8-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- All plates are 4x5 (=) MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Load case(s) 1, 30, 31 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 307 lb down and 128 lb up at 13-4-8, and 300 lb down and 145 lb up at 13-4-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard Except:

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 2-29=-70, 5-29=-520 (F=-450), 5-30=-70, 30-31=-170, 31-32=-70, 32-33=-170, 12-33=-70, 12-13=-520, 14-26=-20
Concentrated Loads (lb)
Vert: 34=-572 (F=-271, B=-300)
- User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-30=18, 30-31=-682, 31-32=18, 32-33=-682, 13-33=18, 14-26=-12, 1-26=-8
Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14, 13-28=22



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A07	Monopitch Girder	1	3	R88389165
					Job Reference (optional)

- Concentrated Loads (lb)
Horz: 27=200, 28=200 (F)
- 31) User defined (2): Lumber Increase=1.60, Plate Increase=1.60
- Uniform Loads (lb/ft)
Vert: 1-30=18, 30-31=-482, 31-32=18, 32-33=-482, 13-33=18, 14-26=-12, 1-26=-8
Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14, 13-28=22
- Concentrated Loads (lb)
Horz: 27=-200 (F), 28=-200



May 27,2025

Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:32 Page: 1
ID:OhXBWUGkT6F7Uk3?EYJTAzHCZF-Rfc?PsB70Hq3NSqPanL8w3u1TXbGKWrCDoi7J4zJC?cf

[illegible]

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinstitute.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916 755 3571 / MiTek-USA.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A08	Monopitch Girder	1	4	R88389166
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:32

Page: 2

ID:OhXBWUGkT6F7Uk73?EYJTAzHCZF-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f

Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14,
13-28=22

Concentrated Loads (lb)

Vert: 15=366 (B), 29=245 (F=128, B=117)

Horz: 27=200, 28=200 (F)

31) User defined (2): Lumber Increase=1.60, Plate
Increase=1.60

Uniform Loads (lb/ft)

Vert: 14-26=-12, 1-30=18, 30-31=-382, 31-32=18,
32-33=-382, 13-33=18, 1-26=-8

Horz: 1-13=-26, 1-26=8, 1-27=32, 13-14=14,
13-28=22

Concentrated Loads (lb)

Vert: 15=366 (B), 29=245 (F=128, B=117)

Horz: 27=-200 (F), 28=-200



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A09	Jack-Closed Girder	2	2	R88389167
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,


Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:33

Page: 1

ID:4LnJ8ItAyJh?2CnBaXTAORzHD7v-RfC?PsB70Hq3NSgPqnL8w3uITxbGKwRCDoi7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.



Scale = 1:87.3

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [6:0-2-0,0-2-0], [10:0-3-8,0-2-0], [14:0-1-12,0-2-8], [16:0-6-0,0-4-8], [18:0-2-0,0-2-0], [21:0-5-8,0-3-0], [23:0-3-4,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-1.00	18-20	>594	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.89	Vert(CT)	-1.42	17-18	>419	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	NO	WB	0.89	Horz(CT)	0.26	14	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
											Weight: 672 lb	FT = 10%

LUMBER

TOP CHORD 2x6 DF 2400F 2.0E
BOT CHORD 2x6 DF 2400F 2.0E
WEBS 2x4 DF 1800F 1.6E *Except*
13-14,25-24:2x6 DF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
3-5-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.
WEBS 1 Row at midpt 10-15

REACTIONS (size) 14= Mechanical, 24=0-5-8, (req.
0-6-1)
Max Horiz 24=251 (LC 7)
Max Grav 14=5590 (LC 30), 24=7329 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=-8800/128, 2-3=-18779/24,
3-4=-18784/26, 4-6=-21861/0, 6-7=-20896/0,
7-9=-23642/0, 9-10=-17932/0,
10-12=-6854/0, 12-13=-79/20,
13-14=-141/24, 1-24=-7266/4, 1-25=0/0
BOT CHORD 23-24=-304/861, 21-23=-105/8777,
20-21=0/21357, 18-20=0/21836,
17-18=0/20934, 15-17=0/23654,
14-15=0/6883
WEBS 2-23=-6020/90, 3-21=-1466/238,
6-20=-2419/106, 7-18=-2674/1046,
9-17=-1280/1753, 10-16=0/2960,
12-15=0/5961, 12-14=-8725/0,
10-15=-12521/0, 9-16=-6407/0,
7-17=-3647/3027, 6-18=-2300/6509,
4-20=0/3571, 2-21=0/10933, 1-23=0/9979,
4-21=-4024/0

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-6-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- WARNING: Required bearing size at joint(s) 24 greater than input bearing size.
- Refer to girder(s) for truss to truss connections.
- Load case(s) 1, 30, 31 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 337 lb down and 117 lb up at 13-4-8, and 337 lb down and 117 lb up at 13-4-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard Except:

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 2-26=-70, 6-26=-520, 6-27=-70, 9-27=-170, 9-28=-70, 28-29=-170, 13-29=-70, 14-24=-20
Concentrated Loads (lb)
Vert: 30=-674 (F=-337, B=-337)
- User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-27=18, 9-27=-882, 9-28=18, 28-29=-882, 13-29=18, 14-24=-12
Horz: 1-13=-26, 13-14=14



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A09	Jack-Closed Girder	2	2	R88389167
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:33
ID:4LnJ8ItAyJh?2CnBaXTAORzHD7v-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 2

Concentrated Loads (lb)

Vert: 30=233 (F=117, B=117)

Horz: 25=200

- 31) User defined (2): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (lb/ft)

Vert: 1-27=18, 9-27=-782, 9-28=18, 28-29=-782,

13-29=18, 14-24=-12

Horz: 1-13=-26, 13-14=14

Concentrated Loads (lb)

Vert: 30=233 (F=117, B=117)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®


400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389168
4623747	A10	Monopitch Supported Gable	1	2	Job Reference (optional)	


Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:33
ID:TwghHC4YmNvVODRZCbgyNzHE9U-RfC?PsB70Hq3NSgPqnL8w3uITXBGKWCrDci7J4JC?f

Page: 1



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.



Scale = 1:96.7

Plate Offsets (X, Y): [32:0-1-13,0-1-0], [36:0-1-12,0-1-0], [38:0-1-12,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.50	Vert(LL)	n/a	-	n/a	999	MT20
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.15	Vert(TL)	n/a	-	n/a	999	220/195
TCDL	10.0	Rep Stress Incr	NO	WB	0.53	Horiz(TL)	-0.02	15	n/a	n/a	
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH							
BCDL	10.0										
Weight: 755 lb FT = 10%											

LUMBER		TOP CHORD	2x6 DF 2400F 2.0E
		BOT CHORD	2x6 DF No.2
		WEBS	2x4 HF No.2 *Except* 43-31,44-14:2x6 DF No.2, 12-15:2x12 DF SS
		OTHERS	2x4 HF No.2
BRACING		TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
		BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
REACTIONS (size)			14=55-11-0, 15=55-11-0, 16=55-11-0, 18=55-11-0, 19=55-11-0, 21=55-11-0, 22=55-11-0, 23=55-11-0, 24=55-11-0, 25=55-11-0, 27=55-11-0, 28=55-11-0, 29=55-11-0, 30=55-11-0, 31=55-11-0
		Max Horiz	31=257 (LC 34)
		Max Uplift	14=-1288 (LC 35), 15=-1053 (LC 34), 16=-314 (LC 40), 22=-146 (LC 40), 25=-242 (LC 40), 29=-649 (LC 35), 30=-57 (LC 35), 31=-1584 (LC 32)
		Max Grav	14=1324 (LC 50), 15=7403 (LC 57), 16=668 (LC 27), 18=999 (LC 1), 19=1119 (LC 1), 21=678 (LC 27), 22=2113 (LC 1), 23=77 (LC 3), 24=47 (LC 3), 25=3763 (LC 1), 27=99 (LC 3), 28=74 (LC 3), 29=2807 (LC 1), 30=125 (LC 48), 31=1785 (LC 59)
FORCES		(lb) - Maximum Compression/Maximum Tension	

TOP CHORD		1-2=-1919/1916, 2-3=-2605/2519, 3-5=-2549/2421, 5-6=-2547/2371, 6-8=-2471/2274, 8-9=-2311/2192, 9-11=-2053/1985, 11-12=-1726/1564, 12-13=-1981/1828, 1-31=-1706/1529, 1-43=0/0, 13-14=-1270/1412, 13-44=0/0
BOT CHORD		30-31=-988/660, 29-30=-1588/1260, 28-29=-1001/827, 27-28=-794/581, 25-27=-1591/1378, 24-25=-688/539, 23-24=-652/504, 22-23=-1759/1610, 21-22=-1883/1776, 19-21=-1960/1904, 18-19=-2033/1998, 16-18=-2194/2083, 15-16=-1918/1761, 14-15=-1694/1689
WEBS		2-29=-2876/893, 1-29=-2364/2518, 13-15=-2328/2170, 5-22=-2166/1138, 6-21=-1365/1024, 8-19=-3311/698, 9-18=-2321/823, 11-16=-1432/1391, 11-15=-2083/2187, 9-16=-2123/2074, 5-21=-2155/2207, 2-25=-1934/2002, 3-25=-3671/1065, 3-22=-2110/2153, 6-19=-2208/2230, 8-18=-2241/2158, 12-15=-397/159

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x12 - 2 rows staggered at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 15-2-12, Exterior (2) 15-2-12 to 40-8-4, Corner (3) 40-8-4 to 55-8-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 (II) MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A10	Monopitch Supported Gable	1	2	R88389168
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:33

Page: 2

ID:TwHgHC4YMnvVODRZCbgyNzHE9U-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWwCDoi7J4zJC?f

- 10) Gable studs spaced at 2-0-0 oc.
- 11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1584 lb uplift at joint 31, 649 lb uplift at joint 29, 1053 lb uplift at joint 15, 146 lb uplift at joint 22, 314 lb uplift at joint 16, 242 lb uplift at joint 25, 1288 lb uplift at joint 14 and 57 lb uplift at joint 30.
- 14) Load case(s) 1, 64, 65 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 15) This truss has been designed for a total drag load of 300 plf. Lumber DOL=(1.33) Plate grip DOL=(1.33) Connect truss to resist drag loads along bottom chord from 0-0-0 to 55-11-0 for 300.0 plf.
- 16) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 7002 lb down and 2014 lb up at 50-1-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 17) Studding applied to ply: 2(Back)

LOAD CASE(S) Standard Except:

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-5=-520, 5-45=-70, 45-46=-170, 46-47=-70, 47-48=-170, 13-48=-70, 14-31=-20
Concentrated Loads (lb)
Vert: 15=-6045 (F)
- 64) User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-45=25, 45-46=-675, 46-47=25, 47-48=-675, 13-48=25, 14-31=-12
Horz: 1-13=-33, 1-31=17, 1-43=70, 13-14=32, 13-44=49
Concentrated Loads (lb)
Vert: 15=860 (F)
- 65) User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-45=25, 45-46=-475, 46-47=25, 47-48=-475, 13-48=25, 14-31=-12
Horz: 1-13=-33, 1-31=17, 1-43=70, 13-14=32, 13-44=49
Concentrated Loads (lb)
Vert: 15=860 (F)



May 27, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:34 Page: 1
ID:oBFAf8ABv2RVtmI6Wm6uoHzHEWc-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWkCDoi7J4zJC?f



LUMBER		1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:	1) Hanger(S) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.
TOP CHORD	2x6 DF 2400F 2.0E	Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.	LOAD CASE(S) Standard Except:
BOT CHORD	2x6 DF 2400F 2.0E *Except* 20-17:2x6 DF No.2	Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.	
WEBS	2x4 HF No.2 *Except* 21-20,22-11:2x6 DF No.2	Web connected as follows: 2x4 - 1 row at 0-9-0 oc.	1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
BRACING		2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.	Uniform Loads (lb/ft) Vert: 11-20=-20, 1-2=-520, 2-23=-70, 5-23=-170, 5-24=-70, 24-25=-170, 9-25=-70, 9-10=-520 (F=-450)
TOP CHORD	Structural wood sheathing directly applied or 3-11-10 oc purlins, except end verticals.	3) Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TC DL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 5-2-12, Exterior (2) 5-2-12 to 37-4-8, Corner (3) 37-4-8 to 42-4-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	4) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	4) TC LL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.	Uniform Loads (lb/ft) Vert: 11-20=-12, 1-23=25, 5-23=-75, 5-24=25, 24-25=-75, 10-25=25, 1-20=-17 Horz: 1-10=-33, 1-20=17, 1-21=67, 10-11=27, 10-22=43
WEBS	1 Row at midpt 6-13, 8-12	5) Provide adequate drainage to prevent water ponding.	Concentrated Loads (lb) Horz: 26=200, 27=200 (F)
REACTIONS		6) All plates are MT20 plates unless otherwise indicated.	26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60
(size)	11=0-5-8, 20=0-5-8	7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
Max Horiz	20=-692 (LC 10)	8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.	
Max Grav	11=4061 (LC 1), 20=4114 (LC 1)	9) Load case(s) 1, 4, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.	
FORCES			
(lb) - Maximum Compression/Maximum Tension			
TOP CHORD	1-2=-5782/0, 2-3=-15000/0, 3-5=-20729/0, 5-6=-18345/0, 6-8=-10698/0, 8-9=-3702/240, 9-10=-3702/245, 1-20=-4612/0, 1-21=0/0, 10-11=-3981/0, 10-22=0/0		
BOT CHORD	19-20=-194/1367, 18-19=0/5918, 16-18=0/15142, 15-16=0/20842, 13-15=0/18457, 12-13=0/10822, 11-12=-63/131		
WEBS	2-19=-4209/0, 1-19=0/6714, 9-12=-1271/194, 10-12=0/5465, 2-18=0/10183, 3-18=-4247/0, 3-16=0/6344, 5-16=-2741/0, 5-15=-2676/0, 6-15=0/1280, 6-13=-8642/0, 8-13=0/4146, 8-12=-7966/0		
NOTES			



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A11	Monopitch	7	2	R88389169
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:34

Page: 2

ID:oBFAf8ABv2RVtMl6Wm6uoHzHEWc-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Uniform Loads (lb/ft)

Vert: 11-20=-12, 1-23=-5, 5-23=-805, 5-24=-5,
24-25=-805, 10-25=-5, 1-20=-18
Horz: 1-10=-4, 1-20=18, 1-26=71, 10-11=28,
10-27=45

- 27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (lb/ft)

Vert: 11-20=-12, 1-23=-5, 5-23=-605, 5-24=-5,
24-25=-605, 10-25=-5, 1-20=-18
Horz: 1-10=-4, 1-20=18, 1-26=71, 10-11=28,
10-27=45



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389170
4623747	A12	Monopitch	14	1	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,


Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:34

Page: 1

ID:nmeY_CzAaALQJ5GaSRosayzHfFA-RfC?PsB70Hq3NSgPqnl8w3uITxbGKwRCDoi7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.



Scale = 1:87.9

Plate Offsets (X, Y): [1:0-4-12,0-4-0], [2:0-2-4,0-2-0], [10:0-4-0,0-3-4], [11:Edge,0-5-8], [12:0-2-8,0-3-8], [18:0-2-0,0-2-0], [19:0-1-12,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.49	15-16	>999	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.44	Vert(CT)	-0.79	15-16	>642	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.14	11	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
											Weight: 288 lb	FT = 10%

LUMBER

TOP CHORD 2x6 DF No.2
BOT CHORD 2x6 DF 2400F 2.0E
WEBS 2x4 HF No.2 *Except* 21-20,22-11:2x6 DF No.2
OTHERS 2x4 HF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-7-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 9-9-7 oc bracing.
WEBS 1 Row at midpt 8-12, 6-13

REACTIONS (size) 11=0-5-8, (req. 0-5-15), 20=0-5-8, (req. 0-5-14)
Max Horiz 20=317 (LC 9)
Max Uplift 11=125 (LC 12), 20=151 (LC 8)
Max Grav 11=3613 (LC 1), 20=3579 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-3376/609, 2-3=-5653/800, 3-5=-6619/842, 5-6=-6323/810, 6-8=-4923/700, 8-9=-2575/473, 9-10=-2591/478, 1-20=-3524/355, 1-21=0/0, 10-11=-3532/365, 10-22=0/0
BOT CHORD 19-20=-724/860, 18-19=-957/3355, 16-18=-1143/5646, 15-16=-1146/6612, 13-15=-980/6317, 12-13=-669/4917, 11-12=-49/126
WEBS 2-19=-2378/328, 1-19=-424/3820, 9-12=-1264/176, 8-12=-2680/515, 3-18=-934/329, 2-18=-559/2529, 3-16=-318/1075, 5-16=-335/220, 5-15=-332/186, 6-15=-3/356, 6-13=-1585/352, 8-13=-75/892, 10-12=-395/3580

NOTES

- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 5-2-12, Exterior (2) 5-2-12 to 37-4-8, Corner (3) 37-4-8 to 42-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- WARNING: Required bearing size at joint(s) 20, 11 greater than input bearing size.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 151 lb uplift at joint 20 and 125 lb uplift at joint 11.
- Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard Except:

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (lb/ft)

Vert: 1-2=-520, 2-9=-70, 9-10=-520, 11-20=-20
26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (lb/ft)

Vert: 1-10=25, 11-20=-12
Horz: 1-10=-33

Concentrated Loads (lb)

Horz: 23=200, 24=200 (F)

- 27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (lb/ft)

Vert: 1-10=25, 11-20=-12
Horz: 1-10=-33

Concentrated Loads (lb)

Horz: 23=200 (F), 24=-200



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#	R88389171
4623747	A13	Monopitch	2	2	Job Reference (optional)	

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,


Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:35

Page: 1

ID:kXOWU7by0vvhCAiZeWMJIZzHEf6-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoI7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.



Scale = 1:87.9

[1:0-5-0,0-2-8], [2:0-2-8,0-2-4], [3:0-2-0,0-2-0], [8:0-3-8,0-2-0], [10:0-4-8,0-2-4], [11:0-3-0,0-2-12], [12:0-4-4,0-2-4], [16:0-2-0,0-2-0], [18:0-2-0,0-2-8], [19:0-3-0,0-2-8],
Plate Offsets (X, Y): [20:0-3-0,0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.93	15-16	>550	240	MT20	220/195
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.63	Vert(CT)	-1.06	15-16	>479	180	M18AHS	169/162
TCDL	10.0	Rep Stress Incr	NO	WB	0.98	Horz(CT)	0.19	11	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-SH								
BCDL	10.0											
											Weight: 577 lb	FT = 10%

LUMBER		
TOP CHORD	2x6 DF 2400F 2.0E	
BOT CHORD	2x6 DF 2400F 2.0E	
WEBS	2x4 HF No.2 *Except* 8-12:2x4 DF No.2, 21-20,22-11:2x6 DF No.2	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 4-4-3 oc purlins, except end verticals.	
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS	1 Row at midpt	8-12, 6-13
REACTIONS		
(size)	11=0-5-8, 20=0-5-8	
Max Horiz	20=317 (LC 9)	
Max Uplift	11=-125 (LC 12), 20=-151 (LC 8)	
Max Grav	11=6674 (LC 1), 20=6607 (LC 1)	
FORCES		
	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-7771/610, 2-3=-16236/800, 3-5=-19779/842, 5-6=-18930/810, 6-8=-14276/700, 8-9=-6011/473, 9-10=-6003/478, 1-20=-6560/354, 1-21=0/0, 10-11=-6567/363, 10-22=0/0, 19-20=-717/850, 18-19=-957/7760, 16-18=-1142/16211, 15-16=-1146/19754, 13-15=-979/18905, 12-13=-671/14253, 11-12=-45/131	
BOT CHORD	9-12=-1665/179, 10-12=-388/8579, 2-19=-5831/323, 1-19=-408/9264, 8-12=-9439/520, 3-18=-3864/330, 2-18=-561/9329, 3-16=-317/3943, 5-16=-1586/220, 5-15=-953/187, 6-15=-2/556, 6-13=-5266/349, 8-13=-76/2611	
WEBS		
NOTES		

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) 0-2-12 to 5-2-12, Exterior (2) 5-2-12 to 37-4-8, Corner (3) 37-4-8 to 42-4-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 151 lb uplift at joint 20 and 125 lb uplift at joint 11.

- Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.
- LOAD CASE(S)** Standard Except:
- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-10=-295, 11-20=-20
 - User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-10=25, 11-20=-12
Horz: 1-10=-33
Concentrated Loads (lb)
Horz: 23=200, 24=200 (F)
 - User defined (2): Lumber Increase=1.60, Plate Increase=1.60



May 27, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A13	Monopitch	2	2	R88389171
					Job Reference (optional)

Uniform Loads (lb/ft)
Vert: 1-10=25, 11-20=-12
Horz: 1-10=-33
Concentrated Loads (lb)
Horz: 23=-200 (F), 24=-200



May 27,2025

Builders FirstSource (Arlington, WA), Arlington, WA - 98223, Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:35 Page: 1
ID:5dQkr9kBIe34g7iOpKuJq1zHfbc-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKwRCdoi7J4zJC?f



LUMBER		Max Grav	25=549 (LC 19), 26=1322 (LC 1), 27=1068 (LC 1), 28=1078 (LC 1), 29=1081 (LC 1), 30=1080 (LC 1), 31=1080 (LC 1), 32=1080 (LC 1), 34=1080 (LC 1), 35=1080 (LC 1), 36=1080 (LC 1), 37=1080 (LC 1), 38=1080 (LC 1), 39=1080 (LC 1), 40=1080 (LC 1), 41=1080 (LC 1), 43=1080 (LC 1), 44=1080 (LC 1), 45=1076 (LC 1), 46=1108 (LC 1), 47=1213 (LC 19), 48=617 (LC 20)	WEBS	2-47=-995/230, 3-46=-1066/67, 4-45=-1037/52, 5-44=-1040/50, 6-43=-1040/50, 7-41=-1040/50, 8-40=-1040/50, 9-39=-1040/50, 11-38=-1040/50, 12-37=-1040/50, 13-36=-1040/50, 14-35=-1040/50, 15-34=-1040/50, 16-32=-1040/50, 17-31=-1040/50, 18-30=-1040/50, 20-29=-1041/50, 21-28=-1038/50, 22-27=-1026/68, 23-26=-1195/143, 1-47=-1006/931, 24-26=-532/488
TOP CHORD	2x6 DF No.2				
BOT CHORD	2x6 DF No.2				
WEBS	2x6 DF No.2 *Except* 1-47,26-24:2x4 HF No.2				
OTHERS	2x4 HF No.2				
BRACING					
TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.				
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing. Except:				

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)



400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	A14	Monopitch Supported Gable	1	1	R88389172
					Job Reference (optional)

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:35

Page: 2

ID:5dQkr9kBE34g7iOpKuJq1zHFbc-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are 2x4 (||) MT20 unless otherwise indicated.
 - 6) Gable requires continuous bottom chord bearing.
 - 7) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 8) Gable studs spaced at 2-0-0 oc.
 - 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 508 lb uplift at joint 48, 456 lb uplift at joint 47, 20 lb uplift at joint 46, 13 lb uplift at joint 45, 12 lb uplift at joint 44, 12 lb uplift at joint 43, 12 lb uplift at joint 41, 12 lb uplift at joint 40, 12 lb uplift at joint 39, 12 lb uplift at joint 38, 12 lb uplift at joint 37, 12 lb uplift at joint 36, 12 lb uplift at joint 35, 12 lb uplift at joint 34, 12 lb uplift at joint 32, 12 lb uplift at joint 31, 12 lb uplift at joint 30, 12 lb uplift at joint 29, 11 lb uplift at joint 28, 8 lb uplift at joint 27, 239 lb uplift at joint 26 and 267 lb uplift at joint 25.
 - 12) Load case(s) 1, 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - 13) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.
 - 14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- LOAD CASE(S)** Standard Except:
- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-24=-520, 25-48=-20
 - 26) User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-24=25, 25-48=-12
Horz: 1-24=-33, 1-48=18, 1-51=71, 24-25=34, 24-52=52
Concentrated Loads (lb)
Horz: 51=200, 52=200 (F)
 - 27) User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-24=25, 25-48=-12
Horz: 1-24=-33, 1-48=18, 1-51=71, 24-25=34, 24-52=52
Concentrated Loads (lb)
Horz: 51=-200 (F), 52=-200 (F)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	B01	Flat	1	3	R88389173
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,


Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:36

Page: 1

ID:ROTNs6uBiqpJnhb?pztaQFzDZdJ-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?i

WARNING: MARK TOP CHORD TO PREVENT IMPROPER INSTALLATION.

PLY-TO-PLY CONNECTION REQUIRES THAT AN APPROVED FACE MOUNT HANGER (SPECIFIED BY OTHERS) IS REQUIRED AT JOINT 7, 8 FOR LOAD REPORTED IN NOTES. FACE MOUNT HANGER SHALL BE ATTACHED WITH A MINIMUM OF 0.25"x 4.5" SCREWS OR OTHER FASTENERS THAT PENETRATES ALL PLIES, PER HANGER MANUFACTURER SPECIFICATIONS.



Scale = 1:34.2

Plate Offsets (X, Y): [5:0-8-0,0-8-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	0.02	5	>999	240	MT20	185/148
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.26	Vert(CT)	-0.02	5	>999	180		
TCDL	10.0	Rep Stress Incr	Yes	WB	0.26	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 151 lb	FT = 10%

LUMBER

TOP CHORD 2x6 DF 2400F 2.0E
BOT CHORD 2x10 DF SS
WEBS 2x4 HF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-3-9 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 4= Mechanical, 6= Mechanical
Max Horiz 6=-92 (LC 8)
Max Uplift 4=-426 (LC 9), 6=-401 (LC 8)
Max Grav 4=6045 (LC 19), 6=5623 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-6=-3367/1955, 1-2=-2101/1165,
2-3=-2101/1165, 3-4=-3384/1955
BOT CHORD 5-6=-130/134, 4-5=-47/51
WEBS 3-5=-2161/3809, 2-5=-2/209, 1-5=-2161/3758

NOTES

- n/a
- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 5 rows staggered at 0-4-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 401 lb uplift at joint 6 and 426 lb uplift at joint 4.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 5665 lb down and 3109 lb up at 1-8-13, and 5665 lb down and 3109 lb up at 3-8-13 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 4-6=-20
Concentrated Loads (lb)
Vert: 7=-5590 (B), 8=-5590 (B)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	B02	Flat Girder	1	1	R88389174
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:36

Page: 1

ID:nNLha04LPXuro4yp8o_dypzDZQ9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:37.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.10	0.02	3-4	>999	240	MT20	185/148
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.34	-0.02	3-4	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.04	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 29 lb	FT = 10%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2x6 DF No.2
WEBS	2x4 HF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-8-6 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	3=0-2-6, 4= Mechanical
Max Horiz	4=98 (LC 5)
Max Uplift	3=-336 (LC 5), 4=-318 (LC 4)
Max Grav	3=372 (LC 15), 4=357 (LC 16)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-4=-119/88, 1-2=-37/28, 2-3=-119/30
BOT CHORD	3-4=-86/77
WEBS	1-3=-76/76

NOTES

- 1) Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 3.

- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 318 lb uplift at joint 4 and 336 lb uplift at joint 3.
- 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 524 lb down and 519 lb up at 1-10-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-70, 3-4=-20
Concentrated Loads (lb)
Vert: 5=-64 (F)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	C01	Roof Special Girder	1	1	R88389175
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:36

Page: 1

ID:1fRxcjbJHJHSh49KGiCuzDZPU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:52.4

Plate Offsets (X, Y): [1:0-4-15,0-2-4], [6:0-4-0,0-4-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.72	Vert(LL)	0.01	5-6	>999	240	M18AHS	145/140
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.01	5-6	>999	180	MT20	185/148
TCDL	10.0	Rep Stress Incr	NO	WB	0.18	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 53 lb	FT = 10%

LUMBER

TOP CHORD 2x4 HF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 HF No.2 *Except* 7-6:2x6 DF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-7-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 4= Mechanical, 6=0-5-8
Max Horiz 6=-421 (LC 30)
Max Uplift 4=-303 (LC 5), 6=-678 (LC 30)
Max Grav 4=442 (LC 15), 6=526 (LC 16)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-511/191, 2-3=-240/194, 3-4=-436/333,
1-6=-84/145, 1-7=0/0
BOT CHORD 5-6=-229/269, 4-5=-37/28
WEBS 2-5=-607/374, 3-5=-376/452, 2-6=-405/556

NOTES

- Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 303 lb uplift at joint 4 and 678 lb uplift at joint 6.
- Load case(s) 30, 31 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 352 lb down and 330 lb up at 2-0-5 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard Except:

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 4-6=-20
Concentrated Loads (lb)
Vert: 8=-164 (F)
- User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-3=7, 4-6=-12
Horz: 1-3=15, 3-4=14, 1-6=11, 1-7=33
Concentrated Loads (lb)
Vert: 8=330 (F)
Horz: 7=200
- User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-3=7, 4-6=-12
Horz: 1-3=15, 3-4=14, 1-6=11, 1-7=33
Concentrated Loads (lb)
Vert: 8=330 (F)
Horz: 7=-200 (F)



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	C02	Roof Special	1	1	R88389176
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:36

Page: 1

ID:JNC1gESkfZLDZ5_q5t2QrrzDZQz-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



ARCHITECT OR BLDG DESIGNER TO VERIFY DESIGN LOAD
AS SHOWN IN NOTES BELOW ACCOUNTS FOR DRIFTING SNOW.

Scale = 1:56.3

Plate Offsets (X, Y): [1:0-6-12,0-3-0], [3:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	0.00	3-4	>999	240	M18AHS	145/140
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.11	Vert(CT)	0.00	3-4	>999	180	MT20	185/148
TCDL	10.0	Rep Stress Incr	NO	WB	0.61	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 30 lb	FT = 10%

LUMBER

TOP CHORD 2x4 HF No.2
BOT CHORD 2x4 HF No.2
WEBS 2x4 HF No.2 *Except* 5-4:2x6 DF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-11-9 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4=0-5-8
Max Horiz 4=212 (LC 11)
Max Uplift 3=-509 (LC 9), 4=-496 (LC 8)
Max Grav 3=534 (LC 10), 4=522 (LC 11)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-51/59, 2-3=-239/109, 1-4=-756/1930, 1-5=0/0
BOT CHORD 3-4=-303/661
WEBS 1-3=-1710/733

NOTES

- Wind: ASCE 7-16; Vult=110mph (3-second gust) Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) interior zone and C-C Corner (3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 509 lb uplift at joint 3 and 496 lb uplift at joint 4.
- Load case(s) 26, 27 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) . The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard Except:

- User defined (1): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-2=63, 3-4=-12, 1-4=-17
Horz: 1-2=71, 2-3=27, 1-4=17, 1-5=67
Concentrated Loads (lb)
Horz: 5=200
- User defined (2): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (lb/ft)
Vert: 1-2=63, 3-4=-12, 1-4=-17
Horz: 1-2=71, 2-3=27, 1-4=17, 1-5=67
Concentrated Loads (lb)
Horz: 5=200



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	P02	Flat	2	1	R88389177
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:36

Page: 1

ID:jFrIzoLOXwZA5MSdI4FMa5zHDpC-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	0.00	3-4	>999	240	MT20	185/148
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	3-4	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0										Weight: 14 lb	FT = 10%

LUMBER

TOP CHORD 2x4 HF No.2
BOT CHORD 2x4 HF No.2
WEBS 2x4 HF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-7-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=82 (LC 9)
Max Uplift 3=-108 (LC 9), 4=-108 (LC 8)
Max Grav 3=352 (LC 1), 4=352 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-4=-339/228, 1-2=-41/45, 2-3=-339/41
BOT CHORD 3-4=-114/118
WEBS 1-3=-201/201

NOTES

- 1) Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.

- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 108 lb uplift at joint 4 and 108 lb uplift at joint 3.
- 8) Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 3-4=-20



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	P03	Flat	3	1	R88389178
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:37

Page: 1

ID:RLGyCj6b9nyScochIktbVtzHDmw-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:36.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	0.00	4	>999	240	MT20	185/148
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	3-4	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 14 lb	FT = 10%

LUMBER

TOP CHORD 2x4 HF No.2
BOT CHORD 2x4 HF No.2
WEBS 2x4 HF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-3-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 3=0-2-6, 4= Mechanical
Max Horiz 4=82 (LC 9)
Max Uplift 3=-138 (LC 9), 4=-138 (LC 8)
Max Grav 3=312 (LC 19), 4=312 (LC 20)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-302/275, 1-2=-41/45, 2-3=-273/31
BOT CHORD 3-4=-114/118
WEBS 1-3=-254/254

NOTES

- 1) Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.

- 7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 3.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 4 and 138 lb uplift at joint 3.
- 9) Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-545, 3-4=-20



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	MKM EAST TOWN CROSSING LOT 1#
4623747	P04	Flat	1	1	R88389179
Job Reference (optional)					

Builders FirstSource (Arlington, WA), Arlington, WA - 98223,

Run: 8.83 S Apr 24 2025 Print: 8.830 S Apr 24 2025 MiTek Industries, Inc. Fri May 23 17:15:37

Page: 1

ID:jFrIzoL0XwZA5MSdI4FMA5zHDpC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:36.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.16	Vert(LL)	0.00	3-4	>999	240	MT20	185/148
(Roof Snow = 25.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	3-4	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IBC2021/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 14 lb	FT = 10%

LUMBER

TOP CHORD 2x4 HF No.2
BOT CHORD 2x4 HF No.2
WEBS 2x4 HF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-5-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=82 (LC 9)
Max Uplift 3=-120 (LC 9), 4=-120 (LC 8)
Max Grav 3=320 (LC 19), 4=320 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-309/246, 1-2=-41/45, 2-3=-302/36
BOT CHORD 3-4=-114/118
WEBS 1-3=-222/222

NOTES

- 1) Wind: ASCE 7-16; Vult=110mph (3-second gust)
Vasd=87mph; TCDL=4.2psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) TCLL: ASCE 7-16; Pf=25.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; IBC 1607.11.2 minimum roof live load applied where required.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.

- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 4 and 120 lb uplift at joint 3.
 - 8) Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- LOAD CASE(S)** Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-520, 3-4=-20



May 27, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®


400 Sunrise Ave., Suite 270
Roseville, CA 95661
916.755.3571 / MiTek-US.com

Symbols

PLATE LOCATION AND ORIENTATION



0- $\frac{1}{16}$ "



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ " from outside edge of truss.

—
This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.


Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)

1 2 3 Joint ID typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

MITek®

MITek Engineering Reference Sheet: MIL-7473 rev. 1/12/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.