FIRE ALARM CONSTRUCTION DOCUMENT SET

LSL OFFICE TI 302 33RD ST SE, PUYALLUP WA 98372 FA25075

SHEET INDEX						
SHEET	REV.	DESCRIPTION				
FA001		GENERAL SHEET, LEGEND & NOTES				
FA101		DEVICE LOCATION VIEWS - FIRST LEVEL				
FA501		SCHEDULES, POWER CALCULATIONS, RISER DIAGRAMS				
FA601		PRODUCT TYPICALS				

SHEET I	SHEET NAMING CONVENTION				
SHEET	DESCRIPTION				
FA0XX	X GENERAL SHEET, LEGEND & NOTES				
FA1XX	DEVICE LOCATION VIEWS - FIRST FLOOR				
FA5XX	SCHEDULES & RISER DIAGRAMS, POWER CALCULATIONS				
FA6XX	PRODUCT TYPICALS				

IDENTIFIER TYPES					
TYPE	DESCRIPTION				
Ţ×	DEVICE IDENTIFIER - EXISTING, ADD, REPLACE, MOVE, DEMO				
X:XX:XXX XX	POINT OF PROTECTION IDENTIFIER / TYPE REFERENCE				
/ xx	REVISION IDENTIFIER				
√⊗	CABLE ID - SEE CABLE LEGEND				
	SHEET ID - SHEET DETAIL "A", "B", "C" / SHEET #XXXX				

إ	DEVICE IDENTIFIERS				
	TYPE	DESCRIPTION			
	√E	DEVICE EXISTING IDENTIFIER			
	A	DEVICE ADD IDENTIFIER			
	R	DEVICE REPLACE IDENTIFIER			
	√ ^M	DEVICE MOVE IDENTIFIER			
	Ţ□	DEVICE DEMO IDENTIFIER			

CABLE LEGEND								
ID	AWG	COND	SHEILD	CLASS	ID	AWG	SHEILD	CLASS
Α	16	2	N	FPLR	AA			
В	16	4	N	FPLR	BB			
С	16	2	N	FPLP	CC			
D	16	4	N	FPLP	DD			
Е	14	2	N	FPLR	EE			
F	14	4	N	FPLR	FF			
G	14	2	N	FPLP	GG			
Н	14	4	N	FPLP	HH			
I	12	2	N	FPLR	II			
J	12	4	N	FPLR	JJ			
K	12	2	N	FPLP	KK			
L	12	4	N	FPLP	LL			
M	16	2	N	TFFN	MM			
N	16	4	N	TFFN	NN			
0	16	2	N	THWN	00			
Р	16	4	N	THWN	PP			
Q					QQ			
U					UU			
R					RR			
S					SS			
Т					TT			
U					UU			
V					VV			
Х					XX			
Υ					YY			
Z					ZZ			

	ORK						
THE SCOPE OF THIS WILL BE F	F THIS PROJECT IS FOR A TENANT IMPR	TO RELOCATE (1) NO ROVEMENT.	OTIFICATION	DEVICE AND ((1) SMOKE DE	TECTOR. ALSO TO ADD (2) ADDITIONAL SMOKE DETECT	ORS.
SYSTEM COD	ES						
CURRENT ADC	PTED CODE VERSI	ON IFC 2021					
JSE & OCCUP	PANCY CLASSI	FICATION					
☐ ASSEMBLY	(A)	☐ A-1	□ A-2	□ A-3	□ A-4	□ A-5	
■ BUSINESS ((B)						
☐ EDUCATION							
	INDUSTRIAL (F)	☐ F-1	☐ F-2				
☐ HIGH HAZA		_ H-1	_ H-2	☐ H-3	☐ H-4	□ H-5	
☐ INSTITUTIO		☐ I-1	☐ I-2	□ I-3	□ I-4		
☐ MERCANTIL							
☐ RESIDENTIA		□ R-1	□ R-2	□ R-3	□ R-4		
☐ STORAGE (☐ S-1	□ S-2	□ S-3	□ S-4		
•	IISCELLANEOUS (U)						
	3 (0)	,					
BUILDING CO	NSTRUCTION T	TYPES					
☐ TYPE I	☐ TYPE I-A	☐ TYPE I-B					
☐ TYPE II	☐ TYPE II-A	☐ TYPE II-B					
	☐ TYPE III-A	☐ TYPE III-B					
☐ TYPE III							
☐ TYPE IV	☐ TYPE V-A	☐ TYPE V-B					
	☐ TYPE V-A	☐ TYPE V-B					

GENERAL NOTES

- 1. INSTALLATION SHALL BE ACCOMPLISHED IN STRICT COMPLIANCE WITH NFPA, LOCAL, AND STATE AHJ'S, NEC, AND CONTRACT DRAWINGS. 2. AS-BUILT DRAWINGS ARE REQUIRED AT THE TIME OF AHJ ACCEPTANCE. SMITH FIRE SYSTEMS REQUIRES ELECTRICAL RED LINES WITH IN TWO WEEKS PRIOR TO
- 3. AGREEMENT AND CONFIRMATION OF ALL MILESTONE EVENTS WILL BE MADE WITH SMITH FIRE SYSTEMS PROJECT MANAGER. ALL SMITH FIRE SYSTEMS FIELD SERVICES MUST BE SCHEDULED WITH SMITH FIRE SYSTEMS PROJECT MANAGER WITH A MINIMUM OF TEN BUSINESS DAY'S ADVANCE NOTICE.
- 4. A SET OF INSTALLATION AS-BUILT DRAWINGS SHOWING ACTUAL CONDUIT AND CONDUCTOR ROUTES SHALL BE KEPT BY PROJECT FOREMAN FOR USE
- 5. FIRE ALARM CONTROL PANEL SHALL NOT BE ENERGIZED WITHOUT THE PRESENCE OF A SMITH FIRE SYSTEMS ALARM TECHNICIAN.
- 6. THE FIRE ALARM SYSTEM SHALL BE MONITORED BY A UNDERWRITERS LISTED MONITORING STATION BEFORE AHJ'S TEST.
- 7. WIRE ROUTING IS DIAGRAMMATIC IN NATURE ONLY AND NOT INTENDED FOR ACTUAL CONDUIT ROUTING. 8. ALL CONDUIT SIZING AND ROUTING BY ELECTRICAL CONTRACTOR PER NEC AND AHJ.
- 9. NO LINE VOLTAGE IN SAME CONDUIT AS POWER LIMITED FIRE ALARM CABLE.
- 10. VERIFY ALL LOCATIONS OF DEVICES WITH ELECTRICAL AND ARCHITECTURAL PLANS. SCALE AND PLACE ALL DEVICES PER ELECTRICAL
- 11. FIELD VERIFY WATERFLOW SWITCHES, TAMPER SWITCHES, PRESSURE SWITCHES, SMOKE DAMPERS, AND DUCT DETECTOR LOCATIONS.
- 12. FIELD VERIFY ALL WIRING LOCATIONS AND REQUIREMENTS FOR HVAC AND FAN CONTROL.
- 13. SMOKE DETECTORS SHALL NOT BE LOCATED WITH IN 36" OF ANY AIR DIFFUSER.
- 14. WALL MOUNTED AUDIBLE/VISUAL APPLIANCES SHALL BE MOUNTED IN SUCH THAT THE ENTIRE LENS IS NOT LESS THAN 80" AND NOT GREATER THE 96" ABOVE FINISHED FLOOR.
- 15. THE OPERABLE PART OF EACH MANUAL FIRE ALARM BOX SHALL BE NOT LESS THAN 3'-6" AND NOT MORE THAN 4'-6" ABOVE THE FINISHED FLOOR.
- 16. NO DETECTOR SHALL BE INSTALLED UNTIL AFTER FINAL CONSTRUCTION CLEAN-UP. DETECTORS THAT HAVE BEEN INSTALLED PRIOR TO CLEAN-UP MUST BE
- 17. A DEDICATED BRANCH CIRCUIT OF ONE OF THE FOLLOWING SHALL SUPPLY PRIMARY POWER.
- B) AN ENGINE-DRIVEN GENERATOR OR EQUIVALENT WHERE A PERSON SPECIFICALLY TRAINED IN ITS OPERATIONS IS ON DUTY AT ALL TIMES. E) AN ENGINE-DRIVEN GENERATOR OR EQUIVALENT ARRANGED FOR COGENERATION WITH COMMERCIAL LIGHT AND POWER WHERE A PERSON SPECIFICALLY
- 18. ALL CIRCUITS WILL BE PROPERLY TAGGED AND TESTED FOR OPENS, SHORTS, GROUNDS, AND PROPER "END-TO-LINE" RESISTANCE. EACH CIRCUITS METER READING MUST BE DOCUMENTED AND PRESENTED TO SMITH FIRE SYSTEMS ALARM TECHNICIAN UPON ARRIVAL ONSITE FOR STARTUP AND CHECKOUT.
- 19. NO TAPPING OF SIGNALING OR INITIATING ZONE CIRCUITS ARE ALLOWED. T-TAPPING OF STYLE 4 ADDRESSABLE CIRCUITS IS ALLOWED PROVIDING A SPLICE IS PROFESSIONALLY INSTALLED, POLARITY IS OBSERVED, AND SHIELDS ARE CONTINUOUS AND FREE OF GROUNDS. SHIELDS MUST BE TERMINATED AT THE FIRE ALARM CONTROL PANEL ONLY. CABLE SHIELDS SHALL BE SPLICED TOGETHER AT EVERY JUNCTION BETWEEN THE FIRE ALARM CONTROL PANEL AND THE LAST DEVICE ON EACH CABLE RUN. SHIELDS AND OTHER FIRE ALARM CONDUCTORS (EXCEPT POWER GROUNDS) SHALL BE INSULATED AND COMPLETELY FREE FROM CONDUIT OR EARTH GROUNDS. SHIELDS WILL BE TIED TO GROUND ONLY AT THE FIR ALARM CONTROL PANEL.

DRAWING ACCEPTANCE

THIS DRAWING IS TO BE USED FOR THE PURPOSE OF PLACING AND LOCATING SMITH FIRE SYSTEMS FIRE ALARM DEVICES AND IS NOT BE USED FOR ANY OTHER

RECORD DRAWINGS

ALL WORK PERFORMED IN THE FIELD SHALL BE ACCURATELY RECORDED ON THESE DRAWINGS AND RETURNED TO SMITH FIRE SYSTEMS CORPORATE OFFICE.

MONITORING COMPANY	INSTALLATION COMPANY
ACI 4500 3RD AVE, LACEY WA 98503 ACCOUNT# LACAES1E028	SMITH FIRE SYSTEMS 1106 54TH AVE E, TACOMA, WA 98424

FIRE ALARM - PANELS

QTY	SYMBOL	DEVICE DESCRIPTION
Е	FACP	FIRE ALARM CONTROL PANEL
	FM200	FM-200 CLEAN AGENT PANEL
	PAP	PRE-ACTION CONTROL PANEL
	EVAC	VOICE EVACUATION CONTROL PANEL
	FSE	FIRE SIGNAL EXPANDER
	ANN	REMOTE ANNUNCIATOR
	UT2	SUBSCRIBER TERMINAL UNIT
	AES	AES TRANSMITTER

FIRE	ALARM	- NOTIFICATION DEVICES
QTY	SYMBOL	DEVICE DESCRIPTION
	Ø	WALL STROBE
	\square_{WP}	WALL STROBE WEATHERPROOF
	Q	CEILING STROBE
	Ŭ _{VP}	CEILING STROBE WEATHERPROOF
	X	WALL HORN-STROBE
		WALL HORN-STROBE WEATHERPROOF
Е	Ξ	CEILING HORN-STROBE
	HWP	CEILING HORN-STROBE WEATHERPROOF
		WALL HORN
	(E)	CEILING HORN
	DØ	WALL MINI-SPEAKER
	2	WALL SPEAKER
	(2)	CEILING SPEAKER
		WALL SPEAKER/STROBE
	<i>(22)</i>	CEILING SPEAKER/STROBE
	С	WALL CHIME
	(c)	CEILING CHIME
	В	WALL BUZZER
	В	CEILING BUZZER
		BELL

FIRE ALARM - DETECTORS

	/ \L/ \l \l \l	BETECTORS
QTY	SYMBOL	DEVICE DESCRIPTION
2	⊘ _P	SMOKE DETECTOR
	O AB	SMOKE DETECTOR ABOVE CEILING
	(S)BL	SMOKE DETECTOR BELOW CEILING
	②	DUCT SMOKE DETECTOR
	RTS	DUCT SMOKE DETECTOR REMOTE TEST SWITCH
	⊘ BT	SMOKE BEAM TRANSMITTER
	⊘ BR	SMOKE BEAM RECEIVER
	⊕ _F	135° FIXED TEMP HEAT DETECTOR
	\bigcirc_{R}	135° RATE OF RISE HEAT DETECTOR
	194* F	194° FIXED TEMP HEAT DETECTOR
	194* R	194° RATE OF RISE HEAT DETECTOR
	190° F	190° FIXED TEMP HEAT DETECTOR
	194*	194° LINE TYPE HEAT DETECTOR
	-	2

FIRE ALARM - MODULE / RELAY

QTY	SYMBOL	DEVICE DESCRIPTION
	F	MANUAL PULL STATION
	ММ	MINI MONITOR MODULE
	М	MONITOR MODULE
	M2	TWO POINT POINT MONITOR MODULE
	M4	FOUR POINT MONITOR MODULE
	R	RELAY MODULE
	(CR)	CONTROL RELAY MODULE
	IN	INPUT MODULE
	IO	FOUR POINT INPUT/OUTPUT RELAY MODULE
	IM	ISOLATION MODULE
	NM	NOTIFICATION MODULE
	MZ	SYNC MODULE
	DH	DOOR HOLDER

FIRE ALARM - SPRINKLER

QTY	SYMBOL	DEVICE DESCRIPTION
\otimes		SPRINKLER RISER
	(WATER GONG BELL
	FS	WATERFLOW SWITCH
	PS	PRESSURE SWITCH
·	ZT	TAMPER SWITCH

QTY	SYMBOL	DEVICE DESCRIPTION
	ESR	ELEVATOR STATUS RECALL
	FFP	FIRE FIGHTERS PHONE
	C _J	FIRE FIGHTERS PHONE JACK
	€ _H	FIRE FIGHTERS HANDSET

	- ALAI IIVI - IVII SCLLLAIN LOOS					
)TY	SYMBOL	DEVICE DESCRIPTION				
	КН	KITCHEN HOOD				
	\Diamond	JUNCTION BOX				
		BATTERY				


FIRE ALARM - FIREMAN'S PHONE

YTÇ	SYMBOL	DEVICE DESCRIPTION
	ESR	ELEVATOR STATUS RECALL
	FFP	FIRE FIGHTERS PHONE
	C J	FIRE FIGHTERS PHONE JACK
	€ _H	FIRE FIGHTERS HANDSET

FIRE ALARM - MISCELLANEOUS

TY	SYMBOL	DEVICE DESCRIPTION
	КН	KITCHEN HOOD
	♦	JUNCTION BOX
		BATTERY

,	SYMBOL	DEVICE DESCRIPTION
	КН	KITCHEN HOOD
	\Diamond	JUNCTION BOX
		BATTERY



REVIEWED COMPLIANCE DDrake 08/22/2025

11:17:29 AM

THE APPROVED CONSTRUCTION PLANS AND ALL ENGINEERING MUST BE POSTED ON THE JOB AT ALL INSPECTIONS IN A VISIBLE AND READILY ACCESSIBLE LOCATION.

> Approval of submitted plans is not an approval of omissions or oversight by this office or noncompliance with any applicable regulations of local government. The contractor is responsible for making sure that the building complies with all applicable building codes and regulations of the local government.


FIRE ALARM


ISSUE DATE: 8/4/25

PROJECT #: FA25075

GENERAL SHEET

LEGEND & NOTES





City of P Development & Pe ISSUED	ermitting Services
Building	Planning
Engineering	Public Works
Fire OF W	Traffic

302 33RD PUYALLUI PARCEL#

CONSTRUCTION SET

DESIGNER: SCOTT JERKE

ISSUE DATE: 8/4/25

PROJECT #: FA25075

SYSTEM:

FIRE ALARM


DEVICE LOCATION VIEWS & RISER DIAGRAM

LOUIS LYNN
FIRE ALARM SYSTEMS III
SPECIAL HAZARDS III
WATER BASED SYSTEMS LAYOUT II
NICET CERTIFICATE #119584
EXP 6/1/28


FA101

DEVICE LOCATIONS - FLOOR PLAN

SCALE: 1/8" = 1'-0"











B

SCHEDULES - SEQUENCE OP OPERATIONS MATRIX




	F/	\25075 LSL	OFFICE TI			
	177.00	IEMENS FC	A COLUMN TO THE PARTY OF THE PA			
Current Load:		5	Standby:	Ala	arm:	
Device Type	Quantity	Amps	Total	Amps	Total	
Dollar Type	Quantity	7111100	Total	ranpo	Total	
Main System Board	1	0.12000	0.1200	0.70000	0.7000	
NAC 1	1	0.00000	0.0000	0.97100	0.9710	
NAC 2	1	0.00000	0.0000	1.02000	1.0200	
OP921 SMOKE DETECTOR	3	0.00025	0.0008	0.00041	0.0012	
Total Panel Loads:			0.121	Amps	2.692	Amps
Standby Current Load:	0.121	Amps	For 24 Hours =	2.898	Amp-hours	
Alarm Current Load:	2.692	Amps	For 5 Minutes=	0.226	Amp-hours	
			20% Derating=	3.749	Amp-hours	
Total S	ystem Curren	t Load:		3.749	Amp-hours	
Battery Pair to be Used:	12VDC		Amp-hours	8		

		Volta	ge Drop Chart			
FA25075 LSL OFFICE TI						
Panel	Circuit	Area	Total Wire Length	Amps	Voltage Drop	EOL Voltage
FACP	1	EXISTING DEVICES	800	0.971	1.958	22.042
FΔCP	2	EXISTING DEVICES	800	1 020	2.056	21 9//



City of Puyallup Development & Permitting Services ISSUED PERMIT					
Building	Planning				
Engineering	Public Works				
Fire					



DESIGNER: SCOTT JERKE
ISSUE DATE: 8/4/25
PROJECT #: FA25075
SYSTEM:

FIRE ALARM


SCHEDULES & CALCULATIONS

FA501

FIRE ALARM - HORN MOUNTING

IF TOTAL HEIGHT IS LESS THAN 90", MOUNT 6" FROM CEILING BUT NOT GREATER THAN 96" AFF NOT LESS THAN 80" AFF

ISSUED PERMIT Engineering Traffic




FIRE ALARM

PRODUCT TYPICALS


FA601

FIRE ALARM - STROBE MOUNTING




PRIMARY PORT PRIMARY PORT SECONDARY PORT -- SECURITY CONTROL PANEL - FIRE ALARM CONTROL PANEL FIRE ALARM - PHONE CONNECTION

- RJ 31X BLOCK




FIRE ALARM - SMOKE & HEAT MOUNTING






FIRE ALARM - CEILING TO WALL TRANSITION AND OPEN WIRING




FIRE ALARM - OS&Y TAMPER GATE VALVE

NOT MORE THAN 48" AFF






FIRE ALARM - CONDUIT WALL & CEILING



FIRE ALARM - DCVA TAMPER SWITCHES



FIRE ALARM - POWER DISCONNECT