



National Accounts Project Quote

Full-Sized legible color report must be on site and made available by the Permittee for all inspections.

PRMH20251022

Project Name: Ross #0593-Puyallup, WA

Project Number: 832043

Quote: 557802

Quote Name: Ross #0593-Puyallup, WA

Engineer: #N/A

National Account: Ross Dress For Less

Project Location:

4102 South Meridian


Puyallup, WA

Prepared For: Ross Dress For

Less

Date: 2/19/2025

Quote valid for 30 days



Roof Top Units: 7

Tag	Qty	Model	Description
RTU 1,2			
	2	LGT036H5-PKG	LGT036H5...Packaged Gas/Electric / 3Ton / Configurable - 460V/3Ph/60Hz - R-454B
RTU-1 & 6			Factory Installed Options High Performance Economizer Factory Installed Global High Performance Economizer Direct Drive Unit Orientation Downflow Supply Fan: Multi-Speed ECM Direct Drive 440V/460V/480V 3Phase 15 Amp Circuit Breaker Factory Installed Built-in BACnet IP and MS/TP (standard) Refrigerant R-454B Supply Motor - 0.50 Hp ECM - w/ MSAV Barometric Relief Damper Factory Installed 65K A.S. (Dual Stage) Low Nox Factory Installed Combination Coil/Hail Guards Factory Installed Hinged Access Doors Factory Installed 15A GFCI Factory Installed/Field Wired Phase/Voltage Detection Factory Installed Supply Air Smoke Detector Factory Installed Return Air Smoke Detector Factory Installed Environ Evaporator and Condenser Coil System Factory Installed 2" MERV8 - Filter Factory installed
	2	31B05	Field Installed Options Curb Adapter AC/LN01/LN06



National Accounts Project Quote

RTU 3		
RTU-2	1	LGT156H5-PKG
		LGT156H5...Packaged Gas/Electric / 13Ton / Configurable - 460V/3Ph/60Hz - R-454B Factory Installed Options High Performance Economizer Factory Installed Global High Performance Economizer Belt Drive Unit Orientation Downflow Supply Fan: Multi-Stage Air Volume Belt 440V/460V/480V 3Phase 40 Amp Circuit Breaker Factory Installed Built-in BACnet IP and MS/TP (standard) Refrigerant R-454B Supply Motor - 3.0 Hp Std- w/ MSAV Supply Drive Kit 2 (710-965 RPM) Std Static Power Exhaust Fan Factory Installed 260K A.S. (Dual Stage) Combination Coil/Hail Guards Factory Installed Hinged Access Doors Factory Installed 15A GFCI Factory Installed/Field Wired Supply Air Smoke Detector Factory Installed Return Air Smoke Detector Factory Installed Environ Condenser Coil System Factory Installed 2" MERV8 - Filter Factory installed
RTU 4		
RTU-3	1	LGT092H5-PKG
		LGT092H5...Packaged Gas/Electric / 7.5Ton / Configurable - 460V/3Ph/60Hz - R-454B Factory Installed Options High Performance Economizer Factory Installed Global High Performance Economizer Direct Drive Unit Orientation Downflow Supply Fan: Multi-Speed ECM Direct Drive 440V/460V/480V 3Phase 25 Amp Circuit Breaker Factory Installed Built-in BACnet IP and MS/TP (standard) Refrigerant R-454B Supply Motor - 3.75 Hp - DirectPlus w/MSAV Std Static Power Exhaust Fan Factory Installed 130K A.S. (Dual Stage) Combination Coil/Hail Guards Factory Installed Hinged Access Doors Factory Installed 15A GFCI Factory Installed/Field Wired Supply Air Smoke Detector Factory Installed Return Air Smoke Detector Factory Installed Environ Condenser Coil System Factory Installed 2" MERV8 - Filter Factory installed
31B30	1	15T04
		Field Installed Options C1ACURB30B LG/C/HA088D,LGA100 TO B



National Accounts Project Quote

RTU 5		
RTU-4	1	LGT120H5-PKG
		LGT120H5...Packaged Gas/Electric / 10Ton / Configurable - 460V/3Ph/60Hz - R-454B Factory Installed Options High Performance Economizer Factory Installed Global High Performance Economizer Direct Drive Unit Orientation Downflow Supply Fan: Multi-Speed ECM Direct Drive 440V/460V/480V 3Phase 30 Amp Circuit Breaker Factory Installed Built-in BACnet IP and MS/TP (standard) Refrigerant R-454B Supply Motor - 3.75 Hp - DirectPlus w/MSAV Std Static Power Exhaust Fan Factory Installed 130K A.S. (Dual Stage) Combination Coil/Hail Guards Factory Installed Return Air Adaptor Plate Factory Installed Hinged Access Doors Factory Installed 15A GFCI Factory Installed/Field Wired Supply Air Smoke Detector Factory Installed Return Air Smoke Detector Factory Installed Environ Condenser Coil System Factory Installed 2" MERV8 - Filter Factory installed

RTU 6,7		
RTU-5 & 7	2	LGT072H5-PKG
		LGT072H5...Packaged Gas/Electric / 6Ton / Configurable - 460V/3Ph/60Hz - R-454B Factory Installed Options High Performance Economizer Factory Installed Global High Performance Economizer Direct Drive Unit Orientation Downflow Supply Fan: Multi-Speed ECM Direct Drive 440V/460V/480V 3Phase 25 Amp Circuit Breaker Factory Installed Built-in BACnet IP and MS/TP (standard) Refrigerant R-454B Supply Motor - 1.5 Hp ECM - w/ MSAV Std Static Power Exhaust Fan Factory Installed 65K A.S. (Dual Stage) Low Nox Factory Installed Combination Coil/Hail Guards Factory Installed Hinged Access Doors Factory Installed 15A GFCI Factory Installed/Field Wired Phase/Voltage Detection Factory Installed Supply Air Smoke Detector Factory Installed Return Air Smoke Detector Factory Installed Environ Evaporator and Condenser Coil System Factory Installed 2" MERV8 - Filter Factory installed Field Installed Options Barometric Relief Dampers (for PE Kit) Field Installed Curb Adapter AC/LN01/LN06
	2	21Z21
	2	31B05

CURB CLIPS		
44	X6523	CRP WIND SEISMIC RESTR BRKTS

EOC		
7	EOC	EOC & Guided Setup

TEMP SENSORS		
7	94L60	COSNZN07AE1- SENSOR, NONADJST TEMP



National Accounts Project Quote

Terms and Conditions

The purchase of goods, products, parts, and supplies is governed by Lennox's terms and conditions of sale, which are located at <https://www.lennox.com/terms-and-conditions>.

- This quotation is contingent upon the Buyer/Contractor meeting all of Lennox's standard terms and conditions as well as satisfactory credit arrangements.
- Payment terms are subject to credit review.
- Buyer/Contractor must provide a tax exemption certificate to claim exemption from taxes.
- Buyer/Contractor agrees not to export or re-export Lennox products, except in full compliance with all applicable U.S. export control laws and related federal agency regulations.
- All storage, returns and cancellations of Commercial Goods are subject to the Lennox Commercial Shipment, Cancellation and Return Policy:

SHIPMENT DELIVERY & STORAGE

Storage charges if Buyer/Contractor unable to take delivery within 4 weeks of Confirmed Delivery Date:

Weekly Storage Charge	1% of Total Order Value
------------------------------	-------------------------

CANCELLATIONS

Cancellation charges if cancelled within 6 weeks of, or after, confirmed Delivery Date:

Configured to Order Units	50% of Unit Value
----------------------------------	-------------------

Aftermarket Items	100% of Item Value
--------------------------	--------------------

RETURNS

Must be new, unused, and in original packaging. Must be initiated within 90 days of delivery.

Restocking Charges apply:

Standard Stock Units	15% of Unit Value, plus standard return shipping costs
-----------------------------	--

Accessories / Parts	15% of Unit Value, plus standard return shipping costs
----------------------------	--

Configured to Order Units	50% of Unit Value, plus standard return shipping costs
----------------------------------	--

Aftermarket Items	Non-returnable
--------------------------	----------------

No equipment may be returned without first obtaining Lennox's written authorization.

- All returns of Residential Goods are subject to the Residential Return Goods Authorization Policy, a copy of which is available upon request.
- This quotation includes a complete list of included equipment.
- Anything not listed on this quote is not included and must be added at an additional cost.
- It is Buyer/Contractor's responsibility to verify the accuracy of the products ordered and received (including model number, voltage, tonnage, etc.)
- Buyer/Contractor will not sell any Lennox product(s) online through a third-party website (e.g., eBay, Craig's List, Amazon, etc.) unless consistent with Lennox's most-current internet sales policy. The Buyer/Contractor acknowledges that the warranty associated with the Lennox products may be voided or no longer in effect as a result of online sales. In addition to any damages that Lennox may be entitled to for breach of this provision, Buyer/Contractor will also indemnify and hold harmless Lennox from any action, default or breach that occurs between Buyer/Contractor and any third-party as a result of a third-party sale.



National Accounts Project Quote

Total Price (Excluding Tax): \$105,147.00 USD

Orders for products will be quoted at current applicable pricing, but Lennox reserves the right to adjust pricing on orders (including placed but not shipped) based on current pricing at the time of shipment to the extent Lennox takes a price action across its customer base. Such price adjustments may be due to delays, shortages, or cost increases related to materials, components, labor, freight, transportation, fuel, regulatory compliance or other events outside of Lennox's control. All quotations expire and become invalid if not accepted within thirty (30) days from the date of issue, unless otherwise noted by Lennox in writing.

Due to high demand and supply chain volatility all quotes are subject to availability at the time of order. The delivery date we offer may be modified by Lennox at any time. We will do our best to communicate any extensions in advance as soon as new information is known.

TO PLACE AN ORDER, PLEASE EMAIL OR FAX THIS QUOTE TO YOUR LENNOX SALES OFFICE OR NATIONAL ACCOUNT DEPARTMENT, COMPLETE WITH THE FOLLOWING INFORMATION:

Orders without accurate delivery dates will not be processed.			
Purchase Order:		Customer Acct Number #:	
Ship-To Address for Equipment:		Delivery Date for Units:	
		Voltage Verified:	
Delivery Contact Name:		Delivery Date for Curbs:	
Delivery Contact Phone #:		Delivery Date for Accessories:	
General Contractor Name:		Ship-To to address for Accessories (if left blank, any field accessories and sensors will be shipped with Equipment):	
General Contractor Phone #:			
General Contractor Mailing Address:		Job Site Address (leave blank if the jobsite address is the same as Equipment ship-to address):	

Customer Signature

Any use or disclosure of this information to anyone other than the identified Lennox customer, or any use of equipment provided pursuant to this quote for anyone other than the identified Lennox customer, is a breach of the terms under which this information and/or equipment was provided to you, for which you may incur legal liability to Lennox.