															All	R HA	NDL	ING	UNIT	SCI	HEDU	JLE												
	10	IIT INFO)				FAI	N SEC	TIONS			C	OOLIN	G								HEAT	ING									UNIT DETA	ILS	
NIT		EFFIC	IENCY	RE	FRIGE	RANT	SI	UPPLY	' AIR	NOM	TOTAL	SENS	EAT	EAT	LAT L	AT TO	OTAL.	EAT	LAT	HE	AT PU	MP		ELEC.	TRIC RES	SIST.			UNI	T ELEC	;	DIMS (IN)	OPER WT	
١٥.	MFR. & MODEL NO.	EER	СОР	TYPE ;	# CKTS	CHARGE	CFM	ESP	TSP	TON	МВН	МВН	°F DB	°F WB	°F DB °F	WB N	ивн	DB	DB	мвн	EAT	LAT	KW S	STAGES	V/PH/HZ	Z MCA	A MOCI	P FILTERS	V/PH/HZ	MCA	МОСР	LxWxH	LBS	NOTES
)HP-1	WFD240B40C	9.8	3.1	R-22	2	22 / 21	8000	1.5	-	20	233	-	-	-	-	-	-	-	-	-	-	-	36	2	460/3/60	-	-	-	460/3/60	-	-	122 x 85 x 54	2410	DEMO, 1
IP-1	WSK240A4S0N	9.5	3.2	R-454B	1	38	8020	1.87	1.63	20	241	216	78	63	55	53	123	70	84	157	70	91	36	4	460/3/60	109	110	-	460/3/60	109	110	124 x 88 x 66	2188	NEW, 1-12
					<u> </u>		- 7																- 3	·	1 2 37 67 6 6				110,0,00					-

1. '-' INFORMATION IS UNAVAILABLE.

2. POWER WIRING AND DISCONNECT BY EC.

3. PROVIDE WITH 100% ECONOMIZER CAPABILITY, RETURN AIR SMOKE DETECTOR, AND DOWNFLOW CONFIGURATION.

4. CONNECT TO EXISTING CONTROLS.

5. INTERNAL ELECTRIC HEATER OPERATES FROM SINGLE POINT POWER CONNECTION.

6. UNIT IEER IS 12.5 AND CODE COMPLIANT WITH ASHRAE 90.1. 7. UNIT TO HAVE MULTISTAGE COOLING IN COMPLIANCE WITH WSEC C403.5.1

8. UNIT TO HAVE FAN CONTROL IN COMPLIANCE WITH WSEC C403.8.5.1 9. MINIMUM MERV 13 FILTER.

10. MATCH OUTSIDE AIR CFM TO THAT OF THE EXISTING UNIT. PRE DEMO TAB MAY BE REQUIRED. 11. EQUIPMENT CONTAINING R-454B REFRIGERANT SHALL INCLUDE REFRIGERANT LEAK DETECTION AND MITIGATION INCLUDING:

ACTIVE SAFETY SHOUTVALVES THAT CLOSE TO REDUCE RELEASEABLE REFRIGERANT CHARGE. -CONTROLS TO ENERGIXZE AIR CIRCULATION FAN(S) PER THA MANUFACTURER'S INSTRUCTIONS.

-CONTROLS TO DE-ENERGIZE POTENTIAL IGNITION SOURCES.

12. FIELD VERIFY IF CURB ADAPTER IS REQUIRED.

	PIPING GE	NERAL NOTES	
	PIPING MAT	TERIAL SCHEDULE	
PIPING	SIZE	MATERIAL	JOINT
INDIRECT DRAIN	1/2" - 2-1/2"	COPPER TYPE L	LEAD FREE SOLDER

- ALL PIPING INSULATION AND COVERINGS SHALL HAVE AN ASTM FLAME SPREAD RATING OF 25 OR LESS AND AN ASTM SMOKE DEVELOPED RATING OF 50 OR

- ELASTOMERIC INSULATIONS SHALL BE CLOSED CELL. - ELASTOMERIC INSULATIONS WHICH MEET THESE RATINGS MAY BE USED AS A SUBSTITUTE FOR FIBERGLASS.

- PROVIDE A VAPOR BARRIER COVERING ON ALL CHILLED WATER PIPING AND COIL CONDENSATE PIPING INSULATION. - PROVIDE A COVERING FOR ALL FIBERGLASS INSULATION WITHIN THE BUILDING.

- PROVIDE A VINYL JACKET FOR ALL INSULATION EXPOSED TO SIGHT WITHIN THE BUILDING EXCEPT MECHANICAL ROOMS. - PROVIDE REMOVABLE LACED INSULATION PAD OVER ALL CONTROL VALVES, WHERE NOT LOCATED WITHIN A MECHANICAL ROOM.

- PROVIDE ALUMINUM JACKET ON ALL INSULATED PIPING OUTSIDE BUILDING. - AT PIPE HANGERS PROVIDE RIGID INSULATION BETWEEN PIPE AND HANGER.

1. THESE PLANS ARE SCHEMATIC AND DO NOT SHOW EXACT ROUTING OR EVERY OFFSET WHICH MAY BE REQUIRED. THE MECHANICAL CONTRACTOR IS TO COORDINATE WITH ALL OTHER TRADES AND IS TO VERIFY ALL CLEARANCES BEFORE COMMENCING WORK.

2. MATERIALS, METHODS, AND INSTALLATION SHALL COMPLY WITH THE PROVISIONS OF THE 2021 INTERNATIONAL BUILDING CODE (IBC), INTERNATIONAL MECHANICAL CODE (IMC), INTERNATIONAL ENERGY CODE (IEC) AND UNIFORM PLUMBING CODE (UPC) AS AMENDED BY THE STATE OF WASHINGTON AND LOCAL

3. ALL PIPE SIZES NOTED ON DRAWINGS ARE MINIMUMS.

4. SLOPE ALL INDIRECT DRAINS AT 2% UNLESS OTHERWISE NOTED ON DRAWINGS. OBTAIN APPROVAL FROM THE CODE AUTHORITY BEFORE INSTALLING PIPING AT LESS THAN 2% (EVEN IF LESSER SLOPE IS INDICATED ON DRAWINGS).

5. HANGERS AND SUPPORTS FOR PIPING SHALL BE IN ACCORDANCE WITH THE 2021 IMC AND IBC AS AMENDED BY THE STATE OF WASHINGTON AND LOCAL AUTHORITIES.

6. PIPING PENETRATIONS OF FIRE RATED WALLS OR FLOORS SHALL BE SLEEVED AND FIRE STOPPED WITH LISTED MATERIALS SO AS TO MAINTAIN THE INTEGRITY AND RATING OF THE FLOOR OR WALL.

7. PROVIDE CHROME PLATE ESCUTCHEON PLATES AT ALL EXPOSED WALL AND CEILING PENETRATIONS.

8. PROVIDE SHUT-OFF VALVES AT ALL EQUIPMENT CONNECTIONS.

9. PROVIDE UNION, GROOVED OR FLANGED CONNECTION AT EQUIPMENT FOR FUTURE REMOVAL AND SERVICING.

10. FOR CONDENSATE PIPING PROVIDE TRAPS WITH A MINIMUM SEAL 2" GREATER THAN THE FAN OPERATING STATIC PRESSURE AT ALL COOLING COIL CONNECTIONS.

11. PROVIDE MINIMUM 1" AIR BREAK FOR ALL CONDENSATE PIPE TERMINATIONS AT DRAINS.

12. PROVIDE DIELECTRIC CONNECTIONS BETWEEN DISSIMILAR METALS.

13. HEAT TRACING OF PIPING, WHERE INDICATED, SHALL BE PROVIDED AND INSTALLED BY THE MECHANICAL CONTRACTOR. COORDINATE ELECTRICAL SUPPLY FOR HEAT TRACE WITH ELECTRICAL CONTRACTOR.

14. TRENCHING, BACKFILLING AND COMPACTING FOR UNDERGROUND PIPING SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR UNLESS STATED OTHERWISE IN CONTRACT DOCUMENTS.

ABBV	FULL NAME	ABBV	FULL NAME	ABBV	FULL NAME
AC	AIR CONDITIONING UNIT	EWT	ENTERING WATER TEMPERATURE	NOM	NOMINAL
AFF	ABOVE FINISHED FLOOR	FCU	FAN COIL UNIT	NTS	NOT TO SCALE
AHU	AIR HANDLING UNIT	FD	FIRE DAMPER	OBD	OPPOSED BLADE DAMPER
AL	ALUMINUM	FLA	FULL LOAD AMPS	OD	OUTSIDE DIMENSION
BAS	BUILDING AUTOMATION SYSTEM	FOB	FLAT ON BOTTOM	POC	POINT OF CONNECTION
BDD	BACK DRAFT DAMPER	FOT	FLAT ON TOP	PRV	PRESSURE REDUCING VALVE
BI	BLACK IRON	FSD	FIRE SMOKE DAMPER	PVC	POLYVINYL CHLORIDE
BOD	BOTTOM OF DUCT	GALV	GALVANIZED	REQ'D	REQUIRED
BOTT	BOTTOM	GC	GENERAL CONTRACTOR	RPBA	REDUCED PRESSURE BACKFLOW ASS'
BTU	BRITISH THERMAL UNITS	GENX	GENERATOR EXHAUST	RTU	ROOFTOP UNIT
BTUH	BRITISH THERMAL UNITS PER HOUR	GLVNL	GALVANNEAL	SA	SUPPLY AIR
CAT1	CATEGORY ONE VENT	GPM	GALLONS PER MINUTE	SD	SMOKE DAMPER
CAT4	CATEGORY FOUR VENT	GREASE	GREASE DUCT	SL	SOUND LINED
CFM	CUBIC FEET PER MINUTE	GWB	GYPSUM WALL BOARD	SM	SHEET METAL
CPVC	CPVC MATERIAL	HP	HORSE POWER, HEAT PUMP	SP	STATIC PRESSURE
DB	DUCTBOARD	HVAC	HEATING, VENTILATION AND AIR COND.	SS	STAINLESS STEEL
DDC	DIRECT DIGITAL CONTROLS	HX	HEAT EXCHANGER	SUSP	SUSPENDED
DEMO	DEMOLISH	ID	INSIDE DIMENSION	T	THERMOSTAT
DP	DIFFERENTIAL PRESSURE	LAT	LEAVING AIR TEMPERATURE	TOD	TOP OF DUCT
DPM	DIFFERENTIAL PRESSURE MONITOR	LBS	POUNDS	TV	TURNING VANES
DIFF	DIFFUSER	LWT	LEAVING WATER TEMPERATURE	TYP	TYPICAL
DMPR	DAMPER	MAT	MIXED AIR TEMPERATURE	UNO	UNLESS NOTED OTHERWISE
DN	DOWN	MBH	ONE THOUSAND BTUH	VAV	VARIABLE AIR VOLUME
E	EXISTING	MCA	MINIMUM CIRCUIT AMPACITY	VD	VOLUME DAMPER
EAT	ENTERING AIR TEMPERATURE	MD	MOTORIZED DAMPER	VFD	VARIABLE FREQUENCY DRIVE
EC	EGGCRATE	MIN	MINIMUM	W	DUCT INSULATION WRAP
EER	ENERGY EFFICIENCY RATIO	M-M	MACDONALD-MILLER	W/	WITH
EF	EXHAUST FAN	NC	NORMALLY CLOSED	WELD	WELDED
ELEV	ELEVATION	NIC	NOT IN CONTRACT	Ø	VOLTAGE PHASE & DUCT DIAMETER
ESP	EXTERNAL STATIC PRESSURE	NO	NORMALLY OPEN		

		HVAC SYSTE	M ABBREVIATIONS		
ABBV	FULL NAME	ABBV	FULL NAME	ABBV	FULL NAME
COMB-GALV	COMBUSTION AIR	EA AL	EXHAUST ALUMINUM	OA	OUTSIDE AIR
SA	SUPPLY AIR LP	EA SS	EXHAUST SS 304	OA-KOOL	OUTSIDE AIR KOOLDUCT
SA-KOOL	SUPPLY AIR LP KOOLDUCT	EA AL WELD	EXHAUST ALUMINUM WELDED	RLF	RELIEF AIR
SA AL	SUPPLY AIR LP ALUMINUM	EA GALV WELD	EXHAUST GALV WELDED	RA	RETURN AIR
SA SS	SUPPLY AIR LP SS 304 2B	EA GLVNL WELD	EXHAUST GALVANNEAL WELDED	DB	DUCTBOARD
SA AL WELD	SUPPLY AIR LP ALUMINUM WELDED	EA SS WELD	EXHAUST SS 304 WELDED	FLU-CAT1	FLUE VENT - CATEGORY 1
SA GALV WELD	SUPPLY AIR MP GALV WELDED	EA BI GREASE	EXHAUST GREASE BLACK IRON WELD	FLU-CAT4	FLUE VENT - CATEGORY 4
SA GLVNL WELD	SUPPLY AIR MP GALVANNEAL WELD	EA GALV GREASE	EXHAUST GREASE GALV WELDED	FLU-CPVC	FLUE VENT - CPVC MATERIAL
SA SS WELD	WELDED SUPPLY AIR LP SS 304 2B	EA GALV SS GREASE	EXHAUST GREASE SS 304 WELDED	FLU-SS	FLUE VENT - SHOP BUILT SS 304
EA	EXHAUST AIR	MUA	MAKE-UP AIR	FLU-GALV	FLUE VENT - SHOP BUILT GALV

		PIPING SY	MBOL LEGEN	D	
SYMBOL	DESCRIPTION	ABBV	SYMBOL	DESCRIPTION	ABBV
Ñ	VALVE TWO-WAY CONTROL	2WAY	\$	SENSOR	SNSR
Ŵ	VALVE THREE-WAY CONTROL	3WAY	0	TEMPERATURE INDICATOR	THERM
AF M	VALVE AUTOMATIC FLOW CONTROL	AF	BTU 	METER BTU	BTU MTR
Ø	VALVE BALANCING	BALV	M	SUB-METER WATER FLOW	MTR
Ø	VALVE BALANCING AUTOMATIC	ABALV	工	PRESSURE / TEMPERATURE PORT	P&T
M	VALVE BALL - FULL PORTED	BV	DP	SENSOR PRESSURE DIFFERENTIAL	DP
\bowtie	VALVE BALL - W/ 3/4" HOSE ADAPTOR	BV W/ HA	7	STRAINER	STRN
Θ	VALVE BUTTERFLY	BFV		SUCTION DIFFUSER	SUC DIFF
⊕	VALVE BUTTERFLY - W/ MEMORY STOP	BFVM	=	UNION	UNION
	VALVE CHECK	CV	—— \	HOSE BIBB	НВ
Т₹Т	VALVE CIRCUIT SETTER	CS	\sim	PIPE BREAK - PIG TAIL	
凩	VALVE GAS COCK	GC	*	POINT OF CONNECTION	P.O.C.
\bowtie	VALVE GATE	GV		CONCENTRIC REDUCER	CR
M	VALVE GLOBE	GLV		ECCENTRIC REDUCER	ER
Θ_{∇}	VALVE PRESSURE REDUCING	PRV	6" CHWS	PIPE - SIZE & ABBREVIATION	
} ₽	VALVE PRESSURE RELIEF	RV	6" CHWS-W	PIPE - SIZE & ABBREVIATION WITH INSULATION	
	VALVE SOLENOID	SV	Σ	THERMAL EXPANSION DEVICE	EXP
P	AUTOMATIC AIR VENT	AV	~	FLEXIBLE CONNECTION	
	MANUAL AIR VENT	MAV	~~~	FLEX PIPE	
Į.	WATER HAMMER ARRESTOR	WHA	XXXXXXXXXXXXXX	PIPE - HEAT TRACE	
	BACKFLOW PREVENTER	BFP	•	PUMP	
	REDUCED PRESS. BACKFLOW PREVENTER	RPBP	Ŷ	AIR SEPARATOR	AIR SEP
 T	BULB WELL	BW	Â	CHEMICAL POT FEEDER	СРОТ
<	FLOW DIRECTION ARROW		69	HEAT EXCHANGER	HTX
P	PRESSURE INDICATOR	PRESS	Ó	EXPANSION TANK	ET

		PIPING S	YSTEM ABBREVIATIONS		
ABBV	FULL NAME	ABBV	FULL NAME	ABBV	FULL NAME
С	CONDENSATE INDIRECT DRAIN	GLWR	GLYCOL WATER RETURN	NGV	NATURAL GAS VENT
CA	AIR COMPRESSED	GLWS	GLYCOL WATER SUPPLY	PA	AIR PNEUMATIC
CDWR	CONDENSER WATER RETURN	HHWR	HEATING HOT WATER RETURN	PC	CONDENSATE PUMPED
CDWS	CONDENSER WATER SUPPLY	HHWS	HEATING HOT WATER SUPPLY	PCHR	CHILLED WATER (PROCESS) RETURN
CHRV	CHILLER RELIEF VENT	HPC	STEAM CONDENSATE HIGH PRESS	PCHS	CHILLED WATER (PROCESS) SUPPLY
CHWR	CHILLED WATER RETURN	HPS	STEAM HIGH PRESS	RGAS	REFRIGERANT HOT GAS
CHWS	CHILLED WATER SUPPLY	HRR	HEAT RECOVERY RETURN	RLIQ	REFRIGERANT LIQUID
CLN STM	STEAM CLEAN	HRS	HEAT RECOVERY SUPPLY	RSUC	REFRIGERANT SUCTION
CLR	CLOSED LOOP WATER RETURN	LPC	STEAM CONDENSATE LOW PRESS	SCHR	CHILLED WATER (SECONDARY) RETURN
CLS	CLOSED LOOP WATER SUPPLY	LPG	LIQUID PROPANE	SCHS	CHILLED WATER (SECONDARY) SUPPLY
COMB-PVC		LPS	STEAM LOW PRESS	SCV	STEAM CONDENSATE VENT
CRYV	CRYO VENT	LTCR	CHILLED WATER (LOW TEMP) RETURN	SPC	STEAM CONDENSATE PUMPED
DTWS	DUAL TEMP WATER SUPPLY	LTCS	CHILLED WATER (LOW TEMP) SUPPLY	SV	STEAM VENT
DTWR	DUAL TEMP WATER RETURN	MPC	STEAM CONDENSATE MEDIUM PRESS	VAC	VACUUM
FOC	FUEL OIL SECONDARY CONTAINMENT	MPS	STEAM MEDIUM PRESS	VAC-E	VACUUM EXHAUST
FOF	FUEL OIL FILL	MUW	MAKE-UP WATER	VRFG	VRF HOT GAS
FOR	FUEL OIL RETURN	NG-CONDUIT	NATURAL GAS CONDUIT	VRFL	VRF HIGH PRESS LIQUID
FOS	FUEL OIL SUPPLY	NG-H	NATURAL GAS HIGH PRESS	VRFS	VRF LOW PRESS SUCTION
FOV	FUEL OIL VENTS	NG-L	NATURAL GAS LOW PRESS		
GENX	GENERATOR EXHAUST	NG-M	NATURAL GAS MEDIUM PRESS		

HVAC GENERAL NOTES - 2021 WSEC

- THESE PLANS ARE SCHEMATIC AND DO NOT SHOW EXACT ROUTING OR EVERY OFFSET WHICH MAY BE REQUIRED. THE HVAC CONTRACTOR IS TO COORDINATE WITH ALL OTHER TRADES AND IS TO VERIFY ALL CLEARANCES BEFORE COMMENCING WORK.
- MATERIALS, METHODS, AND INSTALLATION SHALL COMPLY WITH THE PROVISIONS OF THE 2021 EDITIONS OF THE INTERNATIONAL MECHANICAL CODE, INTERNATIONAL BUILDING CODE, INTERNATIONAL FIRE CODE 2021 WSEC, AND LOCAL CODES AND ORDINANCES. ALL DUCT SIZE ANNOTATIONS REPRESENT ACTUAL OUTSIDE DIMENSIONS OF THE SHEET METAL (UNO). IF APPLICABLE, INTERIOR INSULATION WILL NEED TO BE ACCUNTED FOR
- DUCT CONSTRUCTION AND HANGING SHALL COMPLY WITH CHAPTER 6 OF THE 2021 IMC AND WITH CURRENT SMACNA STANDARDS. EARTHQUAKE BRACE ALL DUCTS 28" DIA AND

WHEN DETERMINING ACTUAL DUCT FREE AREA. SEE DUCTWORK INSULATION SCHEDULE FOR ADDITIONAL SPACE REQUIRED FOR EXTERIOR (WRAP) INSULATION.

- LARGER WHICH ARE SUSPENDED MORE THAN 12" BELOW STRUCTURAL SYSTEM. JOINTS OF MEDIUM AND HIGH VELOCITY DUCT SYSTEMS SHALL BE SEALED WITH GASKETS OR LISTED MASTIC TYPE DUCT SEALANT.
- 6. DUCTS SHALL BE INSULATED AS INDICATED ON PLANS, PER 2021 WASHINGTON STATE ENERGY CODE, COMMERCIAL PROVISIONS. SEE DUCTWORK INSULATION SCHEDULE. - ACOUSTICAL SOUND LINING, WHERE INDICATED, SHALL BE 1" 1.5 LB/CU FT FIBERGLASS DUCT LINING COATED TO PREVENT FIBER EROSION AT VELOCITIES UP TO 6000 FPM.
- FLEX DUCTS SHALL CONSIST OF A REINFORCED VAPOR BARRIER, 1 1/2" FIBERGLASS INSULATION, AND NON-PERFORATED INTERIOR LINER WITH WIRE HELIX. DUCT SHALL BE A UL 181 LISTED CLASS 1 AIR DUCT. FLEX DUCTS SHALL ONLY BE USED WHERE SHOWN AND SHALL NOT EXCEED 12' IN LENGTH UNLESS NOTED OTHERWISE.
- PROVIDE EARTHQUAKE RESTRAINT FOR HVAC EQUIPMENT IN ACCORDANCE WITH SECTION 1613 OF THE 2021 IBC.
- PROVIDE FIRE DAMPERS, SMOKE DAMPERS AND FIRE/SMOKE DAMPERS WHERE INDICATED ON PLANS AND AS REQUIRED BY SECTION 717.5 OF THE 2021 IBC AND SECTION 607.5 OF THE 2021 IMC. PROVIDE CEILING FIRE DAMPERS WHERE INDICATED ON PLANS AND AS REQUIRED BY SECTION 717.6 OF THE 2021 IBC AND SECTION 607.6 OF THE 2021 IMC. INSTALL FIRE DAMPERS SMOKE DAMPERS AND FIRE/SMOKE DAMPERS IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS, THE TERMS OF THEIR LISTING, AND THE
- PIPING PENETRATIONS OF FIRE RATED WALLS OR FLOORS SHALL BE SLEEVED AND FIRE STOPPED WITH LISTED MATERIALS SO AS TO MAINTAIN THE INTEGRITY AND RATING OF
- PROVIDE RETURN DUCT SMOKE DETECTOR AUTOMATIC SHUT DOWN OF ALL NEW HEATING, COOLING, OR VENTILATION EQUIPMENT MOVING IN EXCESS OF 2000 CFM IN ACCORDANCE WITH SECTION 606 OF THE 2021 IMC. POWER AND INTERLOCK WIRING WITH THE BUILDING FIRE ALARM SYSTEM IS BY THE ELECTRICAL CONTRACTOR. BAS TO MONITOR FIRE ALARM CONTROL PANEL AND SHUT DOWN ALL FAN TERMINAL UNITS DURING ANY BUILDING FIRE ALARM EVENT, IN ACCORDANCE WITH 2021 IMC 606.2.2.
- HVAC EQUIPMENT, VALVES AND DAMPERS SHALL BE LOCATED IN EASILY ACCESSIBLE LOCATIONS. UNLESS SHOWN ON ARCHITECTURAL DRAWINGS, REQUIRED ACCESS PANELS SHALL BE PROVIDED AND INSTALLED BY THE GENERAL CONTRACTOR. MINIMUM ACCESS DOOR SIZE FOR VALVES AND DAMPERS TO BE 18" X 18".
- 13. HEAT TRACING OF PIPING, WHERE INDICATED, SHALL BE PROVIDED AND INSTALLED BY THE HVAC CONTRACTOR. THE HVAC CONTRACTOR IS TO COORDINATE THE HEAT TRACE POWER WIRING WITH ELECTRICAL CONTRACTOR.
- 14. MOTORS STARTERS NOT LISTED AS BEING PROVIDED IN THE HVAC EQUIPMENT SCHEDULES ARE TO BE PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR.
- WITHIN 90 DAYS AFTER THE DATE OF SYSTEM ACCEPTANCE, RECORD DRAWINGS OF THE ACTUAL INSTALLATION TO BE PROVIDED TO THE BUILDING OWNER. RECORD DRAWINGS SHALL INCLUDE AS A MINIMUM THE LOCATION AND PERFORMANCE DATA ON EACH PIECE OF EQUIPMENT, GENERAL CONFIGURATION OF DUCT AND PIPE DISTRIBUTION SYSTEM, INCLUDING SIZES, AND THE TERMINAL AIR AND WATER DESIGN FLOW RATES.
- OPERATING AND MAINTENANCE MANUALS TO BE PROVIDED TO THE BUILDING OWNER THAT INCLUDE: SUBMITTAL DATA, NAMES AND ADDRESSES OF AT LEAST ONE SERVICE AGENCY, HVAC CONTROLS SYSTEM MAINTENANCE AND CALIBRATION INFORMATION AND A COMPLETE OPERATIONAL NARRATIVE FOR EACH SYSTEM.
- 17. A COMPLETE REPORT OF TEST PROCEDURES AND RESULTS SHALL BE PREPARED AND FILED WITH THE OWNER.
- 18. SHAFT WALLS CONSTRUCTED TO SUPPORT AIR MOVEMENT FOR RETURN AIR SYSTEMS AND STAIR & ELEVATOR PRESSSURIZATION SYSTEMS SHALL BE CONSTRUCTED TO THE FOLLOWING STANDARDS:
- A. SHAFTS (RATED FOR MAXIMIUM 2" WC) SHALL BE CONSTRUCTED TO WITHSTAND 15 PSF LOADING WITH A DEFLECTION OF L/360 (UNO).
- B. SHAFTS SHALL BE SEALED SUBSTANTIALLY AIR-TIGHT USING THE CRITERIA FROM THE 2021 INTERNATIONAL BUILDING CODE:
- 1. SECTION 715.8 FIRE RESISTANT JOINT SYSTEMS IN SMOKE BARRIERS: LEAKAGE SHALL NOT EXCEED 5 CFM PER LINEAR FOOT OF JOINT AT 0.3" WC. 2. SECTION 909.5 SMOKE BARRIER CONSTRUCTION FOR INTERIOR EXIT STAIRWAYS AND EXIT PASSAGEWAYS: MAXIMUM ALLOWABLE LEAKAGE AREA PER SHAFT
- SHALL NOT EXCEED (0.00035 SF/SF) C. STAIR AND ELEVATOR PRESSURIZATION SHAFTS SHALL BE PRESSURE TESTED DURING COMMISIONING. GENERAL CONTRACTOR SHALL MAKE MODIFCATIONS TO
- DAMPERS USED FOR OUTDOOR AIR INTAKE. EXHAUST, OR RELIEF SHALL HAVE THE FOLLOWING MAXIMUM LEAKAGE RATES AT 1" W.G. (PER AMCA STANDARD 500D): MOTORIZED
- DAMPERS: 4 CFM/S.F. GRAVITY DAMPERS: 20 CFM/S.F. (40 CFM/S.F. FOR DAMPERS SMALLER THAN 24" IN EITHER DIMENSION) PER 2021 WSEC C403.7.8.3.
- 20. OUTSIDE AIR INTAKE, EXHAUST, AND RELIEF DAMPERS SERVING CONDITIONED SPACES MUST BE MOTORIZED (FAIL CLOSED) PER 2021 WSEC SECTION C403.7.8. EXCEPT AS MATERIALS WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL BE LISTED AND LABELED AS HAVING A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A
- SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84 OR UL 723, EXCEPT AS NOTED IN SECTION 602.2.1 OF THE 2021 IMC. 22. ALL MECHANICAL WORK SHOWN ON DRAWINGS INTENDED TO BE INSTALLED SOLELY BY MACDONALD -MILLER FACILITY SOLUTIONS. MACDONALD-MILLER FACILITY SOLUTIONS


SCOPE OF WORK

THE SHBTC BUILDING REQUIRES THE REPLACEMENT OF (1) 20-TON HEAT PUMP, REUSING THE EXISTING CURB FROM THE CURRENT UNIT.


SHALL NOT BE HELD ACCOUNTABLE FOR ANY DESIGN OR CONSTRUCTION DEFICIENCIES IF WORK IS PERFORMED BY AN OUTSIDE PARTY.

- DEMO THE EXISTING HEAT PUMP, DISCONNECTING THE EXISTING DUCTING FROM THE UNDERSIDE OF THE UNIT.
- RECONNECT DUCTING AND PROVIDE NEW HEAT PUMP ON TO THE EXISTING CURB.

NAME	COIVIE	PANY PH	ONE NUMBER EMA	4L
QUINCY BUS	JSCHBACH MACDO	NALD MILLER 503-	-205-8859 QUICN	NY.BUSCHBACH@MACMILLER.CO
GEORGE GF	RAHAM MACDO	NALD MILLER 206-	-768-4288 GEORG	GE.GRAHAM@MACMILLER.COM
MARCUS LE	EE MACDO	NALD MILLER 206-	-768-4154 MARCL	US.LEE@MACMILLER.COM
TIM FELTON	N MACDO	NALD MILLER 206-	-396-9641 TIM.FE	ELTON@MACMILLER.COM
JIM FULLWIL	ILER MACDO	NALD MILLER 206-	-565-4528 JIM.FUI	JLLWILER@MACMILLER.COM
TIM FELTON	N MACDO	NALD MILLER 206-	-396-9641 TIM.FE	ELTON@MACMILLE




The approved construction plans, documents, and all engineering must be posted on the job at all inspections in a visible and readily accessible location. Full sized legible color plans are required to be provided by he permitee on site for inspection.




















Q BUSCHBACH G GRAHAM M HAGBERG


73257921-00 TM0.01











HBIC BLDG C REPLACE HP-1
OUTH HILL BUSINESS & TECHNOLOGY CENTER
JYALLUP, WA 98374

1015 39TH AVE S
PUYALLUP, WA
S
SITE PL

Q BUSCHBACH
CHECKED BY:
G GRAHAM
CAD:


CAD:


M HAGBERG


DRAWING NUMBER:

73257921-00


TM0.01S







DATE	ISSUANCE DESCRIPTION	ISSUANCE
09-18-25	CD / PERMIT SET	-



SHBTC BLDG C REPLACE HP-1

SHBTC BLDG C REPLACE HP-1

SOUTH HILL BUSINESS & TECHNOLO

1015 39TH AVE SE
PUYALLUP, WA 98374

DETAILS

ISSUED FOR PERMIT

AC-UNIT, REFER TO MFR DETAILS — FOR EXACT CONFIGURATION – EARTHQUAKE RESTRAINT PER STRUCTURAL REQUIREMENTS SELF-ADHESIVE 1/4"
FOAM GASKET ON
CURB AND DUCT
DROP SURFACES FACTORY ROOF CURB CANT STRIP/FLASHING (BY G.C) WOOD NAILER -/ 2" RIGID FIBERGLASS -/ ROOFING (BY OTHERS) SOUNDLINER 2 LAYERS 1/2" GWB — AND 4" FIBERGLASS ATTACH TO ROOF STRUCTURE
PER STRUCTURAL
REQUIREMENTS ROOF DECK -STRUCTURAL MEMBER -(BY OTHERS) (SEE ROOF FRAMING PLAN) ROOF OPENING AND TEMPORARY WEATHER COVER OF ROOF OPENING BY G.C. * 14" IS MINIMUM STANDARD. FOR ABOVE DECK INSULATION APPLICATIONS MAINTAIN 8" DISTANCE FROM UNIT GASKET TO TOP OF FINISHED ROOF. ROOFTOP AC UNIT CURB DETAIL (UNITS 5 TO 25 TON) 1 TM6.01

TM6.01