

TODD RD SEWER EXTENSION

CIVIL CONSTRUCTION PERMIT

APPLICANT

E.J. FERNANDEZ
PO BOX 309
SUMNER, WA 98390

CIVIL ENGINEER

JMJ TEAM
905 MAIN STREET
SUITE 200
SUMNER, WA 98390
(206) 596-2020
CONTACT: JUSTIN JONES, PE

SURVEYOR

CONTOUR ENGINEERING LLC
4706 97TH STREET NW, SUITE 100
GIG HARBOR, WA 98335
(253) 857-5454
CONTACT: STEPHEN H. WOODS, PLS

SITE INFORMATION:

SITE ADDRESS: 212, 302, 320 TODD RD NE, PUYALLUP, WA 98371
TAX PARCEL NUMBER: 0420222008, 0420222028, 0420222005
ZONING: RM-20
TOTAL PROJECT AREA: 1.30 AC

VERTICAL DATUM:

BASE: HELD STATION TACO AS PUBLISHED ON WASHINGTON STATE REFERENCE NETWORK WEBSITE ([HTTP://WSRN3.ORG/](http://WSRN3.ORG/)) (2018)

ELEVATION: 341.348' (NAVD88)

SITE #1: CE 500, A SET HUB AND TACK ON THE NORTH SIDE OF TODD ROAD NORTHEAST, 8.8' EAST OF STORM DRAINAGE MANHOLE AS SHOWN HEREON.

ELEVATION: 50.27' (NAVD88)

SITE #2: CE 505, A SET HUB AND TACK IN THE BACK OF YARD OF THE SITE AS SHOWN HEREON.

ELEVATION: 51.35' (NAVD88)

SITE AREA: 145,042 SQ FT (3.330 ACRES)


HORIZONTAL DATUM:

THE NORTH AMERICAN DATUM OF 1983/2011 (NAD 83/2011 EPOCH 2010.00) GRID COORDINATES WERE FOUND TO BE 690850.70 / 1194622.67 AT AN "X" IN A 2.5" BRASS DISK.

SERVICE PROVIDERS:

WATER: CITY OF PUYALLUP
SEWER: ON-SITE SEPTIC
POWER: PUGET SOUND ENERGY
GAS: PUGET SOUND ENERGY

VICINITY MAP



212, 302, 320 Todd Rd NE, Puyallup, WA 98371

SHEET INDEX

Page #	Sheet #	Sheet Name
1	C1-001	Cover Sheet
2	C1-002	General Notes
3	C1-003	General Notes
4	C1-004	General Notes
5	C1-101	Existing Site Plan
6	C1-201	Alignment Control Plan
7	C2-101	TESC Plan
8	C2-201	TESC Details
9	C2-301	Demolition Plan
10	C3-101	Proposed Site Plan
11	C3-201	Hardscape Details
12	C4-101	Sewer Plan
13	C4-201	Sewer Plan & Profile
14	C4-301	Sewer Details

Owner/Developer:

E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:


Engineer:

JMJ TEAM
JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

ONE INCH AT FULL SCALE.
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit



PROJECT DISTURBED AREA

Description ^a	Onsite	Offsite	Total
Existing Conditions			
Total Project Area ^b (ft ²)	3,565-0.082 ac	-	3,565-0.082 ac
Existing hard surface (ft ²)	2,530-0.058 ac	-	2,530-0.058 ac
Existing vegetation area (ft ²)	1,035-0.024 ac	-	1,035-0.024 ac
Proposed Conditions			
Total Project Area ^b (ft ²)	3,565-0.082 ac	-	3,565-0.082 ac
Amount of new hard surface (ft ²)	-	-	-
Amount of new pollution generating hard surface (PGHS) ^c (ft ²)	-	-	-
Amount of replaced hard surface (ft ²)	2,530-0.058 ac	-	2,530-0.058 ac
Amount of replaced PGHS ^d (ft ²)	2,518-0.058 ac	-	2,518-0.058 ac
Amount of new plus replaced hard surface (ft ²)	2,530-0.058 ac	-	2,530-0.058 ac
Amount of new + replaced PGHS (ft ²)	2,518-0.058 ac	-	2,518-0.058 ac
Amount of existing hard surfaces converted to vegetation (ft ²)	-	-	-
Amount of Land Disturbed (ft ²)	3,565-0.082 ac	-	3,565-0.082 ac
Vegetation to Lawn/Landscaped (acres)	-	-	-
Native Vegetation to Pasture (acres)	-	-	-
Existing hard surface to remain unaltered (ft ²)	1,035-0.024 ac	-	1,035-0.024 ac
Existing vegetation area to remain unaltered (ft ²)	-	-	-

STORMWATER THRESHOLD NOTE:

AS INDICATED IN SECTION I-3.2 OF THE 2019 STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON, UNDERGROUND UTILITY PROJECTS THAT REPLACE SURFACE WITH IN-KIND MATERIALS ARE NOT SUBJECT TO STORMWATER MANAGEMENT REQUIREMENTS.

APPROVED	BY _____
	CITY OF PUYALLUP DEVELOPMENT ENGINEERING
DATE	_____
NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE.	
THE CITY WILL NOT BE RESPONSIBLE FOR ERRORS AND/OR OMISSIONS ON THESE PLANS.	
FIELD CONDITIONS MAY DICTATE CHANGES TO THESE PLANS AS DETERMINED BY THE DEVELOPMENT ENGINEERING MANAGER.	

PROJ. NO.	1611-001
DATE	November 24, 2025
DRAWN BY:	DM
DESIGN BY:	JJ
SHEET NUMBER	C1-001
CALL TWO BUSINESS DAYS BEFORE YOU DIG	
1-800-424-5555 UTILITIES UNDERGROUND LOCATION CENTER	
DWG.	1 of 18

GENERAL PLAN NOTES

- All work in City right-of-way requires a permit from the City of Puyallup. Prior to any work commencing, the general contractor shall arrange for a preconstruction meeting at the Development Services Center to be attended by all contractors that will perform work shown on the engineering plans, representatives from all applicable utility companies, the project owner and appropriate city staff. Contact Engineering Services to schedule the meeting (253) 841-5568. The contractor is responsible to have their own approved set of plans at the meeting.
- After completion of all items shown on these plans and before acceptance of the project the contractor shall obtain a "punch list" prepared by the City's inspector detailing remaining items of work to be completed. All items of work shown on these plans shall be completed to the satisfaction of the City prior to acceptance of the water system and provision of sanitary sewer service.
- All materials and workmanship shall conform to the Standard Specifications for Road, Bridge, and Municipal Construction (hereinafter referred to as the "Standard Specifications"), Washington State Department of Transportation and American Public Works Association, Washington State Chapter, latest edition, unless superseded or amended by the City of Puyallup City Standards for Public Works Engineering and Construction (hereinafter referred to as the "City Standards").
- A copy of these approved plans and applicable city developer specifications and details shall be on site during construction.
- Any revision made to these plans must be reviewed and approved by the developer's engineer and the Engineering Services Staff prior to any implementation in the field. The City shall not be responsible for any errors and/or omissions on these plans.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- Any structure and/or obstruction that requires removal or relocation relating to this project, shall be done so at the developer's expense.
- Locations of existing utilities are approximate. It shall be the contractor's responsibility to determine the true elevations and locations of hidden utilities. All visible items shall be the engineer's responsibility.
- The contractor shall install, replace, or relocate all signs, as shown on the plans or as affected by construction, per City Standards.
- Power, street light, cable, and telephone lines shall be in a trench located within a 10-foot utility easement adjacent to public right-of-way. Right-of-way crossings shall have a minimum horizontal separation from other utilities (sewer, water, and storm) of 5 feet.
- All construction surveying for extensions of public facilities shall be done under the direction of a Washington State licensed land surveyor or a Washington State licensed professional civil engineer.
- During construction, all public streets adjacent to this project shall be kept clean of all material deposits resulting from on-site construction, and existing structures shall be protected as directed by the City.
- Certified record drawings are required prior to project acceptance.
- A NPDES Stormwater General Permit may be required by the Department of Ecology for this project. For information contact the Department of Ecology, Southwest Region Office as (360) 407-6300.
- Any disturbance or damage to Critical Areas and associated buffers, or significant trees designated for preservation and protection shall be mitigated in accordance with a Mitigation Plan reviewed and approved by the City's Planning Division. Preparation and implementation of the Mitigation Plan shall be at the developer's expense.

STORMWATER NOTES

- All work in City right-of-way requires a permit from the City of Puyallup. Prior to any work commencing, the general contractor shall arrange for a preconstruction meeting at the Development Services Center to be attended by all contractors that will perform work shown on the engineering plans, representatives from all applicable Utility Companies, the project owner and appropriate City staff. Contact Engineering Services to schedule the meeting (253) 841-5568. The contractor is responsible to have their own approved set of plans at the meeting.
- After completion of all items shown on these plans and before acceptance of the project, the contractor shall obtain a "punch list" prepared by the City's inspector detailing remaining items of work to be completed. All items of work shown on these plans shall be completed to the satisfaction of the City prior to acceptance of the water system and provision of sanitary sewer service.
- All materials and workmanship shall conform to the Standard Specifications for Road, Bridge, and Municipal Construction (hereinafter referred to as the "Standard Specifications"), Washington State Department of Transportation and American Public Works Association, Washington State Chapter, latest edition, unless superseded or amended by the City of Puyallup City Standards for Public Works Engineering and Construction (hereinafter referred to as the "City Standards").
- A copy of these approved plans and applicable city developer specifications and details shall be on site during construction.
- Any revisions made to these plans must be reviewed and approved by the developer's engineer and the Engineering Services Staff prior to any implementation in the field. The City shall not be responsible for any errors and/or omissions on these plans.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- Any structure and/or obstruction which require removal or relocation relating to this project, shall be done so at the developer's expense.
- During construction, all existing and newly installed drainage structures shall be protected from sediments.
- All storm manholes shall conform to City Standard Detail No. 02.01.01. Flow control manhole/oil water separator shall conform to City Standard Detail No. 02.01.06 and 02.01.07.
- Manhole ring and cover shall conform to City Standard Detail 06.01.02.
- Catch basins Type I shall conform to City Standard Detail No.02.01.02 and 02.01.03 and shall be used only for depths less than 5 feet from top of the grate to the invert of the storm pipe.
- Catch basins Type II shall conform to City Standard Detail No.02.01.04 and shall be used for depths greater than 5 feet from top of the grate to the invert of the storm pipe.
- Cast iron or ductile iron frame and grate shall conform to City Standard Detail No.02.01.05. Grate shall be marked with "drains to stream". Solid catch basin lids (square unless noted as round) shall conform to WSDOT Standard Plan B-30.20-04 (Olympic Foundry No. SM60 or equal). Vanned grates shall conform to WSDOT Standard Plan B-30.30-03 (Olympic Foundry No. SM60V or equal).
- Stormwater pipe shall be only PVC, concrete, ductile iron, or dual walled Polypropylene pipe.
 - The use of any other type shall be reviewed and approved by the Engineering Services Staff prior to installation.
 - PVC pipe shall be per ASTM D3034, SDR 35 for pipe sizes 15-inch and smaller and F679 for pipe sizes 18- to 27-inch, ductile iron pipe shall be Class 51 or greater, lined with Protecto 401TM epoxy lining or equivalent, unless otherwise noted, 12-inch through 30-inch Polypropylene Pipe (PP) shall be dual walled, have a smooth interior and exterior corrugations and meet WSDOT 9-05.24(2). It shall meet or exceed ASTM F2764, 36-inch through 60-inch PP pipe shall be triple walled and meet WSDOT 9-05.24(2). It shall meet or exceed ASTM F2764. PP shall have a minimum pipe stiffness of 46 psi when tested in accordance with ASTM D2412. Testing shall be per ASTM F1417. Trenching, bedding, and backfill shall be in accordance with City Standard No. 06.01.01. Minimum cover on PVC and PP pipe shall be 3.0 feet. Minimum cover on ductile iron pipe shall be 1.0 foot.
 - Concrete pipe shall conform to the WSDOT Standard Specifications for concrete underdrain pipe. Minimum cover on concrete pipe shall not less than 3.0 feet.
 - Ductile iron pipe shall be Class 50, conforming to AWWA C151. Minimum cover on ductile iron pipe shall be 1.0 foot.
 - Polypropylene Pipe (PP) shall be dual walled, have a smooth interior and exterior corrugations and meet WSDOT 9-05.24(1), 12-inch through 30-inch pipe shall meet or exceed ASTM F2736 and AASHTO M330, Type S, or Type D. 36-inch through 60-inch pipe shall meet or exceed ASTM F2881 and AASHTO M330, Type S, or Type D. Testing shall be per ASTM F1417. Minimum cover over Polypropylene pipe shall be 3-feet.
- Trenching, bedding, and backfill for pipe shall conform to City Standard Detail No. 06.01.01.
- Storm pipe shall be a minimum of 10 feet away from building foundations and/or roof lines.
- All storm drain mains shall be tested and inspected for acceptance as outlined in Section 406 of the City of Puyallup Sanitary Sewer System Standards.
- All temporary sedimentation and erosion control measures, and protective measures for critical areas and significant trees shall be installed prior to initiating any construction activities.

SANITARY SEWER NOTES

- All work in City right-of-way requires a permit from the City of Puyallup. Prior to any work commencing, the general contractor shall arrange for a preconstruction meeting at the Development Services Center to be attended by all contractors that will perform work shown on the engineering plans, representatives from all applicable Utility Companies, the project owner and appropriate City staff. Contact Engineering Services to schedule the meeting (253) 841-5568. The contractor is responsible to have their own approved set of plans at the meeting.
- After completion of all items shown on these plans and before acceptance of the project, the contractor shall obtain a "punch list" prepared by the City's inspector detailing remaining items of work to be completed. All items of work shown on these plans shall be completed to the satisfaction of the City prior to acceptance of the sewer system and provision of sanitary sewer service.
- All materials and workmanship shall conform to the Standard Specifications for Road, Bridge, and Municipal Construction (hereinafter referred to as the "Standard Specifications"), Washington State Department of Transportation and American Public Works Association, Washington State Chapter, latest edition, unless superseded or amended by the City of Puyallup City Standards for Public Works Engineering and Construction (hereinafter referred to as the "City Standards").
- A copy of these approved plans and applicable city developer specifications and details shall be on site during construction.
- Any revisions made to these plans must be reviewed and approved by the developer's engineer and the Engineering Services Staff prior to any implementation in the field. The City shall not be responsible for any errors and/or omissions on these plans.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- Any structure and/or obstruction which require removal or relocation relating to this project, shall be done so at the developer's expense.
- Minimum grade on all 4 inch residential side sewers shall be 2 percent and 6 inch commercial side sewers shall be 1 percent; maximum shall be 8 percent. All side sewers shall be 6 inches within City right-of-way.
- Side sewers shall be installed in accordance with City Standard Nos. 04.03.01, 04.03.02, 04.03.03 and 04.03.04. Side sewer installation work shall be done in accordance with the Washington Industrial Safety and Health Act (WISHA).
- All sewer pipe shall be PVC, Polypropylene, or Ductile Iron. PVC sewer pipe shall conform to ASTM D-3034, SDR35 for pipe sizes 15-inch and smaller and ASTM F679 for pipe sizes 18- to 27-inch, ductile iron pipe shall be Class 51 or greater, lined with Protecto 401TM epoxy lining or equivalent, unless otherwise noted, 12-inch through 30-inch Polypropylene Pipe (PP) shall be dual walled, have a smooth interior and exterior corrugations and meet WSDOT 9-05.24(2). It shall meet or exceed ASTM F2764, 36-inch through 60-inch PP pipe shall be triple walled and meet WSDOT 9-05.24(2). It shall meet or exceed ASTM F2764. PP shall have a minimum pipe stiffness of 46 psi when tested in accordance with ASTM D2412. Testing shall be per ASTM F1417. Trenching, bedding, and backfill shall be in accordance with City Standard No. 06.01.01. Minimum cover on PVC and PP pipe shall be 3.0 feet. Minimum cover on ductile iron pipe shall be 1.0 foot.
- Sanitary sewer manhole frames and covers shall conform to City Standard No. 06.01.02.
- Sanitary sewer manholes shall conform to City Standard Nos. 04.01.01, 04.01.02, 04.01.03 and 04.01.04. All manholes shall be channelled for future lines as specified on these plans. Manhole steps and ladder shall conform to Standard No. 06.01.03.
- Sanitary sewer pipe and side sewers shall be 10 feet away from building foundations and/or roof lines with the exception of side sewers that provide service to a single-family residence. At the discretion of the review engineer, a Licensed Professional Engineer will be required to stamp the design to account for depth or proximity to foundation, steep slopes, or other factors.
- No side sewers shall be connected to any house or building until all manholes are adjusted to the finished grade of the completed asphalt roadway and the asphalt patch and seal around the ring are accepted.
- For commercial developments in which sources of grease and/or oils may be introduced to the City sanitary sewer system, a City approved grease interceptor shall be installed downstream from the source.
- Once sewer and all other utility construction is completed, all sanitary sewer mains and side sewers shall be tested per Section 406 of the City Standards.

GRADING, EROSION, AND SEDIMENT CONTROL PLAN NOTES

- All work in City right-of-way requires a permit from the City of Puyallup. Prior to any work commencing, the general contractor shall arrange for a preconstruction meeting at the Development Services Center to be attended by all contractors that will perform work shown on the engineering plans, representatives from all applicable Utility Companies, the project owner and appropriate City staff. Contact Engineering Services to schedule the meeting (253) 841-5568. The contractor is responsible to have their own approved set of plans at the meeting.
- After completion of all items shown on these plans and before acceptance of the project, the contractor shall obtain a "punch list" prepared by the City's inspector detailing remaining items of work to be completed. All items of work shown on these plans shall be completed to the satisfaction of the City prior to acceptance of the water system and provision of sanitary sewer service.
- All materials and workmanship shall conform to the Standard Specifications for Road, Bridge, and Municipal Construction (hereinafter referred to as the "Standard Specifications"), Washington State Department of Transportation and American Public Works Association, Washington State Chapter, latest edition, unless superseded or amended by the City of Puyallup City Standards for Public Works Engineering and Construction (hereinafter referred to as the "City Standards").
- A copy of these approved plans and applicable city developer specifications and details shall be on site during construction.
- Any revision made to these plans must be reviewed and approved by the developer's engineer and the Engineering Services Staff prior to any implementation in the field. The City shall not be responsible for any errors and/or omissions on these plans.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- All limits of clearing and areas of vegetation preservation as prescribed on the plans shall be clearly flagged in the field and observed during construction.
- All required sedimentation and erosion control facilities must be constructed and in operation prior to any land clearing and/or other construction to ensure that sediment laden water does not enter the natural drainage system. The contractor shall schedule an inspection of the erosion control facilities PRIOR to any land clearing and/or other construction. All erosion and sediment facilities shall be maintained in a satisfactory condition as determined by the City, until such time that clearing and/or construction is completed and the potential for on-site erosion has passed. The implementation, maintenance, replacement, and additions to the erosion and sedimentation control systems shall be the responsibility of the permittee.
- The erosion and sedimentation control system facilities depicted on these plans are intended to be minimum requirements to meet anticipated site conditions. As construction progresses and unexpected or seasonal conditions dictate, facilities will be necessary to ensure complete site control on the site. During the course of construction, it shall be the obligation and responsibility of the permittee to address any new conditions that may be created by his activities and to provide additional facilities, over and above the minimum requirements, as may be needed to protect adjacent properties, sensitive areas, natural water courses, and/or storm drainage systems.
- Approval of these plans is for grading, temporary drainage, erosion, and sedimentation control only. It does not constitute an approval of permanent storm drainage design, size or location of pipes, restrictors, channels, or retention facilities.
- Any disturbed area which has been stripped of vegetation and where no further work is anticipated for a period of 30 days or more, must be immediately stabilized with mulching, grass planting, or other approved erosion control treatment applicable to the time of year in question. Grass seeding alone will be acceptable only during the months of April through September inclusive. Seeding may proceed outside the specified time period whenever it is in the interest of the permittee but must be augmented with mulching, netting, or other treatment approved by the City.
- In case erosion or sedimentation occurs to adjacent properties, all construction work within the development that will further aggravate the situation must cease, and the owner/contractor will immediately commence restoration methods. Restoration activity will continue until such time as the affected property owner is satisfied.
- No temporary or permanent stockpiling of materials or equipment shall occur within critical areas or associated buffers, or the critical root zone for vegetation proposed for retention.

Owner/Developer:


E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:


JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

ONE INCH AT FULL SCALE,
IF NOT, SCALE ACCORDINGLY
Civil Construction Permit



11/24/25

REV DATE DESCRIPTION

1 01-10-26 REVISED PER CITY COMMENTS

SHEET TITLE:

APPROVED
BY _____
CITY OF PUYALLUP
DEVELOPMENT ENGINEERING
DATE _____

NOTE: THIS APPROVAL IS VOID
AFTER 180 DAYS FROM APPROVAL
DATE.

THE CITY WILL NOT BE
RESPONSIBLE FOR ERRORS
AND/OR OMISSIONS ON THESE
PLANS.

FIELD CONDITIONS MAY DICTATE
CHANGES TO THESE PLANS AS
DETERMINED BY THE
DEVELOPMENT ENGINEERING
MANAGER.

PROJ. NO. 1611-001

DATE November 24, 2025

DRAWN BY: DM

DESIGN BY: JJ

SHEET NUMBER:

C1-002

CALL TWO BUSINESS DAYS
BEFORE YOU DIG



1-800-424-5555

UTILITIES UNDERGROUND LOCATION CENTER

OF _____

File: 1611-001C-Cv1.dwg
Path: C:\Users\DavidMankoska\JMJ TEAM\JMJ TEAM\Projects - General\1611 - Fernandez\2020 Odd Road Development\03 - UE\240

WATER NOTES

- All work in City right-of-way requires a permit from the City of Puyallup. Prior to any work commencing, the general contractor shall arrange for a preconstruction meeting at the Development Services Center to be attended by all contractors that will perform work shown on the engineering plans, representatives from all applicable Utility Companies, the project owner and appropriate City staff. Contact Engineering Services to schedule the meeting (253) 841-5568. The contractor is responsible to have their own approved set of plans at the meeting.
- After completion of all items shown on these plans and before acceptance of the project, the contractor shall obtain a "punch list" prepared by the City's inspector detailing remaining items of work to be completed. All items of work shown on these plans shall be completed to the satisfaction of the City prior to acceptance of the water system and provision of sanitary sewer service.
- All materials and workmanship shall conform to the Standard Specifications for Road, Bridge, and Municipal Construction (hereinafter referred to as the "Standard Specifications"), Washington State Department of Transportation and American Public Works Association, Washington State Chapter, latest edition, unless superseded or amended by the City of Puyallup City Standards for Public Works Engineering and Construction (hereinafter referred to as the "City Standards"), or as directed by Fruitland Mutual Water Company (FMWC), Valley Water (VW), or Tacoma City Water (TCW) is the purveyor.
- A copy of these approved plans and applicable city developer specifications and details shall be on site during construction.
- Any revisions made to these plans must be reviewed and approved by the developer's engineer, the Engineering Services Staff, and the FMWC, VW or TCW when served by that purveyor, prior to any implementation in the field. The City shall not be responsible for any errors and/or omissions on these plans.
- The contractor shall have all utilities verified on the ground prior to any construction. Call (811) at least two working days in advance. The owner and his/her engineer shall be contacted immediately if a conflict exists.
- Any structure and/or obstruction which requires removal or relocation relating to this project shall be done so at the developer's expense.
- Bacteriological (Coliform and Iron Bacteria) test samples will be taken by the City (or FMWC, VW or TCW when served by that purveyor) and paid for by the contractor, except for Capital Improvement Projects (CIP) which shall be paid for by the City.
- Water mains shall have a minimum cover of 36 inches from paved final grade in improved right-of-way and improved easements, and a minimum of 48 inches in unimproved right-of-way and unimproved easements.
- Pipe for water mains shall be ductile iron conforming to Section 7-09 of the Standard Specifications, Class 52 with tyton or approved equal joints. Pipe shall be cement lined in accordance with A.S.A. Specification A 21.4-1964.
- Connections to existing water mains typically shall be wet taps through a tapping tee and tapping valve and shall be made by a city approved contractor. The tapping sleeve shall be Romac SST all stainless steel tapping sleeve or approved equal. A two-piece epoxy coated or ductile iron tapping sleeve may be used on ductile iron pipe, when the tap is smaller than the water main size i.e. 6-inch tap on 8-inch pipe. The City (or FMWC, VW or TCW when served by that purveyor) shall approve the time and location for these connections.
- All water mains and appurtenances shall be hydrostatically tested at 200 psi in accordance with Standard Specification 7-09.3(23). Pressure testing shall not be performed until satisfactory purity samples have been received, except when new water mains are installed independently from the water system piping.
- Fire hydrants shall be installed in accordance with City Standard Detail 03.05.01 and as directed by the City of Puyallup Fire Code Official.
- Valve marker posts shall be installed where valve boxes are hidden from view or in unpaved areas. The installation shall be in accordance with City Standard Detail 03.01.02.
- Resilient seated wedge gate valves shall be used for 10-inch mains and smaller. Butterfly valves shall be used for mains greater than 10 inches.
- Pipe fitting for water mains shall be ductile iron and shall be mechanical joint conforming to AWWA Specification C111-72.
- Water main pipe and service connections shall be a minimum of 10 feet away from building foundations and/or roof lines.
- Where a water main crosses the Northwest Gas pipeline, the water line shall be cased with PVC pipe a minimum of 10 feet beyond each side of the gas line easement. Contact Williams Northwest Pipeline before the crossing is made.
- Trenching, bedding, and backfill for water mains shall be installed in accordance with City Standard Detail 06.01.01.
- All commercial and industrial developments, irrigation systems, and multi-family water service connections shall be protected by a double check valve assembly or a reduced pressure backflow assembly as directed by the City (or FMWC, VW or TCW when served by that purveyor) conforming to City Standard Details 03.04.01, 03.04.02, and 03.04.03.
- Any lead joint fitting disturbed during construction shall be replaced with a mechanical joint fitting at the contractor's expense.
- When hydraulic fire flow modeling is required for a project, the City will issue a permit. The hydraulic modeling criteria is based on the projected 2030 water demand, while maintaining a minimum system pressure of 20 pounds per square inch and a maximum velocity of 10 feet per second.
- When using a fire hydrant for non-firefighting purposes, a city hydrant meter must be used. Coordinate the acquisition of the hydrant meter with the City's Utility Billing Division at Puyallup City Hall. A city approved backflow protection assembly shall be installed by the person requesting use of a fire hydrant. The assembly shall be accompanied by a current backflow assembly test report. The test report shall be available at the site for the duration of the hydrant use.
- Should a break occur on any City water main, the Contractor shall follow the City's adopted "Water Main Break Procedure" issued to them at the Pre-Construction Meeting and notify those connected to the system in the impacted area as outlined in the Procedure.

25. Water Main Repairs (References: AWWA C651-14 and WSDOT Standard Specification Section 7-09) (Note: A planned water main repair shall be approved by the City Inspector and/or Water Division Supervisor prior to commencing work.)

a. **Repair without depressurization** – Small leaks shall be repaired using repair bands while maintaining positive pressure in the water main. Valves surrounding the leak will be partially shut by the City Water Department to reduce the flow and pressure to the area. Blowoffs and hydrants in the reduced pressure area may be opened as needed to further reduce the pressure. The water main trench shall be over-excavated to allow water in the trench to be pumped out and maintained below the level of the water main. The repair shall be completed with the water main pressure remaining positive. After the repair is made, the system shall be fully pressurized and a visual leak inspection will be completed. The water main in the affected area shall be flushed to achieve three pipe volumes pulled from the pipe (distance measured from valve opened for flushing to the exit hydrant or blowoff).

b. **Repair/cut-in with depressurization** – Trench shall be over excavated and dewatered below the water main. Flush water from pipe from each direction until it runs clear. Immediately prior to installation of a new pipe section for repair or cut in tee, all new fittings and pipe spools shall be swabbed with a five percent (5%) chlorine solution (minimum). The interior of the existing pipe shall be swabbed with a five percent (5%) chlorine solution at least 6 feet in each direction from exposed cut ends. The water main in the affected area shall be flushed to achieve three pipe volumes pulled from the pipe (distance measured from the valve opened for flushing to the exit hydrant or blowoff). Customers shall be notified after the water main is flushed and repairs have been completed, as outlined in the "Water Main Break Procedure."

26. New Water Main Installation:

a. Each new water main section shall be delivered, stacked and stored onsite with ends plugged. The plugs shall remain in the pipe until each particular section is installed. National Sanitation Foundation (NSF) approved sixty-five percent (65%) calcium hypochlorite shall be added to the upstream end of each pipe section, and at each hydrant tee in the amount given in the table below (or per approved manufacturer specifications). The minimum amount of calcium hypochlorite added should be sufficient to achieve a 50 mg/L concentration within the impacted area.

Pipe Diameter (Inches)	Pipe Volume per 18 feet (gal)	5-gram tablets per pipe section	Hypochlorite Granules	Maximum Fill Rate (gpm)
4	35	1	1.7	0.2
6	53	1	3.8	0.4
8	70	2	6.7	0.7
12	106	4	15.1	1.4
16	141	6	27	2.5
				600

b. New water mains shall be filled using an approved backflow prevention assembly. The water main shall be filled from the lower elevation end so that as the water main is filled, the chlorine is contacted, dissolved and spread relatively uniform through the length of the new water main. The fill rate shall be minimized so that the velocity of the water is less than 1 ft/sec (see table above). Successful pressure test and bacteriological tests shall be completed and provided to the City prior to any new water main connection to the existing water system.

c. The chlorinated water will be allowed to remain in contact with the new water main system for 24 to 72 hours. After 24 hours, water may be added to the water main for the purposes of pressure testing. The water in the main used for pressure testing must remain in the water main until pressure test is completed. If necessary, liquid chlorine shall be injected into the water main with fill water to maintain a concentration in the water main above 50 mg/L. Under no circumstance shall "super" chlorinated water be allowed to sit within a new water main for more than 5 days.

d. Pressure testing includes testing against new valves and hydrants. Each valve shall be tested by closing each in turn and reducing the pressure beyond the valve. The pressure on the back side of the valve should not be eliminated. Care must be taken that, during this process, positive pressure remains throughout the system being tested at all times. All hydrant valves shall be open during pressure testing so that the pressure test is against the hydrant valve. Pressure testing will not be allowed against any existing valves.

e. After successful pressure testing, the water main shall be thoroughly flushed to remove all "super" chlorinated water from the new water main. Flushing of new or extended water mains shall be conducted per WSDOT Specification 7-09.3(24)A with a minimum velocity developed within the pipe while flushing of 2.5 feet per second (fps). All flushed water shall be dechlorinated prior to disposal. The Contractor shall be responsible for disposal of all chlorinated water flushed from mains. The City shall approve the disposal method prior to implementation in the field. The Contractor shall utilize on-site disposal methods, if available. Disposal of flush water to the sanitary sewer system shall not be allowed without written permission from the Water Pollution Control Plant (WPCP) Supervisor. Any planned discharge to a stormwater system shall be dechlorinated to a concentration of 0.1 ppm or less, pH adjusted (if necessary) to be between 6.5 and 8.5, and volumetrically and velocity controlled to prevent any resuspension of sediments. The City will require independent testing throughout the water discharge process to ensure compliance of these standards are met.

f. Samples for bacteriological analysis shall be collected after flushing and again 24 hours after the first set of samples.

g. All closure/connection fittings shall be sprayed clean and then swabbed with a five percent (5%) chlorine solution immediately prior to installation per AWWA Standard C651. Additional samples for bacteriological analysis shall be collected from the immediate vicinity of the new or replaced water main and analyzed after the final connections are made. If necessary, additional flushing shall be conducted and additional samples shall be collected until satisfactory results are obtained.

SANITARY SEWER TESTING REQUIREMENTS

1. Gravity sanitary sewer cleaning and testing requirements shall be as outlined in WSDOT Section 7-17.3(2). Sanitary sewer cleaning and testing shall be completed to the satisfaction of the Office of the City Engineer and/or Public Works Department prior to final acceptance. After completion of all project utility work (sewer, water, storm, etc.) and associated utility trench backfill and compaction, sewer lines shall be cleaned and tested by the Contractor prior to final project acceptance, as outlined in Section 406.1 through 406.4. At the end of the Maintenance and Warranty Period, the City will perform a final CCTV inspection per 406.4 to verify that the work performed conforms to City Standards prior to bond release.

1.1. Cleaning

Physical connection to the existing City sewer system shall not be allowed until all pipes have been thoroughly cleaned by jetting and/or pigging to remove any solids or construction debris that may have entered the pipe.

The Contractor shall arrange to have the water accumulated during construction and sanitary system cleaning operations removed from the sewer system by a Vactor truck. Water from the new sewer extension shall not be permitted to enter the existing City system until final project approval. Sediment or debris introduced to existing City sewers as a result of any construction activity shall be removed immediately by the Contractor in conformance with WSDOT Section 7-17.

1.2. Deflection Testing

Gravity sanitary sewers shall be tested for deflection prior to visual inspection. Thermoplastic pipe shall be tested for deflection not less than 30 days after the trench backfill and compaction has been completed. Deflection testing shall be conducted by pulling a mandrel (rigid or adjustable) with a diameter not less than 95 percent of the normal diameter of the pipe being tested. Mandrel testing shall be conducted in conformance with WSDOT Section 7-17.3(2).

1.3. Leakage Testing

All new gravity sanitary sewer mains and the right-of-way laterals shall be subject to a low-pressure air test per WSDOT Section 7-17.3(2)F. Low pressure air testing shall be conducted after backfilling is completed and the backfill material has been compacted in conformance with the approved plans. Conforming compaction shall be verified by nuclear gauge testing and/or proof rolling at the discretion of Engineering staff. The City Engineer or designee shall observe all testing to verify satisfactory completion. The City Engineer or designee may require that air test pressure be maintained at 4.0 psig with no drop for 15 minutes for a passing leakage test where groundwater pressure is deemed negligible, or at the City Engineer's or designee's discretion.

The Contractor shall furnish all necessary equipment and personnel for conducting the pressure test. The Contractor shall provide certification from a certified/accredited laboratory that testing equipment is accurate. All equipment and personnel shall be subject to approval by the City Engineer or designee.

If any portion of the sanitary system fails to meet the testing requirements, the Contractor shall determine, at their own expense, the source of leakage and shall repair or replace all defective materials or workmanship. The completed pipe installation shall meet the minimum testing requirements before being considered acceptable.

1.4. Television Inspection

All new gravity sanitary sewer extensions shall be visually inspected in conformance with WSDOT Section 7-17.3(2)H, following satisfactory trench compaction testing, flushing, low pressure air testing, and deflection testing. All manholes shall be channeled and grade rings set in place prior to sewer video inspection.

The remote camera used in sewer visual inspection shall be one specifically designed for such an application, with the ability to rotate the camera 180 degrees and lighting suitable to allow a clear picture of the entire periphery of the pipe. The camera shall proceed through the pipe at a sufficiently slow velocity to allow adequate inspection of all pipe. All sewer lateral fittings and joints and suspect pipe joints shall be closely inspected by rotating the camera as needed to provide a clear view of the pipe.

The Contractor shall introduce water to the new sewer system immediately prior to the visual inspection by adding water to the upstream manhole until water is seen flowing in the lowest manhole. Video inspection of the line shall begin when flow in the lowest manhole has stopped. A 1-inch sewer ball shall be attached to the front of the camera to provide a basis for estimating the depth of the ponding within the sewer pipe.

Television Inspection Acceptance Criteria:

1.4.1. Any ponding within a pipe shall be less than one-half inch (1/2") in depth.

1.4.2. The total accumulated ponding length, regardless of depth, from manhole to manhole shall be less than ten (10) percent of the total length from manhole to manhole.

Any sewer pipe that exceeds either of the above acceptance criteria will be rejected and require repair and/or replacement by the Contractor.

The Contractor shall bear all costs for the correction of any deficiencies found during TV inspection, including the costs for additional TV inspection and leakage testing needed to verify the deficiencies were corrected. All components of the video and recording equipment shall be sufficient to provide picture quality to the satisfaction of the City Engineer or designee.

Upon completion of the video inspection, the digital video, of common format, and written inspection report shall be submitted to the City for review. At a minimum, the inspection report shall contain the following information:

- Size, length, and material type of the sewer main.
- Location of all lateral connections.
- Estimated depth and location of all ponding over 1/4 inch in depth
- Manhole numbers that correspond to the approved plans
- Street name and/or location of sewer main

Owner/Developer:

E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:

JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

ONE INCH AT FULL SCALE,
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit



11/24/25

REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS

SHEET TITLE:

APPROVED

BY _____
CITY OF PUYALLUP
DEVELOPMENT ENGINEERING

DATE _____

NOTE: THIS APPROVAL IS VOID
AFTER 180 DAYS FROM APPROVAL
DATE.

THE CITY WILL NOT BE
RESPONSIBLE FOR ERRORS
AND/OR OMISSIONS ON THESE
PLANS.

FIELD CONDITIONS MAY DICTATE
CHANGES TO THESE PLANS AS
DETERMINED BY THE
DEVELOPMENT ENGINEERING
MANAGER.

DRAWN BY: _____


DESIGN BY: _____

SHEET NUMBER: _____

General Notes
C1-003

CALL TWO BUSINESS DAYS
BEFORE YOU DIG
1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER

DWG. _____
OF _____



LEGEND

■	Mail Box (MB)
☒	Wooden Stake
▲	Gas Valve (GV)
◎	Sanitary Sewer Manhole (SSMH)
○	Sanitary Sewer Cleanout (SSCO)
●	Power Pole (PP)
■	Guy Wire Anchor (GWA)
■	Power Meter (PM)
☒	Light Standard (LS)
◊	Power Hand Hole (HH)
TP	Transformer Pad
PP/T	Power Pole with Transformer
◎	Storm Drainage Manhole (SDMH)
■	Catch Basin (CB)
△	Water Valve (WV)
○	Water Meter (WM)
☒	Hydrant (FH)
○	Water Marking Post (WMP)
☒	Fire Connection (FDC)
△	Irrigation Control Box (ICB)
—	Property Line
—	Stream Buffer 100'
—	Wetland Buffer 150'
—W—	Water Line
—SD—	Stormwater Line
—SS—	Sewer Line
—OP—	Overhead Power Line
—UP—	Underground Power Line

Owner/Developer:

E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:

Engineer:

JMJ TEAM
JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

ONE INCH AT FULL SCALE,
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit



REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS 1

VERTICAL DATUM:

BASE: HELD STATION TACO AS PUBLISHED ON WASHINGTON STATE REFERENCE NETWORK WEBSITE ([HTTP://WSRN3.ORG/](http://WSRN3.ORG/)) (2018)

ELEVATION: 341.348' (NAVD88)

SITE #1: CE 500, A SET HUB AND TACK ON THE NORTH SIDE OF TODD ROAD NORTHEAST, 8.8' EAST OF STORM DRAINAGE MANHOLE AS SHOWN HEREON.

ELEVATION: 50.27' (NAVD88)


SITE #2: CE 505, A SET HUB AND TACK IN THE BACK OF YARD OF THE SITE AS SHOWN HEREON.

ELEVATION: 51.35' (NAVD88)

SITE AREA: 65,123 SQ FT (1.495 ACRES)

HORIZONTAL DATUM:

THE NORTH AMERICAN DATUM OF 1983/2011 (NAD 83/2011 EPOCH 2010.00) GRID COORDINATES WERE FOUND TO BE 690850.70 / 1194622.67 AT AN "X" IN A 2.5" BRASS DISK.



APPROVED

BY CITY OF PUYALLUP DEVELOPMENT ENGINEERING

DATE

NOTE: THIS APPROVAL IS VOID

AFTER 180 DAYS FROM APPROVAL DATE

THE CITY WILL NOT BE

RESPONSIBLE FOR ERRORS

AND/OR OMISSIONS ON THESE

PLANS.

FIELD CONDITIONS MAY DICTATE

CHANGES TO THESE PLANS AS

DETERMINED BY THE

DEVELOPMENT ENGINEERING

MANAGER.

Existing Site Plan

PROJ. NO.: 1611-001

DATE: November 24, 2025

DRAWN BY: DM DESIGN BY: JJ

SHEET NUMBER: C1-101

CALL TWO BUSINESS DAYS

BEST YOU DIG

1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER

DWG. OF



LEGEND

	Construction Entrance
	Staging Area
	Silt Fence
	Property Line

Owner/Developer:
E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:

Engineer:
JMJ TEAM
JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

GENERAL NOTES

- Contractor to install TESC measures as necessary to ensure stormwater leaving the site is free of settleable solids.
- Roads shall be cleaned thoroughly as needed to protect stormwater infrastructure and downstream water resources. Sediment shall be removed from roads by shoveling or pickup sweeping and be transported to a controlled sediment disposal area.
- Install storm drain inlet protection in all existing catch basins within the project vicinity per WSDOT Std Plan I-40.20-00.
- Install straw bale barriers, wattles, and other necessary TESC measures as necessary.
- Exposed soils shall be watered as necessary to prevent dust from leaving the site.
- Concrete handling and equipment washing shall be in accordance with DOE BMP C151.
- Maintain construction entrance and install construction fence as necessary. Construction entrance and fencing to be adjusted during phases of construction.
- Keep all heavy equipment off existing soils under LID facilities that have been excavated to final grade to retain the infiltration rate of the soils.
- Control erosion and avoid introducing sediment from surrounding land uses onto permeable pavements. Do not allow muddy construction equipment on the base material or pavement. Do not allow sediment-laden runoff onto permeable pavements or base materials.


ONE INCH AT FULL SCALE,
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit



11/24/25

REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS 1



SHEET TITLE:

TESC Plan

APPROVED	BY _____
	CITY OF PUYALLUP DEVELOPMENT ENGINEERING
	DATE _____
NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE. THE CITY WILL NOT BE RESPONSIBLE FOR ERRORS AND/OR OMISSIONS ON THESE PLANS. FIELD CONDITIONS MAY DICTATE CHANGES TO THESE PLANS AS DETERMINED BY THE DEVELOPMENT ENGINEERING MANAGER.	
PROJ. NO.:	1611-001
DATE:	November 24, 2025
DRAWN BY:	DM
DESIGN BY:	JJ
SHEET NUMBER:	C2-101

PROJ. NO.:

1611-001

DATE:

November 24, 2025

DRAWN BY:

DM

DESIGN BY:

JJ




SHEET NUMBER:

C2-101

DWG. _____

OF _____

CALL TWO BUSINESS DAYS
BEFORE YOU DIG
 1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER



Owner/Developer:

E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:

Engineer: **JMJ Team**
JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project: Todd Rd Sewer Extension

ONE INCH AT FULL SCALE.
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit

REV DATE DESCRIPTION
1 01-10-26 REVISED PER CITY COMMENTS 1

STATE OF WASHINGTON
REGISTERED
LANDSCAPE ARCHITECT
MARK W. MAURER
CERTIFICATE NO. 000598

NOTE: THIS PLAN IS NOT A LEGAL ENGINEERING DOCUMENT. THE ORIGINAL, SIGNED BY THE ENGINEER AND APPROVED BY THE CITY, IS THE LEGAL ENGINEERING DOCUMENT. A COPY MAY BE OBTAINED UPON REQUEST.

11/24/25

APPROVED
BY: CITY OF PUYALLUP
DEVELOPMENT ENGINEERING
DATE:

NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE.
THE CITY WILL NOT BE RESPONSIBLE FOR ERRORS AND/OR OMISSIONS ON THESE PLANS.
FIELD CONDITIONS MAY DICTATE CHANGES TO THESE PLANS AS DETERMINED BY THE DEVELOPMENT ENGINEERING MANAGER.


PROJ. NO: 1611-001
DATE: November 24, 2025


DRAWN BY: DM DESIGN BY: JJ

SHEET NUMBER: C2-201

CALL TWO BUSINESS DAYS BEFORE YOU DIG
1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER

DWG. OF



Owner/Developer:	E.J. Fernandez PO BOX 309 Sumner, WA 98390	
Consultant Type:		
Engineer:	JMJ TEAM 905 Main Street, Suite #200 Sumner, WA 98390 (206) 596-2020	
Project:	Todd Rd Sewer Extension	
ONE INCH AT FULL SCALE. IF NOT, SCALE ACCORDINGLY		
Civil Construction Permit		
 11/24/25		
REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS 1
SHEET TITLE:		
APPROVED BY CITY OF PUYALLUP DEVELOPMENT ENGINEERING DATE NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE. THE CITY WILL NOT BE RESPONSIBLE FOR ERRORS AND/OR OMISSIONS ON THESE PLANS. FIELD CONDITIONS MAY DICTATE CHANGES TO THESE PLANS AS DETERMINED BY THE DEVELOPMENT ENGINEERING MANAGER.		
PROJ. NO.: 1611-001		
DATE: November 24, 2025		
DRAWN BY:	DESIGN BY:	JJ
SHEET NUMBER:		
C3-101 CALL TWO BUSINESS DAYS BEFORE YOU DIG  1-800-424-5555 UTILITIES UNDERGROUND LOCATION CENTER		
DWG.	10	18

Author/Developer:

Fernandez
BOX 309
Lynnwood, WA 98390


Consultant Type:

Page 10 of 10

ct: dd Rd Sewer Extension

WILSON, 1995: www.sciencedirect.com

Civil Construction Permit



11/24/2

REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS 1

TITLE

Hardscape Details

ALL LANDSCAPE AREAS

2"-4" WOOD CHIP MULCH (TAPERED AT EDGE OF PAVEMENT)

3" OF COMPOST INCORPORATED INTO SOIL TO 8" DEPTH 40% COMPOST BY VOLUME. SEE NOTE #6

SUBSOIL SCARIFIED 4" BELOW COMPOST AMENDED LAYER (12" BELOW SOIL SURFACE)

0"

8"

12"

NOTES:


1. ALL SOIL AREAS DISTURBED OR COMPAKTED DURING CONSTRUCTION, AND NOT COVERED BY BUILDINGS OR PAVEMENT, SHALL BE AMENDED WITH COMPOST AS DESCRIBED BELOW.
2. SUBSOIL SHOULD BE SCARIFIED (LOOSEND) 4 INCHES BELOW AMENDED LAYER, TO PRODUCE 12-INCH DEPTH OF UN-COMPAKTED SOIL, EXCEPT WHERE SCARIFICATION WOULD DAMAGE TREE ROOTS OR AS DETERMINED BY THE ENGINEER. SEE NOTE BELOW REGARDING PLANTING STEPS FOR STREET TREES.
3. COMPOST SHALL BE TILLED IN TO 8 INCH DEPTH INTO EXISTING SOIL, OR PLACE 8 INCHES OF COMPOST-AMENDED SOIL, PER SOIL SPECIFICATION.
4. PLANTING BEDS SHALL RECEIVE 3 INCHES OF COMPOST TILLED IN TO 8-INCH DEPTH, OR MAY SUBSTITUTE 8" OF IMPORTED SOIL CONTAINING 35-40% COMPOST BY VOLUME. MULCH AFTER PLANTING, WITH 4 INCHES OF ARBORIST WOOD CHIP MULCH OR APPROVED EQUAL (6" OF LOOSE WOOD CHIPS AT THE TIME OF PLANTING TO ALLOW SETTLING TO 4").
5. SETBACKS: TO PREVENT UNEVEN SETTLING, DO NOT COMPOST-AMEND SOILS WITHIN 3 FEET OF UTILITY INFRASTRUCTURES (POLES, VAULTS, METERS ETC.). WITHIN ONE FOOT OF PAVEMENT EDGE, CURBS AND SIDEWALKS SOIL SHOULD BE COMPAKTED TO APPROXIMATELY 95% PROCTOR TO ENSURE A FIRM SURFACE.
6. SEE SECTION 8.2(B) OF THE VMS FOR SOIL AMENDMENT AND INSTRUCTION PROCEDURES FOR STREET TREE PLANTER STRIPS. ALL STREET TREE PLANTER STRIPS SHALL RECEIVE 40% COMPOST AMENDED SOIL TO THE FULL DEPTH OF THE STREET TREE ROOTBALL.

**CITY OF
PUYALLUP**

DEVELOPMENT ENGINEERING and
PUBLIC WORKS DEPARTMENTS

**SOIL AMENDMENT
AND DEPTH**

DRAWN BY LINDA LIAN	CHECKED BY CHRIS BEALE	APPROVED BY COLLEEN HARRIS	REVISED BY XXXX	CITY STANDARD
FILE NAME F:\DWG\COMMON\STD\STDS\STDS\STR\01.02.08	DATE APPROVED 08/01/2015	DATE REVISED XX/XX/XX	SCALE 1:1	01.02.08a



CITY OF PUYALLUP

SOIL AMENDMENT AND DEPTH

DEVELOPMENT ENGINEERING and PUBLIC WORKS DEPARTMENTS	DRAWN BY LINDA LIAN	CHECKED BY CHRIS BEALE	APPROVED BY COLLEEN HARRIS	REVISED BY XXXX	CITY STANDARD
	FILE NAME F:\DWG\COMMON\STD\STDS\STC\STDS\STR\01.02.08		DATE APPROVED 08/01/2015	DATE REVISED XX/XX/XX	SCALE 1:1

APPROVED

CITY OF PUYALLUP
DEVELOPMENT ENGINEERING


**TE: THIS APPROVAL IS VOID
TER 180 DAYS FROM APPROVAL
TE.
E CITY WILL NOT BE
SPONSIBLE FOR ERRORS
D/OR OMISSIONS ON THESE
ANS.
LD CONDITIONS MAY DICTATE
ANGES TO THESE PLANS AS
TERMINED BY THE
VELOPMENT ENGINEERING
NAGER.**

BUSINESS DAYS
RE YOU DIG

—424—5555
GROUND LOCATION CENTER

ALL TWO BUSINESS DAYS
BEFORE YOU DIG

Path: C:\Users\Pawarisa0nmun\JMJ TEAM\JMJ Projects - General\1611 - Fernandez\320 Todd Road Development\03 - UE\CAD\Plotted by: Pawarisa0nmun Date: 09-Jan-26 4:30:09pm




DerekMandika Date: 27-Jun-26 11:25:35am

DerekMandika Plotted by: EJ Fernandez

Path: C:\Users\JMJ TEAM\Projects - General\611 - Fernandez\320 Todd Rd Development\03 - UE\CAD\

File: 1611001C-SSWR-PAP.dwg



GENERAL NOTES

- Sewer Pipes to be SDR 35 PVC Piping
- Proposed Sewer Main Extension is Private
- Contractor to locate horizontal and vertical utilities and verify with engineer prior to any utility work.
- All pipe trench bedding and backfill will be installed per City of Puyallup Standard Detail 06.01.01 on Sheet C4-301.

CONSTRUCTION NOTES

1. Install Sewer Manhole per City of Puyallup Standard Detail 04.01.01 on Sheet C4-301.
2. Install Sewer Cleanout per Detail A on Sheet C4-301.
3. Install Sewer Residential Connection per City of Puyallup Standard Detail 04.03.03 on Sheet C4-301.

Owner/Developer:

E.J. Fernandez
PO BOX 309
Sumner, WA 98390

Consultant Type:


Engineer:

JMJ Team
905 Main Street, Suite #200
Sumner, WA 98390
(206) 596-2020

Project:
Todd Rd Sewer Extension

ONE INCH AT FULL SCALE.
IF NOT, SCALE ACCORDINGLY

Civil Construction Permit



REV DATE DESCRIPTION
1 01-10-26 REVISED PER CITY COMMENTS 1

APPROVED
BY CITY OF PUYALLUP
DEVELOPMENT ENGINEERING
DATE
NOTE: THIS APPROVAL IS VOID
AFTER 180 DAYS FROM APPROVAL
DATE.
THE CITY WILL NOT BE
RESPONSIBLE FOR ERRORS
AND/OR OMISSIONS ON THESE
PLANS.
FIELD CONDITIONS MAY DICTATE
CHANGES TO THESE PLANS AS
DETERMINED BY THE
DEVELOPMENT ENGINEERING
MANAGER.

PROJ.NO: 1611-001
DATE: November 24, 2025

DRAWN BY: DM DESIGN BY: JJ






SHEET NUMBER

C4-201

DWG.

CALL TWO BUSINESS DAYS
BEFORE YOU DIG
1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER


13 OF 18



APPROVED		
BY	CITY OF PUYALLUP DEVELOPMENT ENGINEERING	DATE
NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE.		
PROJ. NO:	1611-001	
DATE:	November 24, 2025	
DRAWN BY:	DM	DESIGN BY: JJ
SHEET NUMBER		

CALL TWO BUSINESS DAYS BEFORE YOU DIG
1-800-424-5555
UTILITIES UNDERGROUND LOCATION CENTER

Owner/Developer: E.J. Fernandez PO BOX 309 Sumner, WA 98390
Consultant Type:
Engineer: JMJ Team 905 Main Street, Suite #200 Sumner, WA 98390 (206) 596-2020
Project: Todd Rd Sewer Extension
ONE INCH AT FULL SCALE. IF NOT, SCALE ACCORDINGLY
Civil Construction Permit



11/24/25

REV	DATE	DESCRIPTION
1	01-10-26	REVISED PER CITY COMMENTS 1
SHEET TITLE		
Sewer Details		
APPROVED	BY CITY OF PUYALLUP DEVELOPMENT ENGINEERING DATE	
NOTE: THIS APPROVAL IS VOID AFTER 180 DAYS FROM APPROVAL DATE.		
PROJ. NO:	1611-001	
DATE:	November 24, 2025	
DRAWN BY:	DM	DESIGN BY: JJ
SHEET NUMBER		
C4-301		