

Project: ISO-0539048 – Centeris Data Center – Phase 2

Address: 1023 39th Ave SE. Puyallup, WA 98374

For: Zayo Group

Proposed scope of work:

From existing Zayo vault on the south side of 39th Ave SE trench 16' in concrete sidewalk to bore-pit. Directional bore 770' west under 39th Ave SE to new 233LA vault at 10th St SE. Install (3) 1-1/4" HDPE conduits. Directional bore south under 10th St SE 639' to new 233LA vault. Install (3) 1-1/4" HDPE conduits. Directional bore south under 10th St SE 639' to bore-pit. Install (3) 1-1/4" HDPE conduits. Saw Cut and trench 33' east in asphalt roadway to new 24x36 vault. Install (3) 1-1/4" HDPE conduits. Pull (2) 432ct micro-fibers through. Trench 140' west in gravel area to new 36x36 on 116th St install (3) 1-1/4" HDPE conduits. Pull (1) 432ct micro-fiber through. Directional bore south under 110th Ave E. Exit City of Puyallup. Remove and replace asphalt roadway per City of Puyallup specifications.