

SITE PLAN EXPANDED
(P01/P02)
SCALE: NONE

| | | | |
|--|----------|-------------|--------------|
| City of Puyallup Development & Permitting Services ISSUED PERMIT | | | |
| Building | Planning | Engineering | Public Works |
| Fire | Traffic | | |

- P01: 568002-156538
REPLACE 40FT 80 POLE W/ 45FT CL-1 (W GND) AS STAKED
INST STD 8 PIN SINGLE ARM
INST 2 - PIN & INSUL
INST PTP
INST C/O ARM
REPLACE 25KVA 1Ø W/ 37.5/75/37.5KVA OH TRF BANK 120/208/240V (2)2-24
INST 3 - L/B C/O F: 6T / 25T / 6T
INST 2 - STURRUPS & TAPS
INST. 2 - 3" SEC. RISERS ON S/O BRKTS (2)2-24

- HH1:
INST CONCRETE SECONDARY HANDHOLE 233 W/10-350 6 POS
INST GROUND TO STEEL LID
CONNECT & TAG CUSTOMER RAN UG SVC LINES (3 RUN OF 400AL) (2)2-36 X 2
(2)2-54A X 2

- P01 TO HH1:
INST 2 - 3" DB120 CONDUIT ±20FT (BILLABLE: 20FT)(ACTUAL:)
INST 2 - 350MCM UG QUAD ±55FT (BILLABLE: 55FT)(ACTUAL:)

MAPS & RECORDS:
NOTE CORRECTION TO EXISTING METER LOC. & NO EXISTING STREETLIGHT AT P01

CUSTOMER NOTES:
SITE MUST BE READY 1 WEEK PRIOR TO CONSTRUCTION.
CUSTOMER TO PROVIDE ALL TRENCHING AND EXCAVATING

TRANSFORMER BANK INSTALLATION
Foreman to redline field changes

Installed at site: P01
Grid Number: 568002-156538

Bank Configuration:
□ WYE/WYE □ WYE/DELTA □ OPEN WYE/OPEN DELTA □ WYE/WYE 120/208v W/1Ø 120/240v
Secondary Voltage:
□ 120/208v □ 277/480v □ 120/208v W/120/240v 1Ø □ 120/240v □ 240/480v
AØ Xfmr MID # 6209100 kVA 37.5
BØ Xfmr MID # 6211400 kVA 75
CØ Xfmr MID # 6209100 kVA 37.5

Foreman to redline the following information
AØ Xfmr Company ID#: _____
BØ Xfmr Company ID#: _____
CØ Xfmr Company ID#: _____

Tested Secondary Voltage _____

NOTE: The foreman should record one phase-to-neutral and one phase-to-phase voltage. If the bank is a combination 120/208V with single phase 120/240V, record the tested voltage of the 240V connection in addition to the voltage of the 120/208 transformer connections.

CIRCUIT LOADING TABLE

| | | | | |
|---------------------|--------|-------------------------|---------|---------|
| Circuit: | GAR-16 | Customer 3Ø Load: | 81 | |
| As Of: | 2020 | Power Factor: | .85 | |
| | | Phase to Phase Voltage: | 12500 | |
| | | A Phase | B Phase | C Phase |
| Existing Peak Load: | 263.0 | 274.0 | 272.0 | |
| Estimated New Load: | 4.4 | 4.4 | 4.4 | |
| Total: | 267.4 | 278.4 | 276.4 | |

EROSION & SEDIMENT CONTROL REQUIREMENTS
EROSION & SEDIMENT CONTROL SHALL BE PER PSE STANDARD PRACTICE 0150.3200 TECHNIQUES FOR TEMPORARY EROSION & SEDIMENT CONTROL & ANY ADDITIONAL LOCAL JURISDICTION REQUIREMENTS (LOCAL JURISDICTIONS MAY HAVE ADDITIONAL REQUIREMENTS INCLUDING NOTES DETAILING WHERE EROSION OR SEDIMENT CONTROL STRUCTURES ARE TO BE INSTALLED, CROSS SECTION DETAILS OF THE TYPICAL EROSION STRUCTURES, & SPECIAL REQUIREMENTS FOR WORK IN SENSITIVE AREAS.)


TRANSFORMER REMOVAL

Removed at site: P01
Grid Number: 568002-156538
kVA Rating: 25

Foreman to redline the following information
Company ID#: _____
Primary phase connected to: _____
Tested Secondary Voltage _____

POLE RETIREMENT TABLE

| Wk Loc | Pole Data | | | | | TEMP TRANSFERS | | | |
|--------|---------------|--------|-------|------|--------|----------------|-----|----|-------|
| | Grid # | Length | Class | Year | TOPPED | RMVD | TEL | TV | FIBER |
| P01 | 568002-156538 | 40 | CL-3 | 1973 | | | | | |




FOREMAN (CHECK BOX WHEN COMPLETED)

PSE Equipment LOCKED/SECURED & Work Area left in CLEAN/SAFE Condition.
 Grid, Cable, and Switch numbers INSTALLED & VERIFIED.
 Field Changes RED-LINED on As-built.
 Material VERIFIED and CHANGES noted on Paperwork.
 Total PRIMARY Cable noted on As-built.
 Company ID#s RECORDED in correct location on As-built.
 Indicate correct FUSE SIZE on As-built & VERIFY proper PHASE.
 Deviations noted on the As-built and their reason.

I certify that the work performed meets PSE's standards and procedures and that all quality requirements are met.

Foreman's Signature _____
Print Name _____ Date _____



PROJECT PHASE

| PROJECT PHASE | NOTIF# | ORDER# |
|---------------|-----------|-----------|
| PWR Superior | 511373769 | 105098783 |
| Replace Pole | | 101144776 |
| | | 108132857 |
| | | 593241012 |
| Replace Xfmr | | 583 |
| Perm. Service | 511936007 | 104339951 |
| Distribution | N/A | N/A |
| Service Stubs | N/A | N/A |
| HP Svc/MSA | N/A | N/A |

CABLE TV
PHONE _____

Project Manager Contact Information:
Manager: Jennifer Welch
Cell Phone: 253.682.9813
E-Mail: Jennifer.Welch@pse.com

PSE Locates Required YES
Customer Locates Required YES
Outages Required YES
Flagging Required YES

CALL 811 TWO BUSINESS DAYS BEFORE YOU DIG
THIS SKETCH NOT TO BE RELIED UPON FOR EXACT LOCATION OF EXISTING FACILITIES

| REAL ESTATE/EASEMENT | PERMIT | | | | |
|---------------------------|----------|------------|-------------|--------------|----------|
| | YES | NO | | | |
| 3 | | | | | |
| 2 | | | | | |
| 1 | | | | | |
| REV# | DATE | BY | DESCRIPTION | ENGR - GAS | DATE |
| COUNTY | Pierce | Emer Sect | Gas Wk Ctr | POWER WK CTR | 10/18/21 |
| H4 SEC | | N/A | N/A | QSWPRE | 10/18/21 |
| SW 1/4 Sect 25, T20, R04E | | OP MAP | | PLAT MAP | |
| U-MAP NO (POWER) | 2004E099 | OH CKT MAP | 2004E100 | UG CKT MAP | |
| | | | | CIRCUIT NO | |
| | | | | GAR-16 | |
| | | | | MAPPING | |

JOINT FACILITIES ARRANGEMENTS

| UTILITIES | CONTACT | PHONE# | DATE |
|-----------|---------|--------|------|
| N/A | N/A | N/A | N/A |
| N/A | N/A | N/A | N/A |
| N/A | N/A | N/A | N/A |

STEP BY STEP FAMILY SERVICES
COMMERCIAL INST OH 3Ø XFRM BANK & HH
3303 8TH AVE SE, PUYALLUP

INCIDENT
N/A



MAOP
N/A

Gas Order
N/A

Elect Order
105098783

SCALE
AS NOTED

PAGE
1/1



Apr 19, 2022 11:02am C:\Users\lgakin\Documents\JOBS\105098783_STEP BY STEP\step-by-step-aud.dwg 105098783