


LEDGIBLE REPORT IS REQUIRED TO BE PROVIDED BY THE PERMITTEE ON SITE FOR ALL INSPECTIONS



Dimensions of roof: Sq ft of roof surface to be covered is **~1200sq ft**, at 24.91ft x 45.3ft.

Current decking: metal with a single layer of built up roof system

Load : 3.62lb per sq ft.

1/4 DensDeck	HPR Torch Base	StressPly IV Plus Mineral	Total Load
1.2 lb/sqft	.76 lb/sqft	1.666 lb/sqft	3.62

Scope of Work:

Mobilize materials and equipment needed to complete project.

Set up safety as needed to comply with L&I safety requirements.

Tear off flashing on walls.

Mechanically fasten a layer of 1/4” DensDeck Prime over existing roof.


Install new HPR Torch Base over DensDeck and walls.

Install new StressPly IV Plus Mineral over HPR Torch Base.

Flash all curbs and penetrations.

Install new coping metal.

Clear site of any trash and debris created from project.





City of Puyallup Development & Permitting Services ISSUED PERMIT			
Building	Planning	Engineering	Public Works
Fire	Traffic		

