

BRADLEY HEIGHTS - 27TH AVE SE


206 27TH AVE SE

PROJECT: 2195948

CITY OF PUYALLUP, PIERCE COUNTY, WASHINGTON

City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic



BRADLEY HEIGHTS - 27TH AVE SE
206 27TH AVE SE
PUYALLUP, WA 98374

PROJECT: 2195948
COVER SHEET / VICINITY MAP

DESIGN BY K & B TECHNICAL SOLUTIONS

DATE	DESCRIPTION	DESIGNER	DRAWN
08/12/25	ORIGINAL ISSUE	JN	JN
09/03/25	SIGNS REVISION	JN	JN



P.O. Box 2529, Clackamas, OR 97015
Jack Nygard - (503) 544-5749
Jack_Nygaard@kmail.net

OWNER / APPLICANT


COMCAST
CONTACT: BART SISTEK; NETWORK PROJECT MANAGER
MOBILE: (425) 293-1340
EMAIL: BART_SISTEK@COMCAST.COM


DESIGN BY

K&B TECHNICAL SOLUTIONS
P.O. BOX 2529
CLACKAMAS, OR 97015
CONTACT: JACK NYGARD
MOBILE: (503) 544-5749
EMAIL: JACK_NYGARD@KMAIL.NET / PERMITS@KMAIL.NET

SHEET INDEX

SHT	DESCRIPTION
1	COVER SHEET/VICINITY MAP
2	GENERAL NOTES
3	TRAFFIC CONTROL PLAN





GENERAL NOTES:

TRAFFIC CONTROL PLAN AND ALL DEVICES SHALL COMPLY WITH CURRENT MUTCD AND LOCAL STANDARDS.

SIGNS AND OTHER TRAFFIC CONTROL DEVICES (TCD) SHOWN ARE THE MINIMUM REQUIRED.

WHEN FLAGGING DURING HOURS OF DARKNESS OR LOW VISIBILITY FLAGGER STATIONS SHALL BE ILLUMINATED. FLAGGERS SHALL WEAR A HIGH-VISIBILITY ENSEMBLE WHICH INCLUDES ANSI/ISEA 107 CLASS 2 OR 3 VEST IN AN APPROVED COLOR, ANSI/ISEA 107 CLASS E LOWER GARMNET, AND A HIGH VISIBILITY HARD HAT WITH 12 SQUARE INCHES OF RETROREFLECTIVE MATERIAL PLACED TO PROVIDE 360 DEGREES OF VISIBILITY.

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE SHOWN.
USE FLUORESCENT ORANGE SHEETING FOR THE BACKGROUND OF ALL TEMPORARY WARNING SIGNS.

DO NOT LOCATE SIGN SUPPORTS IN LOCATIONS DESIGNATED FOR BICYCLE OR PEDESTRIAN TRAFFIC.

MAINTAIN PEDESTRIAN ACCESS TO/THROUGH CROSSWALKS AND/OR SIDEWALKS.
IF ACCESS CANNOT BE MAINTAINED, PROVIDE AN ADA COMPLIANT PATH AROUND/THROUGH THE WORK ZONE.

MAINTAIN LOCAL/DRIVEWAY ACCESS.










PLACE NO PARKING SIGNS 48 HOURS IN ADVANCE.

COVER STOP SIGNS AND/OR DISABLE SIGNALS WHEN AT A CONTROLLED INTERSECTION.
CONTACT THE LOCAL TRAFFIC SIGNAL AUTHORITY 7 DAYS IN ADVANCE TO COORDINATE SIGNAL MODIFICATIONS OR SHUTOFF.

ADJUST TO FIELD CONDITIONS AS NEEDED.

K&B TECHNICAL SOLUTIONS, AS THE PREPARER OF THIS TRAFFIC CONTROL PLAN, MAKES NO REPRESENTATION AS TO ITS' GENERAL ADEQUACY OR BEING APPROVED FOR IMPLEMENTATION.
APPROVAL MUST RESULT FROM THE TRAFFIC ENGINEER OR OTHER PUBLIC OFFICIAL HAVING STATUTORY ENFORCEMENT AUTHORITY IN THE JURISDICTION.
UTILIZATION AND IMPLEMENTATION OF THIS PLAN SHALL BE A RESULT OF THIS APPROVAL.

LEGEND:

-  WARNING SIGN
-  ARROW BOARD
-  CONE/CHANNELIZING DEVICE
-  SPOTTER
-  WORK AREA
-  FLAGGER
-  TYPE II BARRICADE
-  WORK VEHICLE
-  TRAFFIC SIGNAL

SIGN SPACING		
FREEWAYS & EXPRESSWAYS	55 / 70 MPH	1500'±
RURAL HIGHWAYS	60 / 65 MPH	800'±
RURAL ROADS	45 / 55 MPH	500'±
RURAL ROADS & URBAN ARTERIALS	35 / 40 MPH	350'±
RURAL ROADS, URBAN ARTERIALS, RESIDENTIAL & BUSINESS DISTRICTS	25 / 30 MPH	200'± (2)
URBAN STREETS	25 MPH OR LESS	100'± (2)

(1) ALL SPACING MAY BE ADJUSTED TO ACCOMMODATE INTERSECTIONS AND DRIVEWAYS.
(2) THIS SPACING MAY BE REDUCED IN URBAN AREAS TO FIT ROADWAY CONDITIONS.

MINIMUM SHOULDER TAPER LENGTH (FEET)										
SHOULDER WIDTH (FEET)	POSTED SPEED (MPH)									
	25	30	35	40	45	50	55	60	65	70
8	40	40	60	90	120	130	150	160	170	190
10	40	60	90	90	150	170	190	200	220	240

USE A 3 DEVICES TAPER FOR SHOULDERS LESS THAN 8'

MINIMUM LANE CLOSURE TAPER LENGTH (FEET)										
LANE WIDTH (FEET)	POSTED SPEED (MPH)									
	25	30	35	40	45	50	55	60	65	70
10	105	150	205	270	450	500	550	-	-	-
11	115	165	225	295	495	550	605	660	-	-
12	125	180	245	320	540	600	660	720	780	840

BUFFER DATA											
LONGITUDINAL BUFFER SPACE											
SPEED (MPH)	25	30	35	40	45	50	55	60	65	70	
LENGTH (FEET)	155	200	250	305	360	425	495	570	645	730	
BUFFER VEHICLE ROLL AHEAD DISTANCE											
TRANSPORTABLE ATTENUATOR MINIMUM HOST VEHICLE WEIGHT 15,000 LBS. THE MAXIMUM WEIGHT SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATION.										30 FEET MIN. TO 100 FEET MAX.	
PROTECTIVE VEHICLE MAY BE A WORK VEHICLE STRATEGICALLY LOCATED TO SHIELD THE WORK AREA.										NO SPECIFIC DISTANCE REQUIRED	

CHANNELIZATION DEVICE SPACING (FEET)		
MPH	TAPER	TANGENT
50/70	40	80
35/45	30	60
25/30	20	40

BRADLEY HEIGHTS - 27TH AVE SE
206 27TH AVE SE
PUYALLUP, WA 98374

DATE	DESCRIPTION	DESIGN/DRAWN		IN		IN	
		JN	JN	JN	JN		
08/12/25	ORIGINAL ISSUE						
09/03/25	SIGNS REVISION						

K&B TECHNICAL SOLUTIONS
P.O. Box 2529, Clackamas, OR 97015
Jack Nygard - (503) 544-5749
Jack_Nygart@kbmail.net

COMCAST
Bart Sistik - Network Project Manager
Mobile: (425) 293-1340
Bart_Sistik@comcast.com

ROAD WORK ALLOWED:

Monday - Friday
9AM - 3PM

Call communications center at 253-287-4456 on day of work. Request a job start inspection through the CityView portal.

The City-issued permit packet shall be posted at the job site and available to inspectors at all times.

Puyallup construction restriction zones and routes shall be in effect during special events in downtown Puyallup or at the Washington State Fair. No work is allowed in the public right-of-way as defined by the Puyallup "Construction Restriction Zone & Routes Map."


The applicant shall notify property owner(s) of blocked driveway(s) at least 24 hours in advance.

Work shall immediately cease in the work zone for a pedestrian spotter, available at all times, to escort pedestrians around the work area.

When shifting traffic into a turn lane, use of double cones is required. Traffic device spacing shall be half distance for opposing traffic devices.

The applicant shall notify public transportation agencies whose routes or stops are affected by the traffic control plan 24 hours in advance of job start. (Pierce County Transit Construction Coordinator: 253-581-8000)

The applicant shall coordinate redundant traffic control devices with other traffic control plans authorized near this site.



PRFUP20260593

City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic



BRADLEY HEIGHTS - 27TH AVE SE
206 27TH AVE SE
PUYALLUP, WA 98374

PROJECT: 2195948
TRAFFIC CONTROL PLAN

DATE	DESCRIPTION	DESIGN/DRAWN	
		JN	JN
08/12/25	ORIGINAL ISSUE	JN	JN
09/03/25	SIGNS REVISION	JN	JN

K&B
TECHNICAL SOLUTIONS

P.O. Box 2529, Clackamas, OR 97015
Jack Nygard - (503) 544-5749
Jack_Nygaard@kbmail.net

COMCAST
Bart Sistik - Network Project Manager
Mobile: (425) 293-1340
Bart_Sistik@comcast.com

SHEET
3

PROJECT ID
CMEX-53347-24337

WHEN WORKING OVER OR NEAR SIDEWALKS: PROVIDE SPOTTERS TO HOLD PEDESTRIAN TRAFFIC UNTIL CONSTRUCTION CAN BE PAUSED, OR IT IS SAFE TO PASS THROUGH THE WORK ZONE.

ROAD WORK ALLOWED:

Monday - Thursday
10AM - 2PM

Call communications center at 253-287-4456 on day of work.
Request a job start inspection through the CityView portal.

Work shall immediately cease in the work zone for a pedestrian spotter, available at all times, to escort pedestrians around the work area.

Work shall immediately cease in the work zone for a pedestrian spotter, available at all times, to escort pedestrians around the work area.

The City-issued permit packet shall be posted at the job site and available to inspectors at all times.

Puyallup construction restriction zones and routes shall be in effect during special events in downtown Puyallup or at the Washington State Fair. No work is allowed in the public right-of-way as defined by the Puyallup "Construction Restriction Zone & Routes Map."

The applicant shall notify property owner(s) of blocked driveway(s) at least 24 hours in advance.

The applicant shall coordinate redundant traffic control devices with other traffic control plans authorized near this site.


PRFUP20260593



NOT TO SCALE

City of Puyallup
Development & Permitting Services
ISSUED PERMIT

Building	Planning
Engineering	Public Works
Fire	Traffic



BRADLEY HEIGHTS - 27TH AVE SE
206 27TH AVE SE
PUYALLUP, WA 98374
PROJECT: 2195948
TRAFFIC CONTROL PLAN

DESIGN BY K & B TECHNICAL SOLUTIONS

DATE	DESCRIPTION	DESIGNER	DRAWN
08/12/25	ORIGINAL ISSUE	JN	JN
09/03/25	SIGNS REVISION	JN	JN

K&B
TECHNICAL SOLUTIONS
P.O. Box 2529, Clackamas, OR 97015
Jack Nygard - (503) 544-5749
Jack_Nygaard@kbmail.net

COMCAST
Bart Sisteck - Network Project Manager
Mobile: (425) 293-1340
Bart_Sisteck@comcast.com

SHEET
4
PROJECT ID
CMEX-53347-24337

WHEN WORKING OVER OR NEAR SIDEWALKS: PROVIDE SPOTTERS TO HOLD PEDESTRIAN TRAFFIC UNTIL CONSTRUCTION CAN BE PAUSED, OR IT IS SAFE TO PASS THROUGH THE WORK ZONE.