



917 134th Street SW
Suite B-3
Everett WA 98204
James Pan Project Manager
jamesp@redhawkfp.com (253)-330-0736

Fire Alarm System Battery Calculation Waiver Request

Project Name: Centeris L2 and L3 T.I.
Site Address: 1023 39th Ave SE. Puyallup, WA 98374
System Description: Fire alarm system modification

Dear Plan Reviewer

We are writing this letter to request a waiver on the battery calculation requirements.

The scope of work for this project is to add (1) addressable monitor module and (1) addressable relay module to the existing Notifier fire alarm control panel. Monitor module will draw max average standby at 300uA, and alarm max at 5.0mA. Addressable relay module will draw 230uA standby and 6.5mA alarm. It is not a significant modification to the existing system. Existing fire alarm panel addressable data loop is not full and operating under normal threshold. 5 ceiling horn strobes are removed and replaced by 5 wall mount horn strobes with same candela settings. All existing fire alarm field devices are to remain the same. All existing sequences of operations to remain the same.

Since we are not making significant modifications to the existing system, we are requesting calculation to be omitted on this project.

Thank you for your consideration.

Signed: _____
Red Hawk Fire Protection Representative

**Red Hawk Fire Protection
Everett Office
917 134th St. SW. Suite B-3
Everett, WA 98204
425-818-3313**