



This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.

1023 39TH AVE SE, PUYALLUP, WA 98374

DESIGNER OF RECORD

TAYLOR HARRIS
NICET III
FIRE ALARM SYSTEMS


CERTIFICATION #155559
EXPIRE DATE: 10-01-2027

FOR VERIFICATION, PLEASE VISIT: NICET.ORG/VERIFY

Taylor Harris

convergent

DRAWING: FA-0-1



SIGNATURE LOOP WIRING LIMITATIONS:

SIGNATURE DUAL DRIVER CONTROLLER MODULES SUPPORTS UP TO 250 INTELLIGENT SIGNATURE DETECTORS AND 250 INTELLIGENT SIGNATURE MODULES

WIRE LENGTH LIMITATIONS:

NON-TWISTED, NON-SHIELDED WIRE

16AWG - 200FT/1 & 4.02 OHMS/1000 FEET	
18AWG - 200FT/1 & 6.38 OHMS/1000 FEET	
DETECTORS ONLY	16AWG - 125 DETECTORS - 9.275'
MODULES ONLY	16AWG - 125 MODULES - 7.521'
DETECTORS AND MODULES	16AWG - 125 OF EACH - 3.608'
DETECTORS ONLY	18AWG - 125 DETECTORS - 5.839'
MODULES ONLY	18AWG - 125 MODULES - 4.486'
DETECTORS AND MODULES	18AWG - 125 OF EACH - 2.271'

TWISTED PAIR, NON-SHIELDED WIRE

16AWG - 500FT/1 & 4.02 OHMS/1000 FEET	
18AWG - 500FT/1 & 6.38 OHMS/1000 FEET	
DETECTORS ONLY	16AWG - 125 DETECTORS - 9.275'
MODULES ONLY	16AWG - 125 MODULES - 7.521'
DETECTORS AND MODULES	16AWG - 125 OF EACH - 3.608'
DETECTORS ONLY	18AWG - 125 DETECTORS - 5.839'
MODULES ONLY	18AWG - 125 MODULES - 4.486'
DETECTORS AND MODULES	18AWG - 125 OF EACH - 2.271'

TWISTED PAIR, SHIELDED WIRE

16AWG - 820FT/1 & 4.02 OHMS/1000 FEET	
18AWG - 820FT/1 & 6.38 OHMS/1000 FEET	
DETECTORS ONLY	16AWG - 125 DETECTORS - 6.098'
MODULES ONLY	16AWG - 125 MODULES - 6.098'
DETECTORS AND MODULES	16AWG - 125 OF EACH - 3.608'
DETECTORS ONLY	18AWG - 125 DETECTORS - 5.839'
MODULES ONLY	18AWG - 125 MODULES - 4.486'
DETECTORS AND MODULES	18AWG - 125 OF EACH - 2.271'

SIGNATURE DATA LOOP WIRING CLASS B ONLY

SERIES PARALLEL WIRING ACCEPTABLE

SIGNATURE DATA LOOP CLASS B ONLY

TAPPING AT EVERY DEVICE UNACCEPTABLE

SIGNATURE DATA LOOP WIRING CLASS B ONLY

TAPPING ACCEPTABLE

SIGNATURE DATA LOOP CLASS B ONLY

STAR TAPPING UNACCEPTABLE

SPEAKER CIRCUIT WIRING LIMITATIONS:

WIRE LENGTH LIMITATIONS:

THE MAXIMUM ALLOWABLE WIRE LENGTH IS THE FARTHEST DISTANCE THAT A SPEAKER CIRCUIT CAN EXTEND FROM THE AMPLIFIER TO THE LAST SPEAKER WITHOUT LOSING 0.5 DB OF SIGNAL. THE FOLLOWING ARE MAXIMUM DISTANCE BASED ON APPROXIMATE WATTAGE OF THE SPEAKER CIRCUIT. CIRCUIT LENGTHS ARE FURTHER BASED ON ORIGINATION OF A CIRCUIT FROM EITHER THE AMPLIFIER OR FROM THE C-1 MODULE.

ALLOWABLE LENGTH AT 25 WATTS, WITH 0.5 DB LOSS

- 16AWG - 20 WATTS - 231'
- 15AWG - 30 WATTS - 154'
- 14AWG - 40 WATTS - 118'

ALLOWABLE LENGTH AT 70 WATTS, WITH 0.5 DB LOSS

- 16AWG - 20 WATTS - 1815'
- 15AWG - 30 WATTS - 1210'
- 14AWG - 40 WATTS - 907'

NAC CIRCUIT (HORN, STROBE) WIRING LIMITATIONS:

FOR 24VDC SYSTEMS, MINIMUM DEVICE OPERATING VOLTAGE IS 16VDC. VOLTAGE DROP CALCULATIONS ARE BASED ON 16VDC AND POWER SUPPLY DE-RATED AND ON DESIGN TEMPERATURE. VOLTAGE DROP PER THE PRESCRIBED PERIOD OF STANDBY AND ALARM RING TIME. THE VOLTAGE DROP WILL LIMIT THE CIRCUITS CAPACITY IN ALMOST ALL CASES AND CURRENT CANNOT BE USED AS ONLY CIRCUIT WIRE LENGTH LIMITATION. ALTERATIONS TO CIRCUIT LENGTH FROM THOSE CALCULATED MAY CAUSE CIRCUITS TO BE OUT OF THE TOLERANCES GRANTED BY THE FIRE ALARM CODE. CHANGES TO DEVICE LOCATION OR CIRCUIT LENGTH SHALL BE COMMUNICATED TO THE CONVERTING TEAM.

NAC CIRCUIT WIRING AND ROUTING MUST NOT EXCEED WHAT IS SHOWN ON THE DESIGN DRAWINGS AND VOLTAGE DROP TEST IS PART OF MOST FIRE FINALS AND IS REQUIRED BY NFPA. A FAILED FIRE FINAL MAY REQUIRE REWIRING OF THE FAILED CIRCUITS.

WIRE RESISTANCE RATINGS USED FOR CALCULATIONS:

- 18AWG - 13 OHMS PER 1000'
- 16AWG - 8 OHMS PER 1000'
- 14AWG - 5.2 OHMS PER 1000'

EXAMPLE: 1.0 AMP CIRCUIT LOAD USING #14 WIRE = 409 FEET MAXIMUM.

CLASS B, STYLE 4 WIRING

CLASS A, STYLE 6 WIRING

SEPARATION OF CLASS A CIRCUITS - INSTALLATION EXCEPTIONS:

CLASS A OUTGOING AND RETURN CONDUCTORS, EXITING AND RETURNING TO THE CONTROL PANEL, ARE TO BE ROUTED SEPARATELY. THE MINIMUM RECOMMENDED SEPARATION IS 1 FT. VERTICALLY AND 4 FT. HORIZONTALLY. THE FOLLOWING EXCEPTIONS STILL DO NOT ELIMINATE THE 2ND PAIR OF WIRES. THEY ALLOW YOU TO USE A SINGLE RACEWAY AND ELIMINATE THE SEPARATION FOR THESE CONDITIONS:

1. WHEN MAXIMUM CABLE ENCLOSURE, OR RACEWAY IS LESS THAN 10 FEET. NO LIMIT TO NUMBER OF DEVICES.
2. UNLIMITED CONDUIT OR RACEWAY DROP TO AN INDIVIDUAL DEVICE.
3. UNLIMITED CONDUIT OR RACEWAY DROP TO A ROOM NOT EXCEEDING 1000 SQ. FT. NO LIMIT TO THE NUMBER OF DEVICES.

AS-BUILT / RECORD DRAWING REQUIREMENTS:

THE FOLLOWING INFORMATION SHOULD BE RECORDED ON A SEPARATE SET OF DRAWINGS FOR EACH PROJECT:

1. ANY CHANGES IN THE LOCATION OF ANY ASSOCIATED FIRE ALARM OR INTERFACE EQUIPMENT, CONTROL PANELS, ANNUNCIATORS, DETECTORS, CONTROL RELAYS, INPUT AND OUTPUT MODULES, TERMINAL CABINETS, ETC.
2. ANY CHANGES TO CIRCUIT WIRING, THIS INCLUDES DELETION OR ADDITIONAL WIRING RUNS, ANY RE-ROUTING OF CIRCUIT WIRING, ANY ADDITIONAL OR DELETIONS OF THE NUMBER, LOCATION, AND ORDER OF DEVICE WIRING ON A CIRCUIT.
3. ADDRESSES AND/OR LABELS FOR ALL ADDRESSABLE DEVICES.
4. CANCELLED LISTING OF DEVICES.
5. WATTAGE TAP SETTINGS OF ALL SPEAKER NOTIFICATION DEVICES.

ANY CHANGES SHALL BE DISCUSSED WITH CONVERGENT PROJECT MANAGER TO ENSURE SYSTEM AND CODE PARAMETERS ARE MET. CONVERGENT SHALL NOT BE HELD ACCOUNTABLE FOR CHANGES MADE WITHOUT APPROVAL.

THIS INFORMATION SHALL BE NEAT AND LEGIBLE WHEN PRESENTED TO THE TECHNICIAN AT THE CONCLUSION OF THE PROJECT. PLEASE NOTE CONTACT INFORMATION ON DRAWINGS FOR INDIVIDUALS WITH FAMILIARITY OF INSTALLATION IN THE EVENT QUESTIONS ARISE DURING THE CLOSEOUT PROCESS.

DATA NETWORK SPECIFICATIONS:

MAXIMUM ALLOWED VALUES BETWEEN ANY THREE NODES OF A NETWORK.

- RESISTANCE: 90 OHMS
- CAPACITANCE: 0.3 MICROFARADS
- DISTANCE: 5,000 FEET

THE FOLLOWING TABLE LISTS THE MAXIMUM CUMULATIVE CAPACITANCE FOR THE ENTIRE DATA NETWORK GIVEN VARIOUS WIRE SIZES AND TRANSMISSION RATES. MAXIMUM CUMULATIVE CAPACITANCE IS THE TOTAL CAPACITANCE OF ALL INSTALLED COPPER WIRE USED IN THE DATA NETWORK.

MAXIMUM CUMULATIVE CAPACITANCE IN MICROFARADS

18AWG - 1.4 @ 38.4K BAUD/2 @ 19.2K BAUD
16AWG - 1.8 @ 38.4K BAUD/2.1 @ 19.2K BAUD
14AWG - 2.1 @ 38.4K BAUD/2.4 @ 19.2K BAUD

CABLE PROPERTIES

CABLE AND AUDIO NETWORKS IN AN EST3 SYSTEM DO NOT REQUIRE THE USE OF SHIELDED CABLE, AND NETWORKS DESIGNED WITH TWISTED-PAIR CAN BE ABOUT TWICE AS LONG AS THOSE DESIGNED WITH SHIELDED CABLE. THE MAXIMUM LENGTH OF A DATA NETWORK VARIES WITH THE PROPERTIES OF THE WIRE USED. WIRE MANUFACTURERS TYPICALLY PROVIDE SPECIFICATIONS FOR WIRE RESISTANCE AND CAPACITANCE.

PATHWAY SURVIVABILITY LEVELS

PATHWAY SURVIVABILITY MUST MEET THE REQUIREMENTS OF NFPA 72, SECTION 12.4 FOR THE CORRESPONDING LEVEL OF SURVIVABILITY REQUIRED BY NFPA 72, CHAPTER 24. THE FOLLOWING IS A CONDENSED DESCRIPTION OF THE SURVIVABILITY LEVELS.

PATHWAY SURVIVABILITY LEVEL 0. LEVEL 0 PATHWAY SHALL NOT BE REQUIRED TO HAVE ANY PROVISIONS FOR PATHWAY SURVIVABILITY.

PATHWAY SURVIVABILITY LEVEL 1. PATHWAY INSTALLED IN FULLY SPRINKLED BUILDING MEETING THE REQUIREMENTS OF NFPA 13 WITH ANY INTERCONNECTING CONDUCTORS, CABLES OR OTHER PHYSICAL PATHWAYS NEEDED IN METAL RACEWAYS.

PATHWAY SURVIVABILITY LEVEL 2. PATHWAY SURVIVABILITY LEVEL 2 SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING:

- (1) 2-HOUR FIRE-RATED CABLE INTEGRITY (CI) CABLE
- (2) 2-HOUR FIRE-RATED CIRCUIT SYSTEM [ELECTRICAL CIRCUIT PROTECTIVE SYSTEMS]
- (3) 2-HOUR FIRE-RATED ENCLOSURE OR PROTECTED AREA
- (4) 2-HOUR PERFORMANCE ALTERNATIVES APPROVED BY THE AUTHORITY HAVING JURISDICTION

PATHWAY SURVIVABILITY LEVEL 3. SAME AS LEVEL 2 WITH ADDITION OF BEING IN A FULLY SPRINKLED BUILDING MEETING THE REQUIREMENTS OF NFPA 13.

CIRCUITS REQUIRING SURVIVABILITY BY NFPA 72

THE FOLLOWING CIRCUIT TYPES, WHEN USED ARE REQUIRED TO BE SURVIVABLE AS DESCRIBED BELOW. REFER TO NFPA 72, CHAPTER 24, FOR ADDITIONAL INFORMATION REGARDING THE FOLLOWING. THIS IS NOT A COMPLETE LIST AND IS MEANT TO SUPPLEMENT ANY NOTES PROVIDED ELSEWHERE IN OUR DRAWING PACKAGE. PLEASE CONTACT OUR CONVENT ENGINEERING DEPARTMENT WITH ANY QUESTIONS ON THE APPLICATION OF SURVIVABILITY.

- IN-BUILDING FIRE EMERGENCY VOICEALARM COMMUNICATIONS SHALL BE SURVIVABLE BASED ON ONE OF TWO CATEGORIES (24.3.6.4)
- ** FOR SYSTEMS EMPLOYING RELOCATION OR PARTIAL EVACUATION, A LEVEL 2 OR 3 PATHWAY SURVIVABILITY SHALL BE REQUIRED (24.3.6.4.1). FOR SYSTEMS THAT DO NOT EMPLOY RELOCATION OR PARTIAL EVACUATION, A LEVEL 0, LEVEL 1, LEVEL 2 OR LEVEL 3 PATHWAY SURVIVABILITY SHALL BE REQUIRED (24.3.6.4.2)
- TWO-WAY IN-BUILDING WIRED EMERGENCY COMMUNICATIONS SYSTEMS SHALL HAVE A PATHWAY SURVIVABILITY OF LEVEL 2 OR LEVEL 3 (24.3.6.7). THIS APPLIES TO STAIRWELL AND ELEVATOR LOBBY TWO-WAY AS REQUIRED BY INTERNATIONAL BUILDING CODE (IBC), SECTIONS, 403 AND 1009.8.
- TWO-WAY RADIO COMMUNICATIONS ENHANCED SYSTEMS (DAS) SHALL COMPLY WITH 24.3.6.8.1 THROUGH 24.3.6.8.4. **DAS IS NOT A COMPONENT OF THE FIRE ALARM DESIGN AND IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY**
- AREA OF REFUGE EMERGENCY COMMUNICATIONS SYSTEMS SHALL HAVE A PATHWAY SURVIVABILITY OF LEVEL 2 OR LEVEL 3 (24.3.6.9.1)
- CIRCUITS INTENDED TO TRANSMIT OR PERMITTANCE SHALL HAVE A PATHWAY SURVIVABILITY OF LEVEL 0, LEVEL 1, LEVEL 2 OR LEVEL 3 (24.3.6.9.2)

FOR SMOKE CONTROL SPECIFIC SURVIVABILITY REQUIREMENTS, REFER TO THE SMOKE CONTROL SECTION OF THE DRAWING. REQUEST CONVEYANT WIRE PROVIDE EQUIVALENT SUBSTITUTIONS FOR ANY SPECIFIED CABLE, ANY CABLE SUBSTITUTED MUST HAVE EQUAL TO OR BETTER PROPERTIES TO THE CABLE SPECIFIED IN OUR WIRE LEGEND.

EACH MAIN FIRE ALARM PANEL REQUIRES (1) 120VAC, 20AMP DEDICATED CIRCUIT.

EACH NAC BOOSTER PANEL REQUIRES (1) 120VAC, 15AMP DEDICATED CIRCUIT.

IN BUILDINGS EMPLOYING EMERGENCY STANDBY POWER SYSTEMS, THE FIRE ALARM SHALL BE SUPPLIED WITH EMERGENCY POWER. THIS IS REQUIRED IN HIGH-RISE AND SMOKE CONTROL APPLICATIONS. ALL OTHER APPLICATIONS ARE SUBJECT TO LOCAL BUILDING AND ELECTRICAL CODES.


WHERE THE FIRE ALARM SYSTEM IS CONNECTED TO EMERGENCY POWER, THE FIRE ALARM SYSTEM MONITORS THE GENERATOR FOR RUNNING, FUEL LOW AND TROUBLE STATES.

FOR ADDITIONAL DETAILS, REFER TO NFPA 72, CHAPTER 10

SEQUENCE OF OPERATIONS		SEQUENCE OF OPERATIONS															
		ACTIVATION OF LOCAL ALARM SIGNAL AT FACP (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATION OF LOCAL SUPERVISORY SIGNAL AT FACP (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATION OF LOCAL TROUBLE SIGNAL AT FACP (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATION OF LOCAL ALARM SIGNAL AT ANNUNCIATOR (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATION OF LOCAL SUPERVISORY SIGNAL AT ANNUNCIATOR (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATION OF LOCAL TROUBLE SIGNAL AT ANNUNCIATOR (LCD DISPLAY & AUDIBLE INDICATION)	ACTIVATE ALARM OUTPUT TO BUILDING FACP	ACTIVATE SUPERVISORY OUTPUT TO BUILDING FACP	ACTIVATE TROUBLE OUTPUT TO BUILDING FACP	ACTIVATE AUDIBLE & VISIBLE DEVICES VIA INTERFACE WITH BUILDING FACP	GENERAL ALARM SIGNAL TO ACCESS/SECURITY SYSTEM	PRE-ACTION SOLENOID ACTIVATION	CLOSE ALL FIRE/SMOKE DAMPERS			
SEQUENCE OF OPERATIONS	SMOKE DETECTOR	X			X			X			X	X		X			
	VESDA DETECTOR - URGENT FAULT			X			X		X								
	VESDA DETECTOR - ACTION		X			X		X									
	VESDA DETECTOR - ALERT		X			X		X									
	VESDA DETECTOR - FIRE 1	X			X			X			X	X	X	X			
	VESDA DETECTOR - FIRE 2	X			X			X			X	X	X	X			
	MANUAL PULL STATION	X			X			X			X	X		X			
	GENERAL TROUBLE CONDITION			X			X		X								
	GENERAL SUPERVISORY CONDITION		X			X			X								
	PRE-ACTION WATERFLOW/ALARM SWITCH	X			X			X			X	X		X			
	PRE-ACTION TAMPER SWITCH		X			X			X								
	PRE-ACTION LOW AIR SWITCH		X			X			X								
	PRE-ACTION RELEASE CIRCUIT DISCONNECT SWITCH		X			X			X								
	FACP - LOSS OF PRIMARY POWER			X			X			X							

NOTE: THE EXISTING SEQUENCE OF OPERATIONS IS NOT AFFECTED BY THE CHANGES IN THIS PROJECT

IF DRAWING IS NOT 30" x 42" IT IS A SCALED COPY



 **LEVEL 2 - EAST**
0 4' 8' 16'
SCALE: 1/8"=1'-0"


convergent

1100 Oakesdale Ave SW, Renton, Washington 98057
Phone: 425-272-2250 Fax: 425-251-0949

This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.

**City of Puyallup
Development & Permitting Services
ISSUED PERMIT**

Building	Planning
Engineering	Public Works
Fire	Traffic



KEY PLAN

REV	JOB - DESCRIPTION	DATE	BY
-	ISSUED FOR PERMIT	06-01-2026	TH
1	VEDSA REVISIONS	06-03-2026	TH


DRAWN BY: TAYLOR H.
PROJECT DESIGNER: TAYLOR H.
PROJECT MANAGER: CHARITY P.
JOB NUMBER: 10001-00000000
SCALE: AS SHOWN **DATE:** 06-01-2026

CENTERIS SHDC
LEVEL 2 ROW D VESDA
1023 39TH AVE SE
PUYALLUP, WA 98374


LEVEL 2 - EAST
FIRE ALARM SYSTEM

DRAWING:
FA-1-2.2

IF DRAWING IS NOT 30" x 42" IT IS A SCALED COPY



This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.



REV	JOB - DESCRIPTION	DATE	BY
-	ISSUED FOR PERMIT	06-01-2026	TH
1	VEDSA REVISIONS	06-03-2026	TH


DRAWN BY:	TAYLOR H.
PROJECT DESIGNER:	TAYLOR H.
PROJECT MANAGER:	CHARITY P.
JOB NUMBER:	0001-00000000
SCALE:	AS SHOWN
DATE:	06-01-2026

CENTERIS SHDC
LEVEL 2 ROW D VESDA
1023 39TH AVE SE
PUYALLUP, WA 98374


TYPICAL RISER
FIRE ALARM SYSTEM

FA-2-1

IF DRAWING IS NOT 30" x 42" IT IS A SCALED COPY



This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.



REV	JOB# - DESCRIPTION	DATE	BY
-	ISSUED FOR PERMIT	06-01-2026	TH
1	VEDSA REVISIONS	06-03-2026	TH

DRAWN BY:	TAYLOR H.
PROJECT DESIGNER:	TAYLOR H.
PROJECT MANAGER:	CHARITY P.
JOB NUMBER:	0001-00000000
SCALE:	AS SHOWN
DATE:	06-01-2026

CENTERIS SHDC
LEVEL 2 ROW D VESDA
1023 39TH AVE SE
PUYALLUP, WA 98374

DEVICE DETAILS
FIRE ALARM SYSTEM

DRAWING:
FA-4-1

IF DRAWING IS NOT 30" x 42" IT IS A SCALED COPY


APS6A NAC N1 - Battery Calculation							
POWER SUPPLY DESIGNATOR		NAC	POWER SUPPLY PREFIX		N1	STANDBY DURATION REQUIRED (HRS)	4
PANEL LOCATION		LEVEL 2 - SERVER ROOM 223C				ALARM RING TIME REQUIRED (MIN)	15
AREA SERVED		LEVEL 2 - SERVER ROOM 223C				SPARE CAPACITY (%)	25
POWER SUPPLY BASE LOAD/AUXILIARY POWER OUTPUT							
PART #	DESCRIPTION	QTY.	SUPV. CURRENT (mA)		ALARM CURRENT (mA)		
			EACH	TOTAL	EACH	TOTAL	
APS6A	AUXILIARY BOOSTER POWER SUPPLY	1	70	70	270	270	
APS AUX	BPS CIRCUITS SET TO AUX OUTPUT	1	35	35	35	35	
NAC/AUX OUTPUTS							
NAC/AUX OUTPUTS		DESCRIPTION	SUPV. CURRENT (mA)		ALARM CURRENT (mA)		
CKT. #	TYPE		TOTAL		TOTAL		
1	AUX. POWER	ASD-01 24V POWER	360		390		
2	SPARE	SPARE	0		0		
3	SPARE	SPARE	0		0		
4	SPARE	SPARE	0		0		
SUBTOTAL SUPERVISORY CURRENT (AMPS):							0.465
TOTAL SUPERVISORY CURRENT WITH STANDBY (AMPS):							1.860
SUBTOTAL ALARM CURRENT (AMPS):							0.695
TOTAL ALARM CURRENT WITH ALARM RING TIME (AMPS):							0.174
SPARE CAPACITY:							25%
TOTAL AMP HOUR REQUIRED (AMPS):							2.542
BATTERY SIZE REQUIRED (AH):							7
BATTERY CABINET PROVIDED:							NO

CIRCUIT N1-1 AUX. POWER SUMMARY		CIRCUIT TYPE	AUX. POWER			
		DESCRIPTION	ASD-01 24V POWER			
POWER SUPPLY INFORMATION			CABLE PROPERTIES			
NOMINAL STARTING VOLTAGE (Vdc)	19.7	LOAD FACTOR (LF)	0.59	WIRE GAUGE (AWG)	14	
MINIMUM DEVICE VOLTAGE (Vdc)	15	VOLTAGE W/LOAD FACTOR (VDC)	19.4699	Ω PER 1K FEET (OHMS)	3.07	
TOTAL SUPERVISORY CURRENT (AMPS)	0.36	TOTAL ALARM CURRENT (AMPS)	0.390			
PART #	DEVICE	QTY	STANDBY CURRENT		ALARM CURRENT	
			(mA)		(mA)	
EACH			TOTAL	EACH	TOTAL	
VEP-A00-1P	VESDA-E, ASPIRATOR @ FIXED RPM	1	360	360	390	390

convergent

1100 Oakesdale Ave SW, Renton, Washington 98057
Phone: 425-272-2250 Fax: 425-251-0949

This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.



REV	JOB# - DESCRIPTION	DATE	BY
-	ISSUED FOR PERMIT	06-01-2026	TH
1	VESDA REVISIONS	06-03-2026	TH

DRAWN BY:	TAYLOR H.
PROJECT DESIGNER:	TAYLOR H.
PROJECT MANAGER:	CHARITY P.
JOB NUMBER:	0901-00009990
SCALE:	AS SHOWN
DATE:	06-01-2026

CENTERIS SHDC
LEVEL 2 ROW D VESDA
1023 39TH AVE SE
PUYALLUP, WA 98374

CALCULATIONS
FIRE ALARM SYSTEM

DRAWING:
FA-5-1

1. DIMENSIONS PROVIDED ON PLANS ARE PRECISE TO $\pm 1/3"$
2. DEVIATIONS FROM PLANS DUE TO FIELD CONDITIONS MUST BE REDLINED AND RETURNED TO CONTRACTOR PRIOR TO CONCRETE POURING. VARIATIONS GREATER THAN 5' OR THE ADDITION OF ELBOWS MUST BE REPORTED BACK TO CONVEGNIPT PRIOR TO COMPLETION OF INSTALLATION FOR RE-CALCULATION.
3. SUPPORT PIPE ON NO GREATER THAN 5 FOOT CENTERS FOR CEILING INSTALLATION.
4. GLUE PIPE WITH THE APPROPRIATE ADHESIVE ON THE OUTSIDE OF THE PIPE. DO NOT ALLOW ANY ADHESIVE INSIDE PIPE.
5. DO NOT GLUE PIPE INTO THE VESDA DETECTOR MANIFOLD.
6. REMOVE ALL DUST AND SHAVINGS FROM INSIDE PIPE AND SAMPLING HOLES PRIOR TO INSTALLATION.
7. VERIFY HOLE LOCATION AND SIZE ACCORDING TO VESDA CALCULATIONS BEFORE DRILLING.
8. ORIENT DRILL PERPENDICULAR TO PIPE TO ENSURE HOLES ARE DRILLED STRAIGHT AND NOT AT AN ANGLE.
9. INSTALL LABELS AT EACH SAMPLING HOLE.
10. INSTALL PIPE LABELS EVERY 20' AND AT EVERY CHANGE OF DIRECTION PER NFPA 72.
11. NOTIFY CONVEGNIPT OF ANY FIELD RELATED OBSTRUCTIONS WHICH COULD EFFECT PIPE PLACEMENT OR ABILITY FOR SOMEONE TO THE REACH SAMPLING HOLES.
12. NOTIFY CONVEGNIPT PRIOR TO MAKING ANY FIELD CHANGES TO THE PIPE NETWORK. CHANGES WILL RESULT IN CHANGES TO THE SAMPLING HOLE SIZES. DO NOT DRILL HOLES, OR ONLY DRILL 5/64" PILOT HOLES ONLY. IF PIPING CHANGES ARE REQUIRED PRIOR TO RECALCULATING.
13. MAINTAIN A LINE SET OF INSTALLATIONS DRAWINGS SHOWING ANY MODIFICATIONS TO THE PIPE NETWORK AND DELIVER TO CONVEGNIPT PRIOR TO FINAL TESTING.
14. ALL VESDA PIPING SHALL BE 3/4" CPVC, UNLESS OTHERWISE NOTED
15. REFERENCE VESDA PIPING CALCULATIONS FOR PROGRAM SETTINGS REQUIRED TO CONFIGURE THE DETECTOR.

 =VESDA SAMPLING HOLE
 =VESDA DETECTOR HEAD
 =TEST POINT BALL VALVE
 =VESDA PIPE
 =1-PIPE DETECTOR




0 8' 16' 32'

SCALE: 1/16"=1'-0"






MOUNT NEW VESDA PIPING TO UNDERSIDE OF THE SERVER ROOM CEILING
ABOVE CEILING VESDA TO REMAIN.

DRAWING: FA-6-1


F DRAWING IS NOT 30" x 42" IT IS A SCALED COPY

This document and the information/depictions contained/shown is the exclusive property of Convergent Technologies LLC and shall be handled as proprietary and confidential information and must be returned upon request. This document cannot be reproduced by any means without the written authorization of Convergent Technologies LLC.

[illegible]

Section 1																	
Pipe Diameter: 0.674																	
#	Start Node	Distance ft	Direction to Node	Relative to Node	Node Diameter in	Capillary Length ft	Transport Time sec	Pressure Pa	Flow m³/sec	Flow % of Total	Node Sensitivity Pa	Pipe Diameter in	Capillary Diameter in	Intersection Pressure Pa	Target Gas Concentration %	ACL Gas Concentration %	ACL Methane Concentration %
1	Start Node	102' 0"	0.7	1	0.674												
1	Section 1	102' 0"	0.7	1	0.674		10	86' 4.1	7.2	1.863	0.874						
2	Section 2	104' 12"	0.8	1	0.674		10	84' 6.6	6.1	1.703	0.874						
3	Section 3	104' 36"	0.8	1	0.674		11	86' 4.1	6.4	1.703	0.874						
4	Section 4	104' 112"	0.8	1	0.674		21	66' 4.1	6.1	1.703	0.874						
5	Section 5	104' 128"	0.8	1	0.674		27	56' 3.6	5.6	1.452	0.874						
6	Section 6	104' 144"	0.8	1	0.674		35	52' 1.7	5.7	1.402	0.874						
7	Section 7	104' 144"	0.8	1	0.674		40	56' 3.6	5.6	1.452	0.874						
8	Section 8	Endcap	102' 0"	1	0.674		40	50' 4.3	6.0	1.202	0.874						

Section 2																
Pipe Diameter 5.076																
#	Band ID	Distance ft	Relative to ft	Direction ft	Hole Diameter in	Capillary Length ft	Transport Time sec	Pressure Psi	Flow Rate in³/sec	Hole Straddle ft	Pipe Diameter in	Capillary Diameter in	Intersection Pressure	Target Gas Concentration	ACL Gas Threshold	ACL Alarm Threshold
1	Band 00	10.0	0.7		5.064											
1	Band 01	14.0	0.7		5.064		10	86	4.1	7.2	1.610	0.874				
2	Band 02	18.0	0.7		5.064		15	14	4.4	6.1	1.215	0.874				
3	Band 03	22.0	0.7		5.064		20	46	4.3	6.4	1.500	0.874				
4	Band 04	26.0	0.7		5.064		25	66	4.0	6.1	1.374	0.874				
5	Band 05	30.0	0.7		5.064		30	66	3.9	5.9	1.420	0.874				
6	Band 06	34.0	0.7		5.064		35	66	3.7	5.7	1.460	0.874				
7	Band 07	38.0	0.7		5.064		40	50	3.6	5.6	1.460	0.874				
8	Band 08	42.0	0.7		5.064		45	50	4.3	6.1	1.260	0.874				
9	Band 09	46.0	0.7		5.064		50	50	4.3	6.1	1.260	0.874				
10	Band 10	50.0	0.7		5.064		55	50	4.3	6.1	1.260	0.874				
11	Band 11	54.0	0.7		5.064		60	50	4.3	6.1	1.260	0.874				
12	Band 12	58.0	0.7		5.064		65	50	4.3	6.1	1.260	0.874				
13	Band 13	62.0	0.7		5.064		70	50	4.3	6.1	1.260	0.874				
14	Band 14	66.0	0.7		5.064		75	50	4.3	6.1	1.260	0.874				
15	Band 15	70.0	0.7		5.064		80	50	4.3	6.1	1.260	0.874				
16	Band 16	74.0	0.7		5.064		85	50	4.3	6.1	1.260	0.874				
17	Band 17	78.0	0.7		5.064		90	50	4.3	6.1	1.260	0.874				
18	Band 18	82.0	0.7		5.064		95	50	4.3	6.1	1.260	0.874				
19	Band 19	86.0	0.7		5.064		100	50	4.3	6.1	1.260	0.874				
20	Band 20	90.0	0.7		5.064		105	50	4.3	6.1	1.260	0.874				
21	Band 21	94.0	0.7		5.064		110	50	4.3	6.1	1.260	0.874				
22	Band 22	98.0	0.7		5.064		115	50	4.3	6.1	1.260	0.874				
23	Band 23	102.0	0.7		5.064		120	50	4.3	6.1	1.260	0.874				
24	Band 24	106.0	0.7		5.064		125	50	4.3	6.1	1.260	0.874				
25	Band 25	110.0	0.7		5.064		130	50	4.3	6.1	1.260	0.874				
26	Band 26	114.0	0.7		5.064		135	50	4.3	6.1	1.260	0.874				
27	Band 27	118.0	0.7		5.064		140	50	4.3	6.1	1.260	0.874				
28	Band 28	122.0	0.7		5.064		145	50	4.3	6.1	1.260	0.874				
29	Band 29	126.0	0.7		5.064		150	50	4.3	6.1	1.260	0.874				
30	Band 30	130.0	0.7		5.064		155	50	4.3	6.1	1.260	0.874				
31	Band 31	134.0	0.7		5.064		160	50	4.3	6.1	1.260	0.874				
32	Band 32	138.0	0.7		5.064		165	50	4.3	6.1	1.260	0.874				
33	Band 33	142.0	0.7		5.064		170	50	4.3	6.1	1.260	0.874				
34	Band 34	146.0	0.7		5.064		175	50	4.3	6.1	1.260	0.874				
35	Band 35	150.0	0.7		5.064		180	50	4.3	6.1	1.260	0.874				

[illegible][illegible]

DRAWN BY:	TAYLOR H.
PROJECT DESIGNER:	TAYLOR H.
PROJECT MANAGER:	CHARITY P.
JOB NUMBER:	US01-J00299650
SCALE: AS SHOWN	DATE: 06-01-2026

CENTERIS SHDC
LEVEL 2 ROW D VESDA
1023 39TH AVE SE
PUYALLUP, WA 98374

VESDA DETAILS

FIRE ALARM SYSTEM

DRAWING: FA-6-2