

## PRELIMINARY TECHNICAL INFORMATION REPORT

## Fortress-Puyallup

240 15<sup>th</sup> Street SE Puyallup, Washington 98372

Prepared for: CREF3 Puyallup, LLC 11611 San Vicente Blvd, 10<sup>th</sup> Floor Los Angeles, CA 90049



Revised August 31, 2023 Revised May 24, 2023 October 24, 2022 Our Job No. 22085

### **TABLE OF CONTENTS**

1.0	PROJECT OVERVIEW		
	Figure 1 – Vicinity Map Figure 2 – Existing Conditions Map		
	Figure 3 – Critical Areas Map		
	Figure 4 – FEMA Flood Map		
2.0	MINIMUM REQUIREMENTS SUMMARY		
	Figure 5 - Minimum Requirements Flowchart		
3.0	OFF-SITE ANALYSIS		
	Figure 6 – Downstream Drainage Map		
4.0	FLOW CONTROL AND WATER QUALITY FACILITY ANALYSIS AND DESIGN		
	4.1 Existing Site Hydrology		
	4.2 Developed Site Hydrology		
	4.3 Flow Control System		
	4.4 Water Quality System		
	4.5 Wetland Protection		
	Figure 7 – Flow Control Calculations		
5.0	CONVEYANCE SYSTEM ANALYSIS AND DESIGN		
6.0	SPECIAL REPORTS AND STUDIES		
	Figure 8 - Geotechnical Report		
7.0	OTHER PERMITS		
8.0	CSWPPP ANALYSIS AND DESIGN		
9.0	BOND QUANTITIES, FACILITY SUMMARIES, AND DECLARATION OF COVENANT		

10.0 OPERATIONS AND MAINTENANCE MANUAL

## **Tab 1.0**

#### 1.0 PROJECT OVERVIEW

The proposed Fortress - Puyallup project is located on a 7.84-acre site located in the City of Puyallup, Washington. The project address is 240 15<sup>th</sup> Street SE, Puyallup, WA 98372 with the parcel numbers being 0420274126, 7845000161, and 7845000170. The site is located northwest of the intersection of 15<sup>th</sup> Street SE and East Pioneer Way. The current zoning of the project site is Limited Manufacturing (ML). Please see the enclosed Figure 1 - Vicinity Map for additional location information.

The existing site contains a cold storage warehouse that is in the process of demolition, a separate industrial building, and an office building. The majority of the site has been developed with buildings and pavement, though a small portion of the site is an undeveloped field. The property is not currently being used other than for demolition activity. There are three driveways serving the site off of 15<sup>th</sup> Street SE. The site is relatively flat and does not contain any steep slopes. The developed portion of the site drains to existing stormwater catch basins and piping, which discharge into the public stormwater systems in East Main Street and 15<sup>th</sup> Street SE, ultimately discharging to Deer Creek near the Puyallup River. See Figure 2 for a map of existing site conditions.

The site is not within a flood zone. See Figure 4 for a FEMA flood map. According to Puyallup GIS mapping, the project does not contain any wetlands or potential landslide hazards. The public stormwater system in 15<sup>th</sup> Street SE discharges to a wetland. See Figure 3 for a critical areas map.

The proposal for this development is to construct one warehouse building, new pavement, associate utilities, and landscaping. The developed runoff from the west portion of the site will be collected and conveyed to both water quality and detention vaults prior to discharge into the public stormwater system draining to East Main Street. The east part of the site will be collected and discharged through a water quality vault to the 15th Street SE system that drains to a wetland. This basin has been sized to match the existing conditions to match existing flows to the wetland. Stormwater treatment will be provided upstream of the detention vault by DOE-approved underground treatment vaults (Oldcastle Biopods).

This site has some incidental run-on from adjacent property that is accounted for by the proposed stormwater improvements.

Figure 1 Vicinity Map




Figure 2
Existing
Conditions
Map






Figure 3 Critical Areas Map



### **City of Puyallup Public Data Viewer**




Figure 4
FEMA Flood
Map

## National Flood Hazard Layer FIRMette




Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020



#### Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

an authoritative property location.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 9/29/2022 at 5:18 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

## **Tab 2.0**

#### 2.0 MINIMUM REQUIREMENTS SUMMARY

Per Figure 1-3.1 of the 2019 Department of Ecology Stormwater Management Manual for Western Washington (the Manual), minimum requirements #1 through #9 apply to this project. Minimum requirements (MRs) as listed in the Manual are listed in this section.

MR1 - Preparation of Stormwater Site Plans.

This report and the prepared construction drawings satisfy this requirement.

MR2 - Construction Stormwater Pollution Prevention Plan (SWPPP)

A SWPPP will be prepared and submitted to the City with the permit submittal plans.

MR3 - Source Control of Pollution

Source Control BMPs will be selected in accordance with Volume IV of the Manual once the property has been leased and actual commercial activities are able to be identified. Good housekeeping measures will be used to keep the site clean and to reduce the chance that stormwater will come into contact with pollutants.

MR4 - Preservation of Natural Drainage Systems and Outfalls

In the existing condition the site discharges into the public stormwater systems in East Main Street and 15<sup>th</sup> Street SE, ultimately discharging to Deer Creek and then to the Puyallup River. These discharge locations will be maintained.

MR5 - On-Site Stormwater Management

To satisfy this Minimum Requirement, the BMPs given by List #2 are evaluated for feasibility. In accordance with the geotechnical report prepared for this project, infiltration of stormwater on the project site is not feasible. Dispersion BMPs are also infeasible due to the absence of available dispersion areas on the project site. Therefore, the project proposes to manage stormwater by implementing BMP T5.13 to all landscape areas and by conveying onsite runoff from the western portion of the site to the proposed stormwater treatment and detention facilities.

MR6 - Runoff Treatment

The use of OldCastle Biopods is proposed. These are proprietary underground treatment vaults that have received a General Use Level Designation (GULD) approval from the DOE. Sizing is not provided with this preliminary report, but it will be provided with the final report included with the permit submittal.

MR7 - Flow Control

The project will meet the duration matching requirement. Flow control will be provided by the proposed detention vault. See Section 4.3 of this report for more information.

MR8 - Wetlands Protection

Some runoff from the project site enters the public stormwater system in 15<sup>th</sup> Street SE, which ultimately discharges to Deer Creek at a location where it is mapped as wetlands per City GIS. In order to protect this wetland, the flow to this discharge location will be maintained. The eastern portion of the site will continue to discharge to the wetland. This area is largely impervious in the existing condition so flows will be matched by discharging the eastern portion of the site without

detention. See Figure 5 for the Flow Chart for Determining Wetland Protection Level Requirements, and see Section 4.5 for additional narrative.

### MR9 - Operation and Maintenance

An operations and maintenance manual will be completed and submitted as a separate document with the permit construction plans.

Figure 5
Minimum
Requirements
Flowchart

Figure I-3.1: Flow Chart for Determining Requirements for New Development




Figure I-3.2: Flow Chart for Determining Requirements for Redevelopment




Figure III-1.1: Runoff Treatment BMP Selection Flow Chart





Figure I-3.5: Flow Chart for Determining Wetland Protection Level
Requirements



## **Tab 3.0**

### 3.0 OFF-SITE ANALYSIS


The project site drains to existing stormwater catch basins and piping, which discharge into the public stormwater systems in East Main Street and 15<sup>th</sup> Street SE, ultimately discharging to Deer Creek near the Puyallup River. The outfall from the 15<sup>th</sup> Street SE system is location within an area classified as wetland per City of Puyallup GIS. See Figure 6. We are not aware of any known drainage issues with the existing downstream drainage systems.

Figure 6 Downstream Drainage Map



## **City of Puyallup Public Data Viewer**

## 



## **Tab 4.0**

#### 4.0 FLOW CONTROL AND WATER QUALITY FACILITY ANALYSIS AND DESIGN

#### 4.1 Existing Site Hydrology

For the purpose of flow control modeling, the predeveloped site condition for the west portion of the site (5.09 acres) is assumed to be forested. To meet the wetland protection guidelines, the eastern portion of the site and offsite improvements (2.96 acres) is modeled as the current conditions which is mostly impervious. In accordance with soil characteristics described in the geotechnical report prepared for this project, existing site soils are modeled as Type C. The total area of the predeveloped basin is 8.05 acres. See Figure 7.

Basin ID	Existing Basin Area	
West Basin	5.09 ac	Forested
East Basin	2.96 acres	0.51 ac lawn
		2.45 ac impervious

#### 4.2 Developed Site Hydrology

The proposed development will convey runoff from the west portion of the site (5.31 acres) to the proposed detention vault using the proposed catch basins and gravity conveyance piping. The eastern portion of the site (2.52 acres) will discharge through a water quality unit prior to discharge. The pervious surface is modeled as pasture in accordance with BMP T5.13.

Basin ID	Basin Area	
West Basin	5.31 ac	4.59 ac impervious
		0.72 ac pasture
East Basin 2.75 acres		2.25 ac impervious
		0.50 ac pasture

### 4.3 Flow Control System

In accordance with the Manual the duration matching requirement that must be satisfied for flow control is: Stormwater discharges shall match developed discharge durations to predeveloped durations for the range of pre-developed discharge rates from 50% of the 2-year peak flow up to the full 50-year peak flow. The proposed detention vault has been modeled using WWHM, a DOE approved continuous rainfall runoff modeling program, to ensure that this requirement is met. See Figure 7 for modeling inputs and outputs. The discharge to the wetland requires flows to match existing/current conditions. Flow control is not necessary for the discharge to the wetland in order to match existing flows.

#### 4.4 Water Quality System


For commercial development, enhanced water quality treatment is required. OldCastle Bipods are proposed to provide the required treatment. These units have received a General Use Level


Designation (GULD) approval from the DOE. Sizing is not provided with this preliminary report, but it will be provided with the final report included with the permit submittal.

#### 4.5 Wetland Protection


The discharge to Deer Creek for the eastern basin is shown as a wetland per the Puyallup critical areas map. It is assumed that the wetland requires General Protection, Protection from Pollutants and Wetland Hydroperiod Protection (Method 2). The discharge from the east basin will be discharged through an enhanced treatment water quality unit prior to discharge to protect the wetland from pollutants. The basin to the wetland was sized to match the existing conditions of the site, which is mostly impervious. Per I-3.4.8 MR8: Wetlands Protection from the DOE Stormwater Management Manual for Western Washington, when the flow control and wetlands protections requirements cannot bot be met, the wetlands protection is the overriding concern. In order to match current discharge conditions to the wetland, flow control matching forested conditions is not possible or flows to the wetland would be overly reduced. See East Basin - Wetland recharge in Figure 7 to see flow durations are being matched for the basin that flows to the wetland.

Figure 7
Flow Control
Calculations







# West Basin - Predeveloped Conditions




# West Basin - Proposed Conditions




## West Basin - Detention Vault




## West Basin -Flow Duration



## West Basin -Flows



# West Basin - Detention Vault Stage



# WWHM2012 PROJECT REPORT

# General Model Information

Project Name: 22085-6 ft live

Site Name: Site Address:

City:

 Report Date:
 7/7/2023

 Gage:
 40 IN EAST

 Data Start:
 10/01/1901

 Data End:
 09/30/2059

 Timestep:
 15 Minute

Precip Scale: 1.000 Version Date: 2019/09/13

Version: 4.2.17

#### **POC Thresholds**

Low Flow Threshold for POC1: 50 Percent of the 2 Year

High Flow Threshold for POC1: 50 Year

# Landuse Basin Data Predeveloped Land Use

#### Basin 1

Bypass: No

GroundWater: No

Pervious Land Use acre C, Forest, Flat 5.09

Pervious Total 5.09

Impervious Land Use acre

Impervious Total 0

Basin Total 5.09

Element Flows To:

Surface Interflow Groundwater

22085-6 ft live 7/7/2023 9:32:57 AM Page 3

### Mitigated Land Use

#### Basin 1

Bypass: No

GroundWater: No

Pervious Land Use acre C, Pasture, Flat 0.72

Pervious Total 0.72

Impervious Land Use acre PARKING FLAT 4.59

Impervious Total 4.59

Basin Total 5.31

Element Flows To:

Surface Interflow Groundwater

Vault 1 Vault 1

# Routing Elements Predeveloped Routing

#### Mitigated Routing

#### Vault 1

Width: 152 ft. Length: 160 ft. Depth: Discharge Structure 6.9 ft.

Riser Height: 5.9 ft. Riser Diameter: 12 in.

Notch Type: Notch Width: Rectangular 0.100 ft. Notch Height: 1.700 ft.

1.07 in. Elevation:0 ft. Orifice 1 Diameter:

Element Flows To:


Outlet 1 Outlet 2


#### Vault Hydraulic Table

Stage(feet)	Area(ac.)	Volume(ac-ft.)	Discharge(cfs)	
0.0000	0.558	0.000	0.000	0.000
0.0767	0.558	0.042	0.008	0.000
0.1533	0.558	0.085	0.012	0.000
0.2300	0.558	0.128	0.014	0.000
0.3067	0.558	0.171	0.017	0.000
0.3833	0.558	0.214	0.019	0.000
0.4600	0.558	0.256	0.021	0.000
0.5367	0.558	0.299	0.022	0.000
0.6133	0.558	0.342	0.024	0.000
0.6900	0.558	0.385	0.025	0.000
0.7667	0.558	0.428	0.027	0.000
0.8433	0.558	0.470	0.028	0.000
0.9200	0.558	0.513	0.029	0.000
0.9967	0.558	0.556	0.031	0.000
1.0733	0.558	0.599	0.032	0.000
1.1500	0.558	0.642	0.033	0.000
1.2267	0.558	0.684	0.034	0.000
1.3033	0.558	0.727	0.035	0.000
1.3800	0.558	0.770	0.036	0.000
1.4567	0.558	0.813	0.037	0.000
1.5333	0.558	0.856	0.038	0.000
1.6100	0.558	0.898	0.039	0.000
1.6867	0.558	0.941	0.040	0.000
1.7633	0.558	0.984	0.041	0.000
1.8400	0.558	1.027	0.042	0.000
1.9167	0.558	1.070	0.043	0.000
1.9933	0.558	1.112	0.043	0.000
2.0700	0.558	1.155	0.044	0.000
2.1467	0.558	1.198	0.045	0.000
2.2233	0.558	1.241	0.046	0.000
2.3000	0.558	1.284	0.047	0.000
2.3767	0.558	1.326	0.047	0.000
2.4533	0.558	1.369	0.048	0.000
2.5300	0.558	1.412	0.049	0.000
2.6067	0.558	1.455	0.050	0.000
2.6833	0.558	1.498	0.050	0.000
2.7600	0.558	1.540	0.051	0.000

4.0633 0.558 2.268 0.062 0.00	00 00 00 00 00 00 00 00 00 00 00 00
4.1400 0.558 2.311 0.063 0.00	00
4.2167       0.558       2.354       0.064       0.00         4.2933       0.558       2.397       0.073       0.00         4.2720       0.558       2.397       0.007       0.007	00
4.3700       0.558       2.439       0.087       0.00         4.4467       0.558       2.482       0.104       0.00         4.5000       0.558       0.558       0.104       0.00	00
4.5233       0.558       2.525       0.123       0.00         4.6000       0.558       2.568       0.144       0.00	00
4.6767       0.558       2.611       0.166       0.00         4.7533       0.558       2.653       0.189       0.00	
4.8300 0.558 2.696 0.213 0.00	00
4.9067       0.558       2.739       0.238       0.00         4.9833       0.558       2.782       0.264       0.00	
5.0600 0.558 2.825 0.289 0.00	00
5.1367	
5.2133 0.558 2.910 0.342 0.00 5.2900 0.558 2.953 0.374 0.00	
5.3667 0.558 2.996 0.407 0.00	00
5.4433 0.558 3.039 0.441 0.00 5.5200 0.558 3.081 0.477 0.00	
5.5260 0.558 3.061 0.477 0.00 5.5967 0.558 3.124 0.513 0.00	
5.6733 0.558 3.167 0.703 0.00	00
5.7500       0.558       3.210       0.753       0.00         5.8267       0.558       3.253       0.804       0.00	
5.9033 0.558 3.295 0.857 0.00	
5.9800 0.558 3.338 1.094 0.00	
6.0567 0.558 3.381 1.499 0.00 6.1333 0.558 3.424 1.971 0.00	
6.2100 0.558 3.467 2.420 0.00	00
6.2867 0.558 3.509 2.770 0.00 6.3633 0.558 3.552 2.989 0.00	
6.3633 0.558 3.552 2.989 0.00 6.4400 0.558 3.595 3.172 0.00	
6.5167 0.558 3.638 3.332 0.00	
6.5933 0.558 3.681 3.481 0.00 6.6700 0.558 3.723 3.623 0.00	
6.7467 0.558 3.766 3.758 0.00	00
6.8233	
6.9000       0.558       3.852       4.010       0.00         6.9767       0.558       3.387       4.129       0.00	

# Analysis Results POC 1





+ Predeveloped x Mitigated

Predeveloped Landuse Totals for POC #1

Total Pervious Area: 5.09
Total Impervious Area: 0

Mitigated Landuse Totals for POC #1 Total Pervious Area: 0.72 Total Impervious Area: 4.59

Flow Frequency Method: Log Pearson Type III 17B

Flow Frequency Return Periods for Predeveloped. POC #1

 Return Period
 Flow(cfs)

 2 year
 0.115006

 5 year
 0.176949

 10 year
 0.212753

 25 year
 0.251534

 50 year
 0.276481

 100 year
 0.298127

Flow Frequency Return Periods for Mitigated. POC #1

Return PeriodFlow(cfs)2 year0.05525 year0.08935510 year0.12184125 year0.17770350 year0.232848100 year0.302375

#### **Annual Peaks**

Annual Peaks for Predeveloped and Mitigated. POC #1

Year	Predeveloped	Mitigated
1902	0.093	0.052
1903	0.071	0.041
1904	0.121	0.050
1905	0.059	0.057
1906	0.031	0.037
1907	0.178	0.050
1908	0.128	0.045
1909	0.126	0.053
1910	0.178	0.050
1911	0.115	0.050

1912 1913 1914 1915 1916 1917 1918 1920 1921 1922 1923 1924 1925 1926 1927 1928 1929 1930 1931 1932 1933 1934 1935 1938 1949 1941 1942 1943 1944 1945 1947 1948 1950 1951 1952 1953 1954 1955 1956 1957 1958 1959 1961 1962 1963 1965	0.387 0.180 0.046 0.075 0.114 0.039 0.123 0.095 0.117 0.128 0.129 0.102 0.050 0.063 0.112 0.082 0.088 0.178 0.114 0.108 0.092 0.234 0.108 0.092 0.234 0.105 0.096 0.096 0.008 0.105 0.0158 0.0159 0.0159 0.0245 0.213 0.062 0.080 0.158 0.092 0.080 0.105 0.0150 0.0150 0.0150 0.0080 0.105 0.0150 0.01	0.058 0.063 0.049 0.045 0.163 0.047 0.050 0.058 0.051 0.058 0.046 0.045 0.049 0.055 0.060 0.051 0.053 0.057 0.053 0.057 0.053 0.057 0.053 0.057 0.053 0.057 0.053 0.057 0.053 0.057 0.053 0.051 0.055 0.060 0.051 0.058 0.049 0.055 0.051 0.058 0.051 0.058 0.051 0.053 0.057 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.051 0.053 0.053 0.051 0.053 0.055 0.056 0.055 0.056
1963	0.051	0.038

22085-6 ft live 7/7/2023 9:33:48 AM Page 9

22085-6 ft live 7/7/2023 9:33:48 AM Page 10

#### Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

Rank	Predeveloped	Mitigated
1	0.3867	0.3301
2 3	0.3168	0.3106
3	0.3121	0.2905
4	0.3085	0.2856
4 5	0.3060	0.2782
6	0.2876	0.2758
7	0.2713	0.2736
8	0.2685	0.2459
9	0.2672	0.2410
10	0.2480	0.2402
11	0.2448	0.2143
12	0.2405	0.2078
13	0.2357	0.1971
14	0.2345	0.1859
15	0.2277	0.1810
16	0.2271	0.1802
17	0.2265	0.1638
18	0.2191	0.1626
19	0.2150	0.1419
20	0.2128	0.1211
21	0.2113	0.0900
22	0.1928	0.0688

22085-6 ft live 7/7/2023 9:33:48 AM Page 12

81 82 83 84 85 86 87 88 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 107 108 110 111 113 114 115 116 117 118 119 120 121 122 123 124 125 127 128 129 130 131 131 131 131 131 131 131 131 131	0.1116 0.1084 0.1080 0.1063 0.1062 0.1053 0.1039 0.1021 0.1020 0.1016 0.1012 0.1004 0.0980 0.0974 0.0963 0.0958 0.0957 0.0954 0.0932 0.0917 0.0915 0.0900 0.0893 0.0891 0.0878 0.0870 0.0849 0.0827 0.0817 0.0811 0.0801 0.0801 0.0778 0.0752	0.0521 0.0518 0.0518 0.0516 0.0514 0.0511 0.0510 0.0509 0.0509 0.0508 0.0507 0.0504 0.0504 0.0504 0.0499 0.0498 0.0498 0.0495 0.0493 0.0493 0.0491 0.0490 0.0489 0.0474 0.0474 0.0474 0.0473 0.0474 0.0473 0.0473 0.0472 0.0474 0.0473 0.0473 0.0473 0.0473 0.0473 0.0473 0.0474 0.0474 0.0474 0.0473 0.0474 0.0474 0.0474 0.0473 0.0474 0.0474 0.0474 0.0473 0.0472 0.0470 0.0463 0.0450 0.0451 0.0450 0.0447 0.0447 0.0447 0.0447 0.0447 0.0447 0.0447 0.0447

22085-6 ft live 7/7/2023 9:33:48 AM Page 13

139	0.0569	0.0424
140	0.0562	0.0423
141	0.0539	0.0420
142	0.0530	0.0419
143	0.0525	0.0411
144	0.0517	0.0403
145	0.0506	0.0396
146	0.0501	0.0393
147	0.0499	0.0391
148	0.0497	0.0390
149	0.0471	0.0389
150	0.0461	0.0382
151	0.0459	0.0382
152	0.0400	0.0379
153	0.0391	0.0378
154	0.0382	0.0374
155	0.0306	0.0368
156	0.0157	0.0363
157	0.0124	0.0357
158	0.0080	0.0313

### **Duration Flows**

# The Facility PASSED

			_	
Flow(cfs)	Predev	Mit	Percentage	Pass/Fail
0.0575	56841	55312	97	Pass
0.0597	52415	34415	65	Pass
0.0619	48365	19329	39	Pass
0.0641	44620	11413	25	Pass
0.0664	41213	10028	24	Pass
0.0686	38226	9341	24	Pass
0.0708	35479	8726	24	Pass
0.0730	32958	8122	24	Pass
0.0752	30526	7706	25	Pass
0.0774	28426	7363	25	Pass
0.0796	26493	7053	26	Pass
0.0818	24747	6753	27	Pass
0.0840	23130	6482	28	Pass
0.0863	21678	6249	28	Pass
0.0885	20326	6039	29	Pass
0.0907	19058	5778	30	Pass
0.0929	17850	5530	30	Pass
0.0951	16714	5352	32	Pass
0.0973	15606	5178	33	Pass
0.0995	14620	4999	34	Pass
0.1017	13734	4854	35	Pass
0.1040	12892	4687	36	Pass
0.1062	12111	4536	37	Pass
0.1084	11407	4386	38	Pass
0.1106	10687	4234	39	Pass
0.1128	9983	4068	40	Pass
0.1150	9357	3914	41	Pass
0.1172	8753	3764	43	Pass
0.1194	8205	3642	44	Pass
0.1216	7734	3488	45	Pass
0.1239	7252	3361	46	Pass
0.1261	6798	3270	48	Pass
0.1283	6432	3188	49	Pass
0.1305	6122	3100	50	Pass
0.1327	5828	3009	51	Pass
0.1349	5557	2922	52	Pass
0.1371	5271	2824	53	Pass
0.1393	5009	2715	54	Pass
0.1416	4790	2624	54	Pass
0.1438	4536	2529	55	Pass
0.1460	4345	2441	56	Pass
0.1482	4166	2357	56	Pass
0.1504	3936	2269	57	Pass
0.1526	3713	2189	58	Pass
0.1548	3537	2090	59	Pass
0.1570	3366	2011	59	Pass
0.1593	3231	1923	59	Pass
0.1615	3091	1830	59 50	Pass
0.1637	2968	1748	58	Pass
0.1659	2853	1677	58	Pass
0.1681	2741	1624	59	Pass
0.1703	2599	1562	60	Pass
0.1725	2477	1499	60	Pass

0.1747       2359         0.1769       2267         0.1792       2160         0.1814       2059         0.1836       1950         0.1858       1840         0.1802       1659         0.1902       1659         0.1946       1510         0.1969       1445         0.1991       1368         0.2013       1298         0.2035       1243         0.2057       1182         0.2079       1129         0.2123       1026         0.2145       980         0.2145       980         0.2168       925         0.2145       980         0.2212       819         0.2234       772         0.2256       717         0.2278       668         0.2300       629         0.2322       588         0.2345       549         0.2433       392         0.24411       429         0.2433       392         0.2447       329         0.2524       264         0.2544       264         0.2545	1448 1386 1323 1262 1210 1150 1094 1042 992 945 903 866 830 793 750 696 671 640 609 591 570 523 486 457 435 413 389 372 354 324 308 290 278 268 278 268 278 278 278 278 278 278 278 278 278 27	0.1769       2267       1386       61       Pass         0.1792       2160       1323       61       Pass         0.1814       2059       1262       61       Pass         0.1836       1950       1210       62       Pass         0.1858       1840       1150       62       Pass         0.1880       1748       1094       62       Pass         0.1902       1659       1042       62       Pass         0.1924       1579       992       62       Pass         0.1946       1510       945       62       Pass         0.1969       1445       903       62       Pass         0.1991       1368       866       63       Pass         0.2013       1298       830       63       Pass         0.2013       1298       830       63       Pass         0.2057       1182       750       63       Pass         0.2079       1129       696       61       Pass         0.2101       1079       671       62       Pass         0.2145       980       609       62       Pass         0.2
1386 1323 1262 1210 1150 1094 1042 992 945 903 866 830 793 750 696 671 640 609 591 570 523 486 457 435 413 389 372 354 324 308 290 278 268 212 201 189 175 157 144 128		61 61 62 62 62 62 63 63 63 63 63 63 63 63 63 63 67 67 68 69 70 73 74 75 78 99 99 99 90 91 10 90 10 10 10 10 10 10 10 10 10 10 10 10 10
1386       61         1323       61         1262       61         1210       62         1150       62         1094       62         1042       62         992       62         945       62         903       62         866       63         830       63         793       63         696       61         671       62         640       62         609       62         591       63         570       65         550       67         523       67         486       67         457       68         435       69         413       70         389       70         372       73         354       74         324       75         308       78         290       79         278       84         268       89         255       90         243       92         233       93	61 61 62 62 62 62 63 63 63 63 63 63 63 63 63 63 67 67 68 69 70 73 74 75 78 99 99 99 90 91 10 90 10 10 10 10 10 10 10 10 10 10 10 10 10	Pass Pass Pass Pass Pass Pass Pass Pass

22085-6 ft live 7/7/2023 9:33:48 AM Page 16

# Water Quality

Water Quality
Water Quality BMP Flow and Volume for POC #1
On-line facility volume: 0 acre-feet
On-line facility target flow: 0 cfs.
Adjusted for 15 min: 0 cfs.
Off-line facility target flow: 0 cfs.
Adjusted for 15 min: 0 cfs.

22085-6 ft live 7/7/2023 9:33:48 AM Page 17

# Model Default Modifications

Total of 0 changes have been made.

### PERLND Changes

No PERLND changes have been made.

### **IMPLND Changes**


No IMPLND changes have been made.

22085-6 ft live 7/7/2023 9:34:02 AM Page 19

# Appendix Predeveloped Schematic

 Basin 1 5.09ac		

# Mitigated Schematic



#### Predeveloped UCI File

```
RUN
```

```
GLOBAL
 WWHM4 model simulation
                   END 3 0
 START 1901 10 01
                           2059 09 30
 RUN INTERP OUTPUT LEVEL
 RESUME 0 RUN 1
                               UNIT SYSTEM 1
END GLOBAL
FILES
<File> <Un#>
          <---->***
<-ID->
WDM
        26
          22085-6 ft live.wdm
MESSU
        25
          Pre22085-6 ft live.MES
        27
           Pre22085-6 ft live.L61
        28 Pre22085-6 ft live.L62
30 POC22085-6 ft live1.dat
END FILES
OPN SEQUENCE
  INGRP
           10
                INDELT 00:15
   PERLND
            501
    COPY
   DISPLY
  END INGRP
END OPN SEQUENCE
DISPLY
 DISPLY-INFO1
  # - #<-----Title---->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND
  Basin 1
                                              1 2 30
 END DISPLY-INFO1
END DISPLY
COPY
 TIMESERIES
 # - # NPT NMN ***
 1 1
501 1
            1
             1
 END TIMESERIES
END COPY
GENER
 OPCODE
 # # OPCD ***
 END OPCODE
 PARM
          K ***
 #
 END PARM
END GENER
PERLND
 GEN-INFO
  <PLS ><----Name---->NBLKS Unit-systems Printer ***
                         User t-series Engl Metr ***
                               in out
                         1
  10 C, Forest, Flat
 END GEN-INFO
 *** Section PWATER***
 ACTIVITY
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
10 0 0 1 0 0 0 0 0 0 0 0
 END ACTIVITY
 PRINT-INFO
   END PRINT-INFO
```

```
PWAT-PARM1
   <PLS > PWATER variable monthly parameter value flags ***
  # - # CSNO RTOP UZFG VCS VUZ VNN VIFW VIRC VLE INFC HWT ***
10 0 0 0 0 0 0 0 0 0 0
 END PWAT-PARM1
 PWAT-PARM2
  END PWAT-PARM2
 PWAT-PARM3
  PWAT-PARM3

<PLS > PWATER input info: Part 3 ***

# - # ***PETMAX PETMIN INFEXP INFILD DEEPFR

10 0 0 2 2 0
                                                          BASETP
                                                0 0
 END PWAT-PARM3
 PWAT-PARM4
  <PLS > PWATER input info: Part 4
  # - # CEPSC UZSN NSUR INTFW IRC LZETP ***
10 0.2 0.5 0.35 6 0.5 0.7
 END PWAT-PARM4
 PWAT-STATE1
  <PLS > *** Initial conditions at start of simulation
    ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
   # - # *** CEPS SURS UZS IFWS LZS AGWS LO 0 0 0 2.5 1
                                                                    GWVS
  10
 END PWAT-STATE1
END PERLND
IMPLND
 GEN-INFO
  <PLS ><----- Name----> Unit-systems Printer ***
  # - #
                           User t-series Engl Metr ***
                                  in out
 END GEN-INFO
 *** Section IWATER***
 ACTIVITY
   <PLS > ******** Active Sections **********************
   # - # ATMP SNOW IWAT SLD IWG IQAL ***
 END ACTIVITY
 PRINT-INFO
   <ILS > ****** Print-flags ****** PIVL PYR
   # - # ATMP SNOW IWAT SLD IWG IQAL *******
 END PRINT-INFO
  <PLS > IWATER variable monthly parameter value flags ***
   # - # CSNO RTOP VRS VNN RTLI ***
 END IWAT-PARM1
 IWAT-PARM2
   <PLS > IWATER input info: Part 2 ***
# - # *** LSUR SLSUR NSUR RETSC
 END IWAT-PARM2
 IWAT-PARM3
   <PLS > IWATER input info: Part 3
   # - # ***PETMAX PETMIN
 END IWAT-PARM3
   <PLS > *** Initial conditions at start of simulation
   # - # *** RETS SURS
 END IWAT-STATE1
```

```
SCHEMATIC
                  <--Area--> <-Target-> MBLK ***
<-factor-> <Name> # Tbl# ***
<-Source->
<Name> #
Basin 1***
                        5.09 COPY 501 12
5.09 COPY 501 13
PERLND 10
PERLND 10
*****Routing*****
END SCHEMATIC
NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
END NETWORK
RCHRES
 GEN-INFO
  RCHRES Name Nexits Unit Systems Printer
  # - #<----- User T-series Engl Metr LKFG
                                                        * * *
                                                        * * *
                               in out
 END GEN-INFO
 *** Section RCHRES***
 ACTIVITY
  # - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***
 END ACTIVITY
 PRINT-INFO
  <PLS > ******** Print-flags ******** PIVL PYR
   # - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR *******
 END PRINT-INFO
 HYDR-PARM1
  RCHRES Flags for each HYDR Section
  # - # VC A1 A2 A3 ODFVFG for each *** ODGTFG for each FUNCT for each FG FG FG possible exit *** possible exit possible exit ***
 END HYDR-PARM1
 HYDR-PARM2
 # - # FTABNO LEN DELTH STCOR
                                         KS
                                               DB50
 <----><----><---->
                                                        * * *
  RCHRES Initial conditions for each HYDR section
  # ***
*** ac-ft
 <---->
                <---><---><---> *** <---><---><--->
 END HYDR-INIT
END RCHRES
SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
END FTABLES
EXT SOURCES
<-Volume-> <Member> SsysSgap<--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name> # # ***
WDM
```

	EVAP EVAP	ENGL ENGL	1		l 999 EXTNL l 999 EXTNL	
END EXT SC	URCES					
<name> #</name>	<-Grp> OUTPUT	<name> #</name>	#<-factor->strg	<name></name>	<pre># <name></name></pre>	Tsys Tgap Amd *** tem strg strg*** ENGL REPL
MASS-LINK <volume> <name> MASS-LIN PERLND END MASS</name></volume>	IK PWATER	<name> # 12</name>	> <mult> #&lt;-factor-&gt; 0.083333</mult>	<target> <name></name></target>	<-Grp	<pre>&gt; &lt;-Member-&gt;***</pre>
MASS-LIN PERLND END MASS	PWATER	13 IFWO 13	0.083333	COPY	INPUT	MEAN

END MASS-LINK

END RUN

#### Mitigated UCI File

```
RUN
```

```
GLOBAL
 WWHM4 model simulation
                     END 2059 09 30
3 0
 START 1901 10 01
 RUN INTERP OUTPUT LEVEL
 RESUME 0 RUN 1
                                   UNIT SYSTEM 1
END GLOBAL
FILES
<File> <Un#>
           <---->***
<-ID->
M \cap M
         26
           22085-6 ft live.wdm
MESSU
         25
           Mit22085-6 ft live.MES
         27
            Mit22085-6 ft live.L61
           Mit22085-6 ft live.L62
POC22085-6 ft livel.dat
         28
         30
END FILES
OPN SEQUENCE
   INGRP
                  INDELT 00:15
    PERLND 13
             11
    IMPLND
             1
    RCHRES
    COPY
               1
             501
    DISPLY
              1
   END INGRP
END OPN SEQUENCE
DISPLY
  # - #<-----Title----->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND 1 Vault 1 MAX 1 2 30 9
 END DISPLY-INFO1
END DISPLY
COPY
 TIMESERIES
  # - # NPT NMN ***
 1 1 1
501 1 1
 END TIMESERIES
END COPY
GENER
 OPCODE
  # # OPCD ***
 END OPCODE
 PARM
            K ***
 #
 END PARM
END GENER
PERLND
 GEN-INFO
  <PLS ><----Name---->NBLKS Unit-systems Printer ***
                            User t-series Engl Metr ***
                          in out
1 1 1 1 27
  C, Pasture, Flat
 END GEN-INFO
 *** Section PWATER***
 ACTIVITY
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
13 0 0 1 0 0 0 0 0 0 0 0
 END ACTIVITY
 PRINT-INFO
   # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ********
```

```
13 0 0 4 0 0 0 0 0 0 0 0 1 9
 END PRINT-INFO
 PWAT-PARM1
  <PLS > PWATER variable monthly parameter value flags ***
  END PWAT-PARM1
           PWATER input info: Part 2 ***
FOREST LZSN INFILT LSUR SLSUR KVARY AGWRC

^ 4 5 0.06 400 0.05 0.5 0.996
 PWAT-PARM2
  <PLS >
   # - # ***FOREST LZSN INFILT
.3 0 4.5 0.06
 END PWAT-PARM2
 PWAT-PARM3
  <PLS > PWATER input info: Part 3 ***
  # - # ***PETMAX PETMIN INFEXP
13 0 0 2
                                     INFILD DEEPFR
                                                      BASETP
                                                              AGWETP
                                              0
 END PWAT-PARM3
 PWAT-PARM4
  PWAT-PARM4

<PLS > PWATER input info: Part 4

# - # CEPSC UZSN NSUR

13 0.15 0.4 0.3
                                     INTFW IRC
                                                      LZETP ***
                                               0.5
                                                      0.4
 END PWAT-PARM4
 PWAT-STATE1
  <PLS > *** Initial conditions at start of simulation
          ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
       # *** CEPS SURS UZS IFWS LZS AGWS 0 0 0 0 2.5 1
                                                                GWVS
  13
 END PWAT-STATE1
END PERLND
IMPLND
 GEN-INFO
  <PLS ><----- Name----> Unit-systems Printer ***
                          User t-series Engl Metr ***
                               in out ***
                             1 1 1
  11 PARKING/FLAT
 END GEN-INFO
 *** Section IWATER***
 ACTIVITY
  # - # ATMP SNOW IWAT SLD IWG IQAL
11 0 0 1 0 0 0
 END ACTIVITY
 PRINT-INFO
  <ILS > ****** Print-flags ****** PIVL PYR
  # - # ATMP SNOW IWAT SLD IWG IQAL ********
11 0 0 4 0 0 0 1 9
 END PRINT-INFO
 IWAT-PARM1
  <PLS > IWATER variable monthly parameter value flags ***
  # - # CSNO RTOP VRS VNN RTLI ***
11 0 0 0 0 0 0
 END IWAT-PARM1
 IWAT-PARM2
   <PLS >
  11
             400 0.01
 END IWAT-PARM2
 IWAT-PARM3
            IWATER input info: Part 3
   <PLS >
```

```
# - # ***PETMAX PETMIN
0 0
  11
 END IWAT-PARM3
 IWAT-STATE1
  <PLS > *** Initial conditions at start of simulation
  # - # *** RETS SURS
11 0 0
 END IWAT-STATE1
END IMPLND
SCHEMATIC
                  <--Area--> <-Target-> MBLK ***
<-factor-> <Name> # Tbl# ***
<-Source->
<Name> #
Basin 1***
                        0.72 RCHRES 1
0.72 RCHRES 1
4.59 RCHRES 1
                                         2
PERLND 13
PERLND 13
IMPLND 11
*****Routing****
                        0.72 COPY 1 12
4.59 COPY 1 15
0.72 COPY 1 13
1 COPY 501 16
PERLND 13
IMPLND 11
PERLND 13
RCHRES 1
END SCHEMATIC
NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
END NETWORK
RCHRES
 GEN-INFO
  RCHRES Name Nexits Unit Systems Printer
                                                       * * *
  # - #<----><--> User T-series Engl Metr LKFG
                                                       * * *
                                                        * * *
                              in out
  1 Vault 1
                       1 1 1 1 28 0 1
 END GEN-INFO
 *** Section RCHRES***
  PRINT-INFO
  <PLS > ********* Print-flags ********* PIVL PYR
  # - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR 1 4 0 0 0 0 0 0 0 0 0 0 1 9
 END PRINT-INFO
 HYDR-PARM1
  RCHRES Flags for each HYDR Section
  END HYDR-PARM1
 HYDR-PARM2
 # - # FTABNO
                  LEN
                               STCOR
                                         KS
                                              DB50
                        DELTH
                                                        * * *
 <----><----><---->
```

```
1 0.03 0.0 0.0 0.5 0.0
   1
 END HYDR-PARM2
 HYDR-INIT
   RCHRES Initial conditions for each HYDR section
   <---><---><---> *** <---><--->
  <---->
   1 0
                      4.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
 END HYDR-INIT
END RCHRES
SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
 FTABLE
  91 4
    Depth
             Area Volume Outflow1 Velocity Travel Time***
 (ft) (acres) (acre-ft) (cfs) (ft/sec) (Minutes)***
0.000000 0.558310 0.000000 0.000000
0.076667 0.558310 0.042804 0.008603
0.153333 0.558310 0.085608 0.012166
  0.230000 0.558310 0.128411 0.014900
  0.306667 0.558310 0.171215 0.017205
  0.383333 0.558310 0.214019 0.019236
  0.460000 0.558310 0.256823 0.021072
  0.536667 \quad 0.558310 \quad 0.299627 \quad 0.022760
 0.843333 0.558310
                    0.470842
                             0.028532
  0.920000 0.558310 0.513646 0.029800
  0.996667 0.558310 0.556449 0.031017
 1.073333 0.558310 0.599253 0.032188
 1.150000 0.558310 0.642057 0.033318
 1.226667 0.558310 0.684861 0.034410
 1.303333 0.558310 0.727665 0.035469
                             0.036498
 1.380000 0.558310 0.770468
1.456667 0.558310 0.813272
                             0.037498
0.038472
 1.533333 0.558310
                    0.856076
 1.610000 0.558310 0.898880 0.039422
 1.686667 0.558310 0.941684 0.040350
 1.763333 0.558310 0.984487 0.041257
  1.840000 0.558310 1.027291 0.042144
 1.916667 0.558310 1.070095 0.043013
 1.993333 0.558310 1.112899 0.043865
  2.070000 0.558310
                    1.155702 0.044700
  2.146667 0.558310
2.223333 0.558310
                    1.198506 0.045521
1.241310 0.046326
                    1.284114 0.047118
  2.300000 0.558310
  2.376667 0.558310 1.326918 0.047897
  2.453333 0.558310 1.369721 0.048664
  2.530000 0.558310 1.412525 0.049418
  2.606667 0.558310 1.455329 0.050161
  2.683333   0.558310   1.498133   0.050894
  2.760000 0.558310 1.540937
                             0.051616
  2.836667
          0.558310
                    1.583740 0.052328
                    1.626544
                             0.053030
  2.913333
           0.558310
  2.990000 0.558310
                             0.053723
                    1.669348
 3.066667 0.558310 1.712152 0.054408
  3.143333 0.558310 1.754956 0.055083
  3.220000 0.558310 1.797759 0.055751
  3.296667 0.558310 1.840563 0.056411
  3.373333 0.558310 1.883367 0.057063
  3.450000 0.558310
                    1.926171 0.057708
          0.558310
                    1.968975 0.058346
  3.526667
  3.603333
           0.558310
                    2.011778
                             0.058976
  3.680000 0.558310
                    2.054582
                             0.059601
  3.756667 0.558310
                    2.097386 0.060218
  3.833333 0.558310
                    2.140190 0.060830
  3.910000 0.558310 2.182994 0.061435
```

```
3.986667 0.558310
                      2.225797
                                 0.062034
  4.063333 0.558310
                      2.268601
                                 0.062628
           0.558310
  4.140000
                      2.311405
                                 0.063216
  4.216667
            0.558310
                      2.354209
                                 0.064513
          0.558310
                      2.397013
  4.293333
                                 0.073694
  4.370000
            0.558310
                      2.439816
                                 0.087495
            0.558310
                      2.482620
  4.446667
                                 0.104298
                      2.525424
  4.523333
            0.558310
                                 0.123342
  4.600000
            0.558310
                      2.568228
                                 0.144139
  4.676667
            0.558310
                       2.611032
                                 0.166330
  4.753333
            0.558310
                      2.653835
                                 0.189633
  4.830000
            0.558310
                       2.696639
                                 0.213816
  4.906667
            0.558310
                      2.739443
                                 0.238681
  4.983333
            0.558310
                      2.782247
                                 0.264055
  5.060000
            0.558310
                      2.825051
                                 0.289786
  5.136667
            0.558310
                      2.867854
                                 0.315736
  5.213333
            0.558310
                      2.910658
                                 0.342685
  5.290000
            0.558310
                      2.953462
                                 0.374620
            0.558310
                       2.996266
                                 0.407677
  5.366667
  5.443333
            0.558310
                      3.039069
                                 0.441818
  5.520000
            0.558310
                                 0.477008
                      3.081873
  5.596667
                      3.124677
            0.558310
                                 0.513218
  5.673333
            0.558310
                      3.167481
                                 0.702981
  5.750000
            0.558310
                      3.210285
                                 0.753208
  5.826667
            0.558310
                      3.253088
                                0.804676
           0.558310
                      3.295892
  5.903333
                                0.857107
                      3.338696
  5.980000
            0.558310
                                 1.094825
            0.558310
                                 1.499909
  6.056667
                      3.381500
  6.133333
            0.558310
                      3.424304
                                 1.971555
  6.210000
            0.558310
                       3.467107
                                 2.420936
            0.558310
                      3.509911
                                 2.770446
  6.286667
            0.558310
                      3.552715
                                 2.989223
  6.363333
  6.440000
            0.558310
                      3.595519
                                 3.172915
  6.516667
            0.558310
                      3.638323
                                 3.332233
                      3.681126
            0.558310
  6.593333
                                 3.481944
                      3.723930
  6.670000
            0.558310
                                 3.623604
  6.746667
            0.558310
                       3.766734
                                 3.758391
            0.558310
                       3.809538
                                 3.887219
  6.823333
  6.900000
           0.558310
                      3.852342
                                 4.010817
  END FTABLE 1
END FTABLES
EXT SOURCES
<-Volume-> <Member> SsysSgap<--Mult-->Tran <-Target vols> <-Grp> <-Member->
         # <Name> # tem strg<-factor->strg <Name>
                                                     # #
<Name>
                                                                   <Name> # #
                          1
MDM
         2 PREC
                    ENGL
                                            PERLND
                                                      1 999 EXTNL
                                                                   PREC
         2 PREC
                                                      1 999 EXTNL
WDM
                    ENGL
                             1
                                            IMPLND
                                                                   PREC
MDM
         1 EVAP
                    ENGL
                             1
                                            PERLND
                                                      1 999 EXTNL
                                                                   PETINP
                                                      1 999 EXTNL
WDM
         1 EVAP
                    ENGL
                             1
                                            IMPLND
                                                                   PETINP
END EXT SOURCES
EXT TARGETS
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Volume-> <Member> Tsys Tgap Amd ***
<Name>
        #
                  <Name> # #<-factor->strg <Name> # <Name>
                                                                 tem strg strg***
RCHRES
         1 HYDR
                  RO
                          1 1
                                    1
                                            WDM
                                                  1002 FLOW
                                                                 ENGL
                                                                            REPL
RCHRES
                          1 1
                                            WDM
                                                   1003 STAG
         1 HYDR
                  STAGE
                                     1
                                                                 ENGL
                                                                            REPL
                                                    701 FLOW
         1 OUTPUT MEAN
                                  48.4
COPY
                          1 1
                                            WDM
                                                                 ENGL
                                                                           REPL
       501 OUTPUT MEAN
                                                    801 FLOW
COPY
                          1 1
                                  48.4
                                            WDM
                                                                 ENGL
                                                                           REPL
END EXT TARGETS
MASS-LINK
                                                            <-Grp> <-Member->***
<Volume>
           <-Grp> <-Member-><--Mult-->
                                            <Target>
                                                                   <Name> # #***
<Name>
                  <Name> # #<-factor->
                                            <Name>
  MASS-LINK
                   2.
PERLND
          PWATER SURO
                              0.083333
                                            RCHRES
                                                            INFLOW IVOL
  END MASS-LINK
                   2
                   3
  MASS-LINK
                              0.083333
           PWATER IFWO
                                            RCHRES
                                                            INFLOW IVOL
PERLND
```

END MASS-LINK	3				
MASS-LINK IMPLND IWATER END MASS-LINK	5 SURO 5	0.083333	RCHRES	INFLOW	IVOL
MASS-LINK PERLND PWATER END MASS-LINK	12 SURO 12	0.083333	COPY	INPUT	MEAN
MASS-LINK PERLND PWATER END MASS-LINK	13 IFWO 13	0.083333	СОРУ	INPUT	MEAN
MASS-LINK IMPLND IWATER END MASS-LINK	15 SURO 15	0.083333	СОРУ	INPUT	MEAN
MASS-LINK RCHRES ROFLOW END MASS-LINK	16 16		COPY	INPUT	MEAN

END MASS-LINK

END RUN

# Predeveloped HSPF Message File

#### Mitigated HSPF Message File

ERROR/WARNING ID: 238 1 The continuity error reported below is greater than 1 part in 1000 and is therefore considered high. Did you specify any "special actions"? If so, they could account for it. Relevant data are: DATE/TIME: 1964/ 9/30 24: 0 RCHRES : 1 RELERR STORS STOR MATIN MATDIF -0.280750.00000 0.0000E+00 0.00000 - 6.855E - 10Where: RELERR is the relative error (ERROR/REFVAL). ERROR is (STOR-STORS) - MATDIF. REFVAL is the reference value (STORS+MATIN). is the storage of material in the processing unit (land-segment or reach/reservior) at the end of the present interval. STORS is the storage of material in the pu at the start of the present printout reporting period. MATIN is the total inflow of material to the pu during the present printout reporting period. MATDIF is the net inflow (inflow-outflow) of material to the pu during the present printout reporting period. ERROR/WARNING ID: 238 The continuity error reported below is greater than 1 part in 1000 and is therefore considered high. Did you specify any "special actions"? If so, they could account for it. Relevant data are: DATE/TIME: 1966/ 8/31 24: 0 RCHRES : 1 STORS RELERR STOR MATTN MATDIF -2.065E-01 0.00000 0.0000E+00 0.00000 -1.028E-09 Where: RELERR is the relative error (ERROR/REFVAL). ERROR is (STOR-STORS) - MATDIF. REFVAL is the reference value (STORS+MATIN). is the storage of material in the processing unit (land-segment or reach/reservior) at the end of the present interval. STORS is the storage of material in the pu at the start of the present printout reporting period. MATIN is the total inflow of material to the pu during the present printout reporting period. MATDIF is the net inflow (inflow-outflow) of material to the pu during the present printout reporting period. ERROR/WARNING ID: 238 1 The continuity error reported below is greater than 1 part in 1000 and is therefore considered high.

22085-6 ft live 7/7/2023 9:34:03 AM Page 33

Did you specify any "special actions"? If so, they could account for it.

Relevant data are:

DATE/TIME: 1989/ 8/31 24: 0

RCHRES : 1

RELERR STORS STOR MATIN MATDIF -7.406E-03 0.00000 0.0000E+00 0.00000 -3.596E-08

#### Where:

RELERR is the relative error (ERROR/REFVAL).

ERROR is (STOR-STORS) - MATDIF.

REFVAL is the reference value (STORS+MATIN).

is the storage of material in the processing unit (land-segment or

reach/reservior) at the end of the present interval.

STORS is the storage of material in the pu at the start of the present

printout reporting period. MATIN is the total inflow of material to the pu during the present printout

reporting period. MATDIF is the net inflow (inflow-outflow) of material to the pu during the

present printout reporting period.

#### ERROR/WARNING ID: 238

The continuity error reported below is greater than 1 part in 1000 and is therefore considered high.

Did you specify any "special actions"? If so, they could account for it.

Relevant data are:

DATE/TIME: 1992/ 8/31 24: 0

RCHRES :

RELERR STORS STOR MATIN MATDIF -1.094E-02 0.00000 0.0000E+00 0.00000 -2.427E-08

#### Where:

RELERR is the relative error (ERROR/REFVAL).

ERROR is (STOR-STORS) - MATDIF.

REFVAL is the reference value (STORS+MATIN).

is the storage of material in the processing unit (land-segment or reach/reservior) at the end of the present interval.

STORS is the storage of material in the pu at the start of the present printout reporting period.

MATIN is the total inflow of material to the pu during the present printout reporting period.

MATDIF is the net inflow (inflow-outflow) of material to the pu during the present printout reporting period.

#### ERROR/WARNING ID: 238 1

The continuity error reported below is greater than 1 part in 1000 and is therefore considered high.

Did you specify any "special actions"? If so, they could account for it.

Relevant data are:

DATE/TIME: 2010/ 8/31 24: 0

RCHRES : 1

RELERR STORS STOR MATIN MATDIF -1.099E-03 0.00000 0.0000E+00 0.00000 -2.443E-07

#### Where:

RELERR is the relative error (ERROR/REFVAL). ERROR is (STOR-STORS) - MATDIF.

REFVAL is the reference value (STORS+MATIN).

STOR is the storage of material in the processing unit (land-segment or reach/reservior) at the end of the present interval.

STORS is the storage of material in the pu at the start of the present printout reporting period.

MATIN is the total inflow of material to the pu during the present printout reporting period.

MATDIF is the net inflow (inflow-outflow) of material to the pu during the present printout reporting period.

The count for the WARNING printed above has reached its maximum.

If the condition is encountered again the message will not be repeated.

## Disclaimer

#### Legal Notice


This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2023; All Rights Reserved.

Clear Creek Solutions, Inc. 6200 Capitol Blvd. Ste F Olympia, WA. 98501 Toll Free 1(866)943-0304 Local (360)943-0304


www.clearcreeksolutions.com

22085-6 ft live 7/7/2023 9:34:03 AM Page 36


# East Basin - Ex Conditions




# East Basin - Proposed Conditions



# East Basin - Wetland recharge



# East Basin -Flows



# WWHM2012 PROJECT REPORT

### General Model Information

Project Name: 22085-wetland recharge ex conditions

Site Name: Site Address:

City:

 Report Date:
 8/31/2023

 Gage:
 40 IN EAST

 Data Start:
 10/01/1901

 Data End:
 09/30/2059

 Timestep:
 15 Minute

 Precip Scale:
 1.000

Version Date: 2019/09/13

Version: 4.2.17

### **POC Thresholds**

Low Flow Threshold for POC1: 50 Percent of the 2 Year

High Flow Threshold for POC1: 50 Year

# Landuse Basin Data Predeveloped Land Use

### Basin 1

Bypass: No

GroundWater: No

Pervious Land Use acre C, Lawn, Flat 0.51

Pervious Total 0.51

Impervious Land Use acre PARKING FLAT 2.45

Impervious Total 2.45

Basin Total 2.96

Element Flows To:

Surface Interflow Groundwater

### Mitigated Land Use

### Basin 1

Bypass: No

GroundWater: No

Pervious Land Use acre C, Pasture, Flat 0.5

Pervious Total 0.5

Impervious Land Use acre PARKING FLAT 2.25

Impervious Total 2.25

Basin Total 2.75


Element Flows To:


Surface Interflow Groundwater

# Routing Elements Predeveloped Routing

# Mitigated Routing

# Analysis Results POC 1





+ Predeveloped

x Mitigated

Predeveloped Landuse Totals for POC #1

Total Pervious Area: 0.51 Total Impervious Area: 2.45

Mitigated Landuse Totals for POC #1

Total Pervious Area: 0.5 Total Impervious Area: 2.25

Flow Frequency Method: Log Pearson Type III 17B

Flow Frequency Return Periods for Predeveloped. POC #1

 Return Period
 Flow(cfs)

 2 year
 0.901539

 5 year
 1.217573

 10 year
 1.448354

 25 year
 1.765409

 50 year
 2.02072

 100 year
 2.292968

Flow Frequency Return Periods for Mitigated. POC #1

 Return Period
 Flow(cfs)

 2 year
 0.813181

 5 year
 1.090728

 10 year
 1.292333

 25 year
 1.568127

 50 year
 1.789378

 100 year
 2.024605

### **Annual Peaks**

Annual Peaks for Predeveloped and Mitigated. POC #1

Year	Predeveloped	Mitigated
1902	1.041	0.955
1903	1.155	1.058
1904	1.395	1.221
1905	0.595	0.538
1906	0.666	0.610
1907	0.921	0.820
1908	0.738	0.667
1909	0.885	0.813
1910	0.864	0.779
1911	0.989	0.881

1946       0.866       0.768         1947       0.647       0.588         1948       0.896       0.809         1949       1.362       1.246         1950       0.749       0.688         1951       1.158       1.064	1947       0.647       0.588         1948       0.896       0.809         1949       1.362       1.246         1950       0.749       0.688	1912 1913 1914 1915 1916 1917 1918 1919 1920 1921 1922 1923 1924 1925 1926 1927 1928 1929 1930 1931 1932 1933 1934 1935 1936 1937 1938 1939 1940 1941 1942 1943 1944 1945	1.743 0.685 3.073 0.606 1.107 0.438 0.879 0.567 0.758 0.644 1.031 0.703 1.282 0.551 1.038 0.890 0.646 1.303 1.338 0.653 0.702 0.690 1.179 0.600 0.834 1.066 0.608 0.740 1.339 1.455 1.031 0.995 1.467 1.072	1.502 0.627 2.688 0.551 1.014 0.402 0.807 0.514 0.674 0.582 0.907 0.629 1.173 0.500 0.953 0.815 0.587 1.153 1.218 0.590 0.636 0.628 1.032 0.551 0.752 0.979 0.554 0.677 1.219 1.333 0.896 1.289 0.969
	1952       1.441       1.230         1953       1.316       1.135         1954       0.728       0.660         1955       0.670       0.614         1956       0.619       0.569         1957       0.721       0.655         1958       0.936       0.827	1947 1948 1949 1950	0.647 0.896 1.362 0.749	0.588 0.809 1.246 0.688

2028	0.411	0.377
2029	0.701	0.631
2030	1.451	1.320
2031	0.436	0.399
2032	0.718	0.658
2033	0.907	0.833
2034	0.689	0.633
2035	0.930	0.828
2036	0.713	0.654
2037	0.955	0.877
2038	0.959	0.844
2039	1.813	1.663
2040	0.728	0.659
2041	0.925	0.831
2042	1.057	0.969
2043	1.160	1.063
2044	0.809	0.733
2045	0.661	0.597
2046	0.733	0.661
2047	0.879	0.807
2048	0.723	0.663
2049	1.072	0.983
2050	0.829	0.744
2051	1.196	1.052
2052	0.868	0.797
2053	0.734	0.672
2054	1.566	1.341
2055	0.840	0.761
2056	1.158	1.059
2057	0.562	0.511
2058	1.082	0.993
2059	1.365	1.253

### Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

Rank	Predeveloped	Mitigated
1	3.0727	2.6882
2	2.8196	2.4655
2 3	2.0894	1.8933
4	2.0673	1.8295
4 5	1.9285	1.6903
6	1.8620	1.6629
7	1.8133	1.6249
8	1.7434	1.5091
9	1.6483	1.5016
10	1.5657	1.4218
11	1.5518	1.3414
12	1.4666	1.3332
13	1.4546	1.3199
14	1.4512	1.2890
15	1.4409	1.2527
16	1.3951	1.2458
17	1.3648	1.2301
18	1.3625	1.2214
19	1.3621	1.2189
20	1.3390	1.2177
21	1.3383	1.2039
22	1.3312	1.1806

139 140 141	0.6468 0.6462 0.6442	0.5880 0.5870 0.5837
142	0.6359	0.5818
143	0.6192	0.5685
144	0.6186	0.5619
145	0.6082	0.5544
146	0.6059	0.5508
147	0.5995	0.5505
148	0.5950	0.5409
149	0.5948	0.5383
150	0.5793	0.5320
151	0.5717	0.5199
152	0.5674	0.5136
153	0.5615	0.5113
154	0.5506	0.5003
155	0.5411	0.4910
156	0.4381	0.4022
157	0.4364	0.3987
158	0.4112	0.3774

# Model Default Modifications

Total of 0 changes have been made.

### PERLND Changes

No PERLND changes have been made.

### **IMPLND Changes**

No IMPLND changes have been made.

# Appendix Predeveloped Schematic

Basin 2.96a	1 c	

# Mitigated Schematic

	74	Basin 2.75ac	1			

### Predeveloped UCI File

RUN

```
GLOBAL
 WWHM4 model simulation
 START 1901 10 01 END 2059 09 30 RUN INTERP OUTPUT LEVEL 3 0
 RESUME 0 RUN 1
                                     UNIT SYSTEM 1
END GLOBAL
FILES
<File> <Un#>
            <---->***
<-ID->
WDM
         26 22085-wetland recharge ex conditions.wdm
MESSII
         25
            Pre22085-wetland recharge ex conditions.MES
         27
            Pre22085-wetland recharge ex conditions.L61
             Pre22085-wetland recharge ex conditions.L62
         30 POC22085-wetland recharge ex conditions1.dat
END FILES
OPN SEQUENCE
   INGRP
            16
                   INDELT 00:15
    PERLND
     IMPLND
              11
    COPY
             501
    DISPLY
   END INGRP
END OPN SEQUENCE
DISPLY
 DISPLY-INFO1
   # - #<-----Title---->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND
   1 Basin 1
 END DISPLY-INFO1
END DISPLY
COPY
 TIMESERIES
  # - # NPT NMN ***
 1 1
501 1
              1
                1
 END TIMESERIES
END COPY
GENER
 OPCODE
  # # OPCD ***
 END OPCODE
 PARM
  #
            K ***
 END PARM
END GENER
PERLND
 GEN-INFO
  <PLS ><----Name---->NBLKS Unit-systems Printer ***
                         User t-series Engl Metr ***
  # - #
                            in out
1 1 1 1
                                             27
  16 C, Lawn, Flat
 END GEN-INFO
 *** Section PWATER***
   <PLS > ******** Active Sections *********************
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
16 0 0 1 0 0 0 0 0 0 0 0
 END ACTIVITY
 PRINT-INFO
   # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC *********
16 0 0 4 0 0 0 0 0 0 0 0 1 9
 END PRINT-INFO
```

```
PWAT-PARM1
  <PLS > PWATER variable monthly parameter value flags ***
  END PWAT-PARM1
 PWAT-PARM2
   <PLS >
  16
 END PWAT-PARM2
 PWAT-PARM3
  <PLS > PWATER input info: Part 3 ***
   # - # ***PETMAX PETMIN INFEXP
16 0 0 2
                                    INFILD DEEPFR BASETP AGWETP 2 0 0 0
                                    2
                                            0 0
 END PWAT-PARM3
 PWAT-PARM4

<PLS > PWATER input info: Part 4

# - # CEPSC UZSN NSUR INTFW IRC LZETP ***

16 0.1 0.25 0.25 6 0.5 0.25
 END PWAT-PARM4
 PWAT-STATE1
  <PLS > *** Initial conditions at start of simulation
         ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
      # *** CEPS SURS UZS IFWS LZS AGWS 0 0 0 0 2.5 1
                                                             GWVS
  16 0
 END PWAT-STATE1
END PERLND
IMPLND
 GEN-INFO
  <PLS ><-----> Unit-systems Printer ***
                         User t-series Engl Metr ***
                           in out
1 1 1 27 0
  11 PARKING/FLAT
 END GEN-INFO
 *** Section IWATER***
 ACTIVITY
  <PLS > ******** Active Sections *********************
  # - # ATMP SNOW IWAT SLD IWG IQAL ***
11 0 0 1 0 0 0
 END ACTIVITY
 PRINT-INFO
  <ILS > ****** Print-flags ****** PIVL PYR
  # - # ATMP SNOW IWAT SLD IWG IQAL ********
11 0 0 4 0 0 0 1 9
 END PRINT-INFO
 IWAT-PARM1
  <PLS > IWATER variable monthly parameter value flags ***
  # - # CSNO RTOP VRS VNN RTLI ***
11 0 0 0 0 0
 END IWAT-PARM1
 IWAT-PARM2
  END IWAT-PARM2
 IWAT-PARM3
           IWATER input info: Part 3
  <PLS >
   # - # ***PETMAX PETMIN
```

```
IWAT-STATE1
   <PLS > *** Initial conditions at start of simulation
   # - # *** RETS SURS
  11 0
                    0
 END IWAT-STATE1
END IMPLND
SCHEMATIC
                     <--Area--> <-Target-> MBLK ***
<-factor-> <Name> # Tbl# ***
<-Source->
<Name> #
Basin 1***
                           0.51 COPY 501 12
0.51 COPY 501 13
2.45 COPY 501 15
PERLND 16
PERLND 16
IMPLND 11
*****Routing*****
END SCHEMATIC
NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
END NETWORK
RCHRES
 GEN-INFO
  RCHRES Name Nexits Unit Systems Printer
                                                               * * *
  # - #<----- User T-series Engl Metr LKFG
                                                               * * *
                                                               * * *
                                   in out
 END GEN-INFO
 *** Section RCHRES***
 ACTIVITY
   <PLS > ******** Active Sections **********************
   # - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***
 END ACTIVITY
 PRINT-INFO
   <PLS > ******** Print-flags ******** PIVL PYR
   # - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR ********
 END PRINT-INFO
 HYDR-PARM1
   RCHRES Flags for each HYDR Section
                                                               * * *
   END HYDR-PARM1
 HYDR-PARM2
  # - # FTABNO LEN DELTH STCOR
                                          KS DB50
 <----><----><---->
 END HYDR-PARM2
 HYDR-INIT
   RCHRES Initial conditions for each HYDR section
 # - # *** VOL Initial value of COLIND Initial value of OUTDGT

*** ac-ft for each possible exit for each possible exit

<----> <---> <---> *** <---> *** <---> ***
 END HYDR-INIT
END RCHRES
```

SPEC-ACTIONS

END IWAT-PARM3

END SPEC-ACTIONS FTABLES END FTABLES

#### EXT SOURCES

<-Volume-	->	<member></member>	SsysSgar	o <mult>Tran</mult>	<-Target	vols>	<-Grp>	<-Member->	* * *
<name></name>	#	<name> #</name>	tem str	g<-factor->strg	<name></name>	# #		<name> # #</name>	* * *
WDM	2	PREC	ENGL	1	PERLND	1 999	EXTNL	PREC	
WDM	2	PREC	ENGL	1	IMPLND	1 999	EXTNL	PREC	
WDM	1	EVAP	ENGL	1	PERLND	1 999	EXTNL	PETINP	
WDM	1	EVAP	ENGL	1	IMPLND	1 999	EXTNL	PETINP	

END EXT SOURCES

#### EXT TARGETS

#### MASS-LINK

<volume> &lt;-Gr <name></name></volume>	-	-> <mult> : #&lt;-factor-&gt;</mult>	<target> <name></name></target>	<-Grp>	<-Member->*** <name> # #***</name>
MASS-LINK	12				
PERLND PWAT	ER SURO	0.083333	COPY	INPUT	MEAN
END MASS-LINK	12				
MASS-LINK	13				
	ER IFWO	0.083333	COPY	INPUT	MEAN
END MASS-LINK	13				
MASS-LINK	15				
IMPLND IWAT		0.083333	COPY	INPUT	MEAN
END MASS-LINK	15				

END MASS-LINK

END RUN

### Mitigated UCI File

RUN

```
GLOBAL
 WWHM4 model simulation
 START 1901 10 01 END 2059 09 30 RUN INTERP OUTPUT LEVEL 3 0
 RESUME 0 RUN 1
                                  UNIT SYSTEM 1
END GLOBAL
FILES
<File> <Un#>
           <---->***
<-ID->
WDM
        26
            22085-wetland recharge ex conditions.wdm
MESSII
        25
           Mit22085-wetland recharge ex conditions.MES
        27
            Mit22085-wetland recharge ex conditions.L61
            Mit22085-wetland recharge ex conditions.L62
           POC22085-wetland recharge ex conditions1.dat
        30
END FILES
OPN SEQUENCE
   INGRP
           13
                 INDELT 00:15
    PERLND
    IMPLND
             11
    COPY
            501
    DISPLY
   END INGRP
END OPN SEQUENCE
DISPLY
 DISPLY-INFO1
   # - #<-----Title---->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND
   1 Basin 1
 END DISPLY-INFO1
END DISPLY
COPY
 TIMESERIES
  # - # NPT NMN ***
 1 1
501 1
             1
               1
 END TIMESERIES
END COPY
GENER
 OPCODE
  # # OPCD ***
 END OPCODE
 PARM
 #
           K ***
 END PARM
END GENER
PERLND
 GEN-INFO
  <PLS ><----Name---->NBLKS Unit-systems Printer ***
                        User t-series Engl Metr ***
  # - #
                         C, Pasture, Flat
                                         27
 END GEN-INFO
 *** Section PWATER***
   <PLS > ******** Active Sections *********************
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
13 0 0 1 0 0 0 0 0 0 0 0
 END ACTIVITY
 PRINT-INFO
   END PRINT-INFO
```

```
PWAT-PARM1
  <PLS > PWATER variable monthly parameter value flags ***
  END PWAT-PARM1
 PWAT-PARM2
  <PLS >
  13
 END PWAT-PARM2
 PWAT-PARM3
  <PLS > PWATER input info: Part 3 ***
  # - # ***PETMAX PETMIN INFEXP
0 0 2
                                 INFILD DEEPFR BASETP AGWETP 2 0 0 0
                                2
                                       0 0
  13
 END PWAT-PARM3
 PWAT-STATE1
  <PLS > *** Initial conditions at start of simulation
         ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
      # *** CEPS SURS UZS IFWS LZS AGWS 0 0 0 0 2.5 1
                                                       GWVS
  13 0
 END PWAT-STATE1
END PERLND
IMPLND
 GEN-INFO
  <PLS ><-----> Unit-systems Printer ***
                      User t-series Engl Metr ***
                         in out
1 1 1 27 0
 11 PARKING/FLAT
 END GEN-INFO
 *** Section IWATER***
 ACTIVITY
  <PLS > ******** Active Sections *********************
  # - # ATMP SNOW IWAT SLD IWG IQAL ***
11 0 0 1 0 0 0
 END ACTIVITY
 PRINT-INFO
  <ILS > ****** Print-flags ****** PIVL PYR
  # - # ATMP SNOW IWAT SLD IWG IQAL ********
11 0 0 4 0 0 0 1 9
 END PRINT-INFO
 IWAT-PARM1
  <PLS > IWATER variable monthly parameter value flags ***
  # - # CSNO RTOP VRS VNN RTLI ***
11 0 0 0 0 0
 END IWAT-PARM1
 IWAT-PARM2
  END IWAT-PARM2
 IWAT-PARM3
          IWATER input info: Part 3
  <PLS >
   # - # ***PETMAX PETMIN
1 0 0
```

```
IWAT-STATE1
   <PLS > *** Initial conditions at start of simulation
   # - # *** RETS SURS
  11 0
                    0
 END IWAT-STATE1
END IMPLND
SCHEMATIC
                     <--Area--> <-Target-> MBLK ***
<-factor-> <Name> # Tbl# ***
<-Source->
<Name> #
Basin 1***
                           0.5 COPY 501 12
0.5 COPY 501 13
2.25 COPY 501 15
PERLND 13
PERLND 13
IMPLND 11
*****Routing*****
END SCHEMATIC
NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
END NETWORK
RCHRES
 GEN-INFO
  RCHRES Name Nexits Unit Systems Printer
                                                               * * *
  # - #<----- User T-series Engl Metr LKFG
                                                               * * *
                                                               * * *
                                   in out
 END GEN-INFO
 *** Section RCHRES***
 ACTIVITY
   <PLS > ******** Active Sections **********************
   # - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***
 END ACTIVITY
 PRINT-INFO
   <PLS > ******** Print-flags ******** PIVL PYR
   # - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR ********
 END PRINT-INFO
 HYDR-PARM1
   RCHRES Flags for each HYDR Section
                                                               * * *
   END HYDR-PARM1
 HYDR-PARM2
  # - # FTABNO LEN DELTH STCOR
                                          KS DB50
 <----><----><---->
 END HYDR-PARM2
 HYDR-INIT
   RCHRES Initial conditions for each HYDR section
 # - # *** VOL Initial value of COLIND Initial value of OUTDGT

*** ac-ft for each possible exit for each possible exit

<----> <---> <---> *** <---> *** <---> ***
 END HYDR-INIT
END RCHRES
```

SPEC-ACTIONS

END IWAT-PARM3

END SPEC-ACTIONS FTABLES END FTABLES

#### EXT SOURCES

<-Volume-	->	<member></member>	SsysSgar	o <mult>Tran</mult>	<-Target	vols>	<-Grp>	<-Member->	* * *
<name></name>	#	<name> #</name>	tem str	g<-factor->strg	<name></name>	# #		<name> # #</name>	* * *
WDM	2	PREC	ENGL	1	PERLND	1 999	EXTNL	PREC	
WDM	2	PREC	ENGL	1	IMPLND	1 999	EXTNL	PREC	
WDM	1	EVAP	ENGL	1	PERLND	1 999	EXTNL	PETINP	
WDM	1	EVAP	ENGL	1	IMPLND	1 999	EXTNL	PETINP	

END EXT SOURCES

#### EXT TARGETS

		_											
<-Volum	ne->	<-Grp>	<-Membe	er-	-> <mu< td=""><td>ılt&gt;Tran</td><td>&lt;-Volum</td><td>ne-&gt;</td><td><member></member></td><td>Tsys</td><td>Tgap</td><td>Amd **</td><td>*</td></mu<>	ılt>Tran	<-Volum	ne->	<member></member>	Tsys	Tgap	Amd **	*
<name></name>	#		<name></name>	#	#<-fac	ctor->strg	<name></name>	#	<name></name>	tem	strg	strg**	*
COPY	1	OUTPUT	MEAN	1	1	48.4	WDM	701	FLOW	ENGL		REPL	
COPY	501	OUTPUT	MEAN	1	1	48.4	WDM	801	FLOW	ENGL		REPL	
END EXT	TAI	RGETS											

#### MASS-LINK

<volume> &lt;-Grp&gt; <name></name></volume>	<-Member-> <name> # #</name>		<target> <name></name></target>	<-Grp>	<-Member->*** <name> # #***</name>
MASS-LINK	12				
PERLND PWATER	SURO	0.083333	COPY	INPUT	MEAN
END MASS-LINK	12				
MASS-LINK PERLND PWATER END MASS-LINK	13 IFWO 13	0.083333	COPY	INPUT	MEAN
MASS-LINK IMPLND IWATEF END MASS-LINK	15 SURO 15	0.083333	COPY	INPUT	MEAN

END MASS-LINK

END RUN



# Mitigated HSPF Message File

## Disclaimer

### Legal Notice

This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2023; All Rights Reserved.

Clear Creek Solutions, Inc. 6200 Capitol Blvd. Ste F Olympia, WA. 98501 Toll Free 1(866)943-0304 Local (360)943-0304

www.clearcreeksolutions.com

# Tab 5.0

### 5.0 CONVEYANCE SYSTEM ANALYSIS AND DESIGN

The conveyance system for this project will consist of a series of catch basins and storm drainage conveyance pipes. This system will convey the stormwater runoff from the developed site to the proposed detention vault located on the west side of the property. Pipe sizing calculations will be included with the permit submittal plans.

# **Tab 6.0**

### 6.0 SPECIAL REPORTS AND STUDIES

The following special reports and studies are included in this section:


Geotechnical Report

Figure 8
Geotechnical
Report

## **GEOTECHNICAL REPORT**

240 – 15th Street SE Industrial 240 – 15th Street Southeast Puyallup, Washington

Project No. T-8661




# Terra Associates, Inc.

## Prepared for:

Cref3 Puyallup Owner, LLC Los Angeles, California

**January 12, 2022 Revised June 23, 2023** 



# TERRA ASSOCIATES, Inc.

Consultants in Geotechnical Engineering, Geology and Environmental Earth Sciences

> January 12, 2022 Revised June 23, 2023 Project No. T-8661

Mr. Michael Cohn Cref3 Puyallup Owner, LLC 11611 San Vicente Boulevard, 10th Floor Los Angeles, California 90049

Subject:

Geotechnical Report

240 – 15th Street SE Industrial 240 – 15th Street Southeast Puyallup, Washington

Dear Mr. Cohn:

As requested, we have conducted a geotechnical engineering study for the subject project. The attached report presents our findings and recommendations for the geotechnical aspects of project design and construction.

The native soils observed in the test borings are alluvial deposits generally consisting of loose to medium dense, wet, fine sand, silty fine sand, and silt with varying proportions of fine sand. The CPT data shows similar interbedded alluvial soils extending to a depth of about 80 feet. Groundwater levels at the site range between depths of about two and one-half feet and five feet. In our opinion, the soil and groundwater conditions observed at the site would not preclude the proposed development provided the recommendations contained herein are incorporated into design and construction.

We trust the information presented in this report is sufficient for your current needs. If you have any questions or require additional information, please call.

Sincerely yours,

TERRA ASSOCIATES, INC.

John G. Salley, L.E.G., L.H.G.

6-23-2023

#### TABLE OF CONTENTS

2.0       Scope of Work       1         3.0       Site Conditions       2         3.1       Surface       2         3.2       Soils       2         3.3       Groundwater       3         3.4       Seismic Site Class       3         3.5       Geologic Hazards       4         3.5.1       Seismic Hazards       4         3.5.2       Volcanic Hazards       5         4.0       Discussion and Recommendations       5         4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figur			Page No
2.0       Scope of Work	1.0	Project	Description 1
3.0   Site Conditions   2   3.1   Surface   2   3.2   Soils   2   2   3.3   Groundwater   3   3.4   Seismic Site Class   3   3.5   Geologic Hazards   4   3.5.1   Seismic Hazards   4   3.5.2   Volcanic Hazards   5   4.0   Discussion and Recommendations   5   4.1   General   5   4.2   Site Preparation and Grading   6   4.3   Preload   7   4.4   Excavations   8   4.5   Foundations   8   4.5   Foundations   8   4.6   Lateral Earth Pressures for Retaining Walls   9   4.7   Slab-on-Grade Floors   9   4.8   Drainage   10   4.9   Infiltration Feasibility   10   4.10   Utilities   10   4.11   Pavements   11   5.0   Additional Services   12   Exploration Location Plan   Figure 2   Typical Settlement Marker Detail   Figure 3   Figure 4   Appendices   Figure 4   Appendices   Figure 4   Appendical   Figure 4   Appendical   Appendix A   Appendix Appe	2.0		
3.1       Surface	3.0		
3.2       Soils       2         3.3       Groundwater       3         3.4       Seismic Site Class       3         3.5       Geologic Hazards       4         3.5.1       Seismic Hazards       4         3.5.2       Volcanic Hazards       5         4.0       Discussion and Recommendations       5         4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Payements       11         5.0       Additional Services       12         Figures         Vicinity Map       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Settlement Marker Detail       Figure 4         Appen	5.0		
3.3       Groundwater       3         3.4       Seismic Site Class       3         3.5       Geologic Hazards       4         3.5.1       Seismic Hazards       4         3.5.2       Volcanic Hazards       5         4.0       Discussion and Recommendations       5         4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices <td></td> <td></td> <td></td>			
3.4       Seismic Site Class       3         3.5       Geologic Hazards       4         3.5.1       Seismic Hazards       4         3.5.2       Volcanic Hazards       5         4.0       Discussion and Recommendations       5         4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices <td></td> <td>_</td> <td></td>		_	
3.5       Geologic Hazards       .4         3.5.1       Seismic Hazards       .4         3.5.2       Volcanic Hazards       .5         4.0       Discussion and Recommendations       .5         4.1       General       .5         4.2       Site Preparation and Grading       .6         4.3       Preload       .7         4.4       Excavations       .8         4.5       Foundations       .8         4.6       Lateral Earth Pressures for Retaining Walls       .9         4.7       Slab-on-Grade Floors       .9         4.8       Drainage       .10         4.9       Infiltration Feasibility       .10         4.10       Utilities       .10         4.11       Pavements       .11         5.0       Additional Services       .12         6.0       Limitations       .12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices			
3.5.1   Seismic Hazards		_	
3.5.2 Volcanic Hazards		5.5	
4.0       Discussion and Recommendations       5         4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices          Field Exploration and Laboratory Testing       Appendix A			
4.1       General       5         4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A	4.0	Discus	
4.2       Site Preparation and Grading       6         4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A			
4.3       Preload       7         4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A			
4.4       Excavations       8         4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A			
4.5       Foundations       8         4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A		_	
4.6       Lateral Earth Pressures for Retaining Walls       9         4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A			
4.7       Slab-on-Grade Floors       9         4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A		_	
4.8       Drainage       10         4.9       Infiltration Feasibility       10         4.10       Utilities       10         4.11       Pavements       11         5.0       Additional Services       12         6.0       Limitations       12         Figures         Vicinity Map       Figure 1         Exploration Location Plan       Figure 2         Typical Settlement Marker Detail       Figure 3         Typical Wall Drainage Detail       Figure 4         Appendices         Field Exploration and Laboratory Testing       Appendix A		_	
4.9 Infiltration Feasibility 10 4.10 Utilities 10 4.11 Pavements 11 5.0 Additional Services 12 6.0 Limitations 12  Figures  Vicinity Map Figure 1 Exploration Location Plan Figure 2 Typical Settlement Marker Detail Figure 3 Typical Wall Drainage Detail Figure 4  Appendices  Field Exploration and Laboratory Testing Appendix A			
4.10 Utilities		_	
4.11 Pavements		_	
5.0 Additional Services			
Figures  Vicinity Map Figure 1 Exploration Location Plan Figure 2 Typical Settlement Marker Detail Figure 3 Typical Wall Drainage Detail Figure 4  Appendices  Field Exploration and Laboratory Testing Appendix A	5.0	Additio	
Vicinity Map	6.0		
Exploration Location Plan Figure 2 Typical Settlement Marker Detail Figure 3 Typical Wall Drainage Detail Figure 4  Appendices  Field Exploration and Laboratory Testing Appendix A	<u>Figures</u>		
Exploration Location Plan Figure 2 Typical Settlement Marker Detail Figure 3 Typical Wall Drainage Detail Figure 4  Appendices  Field Exploration and Laboratory Testing Appendix A	Vioinite	Mon	Eigung 1
Typical Settlement Marker Detail			
Typical Wall Drainage Detail			
Appendices Field Exploration and Laboratory Testing			
Field Exploration and Laboratory Testing	1 ypicai	wan Dra	image Detail Figure 4
	Append	<u>ices</u>	
	Field Ev	nlaration	and Laboratory Testing
Liquefaction Analyses Appendix B			

## Geotechnical Report 240 – 15th Street SE Industrial 240 – 15th Street Southeast Puyallup, Washington

#### 1.0 PROJECT DESCRIPTION

The proposed project is an industrial development consisting of a warehouse-style building and associated paved access, parking, and utility improvements. A conceptual site plan by Mackenzie, dated September 27, 2021, shows a 131,250 square-foot building in the central portion of the site. Truck and trailer parking is shown on the northern and western sides of the building, respectively. Passenger vehicle parking is shown on the eastern side of the building. Building plans are currently not available; however, we expect the building will be constructed using precast concrete tilt-up perimeter wall panels with interior columns spaced at 30 to 50 feet. Building floors will be constructed at grade with dock high access on the northern side of the building. Structural loading is expected to be light to moderate, with isolated columns carrying loads of 50 to 100 kips, and bearing walls carrying 4 to 8 kips per foot.

The recommendations in this report are based on our understanding of the design features outlined above. We should review design drawings as they become available to verify that our recommendations have been properly interpreted and to supplement them, if required.

#### 2.0 SCOPE OF WORK

Our scope of work for this project included subsurface exploration, laboratory testing, office review, engineering analysis, and preparation of this report. Our subsurface exploration included ten test borings drilled to maximum depths of 6.5 feet and 31.5 feet with a limited access, track-mounted drill rig using hollow-stem auger drilling methods, one approximately 60-foot deep cone penetration test (CPTs), and one approximately 84-foot deep CPT.

Using the results of our subsurface explorations and laboratory testing, analyses were undertaken to develop geotechnical recommendations for project design and construction. Specifically, this report addresses the following:

- Soil and groundwater conditions.
- Geologic hazards per the City of Puyallup Municipal Code.
- Seismic Site Class.
- Site preparation and grading including recommendations for building preload or surcharge to mitigate floor and foundation settlement.

- Excavations.
- Foundations.
- Slab-on-grade floors.
- Lateral earth pressures for wall design.
- Subsurface drainage.
- Infiltration feasibility.
- Utilities.
- Pavement.

#### 3.0 SITE CONDITIONS

#### 3.1 Surface

The site is an approximately 8.74-acre assemblage of three parcels located northwest of and adjacent to the intersection of 15th Street Southeast and East Pioneer Avenue in Puyallup, Washington. The site location is shown on Figure 1.

Existing site improvements include a small office building in the northeastern portion of the site, a vacant industrial building in the southeast corner of the site, and the remains of a large cold-storage warehouse in the central portion of the site that was recently destroyed by fire. Areas around the buildings are typically surfaced with asphalt or concrete pavement or crushed gravel. An open area of the site located west of the cold storage building is an undeveloped grass field. Site topography is relatively flat.

#### 3.2 Soils

The native soils observed in the test borings are alluvial deposits generally consisting of loose to medium dense, wet, fine sand, silty fine sand, and silt with varying proportions of fine sand and traces of fine organic particles. Fine-grained sand deposits encountered between depths of 20 and 21.5 feet in Borings B-1, B-2, B-6, and B-10 contained numerous fine pumice grains.

The upper approximately 3 to 4 feet of soil encountered in Borings B-7 through B-10 consists of loose to medium dense, silty fine sand that is interpreted to be fill. The fill materials observed in Borings B-7 and B-10 contain numerous wood shavings or fragments.

The CPT data shows interbedded alluvial soils extending the full 60-foot depth of CPT-2 and to a depth of about 80 feet in CPT-1. Soil behavior types determined from the CPT data generally consist of about 30 feet of sand to silty sand and silty sand to sandy silt with scattered clayey silt to silty clay interbeds underlain primarily by interbedded sandy silt to silty clay. A soil behavior type consistent with gravelly sand to sand was encountered below a depth of about 80 feet in CPT-1. In general, where cohesive silt and clay soils are indicated, correlated N<sub>60</sub> values, indicate consistencies in the medium stiff to stiff range above a depth of about 72 feet and stiff to very stiff below that depth. Where cohesionless sand, silty sand, and silt soils are indicated, correlated N<sub>60</sub> values indicate relative densities typically in the loose to medium dense range. The soil conditions determined from the CPTs are generally consistent with those observed in the test borings.

The Geologic map of the Tacoma 1:100,000-scale quadrangle, Washington, by J.E. Schuster (2015), shows surficial geology at the site mapped as Holocene alluvium (Qa). The soils observed in our subsurface explorations are consistent with this geologic map unit.

Detailed descriptions of the conditions observed in our subsurface explorations are given on the Boring Logs in Appendix A. The CPT data plots are also attached in Appendix A. The approximate test boring and CPT locations are shown on Figure 2.

#### 3.3 Groundwater

Groundwater was encountered in all of the test borings with groundwater levels typically encountered below a depth of about 5 feet. Pore pressure dissipation testing performed in CPT-2 determined a hydrostatic level approximately 5 feet below ground surface as well. Borings B-3 through B-5 and Boring B-7 all encountered wet soils below depths of about 2.5 to 3 feet.

The depths to groundwater at the site will fluctuate on a seasonal basis with maximum levels occurring during the wet winter and spring months. Considering that our field work occurred during late November, we expect that the observed groundwater levels are approaching seasonal high levels.

#### 3.4 Seismic Site Class

Soil conditions at the site, as discussed in the following section, will be subject to the soil liquefaction phenomenon. Because of this condition, per the current International Building Code (IBC), subsurface conditions would be assigned site class "F" which would require performing a site-specific seismic analysis to determine seismic forces for structural design. However, the IBC allows for using code derived seismic values for the soil conditions indicated if the building's fundamental period is equal to or less than 0.5 seconds. We expect that the proposed industrial building will fall into this category. In this case, based on soil conditions encountered and our knowledge of the area geology, site class "D" can be used to determine seismic design forces.

#### 3.5 Geologic Hazards

Chapter 21.06.1210(1) of the Puyallup Municipal Code (PMC) defines geologic hazard areas as "...areas susceptible to erosion, landsliding, earthquake, volcanic activity or other potentially hazardous geological processes." Site conditions do not meet the PMC criteria defining landslide hazard areas or erosion hazard areas. In our opinion, site conditions are susceptible to potential seismic and volcanic hazards as discussed below.

#### 3.5.1 Seismic Hazards

Chapter 21.06.1210(3)(c) of the PMC defines seismic hazard areas as "...areas subject to severe risk of damage as a result of earthquake-induced ground shaking, slope failure, settlement or subsidence, soil liquefaction, or tsunamis. Settlement and soil liquefaction conditions occur in areas underlain by cohesionless, loose, or soft-saturated soils of low density, typically in association with a shallow ground water table."

The site conditions are not susceptible to seismically-induced slope failure and the site is not located within an area that is susceptible to tsunamis inundation. In our opinion, potential hazards associated with ground shaking would be adequately mitigated by designing with seismic forces determined by local building codes or site specific seismic analysis, if needed.

Liquefaction is a phenomenon where there is a reduction or complete loss of soil strength due to an increase in water pressure induced by vibrations. Liquefaction mainly affects geologically recent deposits of fine-grained sands underlying the groundwater table. Soils of this nature derive their strength from intergranular friction. The generated water pressure or pore pressure essentially separates the soil grains and eliminates this intergranular friction; thus, eliminating the soil's strength.

We completed a liquefaction analysis using the computer program LiquefyPro published by CivilTech Corporation. The analysis was completed using a site modified peak ground acceleration (PGA<sub>M</sub>) of 0.60g representing the peak horizontal acceleration for the maximum considered earthquake (MCE) having a 2 percent probability of exceedance 50 The value was obtained for Latitude 47.18978287°N in years. Longitude -122.27573704°W using the Structural Engineers Association of California (SEAOC) U.S. Seismic Design Maps website (https://seismicmaps.org/) accessed on December 27, 2021. The results of the liquefaction analysis are attached in Appendix B.

The results of our analysis indicate the site is a seismic hazard area with respect to soil liquefaction. Soil liquefaction could occur during the design earthquake event resulting in total settlements ranging between about four and one-half and seven inches with about one-half of this settlement likely being differential in nature. In our opinion, this amount of settlement has the potential to structurally impair the building. The structural engineer should review the estimated settlement to determine if additional mitigation measures are necessary. Additionally, cosmetic damage to the structure in the form of misaligned doors and windows, cracking, and floor settlement could occur. Some utility connections may also be impacted. If the owner is not willing to accept the risk of building damage requiring repair should liquefaction-induced settlements occur, foundations should be supported on ground improved using stone columns designed to mitigate soil liquefaction settlements below the building foundations.

#### 3.5.2 Volcanic Hazards

Chapter 21.06.1210(3)(d) of the PMC defines volcanic hazard areas as "...areas subject to pyroclastic flows, lava flows, debris avalanche, inundation by debris flows, lahars, mudflows, or related flooding resulting from volcanic activity. Volcanic hazard areas shall be classified as Case I or Case II lahars per the definitions in PMC 21.06.210." The site is located in a potential Case II lahar inundation zone. Therefore, per the PMC, the site is considered a volcanic hazard area.

#### 4.0 DISCUSSION AND RECOMMENDATIONS

#### 4.1 General

In our opinion, there are no geotechnical considerations that would preclude development of the site as planned. The fine-grained native soils observed at the site will consolidate under static dead loads imposed by the structure and by product loading on structure floor slabs. To mitigate the potential for post-construction settlement due to this consolidation, we recommend preloading the building location. Preloading will involve placing the structural fill required to achieve the finish floor elevation and allowing settlements to occur under this load before building construction is initiated. We expect that these settlements would occur in about two to four weeks following full application of the building fill.

The preloading program will adequately mitigate post-construction settlement under static loading but will not eliminate the risk of damage resulting from seismically-induced soil liquefaction. If the owner is not willing to accept the risk of building damage requiring repair should liquefaction-induced settlements occur, foundations should be supported on ground improved using stone columns designed to mitigate soil liquefaction settlements below the building foundations. The use of stone columns to improve the foundation subgrade would preclude the need for preloading.

After completing the preload, building construction can begin. The buildings can be supported on conventional spread footings bearing on a minimum of two feet of compacted structural fill. Overexcavation of native soils and replacement with structural fill will likely be required where deeper footing depths are required, such as below the perimeter foundations adjacent to the loading dock areas or where perimeter footings are deepened for seismic resistance. In our opinion, mitigation of the weak subgrade soils in paved areas will require cement amending or excavation and replacement with imported gravel base material.

The native soils encountered at the site contain a sufficient percentage of fines that will make it difficult to compact as structural fill when too wet. The ability to use soils from site excavations as structural fill will depend on the soil moisture content and the prevailing weather conditions at the time of construction. The contractor should be prepared to dry the native soils by aeration during the normally dry summer season to facilitate compaction as structural fill. Alternatively, stabilizing the moisture in the native soil with cement or lime can be considered. If grading activities will take place during the winter season, the contractor should be prepared to import clean granular material for use as structural fill and backfill.

The following sections provide detailed recommendations regarding the above issues and other geotechnical design considerations. These recommendations should be incorporated into the final design drawings and construction specifications.

#### 4.2 Site Preparation and Grading

In general, it will not be necessary to strip the organic surface layer where structural fill thicknesses above existing grade are a minimum of 3 feet and 2 feet in building and pavement areas, respectively. However, existing surface vegetation, such as that in the western portion of the site, should be mowed close to the ground with the cut debris removed from the site. Clearing of trees should include removal of the entire tree root ball. Where structural fill thicknesses are less than the recommended minimums, both the organic surface soil and vegetation should be stripped from below building and pavement areas. In this case surface stripping depths of four to six inches should be expected. Topsoil will not be suitable for use as structural fill, but can be used in landscaped areas.

We recommend removing existing building foundations and slabs and abandoning underground septic systems and other buried utilities from the planned development area. Abandoned utility pipes that fall outside of new building areas can be left in place provided they are sealed to prevent intrusion of groundwater seepage and soil.

Prior to placing fill or constructing footings, all exposed bearing surfaces should be observed by a representative of Terra Associates, Inc. to verify that soil conditions are as expected and suitable for support of new fill or building elements. Our representative may request proofrolling the exposed subgrade for pavement and floor slab support with a loaded ten yard dump truck. If unstable soils are observed and cannot be stabilized in place by compaction, the affected soils should be excavated and removed to firm bearing and grade restored with new structural fill.

All building footings should obtain support on a minimum of two feet of granular structural fill. The fill should extend laterally from the edge of footing a minimum distance of one-foot. Based on planned grades, for normal perimeter footings bearing at the frost depth and interior footings immediately below the slab-on-grade floor, we expect that this requirement will be met over most of the building area with the fill depth required to achieve the design floor elevations. Deeper footings such as the perimeter footings adjacent the loading docks and for shear walls may require some overexcavation and grade restoration with structural fill.

Our study indicates that the native soils contain a sufficient percentage of fines (silt and clay size particles) that will make them difficult to compact as structural fill if they are too wet or too dry. Accordingly, the ability to use these native soils from site excavations as structural fill will depend upon their moisture content and the prevailing weather conditions when site grading activities take place. Native soils that are too wet to properly compact could be dried by aeration during dry weather conditions or mixed with an additive such as cement or lime to stabilize the soil and facilitate compaction. If an additive is used, additional Best Management Practices (BMPs) for its use will need to be incorporated into the Temporary Erosion and Sedimentation Control plan (TESC) for the project. If grading activities are planned during the wet winter months, and the onsite soils become too wet to achieve adequate compaction, the owner or contractor should be prepared to treat soils with lime, cement, or import wet weather structural fill.

For this purpose, we recommend importing a granular soil that meets the following grading requirements:

U.S. Sieve Size	Percent Passing
6 inches	100
No. 4	75 maximum
No. 200	5 maximum*

<sup>\*</sup>Based on the 3/4-inch fraction

Prior to use, Terra Associates, Inc. should examine and test all materials to be imported to the site for use as structural fill. If building subgrades were constructed using native soils and will be exposed during wet weather, it would be advisable to place 12 inches of this granular structural fill on the building pad to prevent deterioration of the floor subgrade.

Structural fill should be placed in uniform loose layers not exceeding 12 inches and compacted to a minimum of 95 percent of the soil's maximum dry density, as determined by American Society for Testing and Materials (ASTM) Test Designation D-698 (Standard Proctor). The moisture content of the soil at the time of compaction should be within two percent of its optimum, as determined by this same ASTM standard. In nonstructural areas the degree of compaction can be reduced to 90 percent.

#### 4.3 Preload

We recommend preloading the building areas to limit building and floor slab settlements to tolerable levels. For this procedure, we recommend placing structural fill in the building areas to the design floor elevation, and delaying building construction until settlement under this fill load has occurred. The preload fill should extend a minimum of five feet beyond the building perimeter. A minimum of three feet of fill should be placed. If this fill depth exceeds that required to achieve design floor grade, the surplus depth would be treated as a surcharge and removed following completion of settlement as indicated by survey readings at settlement markers as discussed below.

Total settlement under the building fill is estimated in the range of one to three inches. These settlements are expected to occur in about three to four weeks following full application of the building fill.

To verify the amount of settlement and the time rate of movement, the preload program should be monitored by installing settlement markers. The settlement markers should be installed on the existing grade prior to placing any building or preload fills. Once installed, elevations of both the fill height and marker should be taken daily until the full height of the preload is in place. Once fully preloaded, readings should continue weekly until the anticipated settlements have occurred. A typical settlement marker detail is provided as Figure 3.

It is critical that the grading contractor recognize the importance of the settlement marker installations. All efforts must be made to protect the markers from damage during fill placement. It is difficult, if not impossible, to evaluate the progress of the preload program if the markers are damaged or destroyed by construction equipment. As a result, it may be necessary to install new markers and extend the surcharging time period in order to ensure that settlements have ceased and building construction can begin.

Following the successful completion of the preload program, with foundations designed as recommended in Section 4.5 of this report, you should expect maximum total and differential post-construction static settlements of 0.5 inches for perimeter foundations and 1 inch for interior columns.

#### 4.4 Excavations

All excavations at the site associated with confined spaces, such as lower building level retaining walls, must be completed in accordance with local, state, or federal requirements. Based on current Washington Industrial Safety and Health Act (WISHA) regulations, the site soils would be classified as a Type C soil.

For properly dewatered excavations in Type C soils that are greater than 4 feet and less than 20 feet in depth, the side slopes should be laid back at an inclination of 1.5:1 (Horizontal:Vertical) or flatter. If there is insufficient room to complete the excavations in this manner, or if excavations greater than 20 feet in depth are planned, using temporary shoring to support the excavations may need to be considered.

Based on our study, groundwater seepage should be anticipated within excavations extending below depths of about two and one-half to five feet. Excavations extending below these depths will likely encounter groundwater seepage with volumes and flow rates sufficient to require some level of dewatering. Shallow excavations that do not extend more than two feet below the groundwater table can likely be dewatered by conventional sump-pumping procedures along with a system of collection trenches. Deeper excavations will likely require dewatering by well points or isolated deep-pump wells. The utility subcontractor should be prepared to implement excavation dewatering by well point or deep-pump wells, as needed. This will be an especially critical consideration for any deep excavations such as stormwater detention vaults, lift stations, and sanitary sewer tie-ins.

This information is provided solely for the benefit of the owner and other design consultants and should not be construed to imply that Terra Associates, Inc. assumes responsibility for job site safety. It is understood that job site safety is the sole responsibility of the project contractor.

#### 4.5 Foundations

In our opinion, following the completion of a successful preload program, the building may be supported on conventional spread footing foundations bearing on a minimum of 2 feet of structural fill placed and compacted as recommended in Section 4.2 of this report. Foundations exposed to the weather should bear at a minimum depth of one and one-half feet below adjacent grades for frost protection.

We recommend designing foundations for a net allowable bearing capacity of 2,500 pounds per square foot (psf). For short-term loads, such as wind and seismic, a one-third increase in this allowable capacity can be used. With the expected building loads and this bearing stress applied, in general, total and differential settlements should not exceed 0.5 inches for perimeter foundations and 1 inch for interior column supports.

For designing foundations to resist lateral loads, a base friction coefficient of 0.35 can be used. Passive earth pressures acting on the sides of the footings can also be considered. We recommend calculating this lateral resistance using an equivalent fluid weight of 300 pounds per cubic foot (pcf). We do not recommend including the upper 12 inches of soil in this computation because it can be affected by weather or disturbed by future grading activity. This value assumes the foundation will be constructed neat against competent native soil or backfilled with structural fill, as described in Section 4.2 of this report. The values recommended include a safety factor of 1.5.

#### 4.6 Lateral Earth Pressures for Retaining Walls

The magnitude of earth pressure development on below-grade walls, such as basement or retaining walls, will partly depend upon the quality of the wall backfill. We recommend placing and compacting wall backfill as structural fill as described in Section 4.2 of this report. To guard against hydrostatic pressure development, drainage must be installed behind the wall. A typical wall drainage detail is shown on Figure 4.

With wall backfill placed and compacted as recommended and drainage properly installed, unrestrained walls can be designed for an active earth pressure equivalent to a fluid weighing 35 pcf. For restrained walls, an additional uniform lateral pressure of 100 psf should be included. For evaluating the walls under seismic loading, a uniform earth pressure equivalent to 8H psf, where H is the height of the retained earth in feet, can be used. These values assume a horizontal backfill condition and that no other surcharge loading, such as traffic, sloping embankments, or adjacent buildings, will act on the wall. If such conditions exist, then the imposed loading must be included in the wall design.

Friction at the base of the wall foundation and passive earth pressure will provide resistance to these lateral loads. Values for these parameters are provided in Section 4.5.

#### 4.7 Slab-on-Grade Floors

Slab-on-grade floors may be supported on subgrades prepared as recommended in Section 4.2 of this report. Immediately below the floor slabs, we recommend placing a 4-inch thick capillary break layer of clean, free-draining, coarse sand or fine gravel that has less than 5 percent passing the No. 200 sieve. This material will reduce the potential for upward capillary movement of water through the underlying soil and subsequent wetting of the floor slabs.

The capillary break layer will not prevent moisture intrusion through the slab caused by water vapor transmission. Where moisture by vapor transmission is undesirable, such as covered floor areas, a common practice is to place a durable plastic membrane on the capillary break layer and then cover the membrane with a layer of clean sand or fine gravel to protect it from damage during construction, and aid in uniform curing of the concrete slab.

It should be noted that if the sand or gravel layer overlying the membrane is saturated prior to pouring the slab, it will be ineffective in assisting in uniform curing of the slab and can actually serve as a water supply for moisture transmission through the slab and affecting floor coverings. Therefore, in our opinion, covering the membrane with a layer of sand or gravel should be avoided if floor slab construction occurs during the wet winter months and the layer cannot be effectively drained. We recommend floor designers and contractors refer to the American Concrete Institute (ACI) Manual of Concrete Practice for further information regarding vapor barrier installation below slab-on-grade floors.

For design of the floor slabs on grade, a subgrade modulus (k<sub>s</sub>) of 100 pounds per cubic inch (pci) can be used.

#### 4.8 Drainage

#### Surface

Final exterior grades should promote free and positive drainage away from the building at all times. Water must not be allowed to pond or collect adjacent to foundations or within the immediate building area. We recommend providing positive gradient away from the building perimeter.

#### Subsurface

We expect that building floor elevations will be above existing surface grades and that permanent hard surfaces will extend to the building over most of its perimeter. With these conditions, it is our opinion that building foundation drains would not be required. However, footing drains associated with retaining wall drainage, such as loading dock walls should be installed. Foundation drains should also be installed where landscaping is adjacent to the building.

#### 4.9 Infiltration Feasibility

Based on the shallow seasonal water table and the fine-grained nature of the soils observed across the site, it is our opinion that infiltration is not a feasible option for stormwater management.

#### 4.10 Utilities

Utility pipes should be bedded and backfilled in accordance with American Public Works Associates (APWA) or local jurisdictional specifications. At a minimum, trench backfill should be placed and compacted as structural fill as described in Section 4.2 of this report. At the time of our study, soil moisture contents were generally above optimum; therefore, drying back or other means to condition the material will probably be necessary to facilitate proper compaction. If utility construction takes place during the winter, it may be necessary to import suitable wet weather fill for utility trench backfilling.

For any structure installed below a depth of approximately two and one-half feet, buoyancy effects must be considered. Buoyancy or uplift will be resisted by the weight of the structure and the weight of the soil overlying its foundation or cover. For backfill placed as structural fill, a soil unit weight of 110 pcf can be used.

Buoyancy, or an unbalanced hydrostatic head, will also impact the trench bottom stability. Where an unbalanced hydrostatic head exists in the trench excavation, the trench bottom can heave and, subsequently, become unstable causing installed utility pipes to settle when overburdened stresses from utility trench backfill are replaced.

Two methods for stabilizing the trench bottoms can be considered. The first involves using well point dewatering systems to lower the groundwater table adjacent to utility excavation and prevent development of an unbalanced hydrostatic head. Single-stage well point dewatering systems are typically effective for utility excavations occurring to depths of 15 to 20 feet.

The second method that can be used to mitigate heave or unstable soil conditions at the trench bottom involves overexcavation of the affected soils and replacement with additional free-draining bedding material. As a general rule, the depth of overexcavation below the pipe invert and replacement with free-draining bedding material would be equivalent to one foot for every two feet of unbalanced hydrostatic head.

#### 4.11 Pavements

Pavements should be constructed on subgrades prepared as recommended in Section 4.2 of this report. Regardless of the degree of relative compaction achieved, the subgrade must be firm and relatively unyielding before paving. Proofrolling the subgrade with heavy construction equipment should be completed to verify this condition.

The pavement design section is dependent upon the supporting capability of the subgrade soils and the traffic conditions to which it will be subjected. We expect traffic at the facility will consist of cars and light trucks, along with heavy traffic in the form of tractor-trailer-rigs. For design considerations, we have assumed traffic in parking and in car/light truck access pavement areas can be represented by an 18-kip Equivalent Single Axle Loading (ESAL) of 50,000 over a 20-year design life. For heavy traffic pavement areas, we have assumed an ESAL of 300,000 would be representative of the expected loading. These ESALs represent loading approximately equivalent to 3 and 18, loaded (80,000-pound GVW) tractor-trailer rigs traversing the pavement daily in each area, respectively.

With a stable subgrade prepared as recommended, for the design ESAL values, we recommend the following pavement sections:

Light Traffic/Car Access:

- 2 inches of hot mix asphalt (HMA) over 6 inches of crushed rock surfacing (CRS).
- 4 inches full depth HMA.

Heavy Traffic/Truck Access:

- 3 inches of HMA over 8 inches of CRS.
- 6 inches full depth HMA.

For exterior Portland cement concrete (PCC) pavement, we recommend the following:

- 6 inches of PCC over 2 inches of CRS.
  - 28-day compressive strength 4,000 psi.
  - o Control joints spaced at a maximum of 15 feet.

Soil cement stabilization or constructing a soil cement base for support of the pavement section can also be considered as an alternate to the above conventional pavement sections. Assuming a properly constructed soil cement base having a minimum thickness of 12 inches and a minimum 7-day compressive strength of 100 pounds per square inch (psi), the following pavement sections are recommended:

#### Light Traffic/Car Access:

• 2 inches of HMA over 12 inches of soil cement base (SCB).

#### Heavy Traffic/Truck Access:

- 3 inches of HMA over 12 inches of SCB.
- 6 inches of PCC over 12 inches of SCB.

The design of the soil cement base should be completed using samples of the subgrade exposed at the time of construction.

The paving materials used should conform to the Washington State Department of Transportation (WSDOT) specifications for ½-inch class HMA and CRS.

Long-term pavement performance will depend upon surface drainage. A poorly-drained pavement section will be subject to premature failure as a result of surface water infiltrating into the subgrade soils and reducing their supporting capability. For optimum pavement performance, we recommend surface drainage gradients of at least two percent. Some degree of longitudinal and transverse cracking of the pavement surface should be expected over time. Regular maintenance should be planned to seal cracks when they occur.


#### 5.0 ADDITIONAL SERVICES


Terra Associates, Inc. should review the final design and specifications in order to verify that earthwork recommendations have been properly interpreted and incorporated into project design and construction. We should also provide geotechnical services during construction in order to observe compliance with the design concepts, specifications, and recommendations. This will allow for design changes if subsurface conditions differ from those anticipated prior to the start of construction.

#### 6.0 LIMITATIONS

We prepared this report in accordance with generally accepted geotechnical engineering practices. This report is the property of Terra Associates, Inc. and is intended for specific application to the 240 – 15th Street SE Industrial project in Puyallup, Washington. This report is for the exclusive use of Fortress, LLC, and its authorized representatives.

The analyses and recommendations presented in this report are based upon data obtained from the subsurface explorations completed onsite. Variations in soil conditions can occur, the nature and extent of which may not become evident until construction. If variations appear evident, Terra Associates, Inc. should be requested to reevaluate the recommendations in this report prior to proceeding with construction.





THIS SITE PLAN IS SCHEMATIC. ALL LOCATIONS AND DIMENSIONS ARE APPROXIMATE. IT IS INTENDED FOR REFERENCE ONLY AND SHOULD NOT BE USED FOR DESIGN OR CONSTRUCTION PURPOSES.

#### REFERENCE:

MACKENZIE

#### LEGEND:



APPROXIMATE CPT LOCATION




# Terra Associates, Inc. Consultants in Geotechnical Engineering Geology and Environmental Earth Sciences

EXPLORATION LOCATION PLAN 240 - 15TH STREET SE INDUSTRIAL PUYALLUP, WASHINGTON

Proj. No.T-8661

Date JUNE 2023

Figure 2



#### NOT TO SCALE

#### NOTES:

- 1. BASE CONSISTS OF 3/4" THICK, 2'x2' PLYWOOD WITH CENTER DRILLED 5/8" DIAMETER HOLE.
- 2. BEDDING MATERIAL, IF REQUIRED, SHOULD CONSIST OF CLEAN COARSE SAND.
- 3. MARKER ROD IS 1/2" DIAMETER STEEL ROD THREADED AT BOTH ENDS.
- 4. MARKER ROD IS ATTACHED TO BASE BY NUT AND WASHER ON EACH SIDE OF BASE.
- 5. PROTECTIVE SLEEVE SURROUNDING MARKER ROD SHOULD CONSIST OF 2" DIAMETER PLASTIC TUBING. SLEEVE IS NOT ATTACHED TO ROD OR BASE.
- ADDITIONAL SECTIONS OF STEEL ROD CAN BE CONNECTED WITH THREADED COUPLINGS.
- ADDITIONAL SECTIONS OF PLASTIC PROTECTIVE SLEEVE CAN BE CONNECTED WITH PRESS-FIT PLASTIC COUPLINGS.
- 8. STEEL MARKER ROD SHOULD EXTEND AT LEAST 6" ABOVE TOP OF PLASTIC PROTECTIVE SLEEVE.
- 9. PLASTIC PROTECTIVE SLEEVE SHOULD EXTEND AT LEAST 1" ABOVE TOP OF FILL SURFACE.




# Terra Associates, Inc.

Consultants in Geotechnical Engineering Geology and Environmental Earth Sciences TYPICAL SETTLEMENT MARKER DETAIL 240 - 15TH STREET SE INDUSTRIAL PUYALLUP, WASHINGTON

Proj. No.T-8661

Date JUNE 2023


Figure 3



### **NOT TO SCALE**

#### NOTE:

MIRADRAIN G100N PREFABRICATED DRAINAGE PANELS OR SIMILAR PRODUCT CAN BE SUBSTITUTED FOR THE 12-INCH WIDE GRAVEL DRAIN BEHIND WALL. DRAINAGE PANELS SHOULD EXTEND A MINIMUM OF SIX INCHES INTO 12-INCH THICK DRAINAGE GRAVEL LAYER OVER PERFORATED DRAIN PIPE.



# Terra Associates, Inc. Consultants in Geotechnical Engineering

Consultants in Geotechnical Engineering Geology and Environmental Earth Sciences TYPICAL WALL DRAINAGE DETAIL 240 - 15TH STREET SE INDUSTRIAL PUYALLUP, WASHINGTON

Proj. No.T-8661

Date JUNE 2023

Figure 4

#### **APPENDIX A**

#### FIELD EXPLORATION AND LABORATORY TESTING

# 240 – 15th Street SE Industrial Puyallup, Washington

We explored subsurface conditions at the site by drilling six 31.5-foot deep test borings and four 6.5-foot deep test borings with a track-mounted drill rig using hollow-stem auger drilling methods, and by conducting two cone penetration tests (CPTs) to maximum depths of about 60 feet and about 84 feet. The test boring and CPT locations were approximately determined in the field by pacing and sighting from existing site features. The test boring and CPT locations are shown on Figure 2. The Boring Logs are presented as Figures A-2 through A-11.

An engineering geologist from our office conducted the field exploration. Our representative classified the soil conditions encountered, maintained a log of each boring, obtained representative soil samples, and recorded groundwater levels observed during drilling. Soil samples were obtained during drilling in general accordance with ASTM Test Designation D-1586. Using this procedure, a 2-inch (outside diameter) split barrel sampler is driven into the ground 18 inches using a 140-pound hammer free falling a height of 30 inches the number of blows required to drive the sampler 12 inches after an initial 6-inch set is referred to as the Standard Penetration Resistance value or N value. This is an index related to the consistency of cohesive soils and relative density of cohesionless materials. N values obtained for each sampling interval are recorded on the Boring Logs. All soil samples were visually classified in accordance with the Unified Soil Classification System (USCS) described on Figure A-1.

Representative soil samples obtained from the test borings were placed in sealed plastic bags and taken to our laboratory for further examination and testing. The moisture content of each sample was measured and is reported on the Boring Logs. Grain size analyses were performed on eight soil samples. The results are shown on Figures A-12 through A-14.

In Situ Engineering, under subcontract to Terra Associates, Inc., performed the CPTs at locations selected by Terra Associates, Inc. The CPT consists of pushing an instrumented, approximately one and one-half inch diameter cone into the ground at a constant rate. During advancement, continuous measurements are made of the resistance to penetration of the cone and the friction of the outer surface of a sleeve. The cone is also equipped with a porous filter and a pressure transducer for measuring the generated groundwater or pore water pressure. Measurements of tip and sleeve frictional resistance, pore pressure, and interpreted soil conditions are summarized in graphical form on the attached CPT Logs.

	MAJOR DIVISIONS			LETTER SYMBOL	TYPICAL DESCRIPTION
	More than 50% material larger than No. 200 sieve size	GRAVELS	Clean Gravels (less than 5% fines)	GW	Well-graded gravels, gravel-sand mixtures, little or no fines.
lLS		More than 50% of coarse fraction is larger than No. 4 sieve		GP	Poorly-graded gravels, gravel-sand mixtures, little or no fines.
COARSE GRAINED SOILS			Gravels with fines	GM	Silty gravels, gravel-sand-silt mixtures, non-plastic fines.
AINE		. 0.010		GC	Clayey gravels, gravel-sand-clay mixtures, plastic fines.
Ë GR		CANDO	Clean Sands (less than	sw	Well-graded sands, sands with gravel, little or no fines.
DARS		SANDS More than 50% of coarse fraction is smaller than No. 4 sieve	5% fines)	SP	Poorly-graded sands, sands with gravel, little or no fines.
၂ၓ			Sands with fines	SM	Silty sands, sand-silt mixtures, non-plastic fines.
		110. 4 51676		SC	Clayey sands, sand-clay mixtures, plastic fines.
	More than 50% material smaller than No. 200 sieve size			ML	Inorganic silts, rock flour, clayey silts with slight plasticity.
OILS		SILTS AND Liquid Limit is les		CL	Inorganic clays of low to medium plasticity. (Lean clay)
FINE GRAINED SOILS				OL	Organic silts and organic clays of low plasticity.
RAIN		SILTS AND CLAYS Liquid Limit is greater than 50%		MH	Inorganic silts, elastic.
NE G				СН	Inorganic clays of high plasticity. (Fat clay)
				ОН	Organic clays of high plasticity.
	HIGHLY ORGANIC SOILS			PT	Peat.

#### **DEFINITION OF TERMS AND SYMBOLS**

ESS	Density	Standard Penetration Resistance in Blows/Foot	I	2" OUTSIDE DIAMETER SPILT SPOON SAMPLER
COHESIONLESS	Very Loose Loose	0-4 4-10 10-30 30-50 >50		2.4" INSIDE DIAMETER RING SAMPLER OR SHELBY TUBE SAMPLER
	Medium Dense Dense		▼	WATER LEVEL (Date)
	Very Dense		Tr	TORVANE READINGS, tsf
COHESIVE	Consistancy	Standard Penetration Resistance in Blows/Foot	Рр	PENETROMETER READING, tsf
			DD	DRY DENSITY, pounds per cubic foot
	Very Soft Soft	0-2 2-4	LL	LIQUID LIMIT, percent
	Medium Stiff Stiff	4-8 8-16	PI	PLASTIC INDEX
	Very Stiff Hard	16-32 >32	N	STANDARD PENETRATION, blows per foot



Terra Associates, Inc.
Consultants in Geotechnical Engineering
Geology and
Environmental Earth Sciences

UNIFIED SOIL CLASSIFICATION SYSTEM 240 - 15TH STREET SE INDUSTRIAL PUYALLUP, WASHINGTON

Proj. No.T-8661


Date JUNE 2023

Figure A-1

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site




Terra
Associates, Inc.
Consultants in Geotechnical Engineering

Geology and
Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By; JCS

Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site




Terra
Associates, Inc.
Consultants in Geotechnical Engineering
Geology and
Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 3 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site



Terra
Associates, Inc.
Consultants in Geotechnical Engineering

sultants in Geotechnical Engineering Geology and Environmental Earth Sciences

	OG	OF	BC	RIN	G	NO	4
_	$\mathbf{v}$	VI.			$\mathbf{\mathcal{C}}$	110	. –

		Proj	ect: 240 - 15th Street SE Industrial Project No:	T-8661 Date D	ate Drilled: November 30, 2021					
		Clie	nt: Fortress, LLC Driller: Boretec1	Logged By: JCS						
		Loca	ation: Puyallup, Washington Depth to Groundwater: 2.5 ft	Approx. Elev: <u>NA</u>						
	Depth (ft)	Sample Interval	Soil Description	Consistency/ Relative Density	10	SPT (N) Blows/foot 10 30 50			Moisture Content (%)	
1750	<b>y</b> .		Dark gray-brown SAND, fine to medium grained, wet. (SP)	Loose	•			8	25.5	
			Dark gray-brown SILT to sandy SILT, fine sand, wet, coarse wood fragment at 6.5 feet. (ML)  Boring terminated at 6.5 feet.  Groundwater encountered below about 2.5 feet.						44.0	

NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site

10 -




**Terra** Associates, Inc.
Consultants in Geotechnical Engineering
Geology and
Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 2.5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site




Terra
Associates, Inc.
Consultants in Geotechnical Engineering

Geology and Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site



Terra
Associates, Inc.
Consultants in Geotechnical Engineering

sultants in Geotechnical Engineerin Geology and Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021 Client: Fortress, LLC Driller: Boretec1 Logged By: JCS Location: Puyallup, Washington Depth to Groundwater: 2.5 ft Approx. Elev: NA Sample Interval Content (%) SPT (N) Consistency/ Depth (ft) Moisture Soil Description Relative Density Blows/foot 10 30 50 0 Y 9 Fill: Dark brown silty SAND, fine grained, wet, numerous wood fragments. (SM) 30.8 Brown to gray-brown sandy SILT to silty SAND, fine grained, wet, Loose mottled. (ML/SM) Dark gray-brown SAND, fine grained, wet, scattered silty fine sand seams, trace of wood fragments. (SP) 8 25.2 5 Boring terminated at 6.5 feet. Groundwater encountered below about 2.5 feet. 10

NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site




Terra
Associates, Inc.
Consultants in Geotechnical Engineering

Geology and
Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: November 30, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site



Terra
Associates, Inc.
Consultants in Geotechnical Engineering

ultants in Geotechnical Engineering Geology and Environmental Earth Sciences


#### LOG OF BORING NO. 9

Figure No. A-10

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: December 1, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS

Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA



NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site




Terra
Associates, Inc.
Consultants in Geotechnical Engineering

Geology and Environmental Earth Sciences

Project: 240 - 15th Street SE Industrial Project No: T-8661 Date Drilled: December 1, 2021

Client: Fortress, LLC Driller: Boretec1 Logged By: JCS


Location: Puyallup, Washington Depth to Groundwater: 5 ft Approx. Elev: NA





NOTE: This borehole log has been prepared for geotechnical purposes. This information pertains only to this boring location and should not be interpeted as being indicative of other areas of the site



Terra
Associates, Inc.
Consultants in Geotechnical Engineering
Geology and
Environmental Earth Sciences













CPT CONTRUCTOR: In Situ Engineering CUSTOMER: Terra Asso LOCATION: Puyallup JOB NUMBER: T-8661 COMMENT: 240 - 15th St SE COMMENT: OPERATOR: Okbay CONE ID: DDG1369 TEST DATE: 12/8/2021 9:38:13 AM PREDRILL: 0 ft BACK FILL: 20% Grout + Bentonite Chips SURFACE PATCH: None



## HOLE NUMBER: CPT- 01



OPERATOR: Okbay

CUSTOMER: Terra Asso

LOCATION: Puyallup

JOB NUMBER: T-8661

CPT CONTRUCTOR: In Situ Engineering

CONE ID: DDG1369

TEST DATE: 12/8/2021 9:38:13 AM


COMMENT: 240 - 15th St SE

PREDRILL0 ft

BACK FILL: 20% Grout + Bentonite Chips

SURFACE PATCH: none

#### HOLE NUMBER: CPT- 01




Hammer to Rod String Distance (ft): 2.79
\* = Not Determined

COMMENT: 240 - 15th St SE





CPT CONTRUCTOR: In Situ Engineering CUSTOMER: Terra Asso LOCATION: Puyallup JOB NUMBER: T-8661 COMMENT: 240 - 15th St SE COMMENT: OPERATOR: Okbay CONE ID: DDG1369 TEST DATE: 12/8/2021 12:37:48 PM PREDRILL: 0 ft BACK FILL: 20% Grout + Bentonite Chips SURFACE PATCH: None








CPT CONTRUCTOR: In Situ Engineering CUSTOMER: Terra Asso LOCATION: Puyallup JOB NUMBER: T-8661

OPERATOR: Okbay CONE ID: DDG1369 TEST DATE: 12/8/2021 12:37:48 PM

PREDRILL: 0 ft

BACK FILL: 20% Grout + Bentonite Chips SURFACE PATCH: Cold Patch




## APPENDIX B LIQUEFACTION ANALYSES

## **LIQUEFACTION ANALYSIS** 240 - 15th St SE Industrial Magnitude=7 Hole No.=CPT-1 Water Depth=5.0 ft Acceleration=0.6g Ground Improvement of Fill=3 ft Factor of Safety 0 1 5 Settlement 0 (in.) Shear Stress Ratio 10 - 15 - 30 45 60 75 fs1=1.00 S = 6.88 in.CRR -CSR fs1 Saturated Shaded Zone has Liquefaction Potential Unsaturat. - 90

CivilTech Software USA

- 105

### LIQUEFACTION ANALYSIS



CivilTech Software USA

# **Tab 7.0**

#### 7.0 OTHER PERMITS

Other permits that may be required for this project include:

- SEPA Environmental Checklist
- Civil Construction Permit
- Building Permits
- Construction Stormwater General Permit
- Fire Permit

# **Tab 8.0**

#### 8.0 ESC ANALYSIS AND DESIGN

An erosion and sediment control plan will be prepared as part of the civil construction plan set. These plans will follow the measures outlined in the Erosion and Sediment Control Standards. The measures outlined in the Manual are discussed below.

<u>Clearing Limits</u>: Prior to any site clearing or grading, the construction limits will be clearly marked with a combination of silt fencing and/or brightly colored survey tape.

<u>Cover Measures</u>: Temporary and permanent cover measures shall be provided when necessary to protect disturbed areas. Temporary cover shall be installed if an area is to remain unworked for more than seven days during the dry season (May 1 to September 30) or for more than two days during the wet season (October 1 to April 30), unless otherwise noted by the City. Any area to remain unworked for more than 30 days shall be seeded or sodded, unless the City determines that winter weather makes vegetation establishment unfeasible. During the wet season, slopes and stockpiles 3H:1V or steeper with more than 10 feet of vertical relief shall be covered if they are to remain unworked for more than 12 hours. The CESCL lead shall be responsible for determining what specific measures to implement to suit changing site conditions.

<u>Perimeter Protection</u>: Silt fence shall be installed along the property lines prior to any upstream grading to prevent and filter sediment sheet flow from adjacent areas.

<u>Traffic Area Stabilization</u>: A construction entrance will be installed to minimize erosion tracking of sediment offsite. Should there be parking areas used by construction traffic onsite they shall also require stabilization.

<u>Sediment Retention</u>: Surface water collected from disturbed areas of the site shall be routed through a sediment pond or trap prior to release from the site.

<u>Surface Water Controls</u>: Surface water controls shall be installed in the form of temporary "v" ditches with rock check dams to intercept and convey surface water from disturbed areas to the sediment trap.

<u>Dust Control</u>: Preventative measures to minimize the wind transport of soil shall be taken as necessary depending on site conditions. The most common method shall be to spray exposed soils until wet, but not so wet as to cause the soils to generate runoff from the spraying.

# **Tab 9.0**

#### 9.0 BOND QUANTITIES, FACILITY SUMMARIES, AND DECLARATION OF COVENANT

All required bonding and financial guarantees will be provided as required by the City of Puyallup.

# Tab 10.0

#### 10.0 OPERATIONS AND MAINTENANCE MANUAL

The proposed on-site facilities will be owned and maintained by the owner. An Operations and Maintenance Manual will be completed and submitted as a separate document with the permit construction plans.