



Created: 2022-12-29 13:18:58

PROPOSAL FOR MERIDIAN POINTE

2022 Removals / Meridian Pointe / Palladium







Proposal ID: 265751

Address: 407 Valley Ave NE, Puyallup, WA 98372

Eric Mullin
ISA CA#: WE-9864A
ISA TRAQ Qualified

Parcels: 0420222055 & 0420226014

General Tree Care & Plant Health Care Services

Tree	Line	Name	Treatment	Bid (\$)
	1	Red Sunset Maple (Acer rubrum 'Red Sunset') [1001790613] .	Tree Installation - 15 Gal (Irrigation not included)	
	2	Red Sunset Maple (Acer rubrum 'Red Sunset') [1001790607] .	Tree Installation - 15 Gal (Irrigation not included)	
	3	Red Sunset Maple (Acer rubrum 'Red Sunset') [1001763270] .	Tree Installation - 15 Gal (Irrigation not included)	
	4	Douglas Fir (Pseudotsuga menziesii) [1000860237] 19.4" DBH. Fair. M building Lifting and damaging adjacent walk. Walk has been ground previously. Root pruning not recommended due to proximity to walk, size of tree, surrounding targets & potential damage from root failure. Root pruning would remove significant portion.	Removal	
	5	Douglas Fir (Pseudotsuga menziesii) [1000860238] 16.5" DBH. Fair. M Building Tree has lifted curb & damaging asphalt in adjacent parking area creating a trip hazard. Root pruning not recommended due to proximity, size of tree, limited soil conditions for root development, targets & potential damage from root failure. Root pruning would remove potential anchor/scaffold roots near the base of the tree.	Removal	
	6	Incense Cedar (Calocedrus decurrens) [1000860202] 16.7" DBH. Fair. Roots lifting & cracking adjacent walk. Unsustainable location due to proximity to hardscape. Roots previously cut near the concrete. Tree has corrected lean towards play area. Root pruning not a viable option.	Removal	

Project Management Services

Description	Quantity	Amount	Subtotal
Fuel Surcharge (5%)			
Environmental Waste Fees (Waived if property chooses to keep onsite)			
		Subtotal:	

Definition of Treatments:

- **Removal** - Complete removal of tree as close to ground level as is reasonable and safe, using safety practices as outlined in ANSI Z133.1 safety standard.
- **Tree Installation - 15 Gal (Irrigation not included)** - Installation of 15 Gal container or bare root specimen. Staking or guying may be necessary, to be determined by Arborist or Representative. Client to keep new tree well-watered for at least 2 years for best survivability. We recommend bubblers, tree-gator bag, or hand watering when needed. A Plus Is not responsible for damages to irrigation.

Tree 4



Tree 4: Walk damage & previous surface grinding



Tree 4: Adjacent walk damage & previous surface grinding



Tree 5



Tree 5: Curb & asphalt damage



Tree 5: Adjacent walk damage



Tree 6



Tree 6: Proximity to walk, tension-side response growth & scaffold roots



Tree 6: Previous surface root pruning wounds



Site Map



