



BARGHAUSEN

PRELIMINARY STORMWATER SITE PLAN

Mullan Short Plat
808 14th Street S.W.
Puyallup, Washington 98371

City File No. P-21-0067

November 30, 2022

Our Job No. 22001



BARGHAUSEN CONSULTING ENGINEERS, INC.

18215 72ND AVENUE SOUTH KENT, WA 98032 P) 425.251.6222 F) 425.251.8782
BRANCH OFFICES: CHEHALIS, WA KLAMATH FALLS, OR LONG BEACH, CA RICHLAND, WA ROSEVILLE, CA
barghausen.com

PRELIMINARY STORMWATER SITE PLAN

Mullan Short Plat

TABLE OF CONTENTS

- 1.0 PROJECT OVERVIEW
 - Figure 1.0.1 – Vicinity Map
- 2.0 CONDITIONS AND REQUIREMENTS SUMMARY
 - 2.1 Analysis of the Minimum Requirements
- 3.0 EXISTING CONDITIONS SUMMARY
 - Figure 3.0.1 – Assessor Map
 - Figure 3.0.2 – FEMA Map
 - Figure 3.0.3 – Soil Survey Map
 - Figure 3.0.4 – Sensitive Areas Map
- 4.0 OFF-SITE ANALYSIS
- 5.0 PERMANENT STORMWATER CONTROL PLAN
 - 5.1 Existing Site Hydrology
 - Figure 5.1.1 – Predeveloped Drainage Basin Map
 - 5.2 Developed Site Hydrology
 - Figure 5.2.1 – Developed Drainage Basin Map
 - Figure 5.2.2 – Floodplain Fill and Compensatory Storage Plan
 - 5.3 Performance Standards and Goals
 - Figure 5.3.1 – Flow Chart for Determining Requirements for New Development
 - Figure 5.3.2 – Flow Chart for Determining LID MR#5 Requirements
 - 5.4 Low Impact Development Features
 - 5.5 Flow Control System
 - Figure 5.5.1 – Flow Control Calculations
 - 5.6 Water Quality System
 - Figure 5.6.1 – Treatment Facility Selection Flow Chart
 - 5.7 Conveyance System Analysis and Design
- 6.0 CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
- 7.0 SPECIAL REPORTS AND STUDIES
 - 7.1 Geotechnical Evaluation, prepared by Earth Solutions NW dated December 17, 2021

7.2 Groundwater Monitoring Program Report prepared by Earth Solutions NW dated April 25, 2022


7.3 Critical Area Assessment and Biological Evaluation, prepared by Habitat Technologies dated August 29, 2022

8.0 OTHER PERMITS

9.0 OPERATIONS AND MAINTENANCE MANUAL

10.0 BOND QUANTITIES WORKSHEET

Tab 1.0



1.0 PROJECT OVERVIEW

The Mullan Short Plat project is a proposed two-lot development in which the existing property will be subdivided to create an additional lot for a single-family residence. The 0.93 acre site is located on 808 14th St SW in the City of Puyallup. The project will construct access driveways, utility extensions and eventually a single-family residence on the southern portion property. A carport building will also be constructed on the existing lot near the northern portion of the site. The property is located within a portion of Section 28, Township 20, Range 4 East, Willamette Meridian, in the City of Puyallup, Washington and occupies Tax Parcel No. 5505300831. A Vicinity Map (Figure 1.0.1) has been included in this section for reference.

The property consists of mostly cleared lawn area with an existing two-story residence, garage and office building located near the northeast corner of the property. There is also an existing gravel road used to access the existing home from 14th St SW located directly east of the site. The site consists of a single drainage basin with topography sloping in a southeast manner at a relatively flat grade.


The USDA Web Soil Survey for this area shown in Figure 3.0. indicates that the on-site soils are considered Sultan Silt Loam. The Geotechnical Evaluation prepared by Earth Solutions NW identified the underlying native soil as silty sand and sandy silt.

Stormwater runoff generated by the on-site shared access driveway, single-family residence and shop building will be collected by a tightlined conveyance system and routed to the on-site catch basin near the southeast property corner which conveys runoff to the existing public conveyance system along 14th St SW. Impervious roof runoff from the proposed carport building will be dispersed on-site using splash blocks. A portion of the on-site shared access driveway will also be dispersed through sheet flow dispersion.

As shown in the FEMA map (Figure 3.0.2), the project site is located in the Zone AE Special Flood Hazard Area (100-year floodplain) tributary to Clarks Creek to the southwest of the site. Any fill within the existing flood hazard area will be mitigated by providing on-site compensatory storage. Please refer to Section 5.2 for further detail.

Site drainage designs are based on the 2012 Stormwater Management Manual for Western Washington (2014 SWMMWW), as Amended in December 2014. Please refer to Section 5.5 of this Stormwater Site Plan for further details.

Figure 1.0.1



REFERENCE: MapQuest (2021)

Scale:

Horizontal: N.T.S. Vertical: N/A



**Barghausen
Consulting Engineers, Inc.**

18215 72nd Avenue South
Kent, WA 98032
425.251.6222 barghausen.com

For:

Mullan Short Plat
Puyallup, Washington

Title:


VICINITY MAP

Job Number

22001

DATE: 10/28/21

Tab 2.0



2.0 CONDITIONS AND REQUIREMENTS SUMMARY

This section contains the following information:

2.1 Analysis of the Minimum Requirements


2.1 Analysis of the Minimum Requirements

Minimum Requirements	How Project Has Addressed Requirement
No. 1: Preparation of Stormwater Site Plans	This Minimum Requirement has been fulfilled by the preparation and completion of this Stormwater Site Plan.
No. 2: Construction Stormwater Pollution Prevention (SWPP)	A completed Construction Stormwater Pollution Prevention Plan (SWPPP) will be submitted under a separate cover.
No. 3: Source Control of Pollution	The project is not classified as a high-use site, and no hazardous materials requiring source control BMPs are proposed to be stored on-site.
No. 4: Preservation of Natural Drainage Systems and Outfalls	<p>The existing site topography slopes southeast at a relatively flat grade. Due to the properties of the existing soils, the majority of stormwater runoff from the existing site is infiltrated into the native soil. Any excess runoff flows to the southeast and is collected by an existing catch basin near the southeast property corner. In the developed condition, runoff from the proposed access driveway, single-family residence and shop building will be conveyed to the existing catch basin located at the natural discharge location of the site near the southeast property corner. Roof runoff from the proposed carport building, a portion of the shared access driveway, and the single-family residence entry driveway will be dispersed on-site. The flowpaths for these dispersion devices are positioned so runoff will flow towards the southeast corner of the site, thus maintaining existing natural outfall conditions.</p> <p>The existing road named 14th St SW directly east of the site provides the necessary road section required by the City Standards. Because of this, there will not be any frontage improvements required as part of this development and no additional runoff will be created along the frontage of the project site.</p>

<p>No. 5: On-site Stormwater Management</p>	<p>The developer has opted not to meet the LID Performance Standard for Flow Control, therefore the project will be providing several On-site Stormwater Management BMP's found in List #2 of the 2014 SWMMWW to feasible target surfaces.</p> <p>Roof runoff from the proposed carport building will be dispersed using splash blocks following the Downspout Dispersion BMP at different locations near the building. Runoff tributary to a portion of the shared access driveway and the single-family residence entry driveway will be dispersed using the Sheet Flow Dispersion BMP. The Post-Construction Soil Quality and Depth BMP will be applied to all disturbed lawn and landscaped areas proposed with this development.</p> <p>Full dispersion BMP's are infeasible for this site because native vegetation flowpath areas required with these BMP's cannot be provided due to limited space on-site.</p> <p>According to the Groundwater Monitoring Program Report prepared by Earth Solutions NW, all infiltration BMP's including Bioretention, Permeable Pavement and Perforated Stub-out connections are infeasible due to the high seasonal groundwater elevation present at the project site.</p> <p>Downspout Dispersion Systems BMP's cannot be applied for rooftop runoff from the single-family residence and shop as the available flowpath area is insufficient for the adequate application of these BMP's.</p>
<p>No. 6: Runoff Treatment</p>	<p>According to the 2014 SWMMWW, roof runoff from the proposed single-family residence, carport and shop building is not considered pollution-generating. The approximate total area of the shared access driveway and the single-family residence entry driveway consists of 4,989 square feet. According to the 2014 SWMMWW, a stormwater treatment facility is not required for projects where less than 5,000 square feet of pollution-generating impervious surface is generated. Because of this, a stormwater treatment facility is not required for this project.</p>
<p>No. 7: Flow Control</p>	<p>According to the 2014 SWMMWW, the flow control requirement is met if the developed site does not increase the existing 100-year peak flow by more than 0.15 cfs using 15-minute time steps in the WWHM2012 model.</p> <p>The developed site conditions were modeled in WWHM2012 and the existing 100-year peak flow was not increased by more than 0.15 cfs. Please refer to Section 5.5 for further detail on these calculations.</p>

No. 8: Wetlands Protection	<p>According to the Sensitive Areas Map and the Critical Areas Assessment, there are no wetland or wetland buffers present on-site.</p> <p>The City of Puyallup Critical Areas Map shows a wetland approximately 400 feet south of the project site. Further review of this area showed that four single-family residences were constructed at the location of the offsite wetland, therefore the wetland shown on the online city map appears to be outdated.</p> <p>As shown in the FEMA Map a portion of the site is located within the 100-year floodplain tributary to Clarks Creek to the southwest of the site. Compensatory storage area will be provided on-site for any fill within the floodplain that will occur as part of the development.</p>
No. 9: Operation and Maintenance	An Operations and Maintenance Manual will be submitted at the time of civil application.

Tab 3.0



3.0 EXISTING CONDITIONS SUMMARY


The Mullan Short Plat project is a proposed two-lot development in which the existing property will be subdivided to create an additional lot for a single-family residence. An Assessor's Map (Figure 3.0.1) has been included within this section for visual reference of the parcels around the site. The property is located within a portion of Section 28, Township 20, Range 4 East, Willamette Meridian, in the City of Puyallup, Washington and occupies Tax Parcel No. 5505300831. Please refer to the Vicinity Map (Figure 1.0.1) included in Section 1.0 of this report for a visualization of the exact location of the project site.

The site consists of mostly cleared lawn area with an existing two-story residence, garage and office building located near the northeast corner of the property. There is also an existing gravel road used to access the existing home from 14th St SW located directly east of the site. The site slopes in a southeast manner with relatively flat slopes throughout the property. The site is bounded to the north, south and west by existing homes and lawns.

The USDA Web Soil Survey for this area shown in Figure 3.0.3 indicates that the on-site soils are considered Sultan Silt Loam. The Geotechnical Evaluation prepared by Earth Solutions NW identified the underlying native soil as silty sand and sandy silt.

According to the FEMA Map (Figure 3.0.2), the site is located in the Zone AE Special Flood Hazard Area (100-year floodplain) tributary to Clarks Creek to the southwest.

Figure 3.0.1



REFERENCE: Pierce County Department of Assessments (Feb. 2021)



<p>Scale: Horizontal: N.T.S. Vertical: N/A</p>	<p>For: Mullan Short Plat Puyallup, Washington</p>	<p>Job Number 22001</p>
 <p>Barghausen Consulting Engineers, Inc. 18215 72nd Avenue South Kent, WA 98032 425.251.6222 barghausen.com</p>	<p>Title: ASSESSOR MAP</p>	<p>DATE: 10/28/21</p>

Figure 3.0.2



REFERENCE: Federal Emergency Management Agency (Portion of Map 53053C0126E, March 2017)




<p>Scale: Horizontal: N.T.S. Vertical: N/A</p>	<p>For: Mullan Short Plat Puyallup, Washington</p>	<p>Job Number 22001</p>
 <p>Barghausen Consulting Engineers, Inc. 18215 72nd Avenue South Kent, WA 98032 425.251.6222 barghausen.com</p>	<p>Title: FEMA MAP</p>	<p>DATE: 10/28/21</p>


Figure 3.0.4



REFERENCE: Pierce County PublicGIS

<p>Scale: Horizontal: N.T.S. Vertical: N/A</p>	<p>For: Mullan Short Plat Puyallup, Washington</p>	<p>Job Number 22001</p>
<p> Barghausen Consulting Engineers, Inc. 18215 72nd Avenue South Kent, WA 98032 425.251.6222 barghausen.com</p>	<p>Title: SENSITIVE AREAS MAP</p>	<p>DATE: 10/28/21</p>

Tab 4.0



4.0 OFF-SITE ANALYSIS REPORT

The project is subject to the provisions of the City of Puyallup design and development standards, as well as the 2012 Stormwater Management Manual for Western Washington as amended in 2014, issued by the Washington State Department of Ecology. This report and accompanying plans are intended to satisfy the site plan preparation requirements outlined in the regulatory documents listed above. The DOE Stormwater Manual requires completion of the following four tasks as part of the site plan preparation process:

Task 1: Define and map the study area

The project study area includes the project site itself and a downstream flowpath for a distance of one-quarter mile.

Task 2: Review all available information on the study area

- **Critical Drainage Area Map**

According to the Sensitive Areas Map and the Critical Areas Assessment, there are no wetland or wetland buffers present on-site. The City of Puyallup Critical Areas Map shows a wetland approximately 400 feet south of the project site. Further review of this area showed that four single-family residences were constructed at the location of the offsite wetland, therefore the wetland shown on the online city map appears to be outdated.

- **Floodplain/Floodway (FEMA) Map**

Referencing Figure 3.0.2 - FEMA Map located in Section 3.0 of the report shows that a portion of the project site is located within the 100-year floodplain tributary to Clarks Creek to the southwest of the site.

- **Offsite Analysis Reports**

The City of Puyallup Public Data Viewer Database was used to identify existing drainage structures/facilities surrounding the site.

- **Basin Plans**

The project site drains to the Clarks Creek Drainage Basin. Stormwater tributary to this basin feeds into Clarks Creek which eventually connects to the Lower Puyallup River.

- **Sensitive Area Information**

The Sensitive Areas Map (Figure 3.0.4) shows that a portion of the site is located within the 1% Annual Chance Floodplain tributary to Clarks Creek.

- **Drainage Complaints**

There were no drainage complaints found near the project site according to the City of Puyallup Public Data Viewer.

- **Soils Map**

NRCS soil survey identifies the underlying soils as Sultan Silt Loam, which is common throughout the region. This type of soil is typically silty sand and has moderate permeability. For further information please see Figure 3.0.3 - Soil Survey Map provided in Section 3.0.

Task 3: Field inspect the study area

The on-site and downstream drainage analyses for the site are presented in this section. The site consists of a single drainage basin tributary to Clarks Creek which eventually drains into the Lower Puyallup River. The drainage course from the site was assessed on November 17, 2021 with weather conditions being cloudy and damp.

On-site Drainage

The topography of the site is mostly flat with a gentle slope towards the southeast corner of the property. The site consists of mostly cleared lawn area with an existing two-story residence, garage and office building located near the northeast corner of the property. There is also an existing gravel road used to access the existing home from 14th St SW located directly east of the site. Rooftop runoff from the existing structures is dispersed into the native soils through the use of splash blocks. Due to the infiltration capabilities of the native soil, it is reasonable to assume that most of the on-site runoff is infiltrated into the on-site native soil. Any additional runoff that is not infiltrated is collected by an existing catch basin located near the southeast corner of the site.

Downstream Drainage Course

The downstream conveyance system is described below and illustrated in Figure 4.0.1 –Downstream Basin Map. In addition, a series of photos taken during the site visit with a detailed description of the downstream flowpath are shown below:



The above photo (looking east) shows the existing catch basin located near the southeast corner of the site. Any runoff that does not infiltrate into the on-site native soil is collected by this catch basin and conveyed southward along 14th St SW for approximately 170 feet before reaching the intersection of 14th St SW and 9th Ave SW.



The above photos show the downstream catch basin at the intersection of 14th St SW and 9th Ave SW. Once runoff reaches this catch basin, it begins to flow east along 9th Ave SW for approximately 250 feet. The above right picture shows the catch basin looking east towards 9th Ave SW.



The above left photo shows the existing storm manhole located on 9th Ave SW approximately 250 feet east of the intersection. Once runoff reaches this manhole, it begins to flow south for approximately 500 feet through an existing public storm easement running along the Puyallup Community Baptist Church property. Runoff then flows westward for approximately 80 feet and enters the existing pump station shown in the above right photo.




Once runoff enters the pump station, it is slowly released to Meeker Creek located approximately 50 feet to the south. The controlled discharge is shown in the above left photo. Runoff will continue to flow westward along Meeker Creek and eventually reach 1/4 mile downstream of the project site.

Conclusions

There were no flooding or overtopping issues observed on the existing conveyance system and Meeker Creek. In addition, there were no capacity deficiencies observed in the existing conveyance system. Because of this, it can be confidently determined that the development of this project will not impact the downstream system.

Tab 5.0



5.0 PERMANENT STORMWATER CONTROL PLAN

This section contains the following information:


- 5.1 Existing Site Hydrology
- 5.2 Developed Site Hydrology
- 5.3 Performance Standards and Goals
- 5.4 Low Impact Development Features
- 5.5 Flow Control System
- 5.6 Water Quality System
- 5.7 Conveyance System Analysis and Design

5.1 Existing Site Hydrology

The existing conditions of the project site consist of mostly open space lawn area with an existing home, garage and office building located near the northeast corner of the property. There is also an existing gravel road used to access the existing home from 14th St SW located directly east of the site. The site consists of a single drainage basin with topography sloping in a southeast manner at a relatively flat grade. According to the Geotechnical Report prepared by Earth Solutions NW, the on-site native soil was identified as silty sand and sandy silt. This matches the soil classification indicated in the USDA Web Soil Survey (Figure 3.0.3) which identifies the native soils as Sultan Silt Loam.


Due to the existing native soil, it is reasonable to assume that most of the runoff tributary to the on-site landscaped areas is infiltrated into the native soil. In addition, the existing buildings located near the northeast corner of the property have splash pads at the downspout locations to disperse roof runoff into the on-site native soil.

According to the FEMA Map (Figure 3.0.4), the site is located in the Zone AE Special Flood Hazard Area (100-year floodplain) tributary to Clarks Creek to the southwest. This area consists of approximately 7,600 square feet of area near the southeast corner of the site.



PREDEVELOPED BASIN MAP
FOR
MULLAN SHORT PLAT
A PORTION OF SECTION 28, TOWNSHIP 20 N., RANGE 04 E., W.M.
CITY OF PUYALLUP, PIERCE COUNTY, WASHINGTON

Figure 5.1.1



Job Number
22001

Sheet
1 of **1**

Barghausen Consulting Engineers, Inc.
18215 72nd Avenue South
Kent, WA 98032
425.251.6222 barghausen.com

Designed
Drawn
Checked
Approved
Date 11/28/22

Scale:
Horizontal 1"=20'
Vertical N/A

For:

KRIS MULLAN

Title:

**PREDEVELOPED BASIN MAP
FOR
MULLAN SHORT PLAT**

No.	Date	By	Clk.	Appr.	Revision

5.2 Developed Site Hydrology

When completed, the Mullan Short Plat project will subdivide the existing property into two single-family lots. Lot 1 will consist of the existing buildings, driveways, fence and landscaped areas that will not be altered during construction. Lot 1 will also contain a portion of the shared access driveway and storm system and a new carport building. Lot 2 will contain a portion of the shared access driveway and storm system, new single-family house, entry driveway for the house, new shop building and proposed utilities to serve the home.

The On-Site Drainage basin consists of the shared access driveway, building areas for each of the proposed buildings, and lawn areas created by the development. The table below shows an area breakdown for the Developed Drainage Basin. For further detail, please refer to the Developed Basin Map (Figure 5.2.1) included in this section.

Developed Drainage Basin	
Land Cover	Area
Access Driveways Not Dispersed	0.08 Ac ⁽¹⁾
Single-family Residence	0.06 Ac
Shop	0.01 Ac
Carport	0.03 Ac ⁽²⁾
Dispersed Driveways	0.04 Ac ⁽³⁾
Lawn Area	0.06 Ac
Total	0.28 Ac

Notes:

1. Modeled as 100% Impervious
2. Modeled as Pervious Lawn as allowed by the 2014 SWMMWW because Downspout Dispersion BMP's are used to disperse this rooftop runoff
3. Modeled as Pervious Lawn as allowed by the 2014 SWMMWW because Sheet Flow Dispersion BMP is used to disperse this driveway runoff

Please refer to Section 5.5 for further detail on meeting the flow control requirements for the site in the developed condition.

Floodplain Fill and Compensatory Storage

As noted earlier, this development is located within the 100-year floodplain tributary to Clarks Creek to the southwest. All disturbed areas (Not including the Lot 1 single-family residence) will match existing grade elevations when located within the 100-year floodplain to avoid creating any floodplain fill.

Due to site constraints, the single-family home will be located within the 100-year floodplain. As required by Section 21.07.060 of the PMC, the future single-family residence on Lot 1 will be constructed so the lowest floor elevation is elevated by a minimum of one foot above the Base Flood Elevation of 32' for this area of the floodplain. The enclosed crawlspace area of this home shall meet the requirements of Section 21.07.060 of the PMC to allow for the entry and exit of floodwaters, thus avoiding any floodplain fill within the crawlspace area of the future building.


The only floodplain fill created by the single-family residence results from portions of the footing stemwall located within the floodplain area. The Floodplain Fill and Compensatory Storage Plan (Figure 5.2.2) included in this section shows the location of the floodplain fills and includes a table breakdown of the floodplain fill volumes at each elevation.

A compensatory storage area will be provided near the entrance of the shared access driveway to mitigate the floodplain fill due to the single-family residence stemwall. The Floodplain Fill and Compensatory Storage Plan (Figure 5.2.2) included in this section shows the location of the compensatory storage area and includes a table breakdown of the compensatory storage volumes at each elevation.

FLOODPLAIN FILL AND COMPENSATORY STORAGE PLAN

Figure 5.2.2

FOR
MULLAN SHORT PLAT
 A PORTION OF SECTION 28, TOWNSHIP 20 N., RANGE 04 E., W.M.
 CITY OF PUYALLUP, PIERCE COUNTY, WASHINGTON



FLOODPLAIN FILL AND COMPENSATORY STORAGE


ALL DISTURBED AREAS DUE TO THIS DEVELOPMENT (NOT INCLUDING THE LOT 1 SINGLE-FAMILY RESIDENCE) WILL MATCH EXISTING GRADE ELEVATIONS WHEN LOCATED WITHIN THE ZONE AE SPECIAL FLOOD HAZARD AREA (100-YEAR FLOODPLAIN) TO AVOID CREATING ANY FLOOD PLAIN FILL.

AS REQUIRED BY SECTION 21.07.060 OF THE PMC, THE FUTURE SINGLE-FAMILY RESIDENCE LOCATED WITHIN LOT 1 WILL BE CONSTRUCTED SO THE LOWEST FLOOR ELEVATION IS ELEVATED BY A MINIMUM OF ONE FOOT ABOVE THE BASE FLOOD ELEVATION OF 32' FOR THIS AREA OF THE FLOODPLAIN. THE ENCLOSED CRAWLSPACE AREA OF THIS HOME SHALL MEET THE REQUIREMENTS OF SECTION 21.07.060 OF THE PMC TO ALLOW FOR THE ENTRY AND EXIT OF FLOODWATERS, THUS AVOIDING ANY FLOODPLAIN FILL WITHIN THE CRAWLSPACE AREA OF THE FUTURE BUILDING.

THE ONLY FLOODPLAIN FILL CREATED BY THE SINGLE-FAMILY RESIDENCE RESULTS FROM PORTIONS OF THE FOOTING STEMWALL LOCATED WITHIN THE 100-YEAR FLOODPLAIN. THE LOCATIONS OF THE FLOODPLAIN FILLS FROM PORTIONS OF THE STEMWALL ARE SHOWN ON THIS SHEET ALONG WITH A TABLE BREAKDOWN OF THE FILL VOLUMES AT EACH ELEVATION.

A COMPENSATORY STORAGE AREA WILL BE PROVIDED NEAR THE ENTRANCE OF THE SHARED ACCESS DRIVEWAY TO MITIGATE THE FLOODPLAIN FILL DUE TO THE SINGLE-FAMILY RESIDENCE STEMWALL. THE COMPENSATORY STORAGE VOLUMES AT EACH ELEVATION ARE ALSO PROVIDED IN THE TABLE ON THIS SHEET.

FLOODPLAIN FILL AND COMPENSATORY STORAGE VOLUME		
ELEVATION	FILL VOLUME	COMPENSATORY VOLUME
< 31.6	0 CY	0 CY
31.6-31.7	0.1 CY	0.2 CY
31.7-31.8	0.2 CY	0.2 CY
31.8-31.9	0.3 CY	0.4 CY
31.9-32.0	0.5 CY	0.5 CY



No. Date By Cld. Appr. Revision

Title:
FLOODPLAIN FILL AND COMPENSATORY STORAGE PLAN FOR MULLAN SHORT PLAT

For:
KRIS MULLAN

Scale:
 Horizontal 1"=20'
 Vertical N/A

Designed
 Drawn
 Checked
 Approved
 Date 11/28/22



Barghausen Consulting Engineers, Inc.
 18215 72nd Avenue South
 Kent, WA 98032
 425.251.6222 barghausen.com

Job Number
22001
 Sheet
1 of **1**

5.3 Performance Standards and Goals

The project is subject to the provisions of the Stormwater Management Manual for Western Washington (2014 SWMMWW), as Amended in December 2014, by the Washington State Department of Ecology. This report, along with the accompanying plans, are intended to satisfy the Stormwater Site Plan preparation requirements outlined in the regulatory documents listed above.

Hydrologic modeling was performed using the 2012 Western Washington Hydrology Model hence forth referred to as WWHM 2012. WWHM 2012 is a locally calibrated continuous simulation model developed by the Washington State Department of Ecology. The model evaluates several decades of hydrologic data to derive peak flow rate and duration information.

This project has opted to use the List #2 per the Flow Chart for Determining LID MR #5 Requirements (Figure 5.3.2), located within this section of the report. In order to meet the requirements for List #2, the project will incorporate the Downspout Dispersion Systems BMP and Sheet Flow Dispersion BMP to disperse impervious runoff from the carport building, a portion of the shared access driveway and the single-family residence entry driveway.

Figure 5.3.1





Figure I-2.4.1
Flow Chart for Determining Requirements for
New Development

Figure 5.3.2



*Recommended by Ecology for projects triggering MRs #1 - #5.



Figure I-2.5.1 Flow Chart for Determining LID MR #5 Requirements

Revised June 2015

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.

5.4 Low Impact Development Features

The Mullan Short Plat project is subject to Low Impact Development performance standard requiring the analysis of List #1 and #2 per the 2014 SWMMWW. List #1 requires matching developed discharged durations to pre-developed durations for the range of pre-developed discharge rates from 8% of the 2-year peak flow to 50% of the 2-year peak flow. List #1 becomes unpractical when developing a small site. Therefore, this project has opted to use List #2 per the Flow Chart for Determining LID Requirements (Figure 5.3.2), located within Section 5.3 of this report. List #2 requires the application of On-site Stormwater Management BMP's to all feasible target surfaces for this development. The infeasibility criteria for several BMP's included in List #2 is explained below:

- Full dispersion BMP's are infeasible for this site because native vegetation flowpath areas required with these BMP's cannot be provided due to limited space on-site.
- According to the Groundwater Monitoring Program Report prepared by Earth Solutions NW, all infiltration BMP's including Bioretention, Permeable Pavement and Perforated Stub-out connections are infeasible due to the high seasonal groundwater elevation present at the project site.
- Downspout Dispersion Systems BMP's cannot be applied for rooftop runoff from the single-family residence and shop as the available flowpath area is insufficient for the adequate application of these BMP's.

In order to meet the requirements for List #2, the project will apply On-site Stormwater Management BMP's to several target surfaces. The Downspout Dispersion Systems BMP will be implemented to disperse stormwater runoff from the carport building. The Sheet Flow Dispersion BMP will be implemented to disperse stormwater runoff for a portion of the shared access driveway and the single-family residence entry driveway. The sizing procedures for each of these BMP's are outlined below. The Post-Construction Soil Quality and Depth BMP will be applied to all disturbed lawn and landscaped areas proposed with this development.

Downspout Dispersion Systems BMP

This BMP will be used to disperse roof runoff from the carport building by using splash blocks at several locations adjacent to the building. According to BMP T5.10B of the 2014 SWMMWW, a maximum of 700 square feet of rooftop area may drain to each splash block. Using this requirement, three splash blocks will be provided for the carport building since its building footprint is 1,500 square feet.

Sheet Flow Dispersion BMP

This BMP will be used to disperse runoff tributary to a portion of the shared access driveway and the single-family residence entry driveway. The driveway areas being dispersed and their associated dispersion flowpath are shown in the Developed Basin Map (Figure 5.2.1) in Section 5.2. According to BMP T5.12 in the 2014 SWMMWW, a 10-foot wide buffer shall be provided for up to 20 feet of width of paved surface. An additional 10 feet of vegetated buffer width shall be provided for each additional 20 feet of impervious surface width or fraction thereof.

The width of the shared access driveway being dispersed is 20 feet while the width of the single-family residence entry driveway being dispersed is 22 feet. Because of this, the width of the lawn areas used for dispersion of the driveway areas will be 10 feet and 11 feet respectively.

5.5 Flow Control System

This project is required to meet the flow control requirement as detailed in the 2014 SWMMWW. This requirement specifies that developed discharge durations must match predeveloped durations for the range of predeveloped discharge rates from 50 percent of the 2-year peak flow up to the full 50-year peak flow.

The 2014 SWMMWW states that the flow control requirement is met if the 100-year peak flow rate for the existing on-site drainage basin is not increased by more than 0.15 cfs in the developed condition using an approved continuation simulation model and 15-minute time steps. This condition was met by the proposed development as shown in the Flow Control Calculations included as Figure 5.5.1. A breakdown of the developed basin areas modeled in WWHM is shown in Section 5.2.

As noted in Section 5.2, the carport building area was modeled as pervious lawn as allowed by the 2014 SWMMWW because a 50-foot vegetated flowpath will be provided for the Downspout Dispersion BMP's adjacent to the building. In addition, approximately 0.04 acres of impervious area tributary to the shared access driveway and the single-family residence entry driveway were also modeled as pervious lawn because runoff from these areas will be dispersed using the Sheet Flow Dispersion BMP.

WWHM2012
PROJECT REPORT

Figure 5.5.1

General Model Information

Project Name: Mullan Short Plat
Site Name:
Site Address:
City:
Report Date: 11/28/2022
Gage: 42 IN EAST
Data Start: 10/01/1901
Data End: 09/30/2059
Timestep: 15 Minute
Precip Scale: 1.000
Version Date: 2019/09/13
Version: 4.2.17

POC Thresholds

Low Flow Threshold for POC1:	50 Percent of the 2 Year
High Flow Threshold for POC1:	50 Year

Landuse Basin Data

Predeveloped Land Use

Preveloped On-Site Basin

Bypass: No

GroundWater: No

Pervious Land Use acre
A B, Lawn, Flat 0.28

Pervious Total 0.28

Impervious Land Use acre

Impervious Total 0

Basin Total 0.28

Element Flows To:
Surface

Interflow

Groundwater

Mitigated Land Use

Developed On-Site Basin

Bypass: No

GroundWater: No

Pervious Land Use acre
A B, Lawn, Flat 0.13

Pervious Total 0.13

Impervious Land Use acre
ROADS FLAT 0.08
ROOF TOPS FLAT 0.07



Impervious Total 0.15

Basin Total 0.28

Element Flows To:
Surface Interflow Groundwater

Analysis Results

POC 1



+ Predeveloped x Mitigated

Predeveloped Landuse Totals for POC #1

Total Pervious Area: 0.28
Total Impervious Area: 0

Mitigated Landuse Totals for POC #1

Total Pervious Area: 0.13
Total Impervious Area: 0.15

Flow Frequency Method: Log Pearson Type III 17B

Flow Frequency Return Periods for Predeveloped. POC #1

Return Period	Flow(cfs)
2 year	0.000462
5 year	0.001726
10 year	0.003914
25 year	0.010393
50 year	0.020704
100 year	0.040055

Flow Frequency Return Periods for Mitigated. POC #1

Return Period	Flow(cfs)
2 year	0.05534
5 year	0.074412
10 year	0.088292
25 year	0.10731
50 year	0.122587
100 year	0.138847

100-year peak flow does not increase by more than 0.15 cfs in developed condition

Annual Peaks

Annual Peaks for Predeveloped and Mitigated. POC #1

Year	Predeveloped	Mitigated
1902	0.000	0.065
1903	0.000	0.072
1904	0.001	0.082
1905	0.000	0.037
1906	0.000	0.040
1907	0.000	0.055
1908	0.000	0.045
1909	0.001	0.056
1910	0.002	0.053
1911	0.000	0.060

1912	0.066	0.127
1913	0.001	0.043
1914	0.000	0.183
1915	0.000	0.037
1916	0.000	0.069
1917	0.000	0.028
1918	0.001	0.055
1919	0.000	0.035
1920	0.001	0.046
1921	0.001	0.039
1922	0.004	0.062
1923	0.003	0.044
1924	0.000	0.079
1925	0.000	0.034
1926	0.000	0.064
1927	0.000	0.055
1928	0.000	0.039
1929	0.005	0.078
1930	0.000	0.081
1931	0.001	0.041
1932	0.000	0.043
1933	0.000	0.042
1934	0.019	0.069
1935	0.000	0.038
1936	0.001	0.052
1937	0.001	0.069
1938	0.000	0.038
1939	0.000	0.045
1940	0.000	0.083
1941	0.000	0.083
1942	0.000	0.061
1943	0.000	0.060
1944	0.000	0.087
1945	0.000	0.066
1946	0.000	0.051
1947	0.000	0.040
1948	0.000	0.055
1949	0.000	0.085
1950	0.000	0.050
1951	0.000	0.073
1952	0.024	0.092
1953	0.007	0.078
1954	0.000	0.045
1955	0.000	0.043
1956	0.000	0.039
1957	0.000	0.044
1958	0.017	0.061
1959	0.012	0.060
1960	0.000	0.044
1961	0.013	0.124
1962	0.000	0.053
1963	0.000	0.039
1964	0.000	0.115
1965	0.008	0.055
1966	0.000	0.043
1967	0.000	0.061
1968	0.000	0.051
1969	0.000	0.046

1970	0.001	0.052
1971	0.003	0.051
1972	0.004	0.163
1973	0.004	0.098
1974	0.010	0.071
1975	0.003	0.074
1976	0.001	0.078
1977	0.000	0.033
1978	0.013	0.062
1979	0.000	0.060
1980	0.000	0.059
1981	0.000	0.057
1982	0.000	0.045
1983	0.002	0.060
1984	0.000	0.060
1985	0.000	0.068
1986	0.000	0.035
1987	0.000	0.063
1988	0.000	0.036
1989	0.000	0.039
1990	0.000	0.044
1991	0.001	0.064
1992	0.006	0.064
1993	0.001	0.071
1994	0.001	0.049
1995	0.000	0.038
1996	0.009	0.051
1997	0.000	0.045
1998	0.001	0.054
1999	0.000	0.060
2000	0.000	0.051
2001	0.000	0.043
2002	0.003	0.077
2003	0.000	0.044
2004	0.000	0.066
2005	0.014	0.129
2006	0.000	0.059
2007	0.000	0.066
2008	0.001	0.055
2009	0.000	0.042
2010	0.000	0.053
2011	0.000	0.053
2012	0.000	0.052
2013	0.000	0.049
2014	0.000	0.049
2015	0.000	0.081
2016	0.000	0.047
2017	0.000	0.080
2018	0.015	0.055
2019	0.014	0.072
2020	0.001	0.059
2021	0.003	0.049
2022	0.000	0.083
2023	0.001	0.104
2024	0.048	0.117
2025	0.000	0.054
2026	0.003	0.070
2027	0.000	0.065

2028	0.000	0.026
2029	0.003	0.043
2030	0.008	0.090
2031	0.000	0.027
2032	0.000	0.045
2033	0.000	0.057
2034	0.000	0.044
2035	0.001	0.055
2036	0.000	0.045
2037	0.000	0.060
2038	0.002	0.057
2039	0.000	0.115
2040	0.000	0.045
2041	0.000	0.056
2042	0.000	0.065
2043	0.001	0.072
2044	0.009	0.050
2045	0.000	0.040
2046	0.000	0.044
2047	0.000	0.055
2048	0.000	0.045
2049	0.000	0.067
2050	0.000	0.050
2051	0.001	0.070
2052	0.000	0.054
2053	0.000	0.045
2054	0.000	0.090
2055	0.000	0.053
2056	0.000	0.072
2057	0.000	0.035
2058	0.000	0.068
2059	0.013	0.083

Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

Rank	Predeveloped	Mitigated
1	0.0660	0.1825
2	0.0480	0.1626
3	0.0244	0.1288
4	0.0190	0.1269
5	0.0172	0.1243
6	0.0146	0.1166
7	0.0144	0.1152
8	0.0137	0.1152
9	0.0135	0.1037
10	0.0133	0.0976
11	0.0125	0.0920
12	0.0116	0.0902
13	0.0095	0.0896
14	0.0095	0.0874
15	0.0085	0.0849
16	0.0081	0.0833
17	0.0079	0.0831
18	0.0069	0.0829
19	0.0062	0.0826
20	0.0049	0.0816
21	0.0040	0.0812
22	0.0040	0.0812

23	0.0036	0.0802
24	0.0034	0.0786
25	0.0033	0.0784
26	0.0030	0.0780
27	0.0029	0.0777
28	0.0028	0.0771
29	0.0028	0.0742
30	0.0026	0.0734
31	0.0020	0.0722
32	0.0020	0.0720
33	0.0016	0.0719
34	0.0014	0.0718
35	0.0014	0.0714
36	0.0011	0.0710
37	0.0011	0.0700
38	0.0010	0.0699
39	0.0009	0.0690
40	0.0009	0.0690
41	0.0009	0.0688
42	0.0009	0.0685
43	0.0008	0.0681
44	0.0008	0.0668
45	0.0008	0.0664
46	0.0007	0.0659
47	0.0006	0.0659
48	0.0006	0.0654
49	0.0006	0.0651
50	0.0006	0.0651
51	0.0005	0.0641
52	0.0005	0.0638
53	0.0005	0.0636
54	0.0005	0.0626
55	0.0005	0.0623
56	0.0005	0.0621
57	0.0005	0.0612
58	0.0005	0.0608
59	0.0005	0.0605
60	0.0004	0.0605
61	0.0004	0.0604
62	0.0004	0.0603
63	0.0004	0.0603
64	0.0004	0.0602
65	0.0003	0.0599
66	0.0003	0.0597
67	0.0003	0.0595
68	0.0003	0.0593
69	0.0003	0.0590
70	0.0003	0.0586
71	0.0003	0.0567
72	0.0003	0.0566
73	0.0003	0.0566
74	0.0003	0.0565
75	0.0003	0.0556
76	0.0002	0.0553
77	0.0002	0.0552
78	0.0002	0.0550
79	0.0002	0.0549
80	0.0002	0.0549

81	0.0002	0.0547
82	0.0002	0.0546
83	0.0002	0.0546
84	0.0002	0.0545
85	0.0002	0.0543
86	0.0002	0.0542
87	0.0002	0.0536
88	0.0002	0.0534
89	0.0002	0.0531
90	0.0002	0.0529
91	0.0002	0.0528
92	0.0002	0.0527
93	0.0002	0.0522
94	0.0002	0.0520
95	0.0002	0.0515
96	0.0002	0.0515
97	0.0002	0.0514
98	0.0002	0.0514
99	0.0002	0.0513
100	0.0002	0.0508
101	0.0002	0.0500
102	0.0002	0.0497
103	0.0002	0.0495
104	0.0002	0.0491
105	0.0002	0.0487
106	0.0002	0.0487
107	0.0002	0.0486
108	0.0002	0.0465
109	0.0002	0.0460
110	0.0002	0.0455
111	0.0002	0.0455
112	0.0002	0.0451
113	0.0002	0.0451
114	0.0002	0.0451
115	0.0002	0.0450
116	0.0002	0.0449
117	0.0002	0.0448
118	0.0002	0.0447
119	0.0002	0.0447
120	0.0002	0.0446
121	0.0002	0.0445
122	0.0002	0.0444
123	0.0002	0.0444
124	0.0002	0.0444
125	0.0002	0.0444
126	0.0002	0.0438
127	0.0002	0.0437
128	0.0002	0.0435
129	0.0002	0.0434
130	0.0002	0.0433
131	0.0002	0.0432
132	0.0002	0.0429
133	0.0002	0.0429
134	0.0002	0.0424
135	0.0002	0.0416
136	0.0002	0.0405
137	0.0002	0.0402
138	0.0002	0.0402

139	0.0002	0.0400
140	0.0002	0.0393
141	0.0002	0.0393
142	0.0002	0.0391
143	0.0002	0.0391
144	0.0002	0.0388
145	0.0002	0.0382
146	0.0002	0.0377
147	0.0002	0.0375
148	0.0002	0.0373
149	0.0002	0.0367
150	0.0002	0.0364
151	0.0002	0.0354
152	0.0002	0.0345
153	0.0002	0.0345
154	0.0002	0.0337
155	0.0002	0.0334
156	0.0002	0.0281
157	0.0002	0.0270
158	0.0002	0.0261

Model Default Modifications

Total of 0 changes have been made.

PERLND Changes

No PERLND changes have been made.

IMPLND Changes

No IMPLND changes have been made.

Appendix
Predeveloped Schematic




Preveloped
On-Site
Basin
0.28ac

Mitigated Schematic



Developed
On-Site
Basin
0.28ac



Mitigated UCI File

RUN

GLOBAL

```
WVHM4 model simulation
START      1901 10 01      END      2059 09 30
RUN INTERP OUTPUT LEVEL   3      0
RESUME     0 RUN         1
UNIT SYSTEM 1
```

END GLOBAL

FILES

```
<File> <Un#> <-----File Name----->***
<-ID->                                     ***
WDM      26      Mullan Short Plat.wdm
MESSU    25      MitMullan Short Plat.MES
          27      MitMullan Short Plat.L61
          28      MitMullan Short Plat.L62
          30      POCMullan Short Plat1.dat
```

END FILES

OPN SEQUENCE

```
INGRP          INDELT 00:15
  PERLND        7
  IMPLND        1
  IMPLND        4
  COPY          501
  DISPLY        1
```

END INGRP

END OPN SEQUENCE

DISPLY

DISPLY-INFO1

```
# - #<-----Title----->***TRAN PIVL DIG1 FIL1  PYR DIG2 FIL2 YRND
1      Developed On-Site Basin      MAX      1      2      30      9
```

END DISPLY-INFO1

END DISPLY

COPY

TIMESERIES

```
# - # NPT NMN ***
1      1      1
501    1      1
```

END TIMESERIES

END COPY

GENER

OPCODE

```
#      # OPCD ***
```

END OPCODE

PARM

```
#      #      K ***
```

END PARM

END GENER

PERLND

GEN-INFO

```
<PLS ><-----Name----->NBLKS      Unit-systems      Printer ***
# - #      User      t-series      Engl Metr ***
          in out      ***
7      A/B, Lawn, Flat      1      1      1      1      27      0
```

END GEN-INFO

*** Section PWATER***

ACTIVITY

```
<PLS > ***** Active Sections *****
# - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
7      0      0      1      0      0      0      0      0      0      0      0      0
```

END ACTIVITY

PRINT-INFO

```
<PLS > ***** Print-flags ***** PIVL PYR
# - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC *****
7      0      0      4      0      0      0      0      0      0      0      0      0      1      9
```

END PRINT-INFO

PWAT-PARM1

```

<PLS > PWATER variable monthly parameter value flags ***
# - # CSNO RTOP UZFG VCS VUZ VNN VIFW VIRC VLE INFC HWT ***
7   0   0   0   0   0   0   0   0   0   0   0

```

END PWAT-PARM1

PWAT-PARM2

```

<PLS > PWATER input info: Part 2 ***
# - # ***FOREST LZSN INFILT LSUR SLSUR KVARY AGWRC
7   0   5   0.8   400   0.05   0.3   0.996

```

END PWAT-PARM2

PWAT-PARM3

```

<PLS > PWATER input info: Part 3 ***
# - # ***PETMAX PETMIN INFEXP INFILD DEEPFR BASETP AGWETP
7   0   0   2   2   0   0   0

```

END PWAT-PARM3

PWAT-PARM4

```

<PLS > PWATER input info: Part 4 ***
# - # CEPSC UZSN NSUR INTFW IRC LZETP ***
7   0.1   0.5   0.25   0   0.7   0.25

```

END PWAT-PARM4

PWAT-STATE1

```

<PLS > *** Initial conditions at start of simulation
        ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
# - # *** CEPS SURS UZS IFWS LZS AGWS GWVS
7   0   0   0   0   3   1   0

```

END PWAT-STATE1

END PERLND

IMPLND

GEN-INFO

```

<PLS ><-----Name-----> Unit-systems Printer ***
# - # User t-series Engr Metr ***
              in out ***
1   ROADS/FLAT      1   1   1   27   0
4   ROOF TOPS/FLAT  1   1   1   27   0

```

END GEN-INFO

*** Section IWATER***

ACTIVITY

```

<PLS > ***** Active Sections *****
# - # ATMP SNOW IWAT SLD IWG IQAL ***
1   0   0   1   0   0   0
4   0   0   1   0   0   0

```

END ACTIVITY

PRINT-INFO

```

<ILS > ***** Print-flags ***** PIVL PYR
# - # ATMP SNOW IWAT SLD IWG IQAL *****
1   0   0   4   0   0   0   1   9
4   0   0   4   0   0   0   1   9

```

END PRINT-INFO

IWAT-PARM1

```

<PLS > IWATER variable monthly parameter value flags ***
# - # CSNO RTOP VRS VNN RTLI ***
1   0   0   0   0   0
4   0   0   0   0   0

```

END IWAT-PARM1

IWAT-PARM2

```

<PLS > IWATER input info: Part 2 ***
# - # *** LSUR SLSUR NSUR RETSC
1   400   0.01   0.1   0.1
4   400   0.01   0.1   0.1

```



```

HYDR-INIT
RCHRES Initial conditions for each HYDR section ***
# - # *** VOL Initial value of COLIND Initial value of OUTDGT
*** ac-ft for each possible exit for each possible exit
<-----><-----> <----><----><----><----><----> *** <----><----><----><----><---->
END HYDR-INIT
END RCHRES

```

```

SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
END FTABLES

```

```

EXT SOURCES
<-Volume-> <Member> SsysSgap<--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name> # <Name> # tem strg<-factor->strg <Name> # # <Name> # # ***
WDM 2 PREC ENGL 1 PERLND 1 999 EXTNL PREC
WDM 2 PREC ENGL 1 IMPLND 1 999 EXTNL PREC
WDM 1 EVAP ENGL 1 PERLND 1 999 EXTNL PETINP
WDM 1 EVAP ENGL 1 IMPLND 1 999 EXTNL PETINP

```

```
END EXT SOURCES
```

```

EXT TARGETS
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Volume-> <Member> Tsys Tgap Amd ***
<Name> # <Name> # #<-factor->strg <Name> # <Name> tem strg strg***
COPY 1 OUTPUT MEAN 1 1 48.4 WDM 701 FLOW ENGL REPL
COPY 501 OUTPUT MEAN 1 1 48.4 WDM 801 FLOW ENGL REPL
END EXT TARGETS

```

```

MASS-LINK
<Volume> <-Grp> <-Member-><--Mult--> <Target> <-Grp> <-Member->***
<Name> <Name> # #<-factor-> <Name> <Name> # #***
MASS-LINK 12
PERLND PWATER SURO 0.083333 COPY INPUT MEAN
END MASS-LINK 12

MASS-LINK 13
PERLND PWATER IFWO 0.083333 COPY INPUT MEAN
END MASS-LINK 13

MASS-LINK 15
IMPLND IWATER SURO 0.083333 COPY INPUT MEAN
END MASS-LINK 15

```

```
END MASS-LINK
```

```
END RUN
```

Disclaimer

Legal Notice

This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2022; All Rights Reserved.

Clear Creek Solutions, Inc.
6200 Capitol Blvd. Ste F
Olympia, WA. 98501
Toll Free 1(866)943-0304
Local (360)943-0304


www.clearcreeksolutions.com

5.6 Water Quality System


As detailed in the 2014 SWMMWW this project is required to meet the 2014 SWMMWW requirement for Basic Water Quality. According to the manual, runoff tributary to the rooftop areas of the single-family residence, carport and shop buildings is not considered pollution-generating. As shown in the table below, the total Pollution Generating Impervious Surface Area for this project is 4,989 square feet. The 2014 SWMMWW states that a project is exempt from the construction of a stormwater treatment facility when less than 5,000 square feet of pollution-generating impervious surface will be created. Because of this, no stormwater treatment facility is required for this development.

New and Replaced Hard Surfaces Table Breakdown				
Description	Area (SF)	New Impervious Surface Area (SF)	Replaced Impervious Surface Area (SF)	Pollution Generating Impervious Surface Area (SF)
Onsite Access Driveway	4600	4600	0	4600
New 14 th St SW Driveway Cut	270	270	0	270
Replaced 14 th St SW Sidewalk	119	0	119	119
Single-family Residence (Porch Included)	2,694	2,694	0	0
Shop	429	429	0	0
Carport	1,500	1,500	0	0
Total	9612	9493	119	4989

Figure 5.6.1



*When **Phosphorus Control and Enhanced** treatment are required, the Large Wetpond and certain types of emerging technologies will not meet both types of treatment requirements. A different or an additional treatment facility will be required to meet Enhanced treatment.



DEPARTMENT OF
ECOLOGY
State of Washington

Figure V-2.1.1 Treatment Facility Selection Flow Chart


Revised December 2015

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.

5.7 Conveyance System Analysis and Design

The on-site conveyance system will consist of a tightlined system to convey runoff from the proposed shared access driveway, shop building and single-family residence. This system will convey runoff to the existing on-site catch basin near the southeast property corner. Because the proposed development consists of a two-lot short plat, conveyance calculations are not required for the proposed on-site conveyance system.

Tab 6.0



6.0 CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN

The following is a list of the thirteen SWPPP elements and how they will be addressed for this project:

Element #1 - Preserve Vegetation / Mark Clearing Limits: Clearing Limits will be flagged in the field during construction.

Element #2 - Establish Construction Access: A stabilized gravel construction entrance will be provided during construction.

Element #3 - Control Flow Rates: Flow rates will be controlled during construction using hydroseeding and a sediment trap, if necessary.

Element #4 - Install Sediment Controls: A silt fence will be provided as necessary to prevent transport of sediment offsite.

Element #5 - Stabilize Soils: Cover measures such as plastic coverings will be provided as necessary to protect any soil from erosive forces.

Element #6 - Protect Slopes: There are no significant slopes onsite, existing or proposed that require additional measures beyond the soil stabilization measures such as hydroseeding.

Element #7 - Protect Permanent Drain Inlets: Existing permanent drain inlets will be protected during construction using catch basin inserts.

Element #8 - Stabilize Channels and Outlets: There are no existing or proposed channels and outfalls for this project.

Element #9 - Control Pollutants: The contractor will dispose of all pollutants and waste materials in a safe and timely manner.


Element #10 - Control Dewatering: Any water in underground utility trenches or low spots will be routed to the on-site discharge point.

Element #11 - Maintain Best Management Practices: The contractor will maintain and repair all proposed BMP's to ensure continued performance of their intended function.

Element #12 - Manage the Project: The contractor will be required to follow and maintain the Construction SWPPP throughout all construction activities.

Element #13 - Protect Low Impact Development BMPs: Contractor shall keep all heavy equipment off all permanent BMP's

Tab 7.0




7.0 SPECIAL REPORTS AND STUDIES

This section contains the following information:

- 7.1 Geotechnical Evaluation, prepared by Earth Solutions NW dated December 17, 2021
- 7.2 Groundwater Monitoring Program Report prepared by Earth Solutions NW dated April 25, 2022
- 7.3 Critical Area Assessment and Biological Evaluation, prepared by Habitat Technologies dated August 29, 2022.

7.1 Geotechnical
Evaluation, prepared by
Earth Solutions NW
LLC dated December
17, 2021





December 17, 2021
ES-8181

Earth Solutions NW LLC

Geotechnical Engineering, Construction
Observation/Testing and Environmental Services

Mr. Kris Mullan
808 – 14th Street Southwest
Puyallup, Washington 98371

**Subject: Geotechnical Evaluation
Proposed Single-Family Residence
808 – 14th Street Southwest
Puyallup, Washington**

Reference: Puyallup Municipal Code (PMC) Chapter 21.06: Critical Areas

J.E. Schuster et al.
Geologic Map of the Tacoma 1:100,000-scale Quadrangle, Washington, 2015

Stephen P. Palmer et al.
Liquefaction Susceptibility Map of Pierce County, Washington, 2004

United States Department of Agriculture (USDA)
Natural Resources Conservation Service (NRCS)
Online Web Soil Survey (WSS) resource

Washington State Department of Ecology
2014 Stormwater Management Manual for Western Washington

Dear Mr. Mullan:

As requested, Earth Solutions NW, LLC (ESNW) has prepared this letter for the proposed project. The letter was prepared in general accordance with the scope of services outlined in the October 2021 Change Order to our original proposal, which was authorized by you. A summary of the subsurface exploration on site and preliminary geotechnical recommendations to aid with the site design are provided in this letter.

Project Description

We understand the subject site will be subdivided (creating a two-lot short plat), and one new single-family residence will be constructed. The proposal will also include construction of a new driveway, utility improvements, and outbuildings. Infiltration and other flow control stormwater Best Management Practices (BMPs) must be utilized to the extent practical. At the time of this letter, the proposal included construction of a porous driveway.

Surface Conditions

The subject site is located on the west side of 14th Street Southwest, about 400 feet south of the intersection with 7th Avenue Southwest, in Puyallup, Washington. The approximate location of the property is illustrated on Plate 1 (Vicinity Map). The site consists of one tax parcel (Pierce County Parcel No. 5505300831), totaling about 0.93 acres. The site is surrounded to the west, south, and north by residential structures and to the east by 14th Street Southwest.

Subsurface Conditions

An ESNW representative observed, logged, and sampled five test pits on October 7, 2021. Five additional test pits, three of which had piezometers installed for seasonal groundwater monitoring purposes, were completed on November 2, 2021. The test pits were excavated within accessible site areas, using a mini trackhoe and operator retained by ESNW. The test pits were completed to evaluate and classify site soils, characterize groundwater conditions within accessible site areas, and perform in-situ infiltration testing.

The approximate locations of the test pits are depicted on Plate 2 (Test Pit Location Plan). Please refer to the attached test pit logs for a more detailed description of subsurface conditions. Representative soil samples collected at the test pit locations were analyzed in general accordance with both Unified Soil Classification System (USCS) and USDA methods and procedures.

Topsoil and Fill

Where encountered at surface grades, the topsoil was about 6 to 12 inches thick. The topsoil was characterized by the observed dark brown hue, the presence of fine organics, and small root intrusions.

Fill was encountered at test pit locations TP-3, TP-6, TP-8, TP-9, and TP-10 to depths of about one-and-one-half to two-and-one-half feet below the existing ground surface (bgs). The fill was characterized as silty sand, in a loose to medium dense and damp to moist condition. Small pieces of asphalt, brick, and plastic were observed in the fill.

Native Soil

Underlying the topsoil and fill, the native soil consisted primarily of silty sand and sandy silt (USCS: SM and ML, respectively). The in-situ density of the native soil was characterized primarily as "medium dense" at each test location, and the in-situ moisture content was characterized as damp to wet condition at the time of exploration depending on the presence of groundwater. The maximum exploration depth was approximately nine-and-one-half feet bgs.

Geologic Setting

The referenced geologic map resource identifies alluvium (Qa) as the primary native soil unit underlying the subject site and proximate areas. As reported on the geologic map resource, alluvium is typified by well-rounded and moderately to well-sorted beds of fluvial silt, sand, and gravel. The referenced WSS resource identifies Sultan silt loam as the primary soil unit underlying the subject development area. The Sultan series was formed in stratified alluvial deposits as a result of the Mount Rainier watershed. Based on our field observations, the on-site native soil is consistent with the local geologic mapping of alluvium.

Groundwater

Groundwater was encountered at the test locations at varying depths during the October and November 2021 fieldwork, ranging from about three to eight-and-one-half feet bgs. As previously mentioned, ESNW installed a series of standpipe piezometers in select test locations and is performing groundwater monitoring over the course of the 2021–2022 wet season. An opinion of the seasonal high groundwater table elevation can be provided at the conclusion of the wet season based on review of groundwater information collected by the in-place dataloggers.

It should be noted that seepage rates and elevations fluctuate depending on many factors, including precipitation duration and intensity, the time of year, and soil conditions. In general, groundwater flow rates are higher during the winter, spring, and early summer months.

Geologically Hazardous Areas

We reviewed the referenced PMC chapter to determine the presence of geologically hazardous areas on site. Based on our review, the subject site may be considered within a seismic hazard area. The three remaining geologically hazardous areas recognized by the PMC—erosion hazard area, landslide hazard area, and volcanic hazard area—are not applicable to the subject site.

According to PMC 21.06.1210(3)(c), seismic hazard areas are defined as “areas subject to severe risk of damage as a result of earthquake-induced ground shaking, slope failure, settlement or subsidence, soil liquefaction, or tsunamis.” The referenced liquefaction susceptibility map indicates the site and surrounding areas possess high liquefaction susceptibility. Based on our field observations, it is our opinion the risk of liquefaction during a seismic event can generally be considered low. This opinion is based primarily on the significant percentage of fines (material passing the Number 200 sieve) inherent to the native soil; predominantly silty soils are typically not susceptible to liquefaction during a seismic event. On this basis, it is our opinion the site is not at severe risk of damage during a seismic event and does not meet the PMC definition of a seismic hazard area.

Preliminary Geotechnical Recommendations

The primary geotechnical considerations for the proposal are associated with structural fill placement and compaction, earthwork and grading activities, foundation support, and stormwater management. Based on our field observations and our understanding of the proposed development, pertinent geotechnical recommendations and design parameters are provided below.

In-situ and Imported Soil

The native alluvium is moisture sensitive, and successful use of the native alluvium as structural fill will largely be dictated by the moisture content at the time of placement and compaction. If the native alluvium cannot be successfully compacted, the use of an imported soil may be necessary.

Performing grading activities during summer months of relatively low rainfall activity is recommended to minimize site degradation. In our opinion, a contingency should be provided in the project budget for the export of soil that cannot be successfully compacted as structural fill, particularly if grading activities take place during periods of extended rainfall activity. In general, soil with an appreciable fines content (greater than 5 percent) typically degrades rapidly when exposed to periods of rainfall.

Imported soil intended for use as structural fill should be evaluated by ESNW during construction. The imported soil must be able to achieve the necessary moisture content, as determined by the Modified Proctor Method (ASTM D1557), at the time of placement and compaction. During wet weather conditions, imported soil intended for use as structural fill should consist of a well-graded, granular soil with a fines content of 5 percent or less (where the fines content is defined as the percent passing the Number 200 sieve, based on the minus three-quarter-inch fraction).

Structural Fill

Structural fill is defined as compacted soil placed in foundation, slab-on-grade, roadway, permanent slope, retaining wall, and utility trench backfill areas. Structural fill placed and compacted during site grading activities should meet the following specifications:

- | | |
|----------------------------------|-------------------------------|
| • Structural fill material | Granular soil* |
| • Moisture content | At or slightly above optimum† |
| • Relative compaction (minimum) | 95 percent (Modified Proctor) |
| • Loose lift thickness (maximum) | 12 inches |

* *The existing soil may not be suitable for use as structural fill unless the soil is at (or slightly above) the optimum moisture content at the time of placement and compaction.*

† *Soil shall not be placed dry of optimum and should be evaluated by ESNW during construction.*

Foundations

The proposed residential structures may be supported on conventional continuous and spread footing foundations bearing on either compact structural fill or competent native soil. In general, competent native soil for foundation support should be encountered beginning at a depth of roughly two to three feet bgs. Existing fill intended for reuse as structural fill must be free of debris and should be evaluated by ESNW prior to use. In general, if loose or unsuitable soil conditions are exposed at foundation subgrade elevations, additional mechanical compactive effort or overexcavation and replacement with suitable structural fill will likely be necessary.

Provided foundations will be supported as prescribed, the following parameters may be used for design:

- Allowable soil bearing capacity 2,000 psf
- Passive earth pressure 250 pcf (equivalent fluid)
- Coefficient of friction 0.35

A one-third increase in the allowable soil bearing capacity may be assumed for short-term wind and seismic loading conditions. The above passive pressure and friction values include a factor-of-safety of 1.5. With structural loading as expected, about one inch of total static settlement and about one-half inch of differential static settlement is anticipated. Most of the anticipated settlement should occur during construction when dead loads are applied.

Seismic Design

The 2018 International Building Code (2018 IBC) recognizes the most recent edition of the Minimum Design Loads for Buildings and Other Structures manual (ASCE 7-16) for seismic design, specifically with respect to earthquake loads. Based on the soil conditions encountered at the test pit locations, the parameters and values provided below are recommended for seismic design per the 2018 IBC.

Parameter	Value
Site Class	D*
Mapped short period spectral response acceleration, S_s (g)	1.278
Mapped 1-second period spectral response acceleration, S_1 (g)	0.440
Short period site coefficient, F_a	1.0
Long period site coefficient, F_v	1.860 [†]
Adjusted short period spectral response acceleration, S_{MS} (g)	1.278
Adjusted 1-second period spectral response acceleration, S_{M1} (g)	0.818 [†]
Design short period spectral response acceleration, S_{DS} (g)	0.852
Design 1-second period spectral response acceleration, S_{D1} (g)	0.546 [†]

* Assumes medium dense native soil conditions, encountered to a maximum depth of 9.5 feet bgs during the October and November 2021 field explorations, remain dense to at least 100 feet bgs.

† Values assume F_v may be determined using linear interpolation per Table 11.4-2 in ASCE 7-16.

Please refer to the *Geologically Hazardous Areas* section of this letter for evaluation of site-specific seismic risk and liquefaction susceptibility.

Slab-on-Grade Floors

Slab-on-grade floors for the proposed residential structure should be supported on firm and unyielding subgrades comprised of competent native soil, compacted structural fill, or new structural fill. Unstable or yielding subgrade areas should be recompacted or overexcavated and replaced with suitable structural fill prior to slab construction.

A capillary break, consisting of at least four inches of free-draining crushed rock or gravel, should be placed below each slab. The free-draining material should have a fines content of 5 percent or less (where the fines content is defined as the percent passing the Number 200 sieve, based on the minus three-quarter-inch fraction). In areas where slab moisture is undesirable, installation of a vapor barrier below each slab should be considered. If a vapor barrier is to be utilized, it should be a material specifically designed for use as a vapor barrier and should be installed in accordance with the specifications of the manufacturer.

Retaining Walls

Retaining walls must be designed to resist earth pressures and applicable surcharge loads. The following parameters may be used for design:

- Active earth pressure (unrestrained condition) 40 pcf (equivalent fluid)
- At-rest earth pressure (restrained condition) 60 pcf
- Traffic surcharge* (passenger vehicles) 70 psf (rectangular distribution)
- Passive earth pressure 250 pcf (equivalent fluid)
- Coefficient of friction 0.35
- Seismic surcharge 8H psf[†]

* Where applicable.

† Where H equals the retained height (in feet).

The above design parameters are based on a level backfill condition and level grade at the wall toe under the assumption that native soil will be retained. If a significant zone of imported structural fill will be retained directly behind the wall, less stringent design parameters can be provided. Revised design values will be necessary if sloping grades are to be used above or below retaining walls. Additional surcharge loading from adjacent foundations, sloped backfill, or other relevant loads should be included in the retaining wall design.

Retaining walls should be backfilled with free-draining material that extends along the height of the wall and a distance of at least 18 inches behind the wall. The upper 12 inches of the wall backfill may consist of a less permeable soil if desired. A perforated drainpipe should be placed along the base of the wall and connected to an approved discharge location. A typical retaining wall drainage detail is provided on Plate 3. If drainage is not provided, hydrostatic pressures should be included in the wall design.

Drainage

Groundwater will likely be encountered in site excavations. Temporary measures to control surface water runoff and groundwater during construction would likely involve interceptor trenches and sumps. ESNW should be consulted during preliminary grading to both identify areas of seepage and provide recommendations to reduce the potential for seepage-related instability.

Finish grades must be designed to direct surface drain water away from structures and slopes. Water must not be allowed to pond adjacent to structures. In our opinion, foundation drains should be installed along building perimeter footings. A typical foundation drain detail is provided on Plate 4.

Infiltration Evaluation

Per the requirements of the referenced 2014 Stormwater Management Manual for Western Washington (2014 SWMMWW), one small-scale Pilot Infiltration Test (PIT) was completed during the November 2021 fieldwork. The PIT was completed at TP-10 and at an approximate depth of two-and-one-half feet bgs. The following test results and correction factors were used to determine the calculated (long-term) infiltration rate:

- | | |
|--|-----------------------------|
| • K_{sat} initial (measured infiltration rate; TP-10) | 1.2 inches per hour (in/hr) |
| • Site variability and number of tests (CF_v) | 0.75 |
| • Test method (CF_t) | 0.5 (small-scale PIT) |
| • Degree of influent control (CF_m) | 0.9 |
| • K_{sat} design (calculated infiltration rate; TP-10) | 0.4 in/hr |

Use of the above infiltration rate is considered acceptable near the location and elevation of the PIT. Should different locations of the site be pursued for infiltration, ESNW should be contacted to review the applicability of the above infiltration rate. Supplementary testing may be warranted as project plans develop. In addition, as mentioned in the *Groundwater* section of this letter, ESNW is currently providing groundwater monitoring services during the 2021–2022 wet season. The seasonal high groundwater table elevation may impact infiltration feasibility and should be discussed further as monitoring data becomes available.

ESNW should be contacted to review stormwater management plans if infiltration is used in the final design. Where infiltration facilities are incorporated into construction, ESNW should be contacted to observe installation of infiltration facilities and provide supplementary recommendations, as necessary.

Permeable Pavement Considerations

We understand permeable pavement is being considered as part of the project design. Per the 2014 SWMMWW, the native soil underneath the permeable pavement surface must meet minimum cation exchange capacity (CEC) and organic content (OC) values of 5 meq/100 g and 1.0 percent, respectively, for water quality purposes. Based on the laboratory CEC and OC analysis results (attached to this letter for reference), the native underlying soil is generally expected to meet the minimum CEC and OC requirements. The ability of the proposed permeable pavement to meet the required minimum vertical separation from the seasonal high groundwater table elevation is also an important geotechnical consideration, which is being evaluated by ESNW over the course of the 2021–2022 wet season.

Limitations

This letter has been prepared for the exclusive use of Mr. Kris Mullan and his representatives. No warranty, express or implied, is made. The recommendations and conclusions provided in this letter are professional opinions consistent with the level of care and skill that is typical of other members in the profession currently practicing under similar conditions in this area. Variations in the soil and groundwater conditions encountered at the test pit locations may exist and may not become evident until construction. ESNW should reevaluate the contents of this letter if variations are encountered.

Mr. Kris Mullan
December 17, 2021

ES-8181
Page 9

We trust this letter meets your current needs. Please call if you have any questions about this letter or if we can be of further assistance.

Sincerely,

EARTH SOLUTIONS NW, LLC



Steven K. Hartwig, G.I.T.
Staff Geologist




Keven D. Hoffmann, P.E.
Geotechnical Engineering Services Manager

Attachments: Plate 1 – Vicinity Map
Plate 2 – Test Pit Location Plan
Plate 3 – Retaining Wall Drainage Detail
Plate 4 – Footing Drain Detail
Test Pit Logs
Laboratory Data

cc: Barghausen Consulting Engineers, Inc.
Attention: Mr. Vicente Varas (Email only)
Mr. Barry Talkington, P.E. (Email only)



Reference:
 Pierce County, Washington
 OpenStreetMap.org




Earth Solutions NW LLC
 Geotechnical Engineering, Construction
 Observation/Testing and Environmental Services

Vicinity Map
 Mullan Short Plat
 Puyallup, Washington


NOTE: This plate may contain areas of color. ESNW cannot be responsible for any subsequent misinterpretation of the information resulting from black & white reproductions of this plate.

Drwn. MRS	Date 11/04/2021	Proj. No. 8181
Checked SKH	Date Nov. 2021	Plate 1




LEGEND

TP-1 | — Approximate Location of
ESNW Test Pit, Proj. No.
ES-8181, Oct./Nov. 2021

 Subject Site


 Existing Building



NOTE: The graphics shown on this plate are not intended for design purposes or precise scale measurements, but only to illustrate the approximate test locations relative to the approximate locations of existing and / or proposed site features. The information illustrated is largely based on data provided by the client at the time of our study. ESNW cannot be responsible for subsequent design changes or interpretation of the data by others.

NOTE: This plate may contain areas of color. ESNW cannot be responsible for any subsequent misinterpretation of the information resulting from black & white reproductions of this plate.

		Earth Solutions NW_{LLC} Geotechnical Engineering, Construction Observation/Testing and Environmental Services	
Test Pit Location Plan Mullan Short Plat Puyallup, Washington			
Drwn. MRS	Date 12/14/2021	Proj. No. 8181	
Checked SKH	Date Dec. 2021	Plate 2	




NOTES:


- Free-draining Backfill should consist of soil having less than 5 percent fines. Percent passing No. 4 sieve should be 25 to 75 percent.
- Sheet Drain may be feasible in lieu of Free-draining Backfill, per ESNW recommendations.
- Drain Pipe should consist of perforated, rigid PVC Pipe surrounded with 1-inch Drain Rock.

SCHMATIC ONLY - NOT TO SCALE
NOT A CONSTRUCTION DRAWING

LEGEND:




Free-draining Structural Backfill



1-inch Drain Rock

		Earth Solutions NW_{LLC} Geotechnical Engineering Construction Observation/Testing and Environmental Services	
Retaining Wall Drainage Detail Mullan Short Plat Puyallup, Washington			
Drwn. MRS	Date 11/04/2021	Proj. No. 8181	
Checked SKH	Date Nov. 2021	Plate 3	




Perforated Rigid Drain Pipe
(Surround in Drain Rock)

NOTES:


- Do NOT tie roof downspouts to Footing Drain.
- Surface Seal to consist of 12" of less permeable, suitable soil. Slope away from building.

SCHEMATIC ONLY - NOT TO SCALE
NOT A CONSTRUCTION DRAWING

LEGEND:



Surface Seal: native soil or other low-permeability material.


















1-inch Drain Rock

	Earth Solutions NW_{LLC} Geotechnical Engineering, Construction Observation/Testing and Environmental Services	
	Footing Drain Detail Mullan Short Plat Puyallup, Washington	
Drwn. MRS	Date 11/04/2021	Proj. No. 8181
Checked SKH	Date Nov. 2021	Plate 4

Earth Solutions NW_{LLC}

SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS		
			GRAPH	LETTER			
COARSE GRAINED SOILS MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE	GRAVEL AND GRAVELLY SOILS (LITTLE OR NO FINES)	CLEAN GRAVELS		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES		
		(LITTLE OR NO FINES)		GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES		
		GRAVELS WITH FINES		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES		
		(APPRECIABLE AMOUNT OF FINES)		GC	CLAYEY GRAVELS, GRAVEL - SAND - CLAY MIXTURES		
	SAND AND SANDY SOILS MORE THAN 50% OF COARSE FRACTION PASSED ON NO. 4 SIEVE	CLEAN SANDS (LITTLE OR NO FINES)	CLEAN SANDS		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	
			(LITTLE OR NO FINES)		SP	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES	
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)	SANDS WITH FINES		SM	SILTY SANDS, SAND - SILT MIXTURES	
			(APPRECIABLE AMOUNT OF FINES)		SC	CLAYEY SANDS, SAND - CLAY MIXTURES	
			SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	SILTS AND CLAYS		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				(LIQUID LIMIT LESS THAN 50)		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	SILTS AND CLAYS		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY		
		(LIQUID LIMIT LESS THAN 50)		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS		
	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	SILTS AND CLAYS		CH	INORGANIC CLAYS OF HIGH PLASTICITY		
		(LIQUID LIMIT GREATER THAN 50)		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS		

DUAL SYMBOLS are used to indicate borderline soil classifications.

The discussion in the text of this report is necessary for a proper understanding of the nature of the material presented in the attached logs.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-1

PAGE 1 OF 1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18528 LONGITUDE -122.31428
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 10": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION
0					
		MC = 12.5%	TPSL		Dark brown TOPSOIL, minor root intrusions to 1'
					34.0
		MC = 24.8% Fines = 22.9%	SM		Brown silty SAND, loose to medium dense, damp -becomes gray, trace iron oxide staining -becomes blue-gray [USDA Classification: fine sandy LOAM] -becomes moist
5					28.0
		MC = 44.9%	ML		Gray silty SAND, medium dense, wet -light groundwater seepage -organic debris
					27.0

Test pit terminated at 8.0 feet below existing grade. Groundwater encountered at 7.5 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-2

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.1851 LONGITUDE -122.31418
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
		MC = 12.2%	TPSL		Dark brown TOPSOIL	34.5
			SM		Brown silty SAND, loose to medium dense, damp -becomes gray, light iron oxide staining	31.5
5		MC = 33.9% Fines = 98.4%	ML		Gray SILT, medium dense, moist [USDA Classification: LOAM]	27.0
		MC = 55.6%			-organic debris -becomes wet -light groundwater seepage	27.0

Test pit terminated at 8.0 feet below existing grade. Groundwater encountered at 7.5 feet during excavation. No caving observed.






Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-3

PAGE 1 OF 1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18495 LONGITUDE -122.31412
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0			TPSL		Dark brown TOPSOIL	34.5
			SM		Brown silty SAND with gravel, medium dense, damp (Fill) -asphalt debris	33.0
		MC = 50.0% Fines = 93.2%			Gray SILT, medium dense, wet [USDA Classification: LOAM] -organic debris, light iron oxide staining	
5		MC = 41.6%	ML		-light groundwater seepage, moderate organics	
		MC = 52.4%			-light groundwater seepage	
						25.5

Test pit terminated at 9.5 feet below existing grade. Groundwater encountered at 6.5 and 8.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-4

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18508 LONGITUDE -122.31391
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 10": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
		MC = 12.8% Fines = 32.9%	TPSL		Dark brown TOPSOIL, minor roots to 12"	34.0
			SM		Brown silty SAND, loose to medium dense, damp [USDA Classification: sandy LOAM] -becomes gray, light iron oxide staining	31.0
5		MC = 52.3% MC = 35.2%	ML		Gray SILT, medium dense, moist to wet -trace organics debris -light groundwater seepage -light groundwater seepage	25.5
		MC = 32.7%			Test pit terminated at 9.5 feet below existing grade. Groundwater encountered at 6.5 and 8.5 feet during excavation. No caving observed.	



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-5

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18493 LONGITUDE -122.31369
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 8": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0			TPSL		Dark brown TOPSOIL	34.5
		MC = 10.2%	SM		Brown silty SAND, loose to medium dense, damp to moist	32.5
		MC = 35.0% LL = 44 PL = 35 Fines = 81.1%	ML		Gray SILT with sand, medium dense, moist to wet	
5		MC = 43.7%			-light groundwater seepage, slight caving at seepage point	
		MC = 36.9%			-light groundwater seepage	26.0

Test pit terminated at 9.0 feet below existing grade. Groundwater encountered at 5.0 and 7.5 feet during excavation. Caving observed at 5.0 feet.






Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-6

PAGE 1 OF 1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18498 LONGITUDE -122.31417
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
			TPSL		Dark brown TOPSOIL, root to 1.5'	34.5
			SM		Brown silty SAND, loose to medium dense, damp (Fill) -asphalt debris	33.0
		MC = 42.8%	SP-SM		Brown poorly graded SAND with silt, medium dense, wet -becomes gray, groundwater seepage, moderate iron oxide staining	31.5

Test pit terminated at 3.5 feet below existing grade. Groundwater encountered at 3.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18518 LONGITUDE -122.31399
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 12": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION
0					
			TPSL		Dark brown TOPSOIL, roots to 1.5'
		MC = 16.6% Fines = 26.2%	SM		Brown silty SAND, loose to medium dense, moist [USDA Classification: slightly gravelly loamy SAND] -moderate caving to BOH -groundwater
5		MC = 40.4%	ML		Gray SILT, medium dense, wet -becomes saturated
		MC = 50.1%			

Test pit terminated at 9.0 feet below existing grade. Groundwater encountered at 4.0 feet during excavation. Caving observed from 4.0 feet to BOH.






Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-8

PAGE 1 OF 1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18494 LONGITUDE -122.31338
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION		
0							
		MC = 39.6%	TPSL		0.5	Dark brown TOPSOIL, roots	34.5
			SM			Brown silty SAND, loose to medium dense, damp (Fill) -asphalt debris, plastic debris	
			ML		2.5	Gray SILT, medium dense, wet -moderate iron oxide staining at contact	32.5
		MC = 37.5% CEC = 14.0 meq/100g OC = 2.7%					
		MC = 43.8%			4.5	-groundwater	30.5




Test pit terminated at 4.5 feet below existing grade. Groundwater encountered at 4.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-9

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18506 LONGITUDE -122.31362
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
		MC = 6.7%	TPSL		Dark brown TOPSOIL, roots to 6"	34.5
			SM		Brown silty SAND with gravel, loose to medium dense, damp to moist (Fill)	
					-asphalt debris, brick debris	33.0
		MC = 60.7% CEC = 15.0 meq/100g OC = 4.7%	ML		Brown SILT with sand, medium dense, saturated -becomes gray, moderate to severe iron oxide staining	
		MC = 63.2%			-groundwater	31.0




Test pit terminated at 4.0 feet below existing grade. Groundwater encountered at 3.5 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-10

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18493 LONGITUDE -122.31403
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
			TPSL		Dark brown TOPSOIL, roots to 8"	34.5
			SM		Brown silty SAND, loose to medium dense, moist (Fill) -asphalt debris	33.5
			GM		Brown silty GRAVEL with sand, medium dense, moist -becomes gray, infiltration test [USDA Classification: very gravelly LOAM]	32.5

MC = 20.9%
 Fines = 38.6%

Test pit terminated at 2.5 feet below existing grade. No groundwater encountered during excavation. No caving observed.




Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

GRAIN SIZE DISTRIBUTION

PROJECT NUMBER ES-8181

PROJECT NAME Mullan Short Plat



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification							Cc	Cu
● TP-07 2.00ft.	USDA: Brown Slightly Gravelly Loamy Sand. USCS: SM.								
☒ TP-10 2.50ft.	USDA: Gray Very Gravelly Loam. USCS: GM with Sand.								

Specimen Identification	D100	D60	D30	D10	LL	PL	PI	%Silt	%Clay
● TP-07 2.0ft.	4.75	0.295	0.104					26.2	
☒ TP-10 2.5ft.	37.5	2.294						38.6	

GRAIN SIZE USDA ES-8181 MULLAN SHORT PLAT.GPJ GINT US LAB.GDT 11/19/21

Am Test Inc.
13600 NE 126TH PL
Suite C
Kirkland, WA 98034
(425) 885-1664
www.amtestlab.com



Professional
Analytical
Services

ANALYSIS REPORT

EARTH SOLUTIONS NW
1805 136TH PL NE
BELLEVUE, WA 98005
Attention: KEVEN HOFFMAN
Project Name: MULLAN SHORT PLAT
All results reported on an as received basis.

Date Received: 11/08/21
Date Reported: 11/23/21

AMTEST Identification Number 21-A017058
Client Identification TP-8, 3.5'
Sampling Date


Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	14.	meq/100g		0.5	SW-846 9081	JDR	11/18/21


AMTEST Identification Number 21-A017059
Client Identification TP-9, 3'
Sampling Date

Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	15.	meq/100g		0.5	SW-846 9081	JDR	11/18/21


Kathy Fugiel
President

7.2 Groundwater Monitoring
Program Report
prepared by Earth
Solutions NW dated
April 25, 2022





April 25, 2022
ES-8181

Earth Solutions NW LLC

Geotechnical Engineering, Construction
Observation/Testing and Environmental Services

Mr. Kris Mullan
808 – 14th Street Southwest
Puyallup, Washington 98371

**Subject: Groundwater Monitoring Program and Infiltration BMP Feasibility
Proposed Single-Family Residence
808 – 14th Street Southwest
Puyallup, Washington**

Reference: Earth Solutions NW, LLC
Geotechnical Evaluation
Project No. ES-8181, dated December 17, 2021

Washington State Department of Ecology
2014 Stormwater Management Manual for Western Washington

Dear Mr. Mullan:

As requested, Earth Solutions NW, LLC (ESNW) has prepared this letter summarizing the results of our seasonal groundwater monitoring program on site. Recommendations for infiltration Best Management Practice (BMP) feasibility, from a geotechnical standpoint, are also provided in this letter. The recommendations and conclusions provided in this letter are consistent with applicable portions of the referenced 2014 Stormwater Management Manual for Western Washington (2014 SWMMWW), which is adopted by the City of Puyallup.

Groundwater Monitoring Program

The monitoring program consisted of installing three piezometers at the approximate locations depicted on Plate 2 (Test Pit Location Plan). Test pit logs and laboratory analyses from our field explorations are attached to this letter for reference. Beginning at the time of piezometer installation (November 2, 2021), daily groundwater levels were recorded using dataloggers. ESNW personnel visited the site bimonthly to download the collected data and perform manual measurements at each piezometer location using a depth-to-water meter. The tables on page 2 summarize the groundwater data collected during the monitoring program. With respect to the information presented in the tables, the piezometer locations were not surveyed and therefore present approximate elevations of the seasonal high groundwater table (GWT), which is based on readily available topographic data. Specific depths below the existing ground surface (bgs) are presented in the tables.

Test Pit	Depth of Test Pit (ft)	Ground Elevation (ft)	Peak GWT Depth (ft bgs)	Peak GWT Elevation (ft)	Peak Date
TP-6	3.5	35	0 (surface)	35	1/6/2022
TP-7	9.0	35	0 (surface)	35	1/6/2022
TP-8	4.5	35	0 (surface)	35	1/6/2022

Date of Manual Measurement	TP-6 GWT Depth (ft bgs)	TP-7 GWT Depth (ft bgs)	TP-8 GWT Depth (ft bgs)
11/15/2021	0	0	1.4
11/18/2021	0	0	2.5
12/1/2021	0.7	0	1.9
12/15/2021	0.7	0	1.8
1/6/2022	0	0	0
1/19/2022	0.3	0	0.8
2/3/2022	1.4	0.8	2.4

As indicated in the tables above, the seasonal high GWT elevation occurred at the surface at each of the piezometer locations. Based on the field observations of high groundwater conditions, the monitoring period was terminated prior to the traditional end of the wet season within the City of Puyallup (April 1). Based on the data collected during the monitoring period, it is our opinion the peak GWT depths listed in the tables above are indicative of the seasonal high GWT elevation.

Infiltration BMP Feasibility

The 2014 SWMMWW requires a certain minimum vertical separation distance between the bottom of an infiltration facility and the seasonal high GWT elevation. The code-specified minimum vertical separation distances vary between one to five feet depending on the type of infiltration facility. Based on the groundwater monitoring data presented in the preceding section, it is our opinion infiltration BMPs are not feasible from a geotechnical standpoint due to inadequate minimum vertical separation from the seasonal high GWT elevation.

We trust this letter meets your current needs. Should you have any questions regarding the content herein, or require additional information, please call.

Sincerely,

EARTH SOLUTIONS NW, LLC



Steven K. Hartwig, G.I.T.
Staff Geologist



04/25/2022

Keven D. Hoffmann, P.E.
Associate Principal Engineer

Attachments: Plate 1 – Vicinity Map
Plate 2 – Test Pit Location Plan
Test Pit Logs
Grain Size Distribution
Organic Content Test Results
AmTest Analysis Report

cc: Barghausen Consulting Engineers, Inc.
Attention: Mr. Vicente Varas (Email only)
Mr. Barry Talkington, P.E. (Email only)

Mr. Lou Robinson (Email only)



Reference:
 Pierce County, Washington
 OpenStreetMap.org




Earth Solutions NW LLC
 Geotechnical Engineering, Construction
 Observation/Testing and Environmental Services

Vicinity Map
 Mullan Short Plat
 Puyallup, Washington

NOTE: This plate may contain areas of color. ESNW cannot be responsible for any subsequent misinterpretation of the information resulting from black & white reproductions of this plate.

Drwn. MRS	Date 11/04/2021	Proj. No. 8181
Checked SKH	Date Nov. 2021	Plate 1




LEGEND

TP-1 | — ■ — Approximate Location of
ESNW Test Pit, Proj. No.
ES-8181, Oct./Nov. 2021

▭ Subject Site

▭ Existing Building

















NOTE: The graphics shown on this plate are not intended for design purposes or precise scale measurements, but only to illustrate the approximate test locations relative to the approximate locations of existing and / or proposed site features. The information illustrated is largely based on data provided by the client at the time of our study. ESNW cannot be responsible for subsequent design changes or interpretation of the data by others.

NOTE: This plate may contain areas of color. ESNW cannot be responsible for any subsequent misinterpretation of the information resulting from black & white reproductions of this plate.

	Earth Solutions NW_{LLC} Geotechnical Engineering, Construction Observation/Testing and Environmental Services	
	Test Pit Location Plan Mullan Short Plat Puyallup, Washington	
Drwn. MRS	Date 12/14/2021	Proj. No. 8181
Checked SKH	Date Dec. 2021	Plate 2

Earth Solutions NW_{LLC}

SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS		
			GRAPH	LETTER			
<p>COARSE GRAINED SOILS</p> <p>MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE</p>	<p>GRAVEL AND GRAVELLY SOILS</p>	<p>CLEAN GRAVELS</p> <p>(LITTLE OR NO FINES)</p>		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES		
		<p>GRAVELS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES		
		<p>GRAVELS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES		
	<p>SAND AND SANDY SOILS</p>	<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>	<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	
			<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>		SP	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES	
			<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		SM	SILTY SANDS, SAND - SILT MIXTURES	
		<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>	<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		SC	CLAYEY SANDS, SAND - CLAY MIXTURES	
			<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT LESS THAN 50</p>	<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT LESS THAN 50</p>		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT LESS THAN 50</p>		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT GREATER THAN 50</p>	<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT GREATER THAN 50</p>	<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT GREATER THAN 50</p>		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY		
		<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT GREATER THAN 50</p>		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS		
		<p>SILTS AND CLAYS</p> <p>LIQUID LIMIT GREATER THAN 50</p>		CH	INORGANIC CLAYS OF HIGH PLASTICITY		
<p>HIGHLY ORGANIC SOILS</p>	<p>HIGHLY ORGANIC SOILS</p>	<p>HIGHLY ORGANIC SOILS</p>		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
		<p>HIGHLY ORGANIC SOILS</p>		PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS		

DUAL SYMBOLS are used to indicate borderline soil classifications.

The discussion in the text of this report is necessary for a proper understanding of the nature of the material presented in the attached logs.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18528 LONGITUDE -122.31428
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 10": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION
0					
		MC = 12.5%	TPSL		Dark brown TOPSOIL, minor root intrusions to 1'
		MC = 24.8% Fines = 22.9%	SM		Brown silty SAND, loose to medium dense, damp -becomes gray, trace iron oxide staining -becomes blue-gray [USDA Classification: fine sandy LOAM] -becomes moist
		MC = 44.9%	ML		Gray silty SAND, medium dense, wet -light groundwater seepage -organic debris




Test pit terminated at 8.0 feet below existing grade. Groundwater encountered at 7.5 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-2

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.1851 LONGITUDE -122.31418
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0			TPSL		Dark brown TOPSOIL	34.5
		MC = 12.2%			Brown silty SAND, loose to medium dense, damp -becomes gray, light iron oxide staining	
		MC = 33.9% Fines = 98.4%				31.5
5			ML		Gray SILT, medium dense, moist [USDA Classification: LOAM] -organic debris -becomes wet -light groundwater seepage	27.0
		MC = 55.6%				




Test pit terminated at 8.0 feet below existing grade. Groundwater encountered at 7.5 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-3

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18495 LONGITUDE -122.31412
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0			TPSL		Dark brown TOPSOIL	34.5
			SM		Brown silty SAND with gravel, medium dense, damp (Fill) -asphalt debris	33.0
		MC = 50.0% Fines = 93.2%			Gray SILT, medium dense, wet [USDA Classification: LOAM] -organic debris, light iron oxide staining	
5		MC = 41.6%	ML		-light groundwater seepage, moderate organics -light groundwater seepage	
		MC = 52.4%				25.5

Test pit terminated at 9.5 feet below existing grade. Groundwater encountered at 6.5 and 8.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-4

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18508 LONGITUDE -122.31391
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 10": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
		MC = 12.8% Fines = 32.9%	TPSL		Dark brown TOPSOIL, minor roots to 12"	34.0
			SM		Brown silty SAND, loose to medium dense, damp [USDA Classification: sandy LOAM] -becomes gray, light iron oxide staining	31.0
5		MC = 52.3% MC = 35.2%	ML		Gray SILT, medium dense, moist to wet -trace organics debris -light groundwater seepage -light groundwater seepage	25.5
		MC = 32.7%			Test pit terminated at 9.5 feet below existing grade. Groundwater encountered at 6.5 and 8.5 feet during excavation. No caving observed.	

GENERAL BH / TP / WELL - 8181.GPJ - GRAPHICS TEMPLATE WITH LAT AND LONG.GDT - 4/25/22



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-5

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 10/7/21 COMPLETED 10/7/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18493 LONGITUDE -122.31369
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 8": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0			TPSL		Dark brown TOPSOIL	34.5
		MC = 10.2%	SM		Brown silty SAND, loose to medium dense, damp to moist	
		MC = 35.0% LL = 44 PL = 35 Fines = 81.1%			Gray SILT with sand, medium dense, moist to wet	32.5
5		MC = 43.7%	ML		-light groundwater seepage, slight caving at seepage point	
		MC = 36.9%			-light groundwater seepage	26.0




Test pit terminated at 9.0 feet below existing grade. Groundwater encountered at 5.0 and 7.5 feet during excavation. Caving observed at 5.0 feet.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-6

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18498 LONGITUDE -122.31417
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
			TPSL		Dark brown TOPSOIL, root to 1.5'	0.5 34.5
			SM		Brown silty SAND, loose to medium dense, damp (Fill) -asphalt debris	2.0 33.0
		MC = 42.8%	SP-SM		Brown poorly graded SAND with silt, medium dense, wet -becomes gray, groundwater seepage, moderate iron oxide staining	3.5 31.5

Test pit terminated at 3.5 feet below existing grade. Groundwater encountered at 3.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18518 LONGITUDE -122.31399
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 12": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
			TPSL		Dark brown TOPSOIL, roots to 1.5'	34.0
		MC = 16.6% Fines = 26.2%	SM		Brown silty SAND, loose to medium dense, moist [USDA Classification: slightly gravelly loamy SAND] -moderate caving to BOH -groundwater	30.5
5		MC = 40.4%	ML		Gray SILT, medium dense, wet -becomes saturated	26.0
		MC = 50.1%				




Test pit terminated at 9.0 feet below existing grade. Groundwater encountered at 4.0 feet during excavation. Caving observed from 4.0 feet to BOH.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-8

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18494 LONGITUDE -122.31338
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION		
0							
		MC = 39.6%	TPSL		0.5	Dark brown TOPSOIL, roots	34.5
			SM			Brown silty SAND, loose to medium dense, damp (Fill) -asphalt debris, plastic debris	
			ML		2.5	Gray SILT, medium dense, wet -moderate iron oxide staining at contact	32.5
		MC = 37.5% CEC = 14.0 meq/100g OC = 2.7%					
		MC = 43.8%			4.5	-groundwater	30.5




Test pit terminated at 4.5 feet below existing grade. Groundwater encountered at 4.0 feet during excavation. No caving observed.



Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-9

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18506 LONGITUDE -122.31362
 EXCAVATION METHOD _____ GROUND WATER LEVEL:
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
		MC = 6.7%	TPSL		Dark brown TOPSOIL, roots to 6"	34.5
			SM		Brown silty SAND with gravel, loose to medium dense, damp to moist (Fill)	
					-asphalt debris, brick debris	33.0
		MC = 60.7% CEC = 15.0 meq/100g OC = 4.7%	ML		Brown SILT with sand, medium dense, saturated -becomes gray, moderate to severe iron oxide staining	
		MC = 63.2%			-groundwater	31.0

Test pit terminated at 4.0 feet below existing grade. Groundwater encountered at 3.5 feet during excavation. No caving observed.






Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

TEST PIT NUMBER TP-10

PAGE 1 OF 1

PROJECT NUMBER ES-8181 PROJECT NAME Mullan Short Plat
 DATE STARTED 11/2/21 COMPLETED 11/2/21 GROUND ELEVATION 35 ft
 EXCAVATION CONTRACTOR NW Excavating LATITUDE 47.18493 LONGITUDE -122.31403
 EXCAVATION METHOD _____ GROUND WATER LEVEL: _____
 LOGGED BY SKH CHECKED BY KDH AT TIME OF EXCAVATION _____
 NOTES Depth of Topsoil & Sod 6": grass

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	U.S.C.S.	GRAPHIC LOG	MATERIAL DESCRIPTION	
0						
			TPSL		Dark brown TOPSOIL, roots to 8"	34.5
			SM		Brown silty SAND, loose to medium dense, moist (Fill) -asphalt debris	33.5
			GM		Brown silty GRAVEL with sand, medium dense, moist -becomes gray, infiltration test [USDA Classification: very gravelly LOAM]	32.5

MC = 20.9%
 Fines = 38.6%

Test pit terminated at 2.5 feet below existing grade. No groundwater encountered during excavation. No caving observed.




Earth Solutions NW, LLC
 15365 N.E. 90th Street, Suite 100
 Redmond, Washington 98052
 Telephone: 425-449-4704
 Fax: 425-449-4711

GRAIN SIZE DISTRIBUTION

PROJECT NUMBER ES-8181

PROJECT NAME Mullan Short Plat





Earth Solutions NW, LLC
15365 N.E. 90th Street, Suite 100
Redmond, Washington 98052
Telephone: 425-449-4704
Fax: 425-449-4711

SUMMARY OF LABORATORY RESULTS

PROJECT NUMBER ES-8181

PROJECT NAME Mullan Short Plat

Borehole, Depth	Sample Location	Date Test Completed	Water Content (%)	Ash Content (%)	Organic Content (%)
TP-08, 3.5'		11/17/21	37.5	97.3	2.7
TP-09, 3.0'		11/17/21	60.7	95.3	4.7

Am Test Inc.
13600 NE 126TH PL
Suite C
Kirkland, WA 98034
(425) 885-1664
www.amtestlab.com



Professional
Analytical
Services

ANALYSIS REPORT

EARTH SOLUTIONS NW
1805 136TH PL NE
BELLEVUE, WA 98005
Attention: KEVEN HOFFMAN
Project Name: MULLAN SHORT PLAT
All results reported on an as received basis.

Date Received: 11/08/21
Date Reported: 11/23/21

AMTEST Identification Number 21-A017058
Client Identification TP-8, 3.5'
Sampling Date


Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	14.	meq/100g		0.5	SW-846 9081	JDR	11/18/21


AMTEST Identification Number 21-A017059
Client Identification TP-9, 3'
Sampling Date

Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	15.	meq/100g		0.5	SW-846 9081	JDR	11/18/21


Kathy Fugiel
President

7.3 Critical Area
Assessment and
Biological Evaluation,
prepared by Habitat
Technologies dated
August 29, 2022



HABITAT TECHNOLOGIES

CRITICAL AREAS ASSESSMENT AND BIOLOGICAL EVALUATION

**PARCEL 0420037037
5505300831, 808 – 14th Street SW
City of Puyallup, Pierce County, Washington**

*This document has been updated to incorporate additional information
consistent with City of Puyallup third-party reviews dated March 17, 2022
and July 18, 2022*

prepared for

**Kristian and Joann Mullan
808 – 14th Street SW
Puyallup, Washington 98371
e-mail kjmullan@yahoo.com**

and

**Ms. Cheryl Ebsworth, Senior Planner
@ Barghausen Consulting Engineers, Inc.
18215 – 72nd Avenue South
Kent, Washington 98032
e-mail cebsworth@Barghausen.com**

prepared by

**HABITAT TECHNOLOGIES
P.O. Box 1088
Puyallup, Washington 98371-1088
253-845-5119**

August 29, 2022

wetlands, streams, fisheries, wildlife – mitigation and permitting solutions
P.O. Box 1088, Puyallup, Washington 98371
253-845-5119 contact@habitattechnologies.net

A VETERAN OWNED SMALL BUSINESS COOPERATIVE

Table of Contents

INTRODUCTION	3
PROJECT SITE DESCRIPTION	3
BACKGROUND INFORMATION	3
NATIONAL WETLAND INVENTORY	3
STATE OF WASHINGTON PRIORITY HABITATS AND SPECIES	3
STATE OF WASHINGTON DEPARTMENT OF FISH AND WILDLIFE	4
STATE OF WASHINGTON DEPARTMENT OF NATURAL RESOURCES	4
CITY OF PUYALLUP MAPPING.....	4
SOILS MAPPING	4
ONSITE ASSESSMENT	5
CRITERIA FOR ENVIRONMENTALLY CRITICAL AREAS IDENTIFICATION	5
FIELD OBSERVATION	6
<input type="checkbox"/> <i>Vegetation</i>	6
<input type="checkbox"/> <i>Soil</i>	7
<input type="checkbox"/> <i>Hydrology</i>	7
ASSESSMENT FINDINGS	8
WETLANDS	8
<input type="checkbox"/> <i>Wetland Hydrology Review</i>	8
<input type="checkbox"/> <i>Wetland Hydrology Conclusion</i>	9
STREAMS.....	10
FISH AND WILDLIFE SPECIES AND HABITATS.....	10
<input type="checkbox"/> <i>State Priority Species</i>	11
<input type="checkbox"/> <i>Federally Listed Species</i>	12
PROPOSED ACTION	12
EXISTING PARCEL DIVISION	12
NEW SINGLE-FAMILY HOMESITE CONSTRUCTION	13
<input type="checkbox"/> <i>Unavoidable Floodplain Encroachment Mitigation</i>	13
DETRIMENTAL IMPACT AVOIDANCE METHODS	14
SUMMARY OF POTENTIAL EFFECTS	14
<input type="checkbox"/> <i>Potential Direct or Indirect Effects</i>	14
<input type="checkbox"/> <i>Potential Interrelated Effects</i>	17
<input type="checkbox"/> <i>Potential Interdependent Effects</i>	17
<input type="checkbox"/> <i>Potential Cumulative Effects</i>	17
FLOODPLAIN FUNCTIONS EFFECTS DETERMINATION.....	17
EFFECT DETERMINATION	20
PROPOSED ACTION EFFECTS DETERMINATION	21
STANDARD OF CARE	21
FIGURES	22
REFERENCE AND LITERATURE REVIEW LIST	23
PHOTOS.....	26
APPENDIX A – WETLAND DETERMINATION FORMS.....	30
APPENDIX B – HYDROLOGY MONITORING DATA.....	31

INTRODUCTION

As initially proposed, the overall action would divide an existing approximately 0.93-acre parcel into two (2) generally equal sized new parcels. Following this proposed division of land, the existing single-family homesite would be retained within one of the newly created parcels and the second newly created parcel would be suitable for the development of a new single-family homesite consistent with the community. The project site (**Parcel 5505300831**) was located at 808 – 14th Street SW within the City of Puyallup, Pierce County, Washington (Figure 1).

PROJECT SITE DESCRIPTION

The project area is rectangular in shape, approximately 0.93-acres in size, and located within a well urbanized portion of the City of Puyallup that is well served by existing public roadways along with public and private public utilities. The project site is surrounded by existing single-family homesites, managed yards, a public roadway, and church/religious facilities. Seasonal stormwater runoff from the project site along with this portion of the City of Puyallup that does not infiltrate within managed yards and landscaping enters a City of Puyallup stormwater system located within 14th Street SW adjacent to the eastern boundary of the project site. This City stormwater system leads generally southerly within a City of Puyallup stormwater collection and conveyance system to enter Meeker Ditch approximately 600 feet offsite to the south of the project site. Meeker Ditch is an open City managed ditch within the unimproved 10th Avenue SW Corridor that conveys both a remnant stream and directed stormwater from well-urbanized areas generally to the west to eventually enter Clarks Creek, a tributary to the Lower Puyallup River well offsite to the north of the project site.

BACKGROUND INFORMATION

NATIONAL WETLAND INVENTORY

The *National Wetland Inventory (NWI) Mapping* completed by the U.S. Fish and Wildlife Service was reviewed as a part of this assessment (Figure 2). This mapping resource did not identify any wetlands or surface water drainages within or immediately adjacent to the project site.

STATE OF WASHINGTON PRIORITY HABITATS AND SPECIES

The State of Washington *Priority Habitats and Species (PHS) Mapping* was reviewed as a part of this assessment (Figure 3). This mapping resource did not identify any priority habitats or priority species within or immediately adjacent to the project site.

STATE OF WASHINGTON DEPARTMENT OF FISH AND WILDLIFE

The State of Washington Department of Fish and Wildlife (WDFW) *SalmonScape Mapping* was reviewed as a part of this assessment (Figure 4). This mapping resource did not identify any streams within or immediately adjacent to the project site. This mapping resource did identify both Meeker Ditch offsite to the south and Clarks Creek offsite to the west.

Meeker Ditch has been documented to provide spawning and rearing habitats for coho salmon (*Oncorhynchus kisutch*), cutthroat trout (*Oncorhynchus clarkii*), and chum salmon (*Oncorhynchus keta*). Clarks Creek has been the subject of State of Washington, Puyallup Tribal, and private enhancement programs and has been documented to provide habitats for coho salmon, Chinook salmon (*Oncorhynchus tshawytscha*), chum salmon, cutthroat trout, and steelhead/rainbow trout (*Oncorhynchus mykiss*).

STATE OF WASHINGTON DEPARTMENT OF NATURAL RESOURCES

The State of Washington Department of Natural Resources (WDNR) *Water Type Mapping* was reviewed as a part of this assessment (Figure 5). This mapping resource did not identify any wetlands or drainage corridors within or immediately adjacent to the project site. This mapping resource did identify Meeker Ditch offsite to the south as a Type U Water (unknown) and Clarks Creek offsite to the west as a Type S Water (shoreline of the state).

CITY OF PUYALLUP MAPPING

The City of Puyallup *Mapping Inventory* was reviewed as a part of this assessment (Figure 6). This mapping resource did not identify any wetlands or streams within or immediately adjacent to the project site. This mapping resource did identify a “field verified” wetland offsite to the south of the project site – in the location of two existing single-family homesites. Also identified were Meeker Ditch and an associated created mitigation wetland offsite to the south and Clarks Creek offsite to the west.

The *Flood Plain Mapping* (Figure 6A) prepared by the City of Puyallup identified that the central and southeastern portions of the project site were overlain by an area exhibiting a 1% annual chance of flooding (AE flood zone).

SOILS MAPPING

The *Soil Mapping Inventory* completed by the Natural Resource Conservation Service (NRCS) was reviewed as a part of this assessment (Figure 7). This mapping resource identified the soils throughout the project site as Sultan silt loam. The Sultan soil series is defined as moderately well drained, as formed in alluvium, and as not listed as a “hydric” soil.

ONSITE ASSESSMENT

CRITERIA FOR ENVIRONMENTALLY CRITICAL AREAS IDENTIFICATION

To allow for proposed site planning, the assessment and delineation of specific environmentally critical areas within and immediately adjacent to the project site followed the methods and procedures defined in the *Corps of Engineers Wetland Delineation Manual* (United States Army Corps of Engineers, 1987) with the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region* (United States Army Corps of Engineers, 2010); the Washington State *Wetland Rating System for Western Washington: 2014 Update* Publication #14-06-029 (Hruby, 2014), the State of Washington Department of Natural Resources (WDNR) Forest Practice Rules (WAC 222-16-030), and City of Puyallup – *Chapter 21.06*. This assessment did not include an assessment of potential steep slope, potential critical aquifer recharge areas, floodplain areas, erosion hazard areas, or geotechnically hazardous critical areas.

WETLANDS: Wetlands are transitional areas between aquatic and upland habitats. In general terms, wetlands are lands where the extent and duration of saturation with water is the primary factor determining the nature of soil development and the types of plant and animal communities living in the soil and on its surface (Cowardin, et al., 1979). Wetlands are generally defined within land use regulations as "areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions" (United States Army Corps of Engineers 1987). Wetlands exhibit three essential characteristics, all of which must be present for an area to meet the established criteria (United States Army Corps of Engineers, 1987 and United States Army Corps of Engineers, 2010). These essential characteristics are:

- 1. Hydrophytic Vegetation:** The assemblage of macrophytes that occurs in areas where inundation or soil saturation is either permanent or of sufficient frequency and duration to influence plant occurrence. Hydrophytic vegetation is present when the plant community is dominated by species that require or can tolerate prolonged inundation or soil saturation during the growing season.
- 2. Hydric Soil:** A soil that formed under conditions of saturation, flooding, or ponding long enough during the growing season to develop anaerobic conditions in the upper parts. Most hydric soils exhibit characteristic morphologies that result from recent periods of saturation or inundation. These processes result in distinctive characteristics that persist in the soil during both wet and dry periods.
- 3. Wetland Hydrology:** Permanent or periodic inundation, or surface soil saturation, at least seasonally. Wetland hydrology indicators are used in combination with indicators of hydric soil and hydrophytic vegetation to define the area. Wetland hydrology indications provide evidence that the site has a continuing wetland

hydrology regime. Where hydrology has not been altered vegetation and soils provide strong evidence that wetland hydrology is present.

STREAMS: A stream is defined by the City of Puyallup as a feature where surface waters produce a defined channel or bed. A defined channel or bed is an area that demonstrates clear evidence of the passage of water and includes, but is not limited to, bedrock channels, gravel beds, sand and silt beds, and defined-channel swales. The channel or bed need not contain water year-round. This definition is not intended to include artificially created irrigation ditches, canals, storm or surface water devices, or other entirely artificial watercourses, unless they are used by salmonids or created for the purposes of stream mitigation.

CRITICAL FISH AND WILDLIFE HABITAT AREAS: The City of Puyallup defines “fish and wildlife habitat conservation areas” as those areas that serve a critical role in sustaining needed habitats and species for the functional integrity of the ecosystem, and which, if altered, may reduce the likelihood that the species will persist over the long term.

- (a) These areas may include, but are not limited to, rare or vulnerable ecological systems, communities, and habitat or habitat elements including seasonal ranges, breeding habitat, winter range, and movement corridors; and areas with high relative population density or species richness. These areas also include locally important habitats and species as determined by the city.
- (b) “Habitats of local importance” designated as fish and wildlife habitat conservation areas include those areas found to be locally important by the city.
- (c) These areas do not include such artificial features or constructs as irrigation delivery systems, irrigation infrastructure, irrigation canals, or drainage ditches that lie within the boundaries of and are maintained by a port district or an irrigation district, unless these features are documented as being used by salmonids for habitat.

FIELD OBSERVATION

The project site was accessed via an existing driveway connection to 14th Street SW along the eastern boundary of the project site. The entire project site has been managed as a single-family homesite (initially constructed in 1905) and associated managed yard and garden areas. The project site was generally flat and surrounded by existing single-family homesites and similarly sized and smaller parcels. Representative field data worksheets (**WETLAND DETERMINATION FORMS**) are provided in Appendix A.

- **Vegetation**

The plant community throughout the project site has been altered by prior permitted clearing, grading, homesite removals, and the placement of clean imported gravelly loam fill materials. The existing single-family homesite within the northeastern portion of the project site includes ornamental landscaping, lawn, and garden areas. The remainder of

the project site was dominated by a managed lawn with a few small fruit trees. Observed species throughout the majority of the project site included bluegrass (*Poa* spp.), bentgrass (*Agrostis tenuis*), orchardgrass (*Dactylis glomerata*), quack grass (*Agropyron repens*), fescue (*Festuca* spp.), sweet vernal grass (*Anthoxanthum odoratum*), velvet grass (*Holcus lanatus*), reed canarygrass (*Phalaris arundinacea*), bracken fern (*Pteridium aquilium*), buttercup (*Ranunculus repens*), cats-ear (*Hypochaeris radicata* and *Hypochaeris lanatum*), clover (*Trifolium* spp.), daisy (*Bellis* spp.), mustard (*Brassica campestris*), plantain (*Plantago major*), Queen Annes lace (*Daucus carota*), dandelion (*Taraxacum officinale*), bull thistle (*Cirsium vulgare*), and Canadian thistle (*Cirsium arvensis*).

- **Soil**

The project site had been cleared and leveled several decades ago in the development of an existing single-family homesite and associated managed yard and lawn areas. As defined at representative sample plots the soil throughout the majority exhibited characteristics typical of the Sultan soil series. The surface soil generally to a depth of four (4) to nine (9) inches was very dark grayish brown (10YR 3/2) to dark brown (10YR 3/3) in coloration and silty loam in texture. The surface soil exhibited often dense grass root structure. The subsoil to a depth of 24 inches exhibited a brown (10YR 4/3) to dark yellowish brown (10YR 3/4) coloration and a silty loam texture. The soil throughout the majority of the project site did not exhibit prominent field indicators of hydric soils.

A very shallow topographic depression was present within the northcentral portion of the project site generally within an area of a prior garden. The surface soil to a depth of approximately nine (9) inches within this area exhibited a very dark grayish brown (10YR 3/2) coloration and a silty loam in texture. The subsoil to a depth of 24 inches exhibited a dark grayish brown coloration and a silty loam texture. The subsoil exhibited somewhat faint redoximorphic features and appeared more typical of the Briscot soil series (a somewhat poorly drained soil also mapped within the Lower Puyallup River Valley).

- **Hydrology**

Initial onsite assessments of potential onsite wetland hydrology patterns were completed during the summer and fall of 2021. As noted during these initial assessments the project site did not exhibit prominent field indicators of wetland hydrology patterns. However, City of Puyallup Third-Party review completed on March 2, 2022 identified the potential presence of seasonal surface water throughout the project site and especially within the northcentral portion of the project site. Since this observation was so contrary to those of Habitat Technologies, Habitat Technologies immediately began an assessment of early growing seasonal hydrology patterns to better understand the potential reasons for divergent findings.

On April 17, 2022, Habitat Technologies established a pattern of four (4) monitoring locations to define onsite hydrology patterns from the middle of April through the end of May 2022. Because the project site is actively managed as a part of the existing single-

family homesite each monitoring location was defined with a hand-held GPS so that monitoring would be completed within generally the same locations over the monitoring period. Twice a week at each monitoring location a monitoring hole was dug by hand to a depth of approximately 24 inches. East monitoring hole was allowed to remain open for a period of 30 to 60 minutes. The level of free water and the level of soil saturation was then identified as measured in inches from the soil surface for each monitoring hole (Appendix B).

ASSESSMENT FINDINGS

WETLANDS

As noted above, the entire project site along with adjacent parcels had been modified and manipulated for the past several decades as a part of single-family residential development and utilization. The activities had generally included previous clearing and grading, the establishment and management of single-family homesites, the establishment and management of associated landscaping and yard areas, the creation and maintenance of overground and underground utilities, the creation and management of City stormwater collection and conveyance facilities, and the creation and management of public and private roadways.

Since the character of the project site has been historically disturbed and continuously maintained for ongoing residential utilization, the present character of the existing plant communities and the soil profile within the upper 24 inches may not be reliable indicators of the presence or absence of wetlands. As such, the presence or absence of wetland hydrology would appear to be the most reliable indicator for the determination of whether or not a “wetland” would be present within the project site.

- **Wetland Hydrology Review**

As identified above, an assessment of shallow groundwater/wetland hydrology patterns was completed from the middle of April 2022 through the end of May 2022. This assessment documented both the level of free water and the level of soil saturation within representative monitoring plots. Documented onsite hydrology patterns were then compared to seasonal rainfall data to determine if the hydrology patterns observed occurred during normal climatic conditions or during either wetter than normal or drier than normal seasonal conditions.

2022 MONTH	30%< ^A	AVE ^A	30%> ^A	PPT ^B	CONDITION ^C	CONDITION VALUE	MONTH WEIGHT VALUE	PRODUCT
March	3.46	4.58	5.34	4.92	N	2	1	2
April	2.53	3.51	4.14	3.69	N	2	2	4
May	1.76	2.67	2.67	3.56	W	3	3	9
Sum								15

Notes:

Growing Season: There is a 70% chance of the growing season (24°F or higher) occurring between Jan 30 and Dec 13 (317 days).

If sum is:	Condition Values:
6 - 9 then prior period was drier than normal	Dry (D) = 1
10 – 14 then prior period was normal	Normal (N) = 2
15 – 18 then prior period was wetter than normal	Wet (W) =3

^A AgACIS for McMillin Reservoir, WA WETS Station (NRCS 2022)

^B AgACIS for Parkland 0.9 NE, WA (CoCO RaHS) (NRCS 2022)

^C Conditions are considered normal if they fall within the low and high range around the average

* NOTE that different stations are used due to data availability

Based on the combined review of rainfall occurrence within the general area of the project site between the first of March and the end of May 2022, documented climatic conditions were slightly wetter than normal. This wetter than normal condition is defined by precipitation during May (Condition Value of 3).

• **Wetland Hydrology Conclusion**

Based on the observations documented from the middle of April 2022 through the end of May 2022, shallow seasonal groundwater or saturated soils were not present within 12 inches of the surface for a continuous period of time sufficient to meet the established wetland hydrology criteria as outlined in the *Corps of Engineers Wetland Delineation Manual* (United States Army Corps of Engineers, 1987) with the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region* (United States Army Corps of Engineers, 2010). In addition, since the period documented occurred during a spring period of normal and wetter than normal rainfall conditions the findings can be reasonably extrapolated to be representative of the entire growing season.

The conclusion that no portion of the project site exhibited soil saturation or shallow ground water sufficient to meet the established wetland criteria is supported by the following:

- In accordance with the *Corps of Engineers Wetland Delineation Manual* (United States Army Corps of Engineers, 1987) with the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region* (United States Army Corps of Engineers, 2010) and area exhibits wetland hydrology **if** it is inundated or saturated to the surface for at least 5% of the growing season in most years (50% probability of recurrence) during normal climatic conditions.

- As defined on the WETS Table information, the growing season for the area of the project site is 317 days in length. A such 5% of the growing season results in a total of approximately 16 days.
- For an area to meet the wetland hydrology criterion, such an area would need to exhibit saturated soils or shallow groundwater for 16 consecutive days during the defined growing season.
- As documented from the middle of April 2022 through the end of May 2022 (a total of 46 days), no portion of the project site exhibited 16 consecutive days of saturated soils or shallow groundwater.
- While the 2022 assessment did not begin until the middle of April the onsite assessment did occur during slightly wetter than normal climatic conditions such that the extrapolation of these results to normal conditions would indicate that there are even fewer days when saturated soils or groundwater are within 12 inches of the surface onsite during the growing season.

No portion of the project site, or area within the immediate vicinity of the project site was identified to exhibit all three of the criteria for designation as “wetland.”

STREAMS

No portion of the project site, or area within the immediate vicinity of the project site was identified to exhibit a defined channel or swale created by the concentrated movement of surface water.

FISH AND WILDLIFE SPECIES AND HABITATS

The project area was located within a well-urbanized portion of the City of Puyallup. The project area and adjacent parcels were dominated by existing managed single-family homesites, public roadways, public utilities, and church/religious facilities. Based on direct observations, prior observations within the project area, and a review of existing onsite and adjacent habitats wildlife species that were observed or that would be expected within the project site include American crow (*Corvus brachyrhynchos*), rock dove (*Columba livia*), mourning dove (*Zenaida macroura*), violet green swallow (*Tachycineta thalassina*), song sparrow (*Melospiza melodia*), American robin (*Turdus migratorius*), dark eyed junco (*Junco hyemalis*), Steller’s jay (*Cyanocitta stelleri*), starling (*Sturnus vulgaris*), house sparrow (*Passer domesticus*), purple finch (*Carpodacus purpureus*), Anna’s hummingbird (*Calypte anna*), rufous hummingbird (*Selasphorus rufus*), red tailed hawk (*Buteo jamaicensis*), coyote (*Canis latrans*), raccoon (*Procyon lotor*), striped skunk (*Mephitis mephitis*), opossum (*Didelphis virginianus*), deer mouse (*Peromyscus maniculatus*), vole (*Microtus* spp.), mole (*Scapanus* spp.), bats (*Myotis* spp.), Norway rat

(*Rattus norvegicus*), eastern cottontail (*Sylvilagus floridanus*), and common garter snake (*Thamnophis sirtalis*). The majority of these species would also utilize the managed habitats associated with adjacent parcels and in particular those areas where bird-feeders are available.

The project site was not observed and has not been documented to provide spawning or rearing habitats for amphibian. The project site was also not observed and has not been documented to provide direct habitats for fish species.

Both Meeker Ditch and Clarks Creek well offsite have been documented to provide habitats for a variety of fish and wildlife species. Meeker Ditch has been documented to provide habitats for coho salmon (*Oncorhynchus kisutch*), cutthroat trout (*Oncorhynchus clarkii*), and chum salmon (*Oncorhynchus keta*). Clarks Creek has been the subject of State of Washington, Puyallup Tribal, and private enhancement programs and has been documented to provide habitats for coho salmon, Chinook salmon (*Oncorhynchus tshawytscha*), chum salmon, cutthroat trout, and steelhead/rainbow trout (*Oncorhynchus mykiss*). Addition, non-salmonid fish species within these surface water corridors include sculpin (*Cottus* spp.), three spine stickleback (*Gasterosteus aculeatus*), sucker (*Catostomus* spp.), Western brook lamprey (*Lampetra richardsoni*), bullhead (*Ameiurus* spp.), and sunfish (*Lepomis* spp.).

- **State Priority Species**

A very limited number of species identified by the State of Washington as “Priority Species” were observed onsite or potentially may utilize the habitats provided within the project site. Priority species require protective measures for their survival due to their population status, sensitivity to habitat alteration, and/or recreational, commercial, or tribal importance.

Game Species: Species identified by the State of Washington as “game species” are regulated by the State of Washington through recreational hunting bag limits, harvest seasons, and harvest area restrictions. A single “game species” – mourning dove - may use the habitats provided within the project area.

State Candidate: State Candidate species are presently under review by the State of Washington Department of Fish and Wildlife (WDFW) for possible listing as endangered, threatened, or sensitive. No State Candidate species were observed or have been documented to use the habitats provided within the project site.

State Threatened: State Threatened species are native to the state of Washington and are likely to become an endangered species within the foreseeable future throughout a significant portion of its range within the state without cooperative management or removal of threats. The project site did not provide and has not been documented to provide direct critical habitats for State Threatened species.

State Endangered: State endangered species means any species native to the state of Washington that is seriously threatened with extinction throughout all or a significant portion of its range within the state. The project site did not provide and has not been documented to provide direct critical habitats for State Endangered species.

- **Federally Listed Species**

The project site did not provide and has not been documented to provide direct critical habitats for federally listed endangered, threatened, or candidate species. Clarks Creek offsite to the west has been documented to provide habitats for Puget Sound Chinook salmon and Puget Sound Steelhead trout – both federally listed threatened species. Both Clarks Creek and Meeker Ditch have been documented to provide habitats for coho salmon – a federally listed “species of concern.” In addition, the Clarks Creek Corridor, along with the Puyallup River and local lakes, has been documented to provide habitats for bald eagle (*Haliaeetus leucocephalus*) – a federally listed “species of concern.”

PROPOSED ACTION

EXISTING PARCEL DIVISION

As noted above, the initially proposed action is the division of the existing approximately 0.93-acre parcel into two (2) generally equal sized new parcels. This initial proposed action would not involve the manipulation or modification of the project site. Following this proposed division of land, the existing onsite single-family homesite would be retained within one of the newly created parcels and a new single-family homesite consistent with the neighborhood would be constructed within the second, newly created parcel.

The project site, along with adjacent properties, had been greatly modified since the late 1800s initially for agricultural crop production and then urbanization to establish a residential community. This residential community generally focused on the development and management of single-family homesites, the development and management of public roadways, the development and management of public and private utilities, the development and management of church/religious facilities, and the development and management of a City of Puyallup stormwater capture and conveyance facilities. While the general area of the project site had been modified through prior and ongoing urbanization and well served by City of Puyallup stormwater facilities a portion of the project site has been identified as within the regulated base flood elevation (BFE) for the AE Zone (100-year floodplain) at 32 feet. As presently defined by survey the BFE covers approximately 7,576 square feet of the project site primarily within the central and central-western portion of the project site.

NEW SINGLE-FAMILY HOMESITE CONSTRUCTION

Following the issuance of required environmental and construction permits from the City of Puyallup for new single-family homesite construction within the new second parcel, onsite actions would initially define the required work areas and a working schedule. Initial onsite actions would focus on the clear identification of work and staging areas, the placement of protective construction fencing, the placement of protective security fencing, and the placement of protective erosion controls as required. A small to medium sized excavator would then remove only those onsite soils required for the placement of the homesite foundation, associated structures, and utilities. Removed soils not required onsite for replacement would be placed within a dump truck for export to an offsite approved disposal site.

New homesite construction would not modify the majority of the newly created parcel. In addition, the new homesite construction actions would utilize the existing stormwater systems within and adjacent to the project site within the 14th Street SW Corridor. Best Management Practices for noise, dust, and water quality protections would also be followed during new homesite construction.

As noted above, new homesite construction shall implement a variety of impact avoidance and minimization strategies. These strategies include site preparation and foundation work during the dry season or periods of dry weather; the control and treatment of potential stormwater runoff from the work area; a spill prevention and pollution control program; and the proper short-term storage, staging, inspection, and refueling of equipment. All equipment shall be properly maintained to limit noise and the proposed staging and equipment work areas shall be primarily along the northern/northwestern side of the new homesite foundation. Since the new homesite is generally located approximately 600 feet north of Meeker Ditch and over 1,400 feet east of Clarks Creek, it is expected that noise associated with the new homesite construction would not adversely impact offsite aquatic habitats. In addition, the new homesite construction sequence shall focus initially on the development of the foundation, exterior walls, and roof structures such that the majority of the noise generally associated with this project would be internalized within the homesite.

- **Unavoidable Floodplain Encroachment Mitigation**

The placement of the new single-family homesite within the new parcel would require an unavoidable encroachment into the presently identified floodplain. However, shifting of the new single-family homesite location further to the west to avoid placement within the floodplain would require the construction of a fire truck turnaround thus expanding the development area and impervious surfaces required to be constructed. The impacts to the floodplain as a result of the current proposed location of the new single-family homesite would be minimized by providing openings to the crawlspace of the single-family homesite to allow for the entry and exit of floodwaters. The openings provided would meet the requirements as set forth by section PMC 21.07.060. The small floodplain fill

created by the stem wall of the new single-family homesite would be fully mitigated by a compensatory storage area near the southeastern corner of the site that would be hydrologically connected to the existing floodplain.

DETRIMENTAL IMPACT AVOIDANCE METHODS

Following the initial action to divide an existing parcel into two new parcels the overall action proposes the construction a new single-family homesite within the second of the two newly created parcels. As noted above, the first newly created parcel would retain the existing single-family homesite and managed yard. The new single-family homesite would be consistent with neighborhood and would not require any adverse impacts or modifications to identified environmentally critical areas (wetlands, streams, critical habitats, riparian corridors, or existing vegetated buffers) within or immediately adjacent to the project site. In addition, the construction a new single-family homesite would not alter the existing City of Puyallup stormwater facilities within the general area of the project site. Best Management Practices shall be followed during single-family homesite construction to avoid potential adverse impacts associated with the overall site development actions.

SUMMARY OF POTENTIAL EFFECTS

- **Potential Direct or Indirect Effects**

The initial action to divide an existing parcel into two new parcels would not require site modifications and would have no potential direct or indirect effects.

New single-family homesite construction within the second of the newly created parcels would **not** require any adverse impacts or modification to identified critical areas (wetlands, streams, critical habitats, riparian corridors, or existing vegetated buffers) associated with offsite aquatic corridors. In particular, the project site is separated from Meeker Ditch approximately 600 feet to the south and from Clarks Creek by well over 1,400 feet to the west. The areas between the project site and these offsite aquatic corridors are well established by a variety of residential developments, church/religious facilities, public roadways, and both public and private utilities.

As noted above, the placement of the new single-family homesite within the new parcel would require an unavoidable encroachment into the presently identified floodplain. However, shifting of the new single-family homesite location further to the west to avoid placement within the floodplain would require the construction of a fire truck turnaround thus expanding the development area and impervious surfaces required to be constructed. The impacts to the floodplain as a result of the current proposed location of the new single-family homesite would be minimized by providing openings to the crawlspace of the single-family homesite to allow for the entry and exit of floodwaters.

The openings provided would meet the requirements as set forth by section PMC 21.07.060. The small floodplain fill created by the stem wall of the new single-family homesite would be fully mitigated by a compensatory storage area near the southeastern corner of the site that would be hydrologically connected to the existing floodplain.

FACTOR	EFFECTS DISCUSSION	EFFECTS DETERMINATION
New single-family homesite construction potential to impact the primary constituent elements for a listed species.	<p>The proposed single-family homesite construction would be completed well outside both the Meeker Ditch and the Clarks Creek Corridors and would not require any adverse impacts or modification to identified critical areas (wetlands, streams, critical habitats, riparian corridors, or existing vegetated buffers). In addition, the areas between the project site and these offsite aquatic corridors are well established by a variety of generally residential urban developments and public roadways.</p> <p>Best Management Practices shall also be followed during single-family homesite construction to avoid potential adverse impacts associated with the overall site development actions.</p>	No adverse effects.
Essential fish habitat	The combination of distance away from offsite aquatic areas, the urbanized character of the area of the project site, the avoidance/ minimization elements to be implemented, and the utilization of Best Management Practices the proposed action is not expected to result in direct or indirect adverse impacts to listed EFH.	No adverse effects.
Fish and wildlife conservation areas	The combination of distance away from offsite aquatic areas, the urbanized character of the area of the project site, the avoidance/ minimization elements to be implemented, and the utilization of Best Management Practices the proposed action is not expected to result in direct or indirect adverse impacts to fish and wildlife conservation areas.	No adverse effects.
Vegetation communities and habitat structures	The proposed action would be completed within an existing managed project site dominated by regularly mowed grasses and herbs. The proposed action would not be reasonably expected to impact existing vegetation communities or habitat structures associated with offsite wetlands, streams, critical habitats, riparian corridors, or existing vegetated buffers associated with either the offsite Meeker Ditch or the Clarks Creek Corridors.	No adverse effects.
Water quality	The proposed action would be completed within an existing managed project site dominated by regularly mowed grasses and herbs, and would not alter the existing City of Puyallup surface water management facilities associated with the general	No adverse effects.

	area of the project site. Seasonal surface water runoff from impervious surfaces will be dispersed into vegetated lawn areas where feasible via splash blocks and sheet flow.	
Water quantity, including flood and low flow depths, volumes and velocities	Seasonal surface water runoff from impervious surfaces will be dispersed into vegetated lawn areas where feasible via splash blocks and sheet flow. This action would not alter the existing City of Puyallup stormwater facilities within the general area of the project site. The proposed action would not be reasonably expected to impact existing water quality, including flood and low flow depths, volumes, or velocities associated with either the offsite Meeker Ditch or the Clarks Creek Corridors.	No adverse effects.
The channel's natural planform pattern and migration processes.	The proposed action would not be reasonably expected to impact channel planform patterns or migration processes associated with either the offsite Meeker Ditch or the Clarks Creek Corridors.	No adverse effects.
Spawning substrate.	The proposed action would not be reasonably expected to impact spawning substrates associated with either the offsite Meeker Ditch or the Clarks Creek Corridors.	No adverse effects.
Floodplain refugia.	The proposed action would not be reasonably expected to impact floodplain refugia associated with either the offsite Meeker Ditch or the Clarks Creek Corridors.	No adverse effects.

Direct effects generally occur at or very close to the time of the proposed action. Because the proposed action would be completed within the onsite area previously leveled and presently managed as lawn, would implement a variety avoidance/ minimization strategies such as splash blocks for the new carport building and sheet flow dispersion for portions of the shared access driveway. As such, the proposed single-family homesite construction would not be reasonable expected to result in a change to the hydrologic or aquatic habitats within either the offsite Meeker Ditch or the offsite Clarks Creek Corridors.

Indirect effects are also a direct result of the proposed actions but are likely to occur later in time. These indirect effects may occur within the area of the proposed action or may occur outside the area directly affected by the proposed action. Because the proposed action would be completed within the general location onsite of a prior single-family homesite and would not be reasonably expected to alter existing seasonal stormwater runoff patterns within the general area of the project site the proposed new single-family homesite construction would not result in adverse impacts to modifications to high or low stream flows, modifications to stormwater runoff, the contribution of sediments that impact aquatic substrates, the blocking of connective corridors within habitat areas, an increase in instream water temperatures, the degradation of chemical or biological water quality parameters, the disturbance of riparian vegetation, the modification of large woody debris,

the destabilization of stream channels or channel forming processes, or the degradation of wetlands associated with aquatic drainage corridors within either the offsite Meeker Ditch or Clarks Creek Corridors.

- **Potential Interrelated Effects**

Following the new single-family homesite construction and associated yard establishment no further actions are presently proposed. The new single-family homesite would be occupied and managed in a similar manner as the prior onsite homesite and shall be consistent with the other residents within this portion of the City of Puyallup. Best Management Practices shall be implemented during and following homesite construction activities to ensure protection of local water quality and identified offsite aquatic habitats. No interrelated effects have been identified for this new single-family homesite construction.

- **Potential Interdependent Effects**

The proposed new single-family homesite construction would be completed within an area that has previously been leveled and managed as a part of the adjacent single-family homesite. Seasonal stormwater from the new homesite would be directed via splash blocks and topography into vegetated lawn and landscaped areas onsite for dispersion. As such, the proposed homesite construction would not cause a measurable adverse impact to existing habitats within or adjacent to the project area. No interdependent effects have been identified for this new single-family homesite construction.

- **Potential Cumulative Effects**

The project area is located within an existing, well-urbanized portion of the City of Puyallup. The proposed action would construct a new single-family homesite in an area that has previously been leveled and managed as a part of the adjacent single-family homesite. Upon the completion of the new single-family homesite construction the project site would be consistent with the neighborhood. As such, the new homesite construction would not be to result in adverse impacts associated with traffic, lighting, and noise within the project area, adjacent public roadways, and adjacent urbanized areas. In addition, new homesite development would not be reasonably expected to adversely impact downstream water quality as a result of onsite dispersion of stormwater from new applicable impervious surfaces, or any critical habitats within offsite Meeker Ditch, Clarks Creek, or Lower Puyallup River Corridors.

FLOODPLAIN FUNCTIONS EFFECTS DETERMINATION

The purpose of the *Floodplain Functions Analysis* is to define whether or not a proposed action would potentially result in adverse impacts on the existing floodplain functions. As noted above, the presently proposed action is the construction of a new single-family

homesite within the area of a prior single-family homesite. This construction of a new single-family homesite would **not** require any adverse impacts or modification to identified critical areas (wetlands, streams, critical habitats, riparian corridors, or existing vegetated buffers) within or immediately adjacent to the project site. Potential impact avoidance/minimization strategies associated with this new homesite construction include implementation of a variety of Best Management Practices associated with dust, noise, water quality, and potential erosion controls; the dispersion of seasonal stormwater runoff from impermeable onsite surfaces; and a limited footprint of area modification onsite.

FLOODPLAIN FUNCTIONS	PROPOSED PROJECT ELEMENTS	DETERMINATION
Water quantity and quality within adjacent aquatic system.	The proposed action would utilize onsite dispersion of seasonal stormwater runoff from impermeable surfaces where feasible. In addition, Best Management Practices shall be implemented. As such, the pre-construction water patterns shall be substantially the same as the post-construction water patterns.	No effects on these floodplain functions.
Flood velocities and volumes.	<p>The proposed action would utilize onsite dispersion of stormwater runoff from impermeable surfaces where feasible. In addition, Best Management Practices shall be implemented. As such, the pre-construction water patterns shall be substantially the same as the post-construction water patterns.</p> <p>The placement of the new single-family homesite within the new parcel would require an unavoidable encroachment into the presently identified floodplain. The impacts to the floodplain as a result of the current proposed location of the new single-family homesite would be minimized by providing openings to the crawlspace of the single-family homesite to allow for the entry and exit of floodwaters. The openings provided would meet the requirements as set forth by section PMC 21.07.060. The small floodplain fill created by the stem wall of the new single-family homesite would be fully mitigated by a compensatory storage area near the southeastern corner of the site that would be hydrologically connected to the existing floodplain.</p>	No effects on these floodplain functions.
Flood storage capacity	The proposed action would utilize onsite dispersion of seasonal stormwater runoff from impermeable surfaces where feasible. In addition, Best Management Practices shall be implemented. As such, the pre-construction	No effects on these floodplain functions.

	<p>flood storage capacity shall be substantially the same as the post-construction water patterns.</p> <p>The placement of the new single-family homesite within the new parcel would require an unavoidable encroachment into the presently identified floodplain. The impacts to the floodplain as a result of the current proposed location of the new single-family homesite would be minimized by providing openings to the crawlspace of the single-family homesite to allow for the entry and exit of floodwaters. The openings provided would meet the requirements as set forth by section PMC 21.07.060. The small floodplain fill created by the stem wall of the new single-family homesite would be fully mitigated by a compensatory storage area near the southeastern corner of the site that would be hydrologically connected to the existing floodplain.</p>	
Riparian vegetation	The project site is separated from the Meeker Ditch and Clarks Creek Corridors by existing urbanization. In addition, Best Management Practices shall be implemented. As such, the pre-construction riparian vegetation along these corridors shall not be altered and would be substantially the same as the post- construction riparian vegetation.	No effects on these floodplain functions.
Aquatic habitat forming processes	The project site is separated from the Meeker Ditch and Clarks Creek Corridors by existing urbanization. In addition, Best Management Practices shall be implemented. As such, the pre-construction aquatic habitat forming processes along these corridors shall not be altered and would be substantially the same as the post-construction aquatic habitat forming processes.	No effects on these floodplain functions.
Refuge from higher velocity floodwaters.	The project site is separated from the Meeker Ditch and Clarks Creek Corridors by existing urbanization. In addition, Best Management Practices shall be implemented. As such, the pre-construction refuge processes forming processes along these corridors shall not be altered and would be substantially the same as the post-construction aquatic habitat forming processes.	No effects on these floodplain functions.
Spawning substrate.	The proposed action would utilize onsite dispersion of seasonal stormwater runoff from impermeable surfaces where feasible. In	No effects on these floodplain functions.

	addition, Best Management Practices shall be implemented. As such, the pre-construction spawning substrate along these offsite corridors shall be substantially the same as the post-construction spawning substrate.	
Habitat isolation, channel modifications, sediment inputs, construction noise.	The project site is separated from the Meeker Ditch and Clarks Creek Corridors by existing urbanization. In addition, Best Management Practices shall be implemented. As such, the pre-construction habitat, channel, and sediment forming processes along these offsite corridors shall not be altered and would be substantially the same as the post-construction forming processes. Best Management Practices shall ensure the construction noise, dust, or water quality do not adversely impact these offsite corridors.	No effects on these floodplain functions.

EFFECT DETERMINATION

The overall purpose of the *Habitat Assessment* (HA) program is to provide a detailed analysis of the potential project related impacts (the development of a new single-family homesite within the second of the newly created parcels) on federally listed salmonid species and orcas generally associated with the Puyallup River Corridor and Puget Sound.

- Puget Sound Chinook salmon (*Oncorhynchus tshawytscha*) – ESA threatened
- Puget Sound steelhead trout (*Oncorhynchus mykiss*) – ESA threatened
- Bull trout - native char (*Salvelinus confluentus*) – ESA threatened
- Coho salmon (*Oncorhynchus kisutch*) – ESA species of concern
- Pink salmon (*Oncorhynchus gorbuscha*) – EFH listed
- Southern resident Orcas (*Orcinus orca*) – ESA endangered

The effects determination is defined as follows:

- **No Effect (NE):** The project will have no effect whatsoever on listed species and designated floodplain functions. An insignificant or discountable affect is not the same as no effect. If work affects any item evaluated in the HA, even insignificantly, an NE determination is typically not appropriate.
- **May Affect, Not Likely to Adversely Affect (NLAA):** The appropriate conclusion when effects on the species of floodplain functions that support these species are expected to be beneficial, discountable, or insignificant – even when considering direct, indirect, and cumulative impacts. Beneficial effects are positive impacts without and adverse effects on fish or habitats. Insignificant effects refer to the

size of the impact and discountable effects are those extremely unlikely to occur due to timing. Based on best judgement, a person cannot meaningfully measure, detect, or evaluated insignificant effects or expect discountable effects to occur. The term “negligible” means the same as “insignificant.”

- **Likely to Adversely Affect (LAA):** The effect of the project is likely to result in a short or long-term adverse effect on listed species or floodplain functions.

PROPOSED ACTION EFFECTS DETERMINATION

As outlined above, the proposed construction of a new single-family homesite within the second of the newly created parcels would not require any adverse impacts or modification to identified critical areas (wetlands, streams, critical habitats, riparian corridor, or existing vegetated buffers) or to the physical and biological processes that support and form these critical areas within or immediately adjacent to the project area. In addition, the proposed action would not impact existing floodplain functions within or adjacent to the project area. As such, a **No Effect** is appropriate for the proposed new single-family homesite construction action.

STANDARD OF CARE


This document has been completed by Habitat Technologies for the use by **Kristian and Joann Mullan**. Prior to extensive site planning the findings documented in this report should be reviewed, verified, and approved by the City of Puyallup and potentially other resource and permitting agency(s) staff. Habitat Technologies has provided professional services that are in accordance with the degree of care and skill generally accepted in the nature of the work accomplished. No other warranties are expressed or implied. Habitat Technologies is not responsible for design costs incurred before this document is approved by the appropriate resource and permitting agencies.

Bryan W. Peck
Bryan W. Peck
Senior Wetland Biologist



Thomas D. Deming
Thomas D. Deming, SPWS
Habitat Technologies


FIGURES

Figure 1 Site Vicinity




Legend

-  Roads
-  Priority Habitat and Species



1:4,800




The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

Figure 2 NWI Mapping




Legend

- Roads
- National Wetlands Inventory



1:3,600






The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

Figure 3 PHS Mapping




Legend

-  Roads
-  Priority Habitat and Species




1:3,600



The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.


Figure 4 WDFW Salmonscape Mapping



October 27, 2021


1:9,028

— All SalmonScape Species



Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, USGS/NHD, Dale Gombert (WDFW), WDFW

Figure 5 Forest Practices Water Type Map



Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DSng Division












Map Symbols	Additional Information	Legal Description
<ul style="list-style-type: none">  New Stream  Proposed Water Type  Stream Removal  Break between water types  Start and End Point of Surveyed Reach  Natural Fish Barrier  Manmade Barrier  End of Fish or Last Fish 	<p>Extreme care was used during the compilation of this map to ensure its accuracy. However, due to changes in data and the need to rely on outside information, the Department of Natural Resources cannot accept responsibility for errors or omissions, and therefore, there are no warranties that accompany this material.</p>	<p>S37 T20.0N R04.0E, S33 T20.0N R04.0E S32 T20.0N R04.0E</p>
 <p>WASHINGTON STATE DEPARTMENT OF NATURAL RESOURCES</p>	<p>Date: 10/27/2021 Time: 10:26:35 AM</p>	<p>0 0.1 Miles</p>

Figure 6 City of Puyallup Mapping




Legend

- Streams - Puyallup
- Roads
- Wetlands - Puyallup**
 - Field-verified Delineated
 - Field-verified
 - Unverified
 - Unverified
 - Unverified
 - Buffer
 - Mitigation Site




1:3,600




The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

Figure 6A Flood Plain Mapping



Legend

- Roads
- Regulated Floodplain 2017 - New
- 1% Annual Chance Flood
- 1% Annual Chance Flood
- 1% Annual Chance Flood
- 1% Annual Chance Flood
- X BEHIND LEVEE
- 0.2 PCT
- X (SHADED)
- Coastal High Hazard Areas
- Coastal High Hazard Areas
- See King County FIRM




1:3,600

0 80 160 320 Feet


The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose. Date: 10/27/2021 10:12 AM

Figure 7 Soils Mapping



Legend

- Roads
- Soils
- Priority Habitat and Species




1:2,400




0 50 100 200 Feet


The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

Figure 8 Action Area



Legend

-  Action Area
-  Select_Tax Parcels
-  Roads



1:3,600

0 80 160 320 Feet

The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

REFERENCE AND LITERATURE REVIEW LIST

- Bent, A.C. 1961. *Life Histories of North American Birds of Prey*. Cover Publications, Inc. New York, NY 482pp.
- Berge, M.B. and B.V. Mavros, 2001, King County Bull Trout Program 2000 Bull Trout Surveys. King County Department of Natural Resources Water and Land Resources Division. 41 pp.
- Cavender, T.M. 1978. Taxonomy and distribution of the bull trout, *Salvelinus confluentus* (Suckley), from the American Northwest. *California Fish and Game* 64:139-174.
- Duker, G., C. Whitmus, E.O. Salo, G.B. Grette, and W.M. Schuh. 1989. Distribution of juvenile salmonids in Commencement Bay, 1983. Final report to Port of Tacoma, Washington. Fisheries Research Institute, FRI-UW-8908, School of Fisheries, University of Washington, Seattle.
- Dunstan, W. 1955. White River downstream migration. Puget Sound stream studies (1953-1956) Washington Department of Fisheries. Olympia, Washington.
- Federal Emergency Management Agency (FEMA), 2010. Regional Guidance for Floodplain Habitat Assessment and Mitigation. FEMA Region X. Bothell, Washington.
- Fisher, Larry. 1998. Personal communication. Washington Department of Fish and Wildlife. Mill Creek, Washington.
- Healey, M. 1982. Juvenile Pacific salmon in estuaries: The life support system. pp. 315-341. In *Estuarine Comparison*, edited by V.S. Kennedy. Academic Press, Inc. New York, NY.
- Healey, M. 1991. Life history of chinook salmon (*Oncorhynchus tshawytscha*). Pages 311-394. In Groot, C. and L. Margolis (eds.) *Pacific Salmon Life Histories*. UBC Press. University of British Columbia. Vancouver, Canada.
- Johnson, A., K. Macdonald, and P. Trotter. 2003. Programmatic Biological Effects Analysis - King County River Management Program. Prepared for King County Department of Natural Resources and Parks Water and Land Resources Division. Seattle, Washington, 96 pp.
- Kalinowski, Stephan A. 1998. Personal communication. Regional Habitat Biologist. State of Washington Department of Fish and Wildlife. Port Orchard, Washington.
- Kraemer, C. 1994. Some observations on the life history and behavior of the native char, dolly varden (*Salvelinus malma*) and bull trout (*Salvelinus confluentus*) of the north Puget Sound region. Unpublished.

- Kraemer, Curt. 1995. Personal communication. Washington Department of Fish and Wildlife. Mill Creek, Washington.
- Lee, D.C., J.R. Sedell, B.E. Rieman, R.F. Thorow, J.C. Williams. 1997. Chapter 4: Broadscale Assessment of Aquatic Species and Habitats. In T.M. Quigley and S.J. Arbelbide editors An Assessment of Ecosystem Components in the Interior Columbia Basin and Portions of the Klamath and Great Basins Volume III. U.S. Department of Agriculture, Forest Service, and U.S. Department of Interior, Bureau of Land Management. Gen Tech Rep PNW-GTR-405.
- Levy, D. and T. Northcote. 1982. Juvenile salmon residency in a marsh area of the Fraser River estuary. Canadian Journal of Fisheries and Aquatic Sciences. 39:270-276.
- McPhail, J.D. and J.S. Baxter. 1996. A review of bull trout (*Salvelinus confluentus*) life-history and habitat use in relation to compensation and improvement opportunities. Fisheries Management Report No. 104. Ministry of Environment, Lands and Parks, Fisheries Branch, Canada.
- Miyamoto, Sr. J., T. Deming, and D. Thayer. 1980. Estuarine residency and habitat utilization by juvenile anadromous salmonids within Commencement Bay, Tacoma, Washington. Puyallup Tribal Fisheries Division, Fisheries Management Division, Technical Report No. 80-1, unpublished, Puyallup, Washington.
- Miyamoto, Sr. J., T. Deming, and C. Matheson. 1985. Estuarine residency and habitat utilization by juvenile anadromous salmonids within Commencement Bay, Tacoma, Washington. Puyallup Tribal Fisheries Division, Fisheries Management Division, Technical Report No. 85-1, unpublished, Puyallup, Washington.
- Molenaar, David. 1999. Personal communication. Washington Department of Fish and Wildlife. Olympia, Washington.
- Muckelshoot Indian Tribe, Puyallup Tribe of Indians, and Washington Department of Fish and Wildlife. 1996. Recovery plan for White River spring chinook salmon. Washington Department of Fish and Wildlife. Olympia, Washington.
- NMFS. 1996. Making Endangered Species Act Determination of effect for individual or group actions at the watershed scale. National Marine Fisheries Service, Environmental and Technical Services Division, Habitat Conservation Branch. Lacey Washington. 28 p.
- NMFS. 1999. A Guide to Biological Assessments. National Marine Fisheries Service, Washington Habitat Conservation Branch. Lacey, Washington.
- Simenstad, C., K.L. Fresh, and E.O. Salo, 1982. The role of Puget Sound and Washington coastal estuaries in the life history of Pacific Salmon. An unappreciated function.

Pages 343-364 in V.S. Kennedy (ed.). Proceedings of the Sixth Biennial International Estuarine Research Conference; November 1981. Academic Press, New York, NY.

Skagen, S.K. 1980. Behavioral Responses of Wintering Bald Eagles to Human Activities on the Skagit River, Washington. Biology Department, Western Washington University. Proceedings of the Washington Bald Eagle Symposium. June 14-15, 1980.

Stalmaster, M.V. 1980. Management Strategies for Wintering Bald Eagles in the Pacific Northwest. Dept. of Biology and Ecology Center, Utah State University (Washington Bald Eagle Symposium- June 1980).

Thompson, J.N., J.L. Whitner, and R.E. Lamb, 2011, Snoqualmie River Game Fish Enhancement Plan. Washington Department of Fish and Wildlife, Region 4, Mill Creek, Washington.

USFWS, 1998. A framework to assist in making Endangered Species Act determinations of effect for individual or grouped actions as the bull trout subpopulation watershed scale. 47 pp.

Washington Department of Ecology. 2008. Access Washington at www.ecy.wa.gov/services/gis/maps/wria. Olympia, Washington.

Washington Department of Fish and Wildlife. 1999. Bull trout in the Snohomish River System. Mill Creek, Washington Department of Fish and Wildlife Management Brief, April 1999.

Washington Department of Wildlife. 1991. Management Recommendations for Washington's Priority Habitats and Species. Wildlife Management, Fish Management, and Habitat Management Divisions. Olympia, Washington.

Williams, R. W., R.M. Laramie, and J.J. Ames. 1975. A catalog of Washington streams and salmon utilization Volume 1 Puget Sound Region. Washington Department of Fisheries. Olympia, Washington.

Wydoski, R.S. and R.R. Whitney. 1979. Inland Fishes of Washington. University of Washington Press: Seattle, Washington, 220 pp.

PHOTOS



View northeasterly from the southwestern corner. The existing homesite shown in this photo will be retained in the first of the newly created parcels.



View easterly from the southwestern corner of the project site. The proposed new homesite would likely be located in the eastern portion of the new parcel.



View westerly from the eastern boundary of the project site at the likely location for the new single family homesite.



Typical hydrology, soil, and plant community monitoring plot – spring 2022.



View northward across the western portion of the project site. Spring 2022

**APPENDIX A – WETLAND DETERMINATION FORMS
FIELD DATA WORKSHEETS**

Monitoring Plot Locations



The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.

Date: 6/15/2022 11:04 AM

WETLAND DETERMINATION DATA FORM – Western Mountains, Valleys, and Coast Region

Project/Site: Parcel 5505300831 City/County: City of Puyallup Sampling Date: SEP 21/MAY 22
 Applicant/Owner: _____ State: WA Sampling Point: SP1
 Investigator(s): Habitat Technologies Section, Township, Range: S28 T20N R04E
 Landform (hillslope, terrace, etc.): valley Local relief (concave, convex, none): none Slope (%): flat
 Subregion (LRR): A Lat: _____ Long: _____ Datum: _____
 Soil Map Unit Name: Sultan silt loam NWI classification: mod well drained

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes No

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Hydric Soil Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Wetland Hydrology Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Is the Sampled Area within a Wetland? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Remarks: Area of well manage lawn with a well mixture of grasses and herbs. Hydrology monitoring shows area to drain moderately well following seasonal rainfall events in the spring of 2022.	

VEGETATION – Use scientific names of plants.

	Absolute % Cover	Dominant Species?	Indicator Status	
Tree Stratum (Plot size: 15ft radius)				
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
3. _____	_____	_____	_____	
4. _____	_____	_____	_____	
	_____	= Total Cover		
Sapling/Shrub Stratum (Plot size: 15ft radius)				
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
3. _____	_____	_____	_____	
4. _____	_____	_____	_____	
5. _____	_____	_____	_____	
	_____	= Total Cover		
Herb Stratum (Plot size: 15ft radius)				
1. <u>Agristis tenuis</u>	_____	_____	FAC	
2. <u>Poa spp.</u>	_____	_____	FAC	
3. <u>Taraxacum officinale</u>	_____	_____	FACU	
4. <u>Hypochaeris lanatum</u>	_____	_____	FACU	
5. <u>Ranunculus repens</u>	_____	_____	FACW	
6. <u>Festuca spp.</u>	_____	_____	FAC	
7. <u>Ranunculus acris</u>	_____	_____	FAC	
8. <u>Plantago major</u>	_____	_____	FACU	
9. _____	_____	_____	_____	
10. _____	_____	_____	_____	
11. _____	_____	_____	_____	
	100	= Total Cover		
Woody Vine Stratum (Plot size: 15ft radius)				
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
	_____	= Total Cover		
% Bare Ground in Herb Stratum _____				

Dominance Test worksheet:
 Number of Dominant Species That Are OBL, FACW, or FAC: _____ (A)
 Total Number of Dominant Species Across All Strata: _____ (B)
 Percent of Dominant Species That Are OBL, FACW, or FAC: _____ (A/B)

Prevalence Index worksheet:
 Total % Cover of: _____ Multiply by: _____
 OBL species _____ x 1 = _____
 FACW species _____ x 2 = _____
 FAC species _____ x 3 = _____
 FACU species _____ x 4 = _____
 UPL species _____ x 5 = _____
 Column Totals: _____ (A) _____ (B)
 Prevalence Index = B/A = _____

Hydrophytic Vegetation Indicators:
 Rapid Test for Hydrophytic Vegetation
 Dominance Test is >50%
 Prevalence Index is ≤3.0¹
 Morphological Adaptations¹ (Provide supporting data in Remarks or on a separate sheet)
 Wetland Non-Vascular Plants¹
 Problematic Hydrophytic Vegetation¹ (Explain)

¹Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
--	---

Remarks: Well managed lawn with a mix of grasses and herbs mostly FAC and a few FACW and FACU. No really dominant species

SOIL

Sampling Point: SP1 _____

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features			Loc ²	Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹			
0-11	10YR 3/2	100					Silty loam	dense grass roots
11-24	10YR 4/3	99	10YR 4/6	<1	d	m	silty loam	

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators: (Applicable to all LRRs, unless otherwise noted.) <input type="checkbox"/> Histic Epipedon (A2) <input type="checkbox"/> Black Histic (A3) <input type="checkbox"/> Hydrogen Sulfide (A4) <input type="checkbox"/> Depleted Below Dark Surface (A11) <input type="checkbox"/> Thick Dark Surface (A12) <input type="checkbox"/> Sandy Mucky Mineral (S1) <input type="checkbox"/> Sandy Gleyed Matrix (S4)	Indicators for Problematic Hydric Soils³: <input type="checkbox"/> 2 cm Muck (A10) <input type="checkbox"/> Red Parent Material (TF2) <input type="checkbox"/> Very Shallow Dark Surface (TF12) <input type="checkbox"/> Other (Explain in Remarks)
--	---

³Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if present): Type: _____ Depth (inches): _____	Hydric Soil Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
--	---

Remarks: NO prominent field indicators of hydric soils.

HYDROLOGY

Wetland Hydrology Indicators:	
Primary Indicators (minimum of one required; check all that apply)	Secondary Indicators (2 or more required)
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Saturation (A3) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Water-Stained Leaves (B9) (except MLRA 1, 2, 4A, and 4B) <input type="checkbox"/> Salt Crust (B11) <input type="checkbox"/> Aquatic Invertebrates (B13) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) <input type="checkbox"/> Other (Explain in Remarks)
<input type="checkbox"/> Water-Stained Leaves (B9) (MLRA 1, 2, 4A, and 4B) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> FAC-Neutral Test (D5) <input type="checkbox"/> Raised Ant Mounds (D6) (LRR A) <input type="checkbox"/> Frost-Heave Hummocks (D7)	
Field Observations: Surface Water Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Depth (inches): _____ Water Table Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Depth (inches): _____ Saturation Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Depth (inches): _____ (includes capillary fringe)	Wetland Hydrology Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available: Hydrology monitoring during period of seasonal rainfall events between mid-April 2022 and end of May 2022 shows site drains moderately well following rainfall events	
Remarks: NO prominent field indicators of wetland hydrology free water below -14 inches mid-April to end of May 2022	

WETLAND DETERMINATION DATA FORM – Western Mountains, Valleys, and Coast Region

Project/Site: Parcel 5505300831 City/County: City of Puyallup Sampling Date: SEP 21/MAY 22
 Applicant/Owner: _____ State: WA Sampling Point: SP2
 Investigator(s): Habitat Technologies Section, Township, Range: S28 T20N R04E
 Landform (hillslope, terrace, etc.): valley Local relief (concave, convex, none): none Slope (%): flat
 Subregion (LRR): A Lat: _____ Long: _____ Datum: _____
 Soil Map Unit Name: Sultan silt loam NWI classification: mod well drained

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If no, explain in Remarks.)
 Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Hydric Soil Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Wetland Hydrology Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Is the Sampled Area within a Wetland? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Remarks: Area of well manage lawn with a well mixture of grasses and herbs. Hydrology monitoring shows area to drain moderately well following seasonal rainfall events in the spring of 2022.	

VEGETATION – Use scientific names of plants.

	Absolute % Cover	Dominant Species?	Indicator Status		
Tree Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____	Dominance Test worksheet: Number of Dominant Species That Are OBL, FACW, or FAC: _____ (A) Total Number of Dominant Species Across All Strata: _____ (B) Percent of Dominant Species That Are OBL, FACW, or FAC: _____ (A/B)	
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
_____	_____	_____	_____		
_____ = Total Cover				Prevalence Index worksheet: Total % Cover of: _____ Multiply by: OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____	
Sapling/Shrub Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____		
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
5. _____	_____	_____	_____		
_____ = Total Cover					
Herb Stratum (Plot size: 15ft radius)					
1. <u>Agristis tenuis</u>	_____	_____	FAC	Hydrophytic Vegetation Indicators: <input type="checkbox"/> Rapid Test for Hydrophytic Vegetation <input checked="" type="checkbox"/> Dominance Test is >50% <input type="checkbox"/> Prevalence Index is ≤3.0 ¹ <input type="checkbox"/> Morphological Adaptations ¹ (Provide supporting data in Remarks or on a separate sheet) <input type="checkbox"/> Wetland Non-Vascular Plants ¹ <input type="checkbox"/> Problematic Hydrophytic Vegetation ¹ (Explain) ¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
2. <u>Poa spp.</u>	_____	_____	FAC		
3. <u>Taraxacum officinale</u>	_____	_____	FACU		
4. <u>Hypochaeris lanatum</u>	_____	_____	FACU		
5. <u>Ranunculus repens</u>	_____	_____	FACW		
6. <u>Festuca spp.</u>	_____	_____	FAC		
7. <u>Ranunculus acris</u>	_____	_____	FAC		
8. <u>Plantago major</u>	_____	_____	FACU		
9. _____	_____	_____	_____		
10. _____	_____	_____	_____		
11. _____	_____	_____	_____		
100 = Total Cover					
Woody Vine Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____		
2. _____	_____	_____	_____		
_____ = Total Cover					
% Bare Ground in Herb Stratum _____					
Remarks: Well managed lawn with a mix of grasses and herbs mostly FAC and a few FACW and FACU. No really dominant species					

WETLAND DETERMINATION DATA FORM – Western Mountains, Valleys, and Coast Region

Project/Site: Parcel 5505300831 City/County: City of Puyallup Sampling Date: SEP 21/MAY 22
 Applicant/Owner: _____ State: WA Sampling Point: SP3
 Investigator(s): Habitat Technologies Section, Township, Range: S28 T20N R04E
 Landform (hillslope, terrace, etc.): valley Local relief (concave, convex, none): none Slope (%): flat
 Subregion (LRR): A Lat: _____ Long: _____ Datum: _____
 Soil Map Unit Name: Sultan silt loam NWI classification: mod well drained

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If no, explain in Remarks.)
 Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Hydric Soil Present? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Wetland Hydrology Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Is the Sampled Area within a Wetland? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Remarks: Area of well manage lawn with a well mixture of grasses and herbs. Hydrology monitoring shows area to drain moderately well following seasonal rainfall events in the spring of 2022. Very shallow depressional area with shallow surface water during heavy seasonal rainfall that then drains moderately well between storm events.	

VEGETATION – Use scientific names of plants.

	Absolute % Cover	Dominant Species?	Indicator Status	
Tree Stratum (Plot size: 15ft radius)				Dominance Test worksheet: Number of Dominant Species That Are OBL, FACW, or FAC: <u>3</u> (A) Total Number of Dominant Species Across All Strata: <u>3</u> (B) Percent of Dominant Species That Are OBL, FACW, or FAC: <u>100%</u> (A/B)
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
3. _____	_____	_____	_____	
4. _____	_____	_____	_____	
_____ = Total Cover				
Sapling/Shrub Stratum (Plot size: 15ft radius)				Prevalence Index worksheet: Total % Cover of: _____ Multiply by: OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
3. _____	_____	_____	_____	
4. _____	_____	_____	_____	
_____ = Total Cover				
Herb Stratum (Plot size: 15ft radius)				Hydrophytic Vegetation Indicators: <input type="checkbox"/> Rapid Test for Hydrophytic Vegetation <input checked="" type="checkbox"/> Dominance Test is >50% <input type="checkbox"/> Prevalence Index is ≤3.0 ¹ <input type="checkbox"/> Morphological Adaptations ¹ (Provide supporting data in Remarks or on a separate sheet) <input type="checkbox"/> Wetland Non-Vascular Plants ¹ <input type="checkbox"/> Problematic Hydrophytic Vegetation ¹ (Explain) ¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.
1. <u>Agristis tenuis</u>	<u>25%</u>	<u>yes</u>	<u>FAC</u>	
2. <u>Poa spp.</u>	_____	_____	<u>FAC</u>	
3. <u>Taraxacum officinale</u>	<u>trace</u>	_____	<u>FACU</u>	
4. <u>Hypochaeris lanatum</u>	<u>trace</u>	_____	<u>FACU</u>	
5. <u>Ranunculus repens</u>	<u>60%</u>	<u>yes</u>	<u>FACW</u>	
6. <u>Festuca spp.</u>	_____	_____	<u>FAC</u>	
7. <u>Ranunculus acris</u>	<u>10%</u>	<u>yes</u>	<u>FAC</u>	
8. <u>Plantago major</u>	<u>trace</u>	_____	<u>FACU</u>	
9. _____	_____	_____	_____	
10. _____	_____	_____	_____	
11. _____	_____	_____	_____	
_____ = Total Cover				
Woody Vine Stratum (Plot size: 15ft radius)				Hydrophytic Vegetation Present? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
1. _____	_____	_____	_____	
2. _____	_____	_____	_____	
_____ = Total Cover				
% Bare Ground in Herb Stratum _____				

Remarks: Well managed lawn with a mix of grasses and herbs mostly FAC and FACW. limited dominant species

WETLAND DETERMINATION DATA FORM – Western Mountains, Valleys, and Coast Region

Project/Site: Parcel 5505300831 City/County: City of Puyallup Sampling Date: SEP 21/MAY 22
 Applicant/Owner: _____ State: WA Sampling Point: SP4
 Investigator(s): Habitat Technologies Section, Township, Range: S28 T20N R04E
 Landform (hillslope, terrace, etc.): valley Local relief (concave, convex, none): none Slope (%): flat
 Subregion (LRR): A Lat: _____ Long: _____ Datum: _____
 Soil Map Unit Name: Sultan silt loam NWI classification: mod well drained

Are climatic / hydrologic conditions on the site typical for this time of year? Yes No (If no, explain in Remarks.)
 Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes No
 Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes <input type="checkbox"/> No <input type="checkbox"/> Hydric Soil Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Wetland Hydrology Present? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Is the Sampled Area within a Wetland? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Remarks: Area of well manage lawn with a well mixture of grasses and herbs. Hydrology monitoring shows area to drain moderately well following seasonal rainfall events in the spring of 2022.	

VEGETATION – Use scientific names of plants.

	Absolute % Cover	Dominant Species?	Indicator Status		
Tree Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____	Dominance Test worksheet: Number of Dominant Species That Are OBL, FACW, or FAC: _____ (A) Total Number of Dominant Species Across All Strata: _____ (B) Percent of Dominant Species That Are OBL, FACW, or FAC: _____ (A/B)	
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
_____	_____	_____	_____		
_____ = Total Cover				Prevalence Index worksheet: Total % Cover of: _____ Multiply by: OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____	
Sapling/Shrub Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____		
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
5. _____	_____	_____	_____		
_____ = Total Cover				Hydrophytic Vegetation Indicators: <input type="checkbox"/> Rapid Test for Hydrophytic Vegetation <input checked="" type="checkbox"/> Dominance Test is >50% <input type="checkbox"/> Prevalence Index is ≤3.0 ¹ <input type="checkbox"/> Morphological Adaptations ¹ (Provide supporting data in Remarks or on a separate sheet) <input type="checkbox"/> Wetland Non-Vascular Plants ¹ <input type="checkbox"/> Problematic Hydrophytic Vegetation ¹ (Explain) ¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
Herb Stratum (Plot size: 15ft radius)					
1. <u>Agristis tenuis</u>	_____	_____	FAC		
2. <u>Poa spp.</u>	_____	_____	FAC		
3. <u>Taraxacum officinale</u>	_____	_____	FACU		
4. <u>Hypochaeris lanatum</u>	_____	_____	FACU		
5. <u>Ranunculus repens</u>	_____	_____	FACW		
6. <u>Festuca spp.</u>	_____	_____	FAC		
7. <u>Ranunculus acris</u>	_____	_____	FAC		
8. <u>Plantago major</u>	_____	_____	FACU		
9. _____	_____	_____	_____		
10. _____	_____	_____	_____		
11. _____	_____	_____	_____		
_____ = Total Cover				Hydrophytic Vegetation Present? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
Woody Vine Stratum (Plot size: 15ft radius)					
1. _____	_____	_____	_____		
2. _____	_____	_____	_____		
_____ = Total Cover				Remarks: Well managed lawn with a mix of grasses and herbs mostly FAC and a few FACW and FACU. No really dominant species	
% Bare Ground in Herb Stratum _____					

APPENDIX B – HYDROLOGY MONITORING DATA

Monitoring Plot Locations



The map features are approximate and are intended only to provide an indication of said feature. Additional areas that have not been mapped may be present. This is not a survey. Orthophotos and other data may not align. The County assumes no liability for variations ascertained by actual survey. ALL DATA IS EXPRESSLY PROVIDED 'AS IS' AND 'WITH ALL FAULTS'. The County makes no warranty of fitness for a particular purpose.


Date: 6/15/2022 11:04 AM

2022 Hydrology Monitoring Program – Open Hole

DATE	# 1	# 2	# 3	# 4
15 APR 22	Free -16" Sat -8"	Free -15" Sat -8"	Free -8" Sat surface	Free -11" Sat surface
19 APR 22	Sat -14"	Free -20" Sat -13"	Free -14" Sat -10"	Free -14" Sat -10"
22 APR 22	Free -14" Sat -8"	Free -12" Sat -6"	Free -6" Sat surface	Free -9" Sat -3"
25 APR 25	Free -21" Sat -14"	Free -20" Sat -14"	Free -15" Sat -9"	Free -15" Sat -10"
28 ARP 25	Free -15" Sat -10"	Free -14" Sat -10"	Free -8" Sat -4"	Free -10" Sat -4"
2 MAY 22	Free -22" Sat -14"	Free -21" Sat -15"	Free -15" Sat -10"	Free -17" Sat -12"
5 MAY 22	Free -20" Sat -15"	Free -20" Sat -14"	Free -16" Sat -12"	Free -16" Sat -13
10 MAY 22	Free -21" Sat -16"	Free -20" Sat -15"	Free -15" Sat -11"	Free -17" Sat -13"
13 MAY 22	Free -19" Sat -14"	Free -17" Sat -12"	Free -11" Sat -5"	Free -12" Sat -5"
17 MAY 22	Free none Sat -18"	Free none Sat -17"	Free -15" Sat -12"	Free -16" Sat -12"
20 MAY 22	Free -17" Sat -13"	Free -17" Sat -14"	Free -12" Sat -8"	Free -14" Sat -9"
23 MAY 22	Free none Sat -24"	Free none Sat -22"	Free -19" Sat -16"	Free -18" Sat 16"
26 MAY 22	Free -22" Sat -19"	Free -22" Sat -18"	Free -16" Sat -13"	Free -17" Sat -13"
31 MAY 22	Free none Sat -22"	Free none Sat -22"	Free none Sat -18"	Free none Sat -17"

* as measured in inches from soil surface

Tab 8.0



8.0 OTHER PERMITS

Any permits required for this development will be acquired at a later date.


Tab 9.0



9.0 OPERATIONS AND MAINTENANCE MANUAL

An Operations and Maintenance Manual will be submitted at the time of civil application.

Tab 10.0



10.0 BOND QUANTITIES WORKSHEET

The proposed development consists of a private two-lot short plat. Because of this, a bond quantity worksheet is not required.